AGENDA
CITY OF WATSONVILLE
JOINT COUNCIL, SUCCESSOR HOUSING AGENCY, & SUCCESSOR AGENCY MEETING

Working with our community to create positive impact through service with heart.
Values: Teamwork, Integrity, Honesty, Service and Respect

Kristal Salcido, Mayor, District 4
Casey K. Clark, Mayor Pro Tempore, District 5

Eduardo Montesino, Council Member, District 1
Vanessa Quiroz-Carter, Council Member, District 2
Maria Orozco, Council Member, District 3
Jimmy Dutra, Council Member, District 6
Ari Parker, Council Member, District 7

Tamara Vides, City Manager
Samantha W. Zutler, City Attorney
Irwin I. Ortiz, City Clerk

Location:
City of Watsonville
City Council Chambers
275 Main Street, Top Floor
Watsonville, CA 95076

Pursuant to Government Code Section 54953(b), Mayor Pro Tempore Clark will be participating in the meeting via teleconferencing from: 751 Larkin Valley Road, Watsonville, CA 95076.

Anyone addressing the City Council is asked to fill out a speaker card and leave it at the podium for recording purposes

IF YOU CHALLENGE ANY ACTION APPEARING ON THIS AGENDA IN COURT, YOU MAY BE LIMITED TO RAISING ONLY THOSE ISSUES YOU OR SOMEONE ELSE RAISED AT THE PUBLIC MEETING DESCRIBED ON THIS AGENDA, OR IN WRITTEN CORRESPONDENCE DELIVERED TO THE CITY CLERK PRIOR TO, OR AT, THE PUBLIC MEETING.

SPANISH INTERPRETATION WILL BE AVAILABLE

Americans with Disabilities Act

The Council Chambers is an accessible facility. If you wish to attend a meeting and you will require assistance in order to attend and/or participate, please call the City Clerk's Office at least three (3) business days in advance of the meeting to make arrangements. The City of Watsonville TDD number is (831) 763-4075.

For information regarding this agenda, please call the City Clerk's Office at (831) 768-3040

REVISED AGENDA WITH ADDENDUM
CITY OF WATSONVILLE
JOINT COUNCIL, SUCCESSOR HOUSING AGENCY, &
SUCCESSOR AGENCY

City of Watsonville
City Council Chambers
275 Main Street, Top Floor
Watsonville, CA 95076

Pursuant to Government Code Section 54953(b), Mayor Pro Tempore Clark will be participating in the meeting via teleconferencing from: 751 Larkin Valley Road, Watsonville, CA 95076.

Tuesday, April 14, 2026, 4:30 p.m.

Pages

1. ROLL CALL

   1.a INTRODUCTION OF NEW EMPLOYEES & RECOGNITION OF RETIREES

2. REPORTS TO COUNCIL -- No Action Required

   2.a CITY BUILDING ASSESSMENT STUDY REPORT BY ADMINISTRATIVE SERVICES MANAGER GORDO 6

   2.b STUDY SESSION ON CITY SPECIAL EVENTS BUDGET - REPORT BY DEPUTY CITY MANAGER CALUBAQUIB & RECREATION SUPERVISOR BEEBE 16

3. CLOSED SESSION

   CLOSED SESSION ANNOUNCEMENT:

   PUBLIC COMMENTS REGARDING ONLY THE CLOSED SESSION AGENDA WILL BE ACCEPTED BY THE CITY COUNCIL AT THIS TIME.

   The City Council of the City of Watsonville will recess to Closed Session to discuss the matters that follow:

   3.a CONFERENCE WITH REAL PROPERTY NEGOTIATOR
   (Government Code Section 54956.8)

   Property: (APN: 014-021-01) located between Corralitos Creek & Airport Blvd., Watsonville

   Negotiating parties: Karam Singh, KDS Dhaliwal Investments Inc.

   Tamara Vides & Samantha Zutler (City)

   Under negotiation: Price & Terms of Payment

3.b CONFERENCE WITH LEGAL COUNSEL—ANTICIPATED LITIGATION
(Government Code Section 54956.9)

Initiation of litigation pursuant to subdivision (d)(4) of Section 54956.9: [1 Case]

CITY COUNCIL RESUMES AT 6:00 P.M.

4. ROLL CALL

4.a MOTION TO EXCUSE ABSENT COUNCIL MEMBER(S) (If any)

5. PLEDGE OF ALLEGIANCE

6. INFORMATION ITEMS

6.a REPORT OF DISBURSEMENTS 32

6.b MISCELLANEOUS DOCUMENTS REPORT 98

6.c WRITTEN REPORTS BY COUNCIL MEMBERS 103

6.d 2026 1ST QUARTER COMMISSIONER ATTENDANCE REPORT 106

7. REPORT OUT OF CLOSED SESSION

8. ORAL COMMUNICATIONS

This time is set aside for members of the general public to address the Council on any item not on the Council Agenda, which is within the subject matter jurisdiction of the City Council. No action or discussion shall be taken on any item presented except that any Council Member may respond to statements made or questions asked, or may ask questions for clarification. All matters of an administrative nature will be referred to staff. All matters relating to Council will be noted in the minutes and may be scheduled for discussion at a future meeting or referred to staff for clarification and report.

ALL SPEAKERS ARE ASKED TO FILL OUT A SPEAKER CARD & LEAVE IT AT THE PODIUM. SPEAKERS ARE ASKED TO ANNOUNCE THEIR NAME AND DISTRICT IN WHICH THEY LIVE IN ORDER TO OBTAIN AN ACCURATE RECORD FOR THE MINUTES.

8.a ORAL COMMUNICATIONS FROM THE PUBLIC (2 MINUTES EACH)

8.b ORAL COMMUNICATIONS FROM THE COUNCIL (2 MINUTES EACH)

9. PRESENTATIONS

9.a MAYOR'S PROCLAMATION RECOGNIZING APRIL AS SEXUAL ASSAULT AWARENESS MONTH

9.b MAYOR'S PROCLAMATION RECOGNIZING APRIL AS ARTS, CULTURE, & CREATIVITY MONTH

*9.c MAYOR'S PROCLAMATION HONORING MARIA G. QUIROZ ON HER 100TH BIRTHDAY

10. CONSENT AGENDA

All items appearing on the Consent Agenda are recommended actions that are considered to be routine and will be acted upon as one motion. Any items removed will be considered immediately after the motion. The Mayor will allow public input prior to the approval of the Consent Agenda.

PUBLIC INPUT (2 MINUTES EACH)

10.a MOTION APPROVING MINUTES OF MARCH 24, 2026 107

10.b ADOPT THE CITY OF WATSONVILLE INVESTMENT POLICY FOR CALENDAR YEAR 2026 (Recommended by Administrative Services Director Duran) 117
RESOLUTION ADOPTING & CONFIRMING THE CITY OF WATSONVILLE INVESTMENT POLICY FOR CALENDAR YEAR 2026 & DIRECTING THE ADMINISTRATIVE SERVICES DIRECTOR TO IMPLEMENT THE POLICY

10.c APPROVE THIRD AMENDMENT TO CONTRACT WITH GRIFFIN STRUCTURES, INC. FOR THE RAMSAY PARK RENAISSANCE PROJECT (Recommended by Parks & Community Services Director Calubaquib) 126
RESOLUTION OF WATSONVILLE APPROVING A THIRD AMENDMENT TO CONSULTANT CONTRACT WITH GRIFFIN STRUCTURES, INC., FOR PROJECT MANAGEMENT SERVICES FOR THE RAMSAY PARK RENAISSANCE PROJECT, NO. PK-22-01; INCREASING CONTRACT COMPENSATION BY $87,450; EXTENDING THE TERM OF THE CONTRACT TO DECEMBER 31, 2026

10.d APPROVE CHANGE ORDER NO. 2 WITH KJ WOODS CONSTRUCTION INC. FOR THE WATER LINE REPLACEMENT PROJECT – BEACH ST., UNION ST., LINCOLN ST. (Recommended by Interim Public Works & Utilities Director Green) 139
RESOLUTION APPROVING CHANGE ORDER NO. 2 WITH K.J. WOODS CONSTRUCTION, INC., FOR THE WATER LINE REPLACEMENT BEACH ST., UNION ST., LINCOLN ST. PROJECT, NO. WA-25-14834, IN THE AMOUNT OF $388,000 FROM THE WATER ENTERPRISE FUND FOR A REVISED TOTAL CONTRACT AMOUNT OF $5,366,726.75; & AUTHORIZING A $210,000 BUDGET APPROPRIATION FROM THE WATER ENTERPRISE FUND [0720] TO BUDGET ACCOUNT 0720-913-7831-14834

10.e AUTHORIZE INCREASE OF OPEN PURCHASE ORDERS WITH PAJARO VALLEY FABRICATION, INC, ARATA EQUIPMENT COMPANY & FASTENAL COMPANY (Recommended by Interim Public Works & Utilities Director Green) 163
RESOLUTION AUTHORIZING THE INCREASE OF OPEN PURCHASE ORDERS WITH PAJARO VALLEY FABRICATION, INC., ARATA EQUIPMENT COMPANY & FASTENAL COMPANY BY $50,000.01, IN AN AMOUNT NOT TO EXCEED $150,000 EACH TO FACILITATE PURCHASES $10,000 & SMALLER

10.f APPROVE SOLE SOURCE PURCHASE WITH ESRI, INC., FOR 167

PURCHASE OF GEOGRAPHIC INFORMATION SYSTEMS SOFTWARE (Recommended by I.T. Director Gill)
RESOLUTION APPROVING SOLE SOURCE PURCHASE WITH ENVIRONMENTAL SYSTEMS RESEARCH INSTITUTE (ESRI), INC., FOR THE PURCHASE OF GEOGRAPHIC INFORMATION SYSTEMS SOFTWARE, IN AN AMOUNT NOT TO EXCEED $180,900; & AUTHORIZING CITY MANAGER TO EXECUTE A SERVICES & PURCHASING AGREEMENT (FUNDED FROM 285-7226 IT SOFTWARE FUND)

10.g APPROVE CONTRACT WITH SANTA CRUZ COUNTY SHERIFF FOR SANE PROGRAM AGREEMENT, NOT TO EXCEED $119,295 FY 26-27 (Recommended by Police Chief Shab) 179
RESOLUTION APPROVING & AUTHORIZING THE CITY MANAGER TO SIGN THE SEXUAL ASSAULT NURSE EXAMINER'S PROGRAM REVENUE CONTRIBUTION AMENDMENT TO AGREEMENT FOR FY 26/27, IN THE AMOUNT OF $119,295

10.h AUTHORIZE FY 25-26 CONTRACT WITH COUNTY OF SANTA CRUZ FOR MENTAL HEALTH LIAISON, NOT TO EXCEED $102,233 (Recommended by Police Chief Shab) 185
RESOLUTION APPROVING A CONTRACT WITH THE COUNTY OF SANTA CRUZ HEALTH SERVICES AGENCY FOR ONE (1) MENTAL HEALTH LIAISON TO PARTNER WITH THE WATSONVILLE POLICE DEPARTMENT FOR FY25-26, IN AN AMOUNT NOT TO EXCEED $102,233.00

10.i RESOLUTION DECLARING SUPPORT FOR CALIFORNIA CITIES WEEK, APRIL 19 - 25, 2026 199
RESOLUTION DECLARING SUPPORT FOR CALIFORNIA CITIES WEEK, APRIL 19 THROUGH APRIL 25, 2026

10.j ADOPT THE SANTA CRUZ COUNTY MULTI-JURISDICTIONAL MITIGATION PLAN 2025 UPDATE (Recommended by Interim Public Works & Utilities Director Green) 202
RESOLUTION ADOPTING THE SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN 2025 UPDATE (VOLUME 1 & VOLUME 2)

*10.k APPOINT MARTHA VEGA TO PLANNING COMMISSION *1160*
RESOLUTION APPOINTING MARTHA VEGA TO THE PLANNING COMMISSION

11. ITEMS REMOVED FROM CONSENT AGENDA

12. REPORTS TO COUNCIL -- No Action Required

12.a CITY MANAGER'S UPDATE REPORT

13. PUBLIC HEARINGS, ORDINANCES, & APPEALS

13.a ORDINANCE AMENDING CHAPTER 14-16 (DISTRICT REGULATIONS) OF 1165

TITLE 14 (ZONING) OF THE WATSONVILLE MUNICIPAL CODE TO CONDITIONALLY PERMIT COMMERCIAL USES ON PARCELS ZONED PUBLIC FACILITIES (PF) & LOCATED IN THE DOWNTOWN WATSONVILLE SPECIFIC PLAN AREA

1) Staff Report by Community Development Director Orbach
2) City Council Clarifying & Technical Questions
3) Public Comments
4) Motion
5) City Council Deliberation on Motion
6) By Motion, Introduce for First Reading, by Title Only, Waiving the Full Reading of the Text, an Ordinance Amending Chapter 14-16 (District Regulations) Within Title 14 (Zoning) of the Watsonville Municipal Code to Conditionally Permit Commercial Uses on Parcels Zoned Public Facilities (PF) & Located in the Downtown Watsonville Specific Plan Area; & Finding the Action Exempt From Review Under the California Environmental Quality Act (CEQA) Pursuant To CEQA Guidelines Section 15061(B)(3)

14. EMERGENCY ITEMS ADDED TO AGENDA

15. REQUESTS & SCHEDULING FUTURE AGENDA ITEMS

16. ADJOURNMENT

This agenda was posted in accordance with the California Ralph M. Brown Act. The agenda packet can be accessed on the City of Watsonville website at https://watsonville.gov/2123/City-Council-Agendas-Minutes and is available for public inspection in the City Clerk's Office (275 Main Street, 4th Floor) during normal business hours. Any materials related to an item on this Agenda submitted to the Council after the distribution of the agenda packet will be made available to the public in accordance with Government Section 54957.5.

Public comments received three (3) hours or more before the meeting will be included in the online agenda packet before the meeting starts. All comments received less than three (3) hours, during the meeting, or after the conclusion of the meeting will be uploaded to the agenda packet as soon as possible, depending on staff availability.

CITY OF WATSONVILLE

CITY BUILDING FACILITY ASSESSMENT STUDY

February 2023



BUILDING FACILITY ASSESSMENT STUDY

- CITY INVESTMENT PRIORITIZATION – FACILITIES (CAPITAL REQUESTS)
- 2022 CITY HIRED KPA GROUP
- 2023 STUDY COMPLETED
- 18 FACILITIES

BUILDING FACILITY ASSESSMENT STUDY

CITY FACILITIES EVALUATED

- Beach Street Parking Garage
- Callaghan Park Cultural Center
- City Hall
- Fire Station 1
- Fire Station 2
- Hoularis Youth Center
- Marinovich Community Center
- Municipal Service Center
- PCS One Stop
- Pinto Lake City Park
- Police Activities League
- Ramsay Park Family Center
- Watsonville Senior
- YWCA Daycare

BUILDING FACILITY ASSESSMENT STUDY

PURPOSE: COMPRENHENSIVE EVALUATION OF FACILITY CONDITIONS

- SITE
- BUILDING EXTERIOR /INTERIOR/STRUCTURE
- ADA
- MECHANICAL
- ELECTRICAL & PLUMBING (MEP)

BUILDING FACILITY ASSESSMENT STUDY

PROCESS

- MEETINGS WITH STAFF/MANAGEMENT
- SITE VISITS
- CHECKLIST
- PHOTOS
- SPACE SURVEYS
- COST ESTIMATES

BUILDING FACILITY ASSESSMENT STUDY

FINDINGS

- EVIDENCE OF AGE & WEAR OF INTERIOR
- UPDATE OF MECHANICAL, ELECTRICAL & PLUMBING (MEP)
- MOST PARKING LOTS REQUIRE RESURFACING & STRIPING
- MINOR STRUCTURAL CRACKING AT SOME FACILITIES
- ALL CITY BUILDING REQUIRE MODERATE IMPROVEMENTS TO MAINTAIN VALUE, OPERATION & MEET PUBLIC NEEDS

BUILDING FACILITY ASSESSMENT STUDY

COST ESTIMATE OVERVIEW
2023

Facility Name	Deferred Maintenance
Beach Street Parking Garage	$ 3,038,875
Callaghan Park Cultural Center	$ 2,042,400
City Hall	$ 8,375,450
Fire Station 1	$ 5,808,650
Fire Station 2	$ 6,290,500
Gene Hoularis & Waldo Rodriguez Youth Center	$ 4,899,575
Marinovich Community Center	$ 3,290,725
Municipal Service Center	$ 18,927,850
Pinto Lake City Park	$ 3,642,625
Police Activities League	$ 1,132,750
Police Station	$ 8,029,300
Ramsay Park Family Center	$ 2,591,525
Rec Department One Stop	$ 3,047,500
Watsonville Senior Center	$ 4,160,700
YWCA State Preschool	$ 1,177,025
TOTAL	$ 76,455,450

FACILITIES INVESTMENTS TO DATE

SENIOR CENTER IMPROVEMENTS	**~ $450K**
FIRE STATION 1 IMPROVEMENTS	**~ $640K**
MSC ADMIN BUILDING DESIGN (IN PROCESS)	**~ $1.2M**
RAMSAY PARK FAMILY CENTER (IN PROCESS)	**~ $1.08M**

FUTURE PLANNING/FUNDING PURSUITS

FIRE STATION 2:
SEEK GRANT /FEDERAL FUNDING

PINTO LAKE PARK:
FUTURE PARKS MASTER PLAN

MSC FACILITY SITE IMPROVEMENTS:
CURRENTLY IN PRELIMINARY DESIGN, FUNDING NEEDED

BEACH ST. PARKING GARAGE:
POSSIBLE METRO HOUSING PROJECT

CITY HALL:
EXPLORE PUBLIC/PRIVATE PARTNERSHIP

CITY OF WATSONVILLE

CITY BUILDING FACILITY ASSESSMENT STUDY

Watsonville

PARKS & COMMUNITY SERVICES

CITY SPECIAL EVENTS BUDGET

PARKS & COMMUNITY SERVICES DEPARTMENT

VALUE OF OUR EVENTS

Annual Attendance: 71,150

- Economic development impact
- Aligned with Downtown Specific Plan
- Positively activate public spaces
- Family-friendly experiences
- Offer accessibility & inclusion (low cost/free)
- Involvement of non -profits, local art organizations & businesses: 350+ annually
- Promote cultural celebration & expression
- Create cross-cultural connections
- Build community & civic pride
- Support local artists & makers

Thank you for this amazing event. My family and I truly enjoyed it
-Instagram comment

My family and I had a great time!
-Instagram comment

Honestly, the city didn't disappoint - it exceeded expectations!
-Instagram comment

2021-27 EVENTS

EXPENSES & REVENUE



SERVICES & PERSONNEL COSTS



BUDGET NET EXPENSE

2025-26



25.26 Budget Total Variance	$68,601

2026-27



26.27 Budget Total Variance	$125,232

SPECIAL EVENTS PROJECTED BUDGET - FY 26-27

Event	Contract Services/Non - PCS Personnel	Materials	Total Costs	Personnel Costs	Revenue	Net Cost	Attendance
Egg Hunt Eggstravaganza		$900	$1,673	$773	-	**$1,673**	2,000
Wine Walk	$3,000	$10,000	$13,618	$618	$ (18,000)	**$ (4,382)**	350
Spirit of Watsonville Parade	$20,707	$2,500	$41,920	$18,713	$ (7,500)	**$34,420**	9,100
Music in the Plaza	$24,000		$24,000		$ (5,000)	**$19,000**	900
July Is PMLB (Movies, Etc.)	$1,000	$100	$2,501	$1,401	-	**$2,501**	200
Strawberry Festival	$186,493	$14,166	$222,112	$21,453	$ (155,194)	**$66,918**	53,500
Candy Crawl	$200	$178	$888	$510	-	**$888**	1,000
Plaza/Tree/Pole Lighting	$37,508	$2,906	$41,731	$1,317	$ (6,989)	**$34,742**	130
Noche de Brillo*	$23,000	$15,730	$50,641	$11,911	$ (19,776)	**$30,865**	4,000
Other Expenses/Fees	$4,000	$2,400	$6,607	$207	$ (2,500)	**$4,107**	-
Totals	**$299,908**	**$48,880**	**$405,691**	**$56,903**	**$(214,959)**	**$190,732**	**71,180**

26.27 Total Net Cost	**$190,732**

*Not included in 26.27 budget

COMMUNITY EVENT SPONSORSHIPS

Event	Attendance	FY 25 -26
Salvation Army | Backpack Giveaway	107	$560
Art on Wheels	946	$9,519
Mexican Independence Day	1,800	$10,838
Tobera Project | Filipino American History Festival	1,339	$1,500
Veterans Day Parade	550	$167
Peace and Unity Coalition	*	$1,417
Cinco de Mayo Festival*	2,600*	$10,000

*Unknown, estimated fewer than 100

**Projected

Allotted Amount	Projected Amount Awarded
$35,000	$35,000

NET COSTS PER EVENT

Event	FY 26 -27	FY 25 -26
Egg Hunt Eggstravaganza	$1,673	$1,650
Wine Walk	$ (4,382)	$ (6,335)
Spirit of Watsonville Parade	$34,420	$27,475
Music in the Plaza	$19,000	$23,000
July Is PMLB (Movies, Etc.)	$2,501	$2,460
Strawberry Festival	$66,918	$62,193
Candy Crawl	$888	$873
Plaza/Tree/Pole Lighting	$34,742	$34,705
Noche de Brillo	$30,865	$64,018
Other Expenses/Fees	$4,107	$ (10,938)
TOTAL	$190,732	$199,101

OPTION A: INCREASE BUDGET BY $125,232

Keep	Remove
Egg Hunt Eggstravaganza	
Wine Walk	
Spirit of Watsonville Parade	
Music in the Plaza	
July Is PMLB (Movies, Etc.)	
Strawberry Festival	
Candy Crawl	
Plaza/Tree/Pole Lighting	
Noche de Brillo	

OPTION B: INCREASE BUDGET BY $75,367

Keep	Remove
Egg Hunt Eggstravaganza	Music in the Plaza
Wine Walk	Noche de Brillo
Spirit of Watsonville Parade	
July Is PMLB (Movies, Etc.)	
Strawberry Festival	
Candy Crawl	
Plaza/Tree/Pole Lighting	

OPTION C: INCREASE BUDGET BY $58,314

Keep	Remove
Egg Hunt Eggstravaganza	Strawberry Festival
Wine Walk	
Spirit of Watsonville Parade	
Music in the Plaza	
July Is PMLB (Movies, Etc.)	
Candy Crawl	
Plaza/Tree/Pole Lighting	
Noche de Brillo	

OPTION D: INCREASE BUDGET BY $40,947

Keep	Remove
Egg Hunt Eggstravaganza	Spirit of Watsonville Parade
Wine Walk	Music in the Plaza
July Is PMLB (Movies, Etc.)	Noche de Brillo
Strawberry Festival	
Candy Crawl	
Plaza/Tree/Pole Lighting	

OPTION E: NO INCREASE IN BUDGET

Keep	Remove
Wine Walk	Egg Hunt Eggstravaganza
Spirit of Watsonville Parade	Music in the Plaza
Plaza/Tree/Pole Lighting	July Is PMLB (Movies, Etc.)
	Strawberry Festival
	Candy Crawl
	Noche de Brillo

SCENARIOS TO ADDRESS VARIANCE

Option A Increase budget by **$125,232**
Keep
Egg Hunt Eggstravaganza
Wine Walk
Spirit of Watsonville Parade
Music in the Plaza
July Is PMLB (Movies, Etc.)
Strawberry Festival
Candy Crawl
Plaza/ Tree/ Pole Lighting
Remove
None

Option B Increase budget by **$75,367**
Keep
Egg Hunt Eggstravaganza
Wine Walk
Spirit of Watsonville Parade
July Is PMLB (Movies, Etc.)
Strawberry Festival
Candy Crawl
Remove
Music in the Plaza
Noche de Brillo

Option C Increase budget by **$58,314**
Keep
Egg Hunt Eggstravaganza
Wine Walk
Spirit of Watsonville Parade
Music in the Plaza
July Is PMLB (Movies, Etc.)
Candy Crawl
Plaza/ Tree/ Pole Lighting
Remove
Strawberry Festival

Option D Increase budget by **$40,947**
Keep
Egg Hunt Eggstravaganza
Wine Walk
July Is PMLB (Movies, Etc.)
Strawberry Festival
Candy Crawl
Plaza/ Tree/ Pole
Remove
Spirit of Watsonville Parade
Music in the Plaza
Noche de Brillo

Option E No Increase in budget
Keep
Wine Walk
Spirit of Watsonville Parade
Plaza/ Tree/ Pole
Remove
Egg Hunt Eggstravaganza
Music in the Plaza
Strawberry Festival
July Is PMLB (Movies, Etc.)
Candy Crawl
Noche de Brillo

QUESTIONS & COMMENTS

CITY SPECIAL EVENTS - FY 26-27 PROJECTED BUDGET

PARKS & COMMUNITY SERVICES DEPARTMENT

Event	Attendance	Personnel Costs	Materials	Contract Services/Non-PCS Personnel	Total Costs	Revenue	Net Cost	Materials & Services
Egg Hunt Eggstravaganza	2,000	$773	$900		$1,673	-	**$1,673**	Eggs for hunts, minimal supplies, personnel
Wine Walk	350	$618	$10,000	$3,000	$13,618	$ (18,000)	**$ (4,382)**	Wine/Beer, Sponsored Swag (wineglasses, bags), Event Passport, ABC Permits, Traffic Services, PV Chamber Services
Spirit of Watsonville Parade	9,100	$18,713	$2,500	$20,707	$41,920	$ (7,500)	**$34,420**	PD, Traffic Team & equipment rentals (e.g., traffic boards), Trash services, Parks Teammates), Restroom rentals, Materials (e.g., vehicle banners), Insurance
Music in the Plaza	900			$24,000	$24,000	$ (5,000)	**$19,000**	Stage and sound management, musical acts
July Is PMLB (Movies, Etc.)	200	$1,401	$100	$1,000	$2,501	-	**$2,501**	Movie Licensing, movies
Strawberry Festival	53,500	$21,453	$14,166	$186,493	$222,112	$ (155,194)	**$66,918**	PD, Traffic Team & equipment rentals (traffic boards, water barriers, forklifts), Trash services, Security, Infrastructure (Electrical, Stages, Tents, Fencing, Toilets & Handwashing), Insurance, Marketing
Candy Crawl	1,000	$510	$178	$200	$888	-	**$888**	Traffic Services, Info. booth supplies
Plaza/Tree/Pole Lighting	130	$1,317	$2,906	$37,508	$41,731	$ (6,989)	**$34,742**	Plaza Lighting, Tree Lighting, Equipment Rentals, Traffic Team
Noche de Brillo*	4,000	$11,911	$15,730	$23,000	$50,641	$ (19,776)	**$30,865**	PD, Traffic Team & equipment rentals (water barriers, forklifts), Trash & Street Sweep services, Entertainment, Insurance, Marketing
Other Expenses	-	$207	$2,400	$4,000	$6,607	$ (2,500)	**$4,107**	
Totals	**71,180**	**$56,903**	**$48,880**	**$299,908**	**$405,691**	**$(214,959)**	**$190,732**	

*Not included in 26.27 budget

CITY OF WATSONVILLE
CHECK REGISTER FOR 3/18/2026 TO 4/9/2026

Fund #	Vendor Name	Amount
0130	PAYROLL FUND	$1,860,165.51
0150	GENERAL FUND	$741,832.10
0201	MEASURE R FUND	$269,405.29
0202	RDA OBLIGATION FUND	$95.37
0204	RDA HOUSING FUND	$201.28
0215	RELOCATION FUND	$1,064.22
0221	AFFORDABLE HOUSING FUND	$1,605.50
0246	CIVIC CENTER FUND	$38,012.98
0250	LIBRARY FUND	$101,681.31
0260	SPECIAL GRANT FUND	$1,563,750.36
0305	GAS TAX FUND	$37,279.18
0306	SB-1 GAS TAX FUND	$82,357.99
0309	PARKING FUND	$12,571.74
0310	MEASURE Y FUND	$119,046.16
0312	MEASURE D FUND	$278.64
0354	LLMAD FUND	$42.92
0360	LLMAD BAY BREEZE SPECIAL	$1,967.00
0510	DEBIT SERVICE FUND	$1,242,205.96
0710	WASTE WATER FUND	$874,717.10
0720	WATER FUND	$823,527.47
0730	AIRPORT FUND	$159,642.09
0740	SOLID WASTE FUND	$175,274.70
0741	LANDFILL CLOSURE FUND	$570.94
0760	MSC INTERNAL SERVICE FUND	$104,649.06
0780	WORKER'S COMPENSATION	$3,326.46
0787	HEALTH INSURANCE FUND	$985,087.61
0790	INFORMATION AND	$10,499.28
0825	NARCOTICS FUND	$5,827.59

Total	**Total**	**$9,216,685.81**

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0130	AFLAC	78177	4/3/2026	138729	Payroll Run 1 - Warrant 260403	$7,161.65
		77895	3/20/2026	138163	Payroll Run 1 - Warrant 260320	$7,293.15
	BENEFIT COORDINATORS CORPORATION	77896	3/20/2026	138150	Payroll Run 1 - Warrant 260320	$957.87
		78178	4/3/2026	138713	Payroll Run 1 - Warrant 260403	$4,073.60
	CA STATE DISBURSEMENT UNIT	78176	4/3/2026	138731	Payroll Run 1 - Warrant 260403	$5,535.96
		77894	3/20/2026	138165	Payroll Run 1 - Warrant 260320	$5,787.46
	CITY EMPLOYEES ASSOCIATION	78179	4/3/2026	138714	Payroll Run 1 - Warrant 260403	$420.00
	COLONIAL LIFE & ACCIDENT INS	77897	3/20/2026	138151	Payroll Run 1 - Warrant 260320	$71.35
		78180	4/3/2026	138715	Payroll Run 1 - Warrant 260403	$71.35
	COUNTY OF SANTA CRUZ-SHERIFF-CORONER	77898	3/20/2026	138152	Payroll Run 1 - Warrant 260320	$50.00
		78181	4/3/2026	138716	Payroll Run 1 - Warrant 260403	$50.00
	COURT-ORDERED DEBT COLLECTIONS	77899	3/20/2026	138155	Payroll Run 1 - Warrant 260320	$20.00
		78182	4/3/2026	138719	Payroll Run 1 - Warrant 260403	$20.00
	MASSMUTUAL FINANCIAL GROUP	77900	3/20/2026	138153	Payroll Run 1 - Warrant 260320	$3,062.02
		78183	4/3/2026	138717	Payroll Run 1 - Warrant 260403	$3,062.02
	MISSIONSQUARE RETIREMENT	77901	3/20/2026	138154	Payroll Run 1 - Warrant 260320	$72,594.55
		78171	4/3/2026	138797	Payroll Run 1 - Warrant 260403	$5,543.42
		78170	4/3/2026	138718	Payroll Run 1 - Warrant 260403	$72,518.03
		77902	3/20/2026	138334	Payroll Run 1 - Warrant 260320	$5,763.25
	OPERATING ENGINEERS LOCAL #3	78184	4/3/2026	138722	Payroll Run 1 - Warrant 260403	$5,688.00
	PRE-PAID LEGAL SERVICES INC.	78185	4/3/2026	138732	Payroll Run 1 - Warrant 260403	$51.80
	PROF FIRE FIGHTERS-WATSONVILLE	78186	4/3/2026	138723	Payroll Run 1 - Warrant 260403	$2,635.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0130	PROF FIRE FIGHTERS-	77903	3/20/2026	138158	Payroll Run 1 - Warrant 260320	$2,635.00
	PUBLIC EMP RETIREMENT SYSTEM	78187	4/3/2026	138724	Payroll Run 1 - Warrant 260403	$353,948.39
		77891	3/20/2026	138159	Payroll Run 1 - Warrant 260320	$356,188.16
	SEIU LOCAL 521	78189	4/3/2026	138800	Payroll Run 1 - Warrant 260403	$25.00
		78188	4/3/2026	138725	Payroll Run 1 - Warrant 260403	$1,089.78
		77905	3/20/2026	138336	Payroll Run 1 - Warrant 260320	$25.00
		77904	3/20/2026	138160	Payroll Run 1 - Warrant 260320	$1,125.86
	UPEC	78190	4/3/2026	138720	Payroll Run 1 - Warrant 260403	$1,286.25
		77906	3/20/2026	138156	Payroll Run 1 - Warrant 260320	$1,286.25
	WAGEWORKS INC	78191	4/3/2026	138730	Payroll Run 1 - Warrant 260403	$4,418.38
		77907	3/20/2026	138164	Payroll Run 1 - Warrant 260320	$4,495.30
	WASHINGTON STATE COUNCIL OF FIRE FIGHTERS EMPLOYEE	78172	4/3/2026	138721	Payroll Run 1 - Warrant 260403	$1,661.76
		77890	3/20/2026	138157	Payroll Run 1 - Warrant 260320	$1,661.76
	WATSONVILLE POLICE ASSOCIATION	78192	4/3/2026	138727	Payroll Run 1 - Warrant 260403	$6,361.00
	WIRE TRANSFER-IRS	78175	4/3/2026	138728	Payroll Run 1 - Warrant 260403	$373,507.41
		77893	3/20/2026	138162	Payroll Run 1 - Warrant 260320	$388,705.07
	WIRE TRANSFER-STATE OF CALIFORNIA	78174	4/3/2026	138726	Payroll Run 1 - Warrant 260403	$77,820.39
		77892	3/20/2026	138161	Payroll Run 1 - Warrant 260320	$81,494.27
	Fund Total					$1,860,165.51
0150	A-1 JANITORIAL SERVICE	77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$622.87
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$622.87

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	A-1 JANITORIAL SERVICE	77910	3/24/2026	9349	MONTHLY CLEANING FOR RESTROOMS	$1,325.00
		77910	3/24/2026	9350	JANITORIAL SERVICE	$1,075.00
	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$6.10
		78137	4/1/2026	2/28/26	PURCHASES	$93.17
		78137	4/1/2026	2/28/26	PURCHASES	$24.11
		78137	4/1/2026	2/28/26	PURCHASES	$36.21
		78137	4/1/2026	2/28/26	PURCHASES	$29.59
		78137	4/1/2026	2/28/26	PURCHASES	$41.68
		78137	4/1/2026	2/28/26	PURCHASES	$17.54
		78137	4/1/2026	2/28/26	PURCHASES	$3.16
		78137	4/1/2026	2/28/26	PURCHASES	$21.93
		78137	4/1/2026	2/28/26	PURCHASES	$19.73
		78137	4/1/2026	2/28/26	PURCHASES	$21.93
		78137	4/1/2026	2/28/26	PURCHASES	$21.94
		78137	4/1/2026	2/28/26	PURCHASES	$31.79
		78137	4/1/2026	2/28/26	PURCHASES	$38.40
		78137	4/1/2026	2/28/26	PURCHASES	$42.77
		78137	4/1/2026	2/28/26	PURCHASES	$27.43
		78137	4/1/2026	2/28/26	PURCHASES	$31.27
		77868	3/18/2026	1/31/26	PURCHASES	$48.24
		77868	3/18/2026	1/31/26	PURCHASES	$18.65
		77868	3/18/2026	1/31/26	PURCHASES	$109.74

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	ACE HARDWARE	77868	3/18/2026	1/31/26	PURCHASES	$21.94
		77868	3/18/2026	1/31/26	PURCHASES	$26.33
		77868	3/18/2026	1/31/26	PURCHASES	$30.92
		77868	3/18/2026	1/31/26	PURCHASES	$17.54
		77868	3/18/2026	1/31/26	PURCHASES	$43.89
		77868	3/18/2026	1/31/26	PURCHASES	$16.43
		77868	3/18/2026	1/31/26	PURCHASES	$35.09
		77868	3/18/2026	1/31/26	PURCHASES	$98.74
		77868	3/18/2026	1/31/26	PURCHASES	$28.51
		77868	3/18/2026	1/31/26	PURCHASES	$16.45
		77868	3/18/2026	1/31/26	PURCHASES	$10.96
		77868	3/18/2026	1/31/26	PURCHASES	$10.96
		77868	3/18/2026	1/31/26	PURCHASES	$10.96
		77868	3/18/2026	1/31/26	PURCHASES	$109.74
		77868	3/18/2026	1/31/26	PURCHASES	$2.85
		77868	3/18/2026	1/31/26	PURCHASES	$8.77
	AIR UNLIMITED	77912	3/24/2026	379873	INV#379873 TRAFFIC OPS PROPANE 18 GAL ON 3/5/2026	$191.77
	AIRTEC SERVICE,INC	77914	3/24/2026	36310	CITYWIDE HVAC MAINTENANCE	$969.33
		77914	3/24/2026	36490	CITYWIDE HVAC MAINTENANCE	$673.20
		77914	3/24/2026	36698	CITYWIDE HVAC MAINTENANCE	$1,182.18
		77914	3/24/2026	36956	INSTALL INDUCE DRAFT MOTOR ASSEMBLY	$1,253.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	AMAZON CAPITAL SERVICES	77916	3/24/2026	16N9-NYLX-7D3G	CIRCULATION SUPPLIES	$60.24
		77916	3/24/2026	1YVP-P6Y7-D1KH	COMPUTER SUPPLIES	$1,265.03
		77916	3/24/2026	19FV-NK6C-G7RL	TECH SUPPLIES	$129.46
	ANAHI CORTEZ - JACOBO	77918	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	ANGEL O. MAGANA	77919	3/24/2026	49	CUSTODIAL SERVICES AT WRC AND	$2,350.00
	ANTONETTE WOOD	77869	3/18/2026	4983	CATERING FOR COUNCIL MEETING DINNER	$658.50
	ARRIAGA, JOHN	77923	3/24/2026	8327	State Advocacy and Consulting	$1,750.00
	AT&T	77870	3/18/2026	292375992-2/24/26	ACCT 292375992-2/24/26	$260.19
	AT&T MOBILITY LLC	77925	3/24/2026	87322287772X03102026	CELL & DATA CHARGES PD/FIRE FR 02/03/26-03/02/26	$28.95
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$264.36
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$30.37
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$72.48
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$144.58
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$43.74
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$84.33
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$476.10
		77924	3/24/2026	87320260154X03102026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$43.21

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$673.78
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$378.07
	AXON ENTERPRISE, INC.	77926	3/24/2026	INUS401587	BODY WORN CAMERAS AND TASER PU	$271,727.43
	BEAR ELECTRICAL SOLUTIONS, LLC	77927	3/24/2026	10132	2023-2026 STREET LIGHT MAINTEN	$3,631.47
	BRODART CO.	77931	3/24/2026	BRO033126-755922	BOOKS	$5,249.68
	BURKE, WILLIAMS & SORENSEN, LLP	77932	3/24/2026	360856	CITY ATTORNEY SERVICES	$6,496.00
		77932	3/24/2026	360853	CITY ATTORNEY SERVICES	$2,324.00
		77932	3/24/2026	360854	CITY ATTORNEY SERVICES	$13,152.00
		77932	3/24/2026	360869	CITY ATTORNEY SERVICES	$234.50
		77932	3/24/2026	360866	CITY ATTORNEY SERVICES	$134.00
		77932	3/24/2026	360860	CITY ATTORNEY SERVICES	$87.95
		77932	3/24/2026	360851	CITY ATTORNEY SERVICES	$402.00
		77932	3/24/2026	360862	CITY ATTORNEY SERVICES	$604.50
		77932	3/24/2026	360867	CITY ATTORNEY SERVICES	$670.00
		77932	3/24/2026	360846	CITY ATTORNEY SERVICES	$732.00
		77932	3/24/2026	360846	CITY ATTORNEY SERVICES	$1,586.00
		77932	3/24/2026	360848	CITY ATTORNEY SERVICES	$1,288.00
		77932	3/24/2026	360843	CITY ATTORNEY SERVICES	$507.36
		77932	3/24/2026	360843	CITY ATTORNEY SERVICES	$5,768.00
		77932	3/24/2026	360852	CITY ATTORNEY SERVICES	$616.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	BURKE, WILLIAMS & SORENSEN, LLP	77932	3/24/2026	360857	CITY ATTORNEY SERVICES	$837.50
		77932	3/24/2026	360858	CITY ATTORNEY SERVICES	$2,244.85
		77932	3/24/2026	360858	CITY ATTORNEY SERVICES	$1,204.00
		77932	3/24/2026	360858	CITY ATTORNEY SERVICES	$12,869.00
		77932	3/24/2026	360863	CITY ATTORNEY SERVICES	$469.00
		77932	3/24/2026	360864	CITY ATTORNEY SERVICES	$2,412.00
		77932	3/24/2026	360849	CITY ATTORNEY SERVICES	$10,519.00
		77932	3/24/2026	360855	CITY ATTORNEY SERVICES	$1,507.50
	CAMILA ROCHA	77938	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	CAPITAL EDGE ADVOCACY, INC.	77940	3/24/2026	26-40	Federal Legislative Advocacy a	$1,000.00
	CDW GOVERNMENT, INC.	77945	3/24/2026	AI47N2V	DELL 24" MONITORS FOR PD CUBICLE	$476.42
		77945	3/24/2026	AH2QA9J	BLUEBEAM RENEWALS FOR VARIOUS DEPTS	$2,528.58
		77945	3/24/2026	AH2QA9J	BLUEBEAM RENEWALS FOR VARIOUS DEPTS	$421.43
		77945	3/24/2026	AH2QA9J	BLUEBEAM RENEWALS FOR VARIOUS DEPTS	$421.43
	CHARTER COMMUNICATIONS	78108	3/25/2026	170045401031426 -3/14	INTERNET	$317.49
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$47.12
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$240.56
	CITYWIDE CART SAVERS LLC	77947	3/24/2026	2943	Citywide Shopping Cart Removal	$900.00
	CLAIRE LAUGHLIN CONSULTING	77948	3/24/2026	1414	LEADERSHIP RETREAT	$4,425.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	CRISTINA E. NOLASCO	77954	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	CRUZIO/THE INTERNET STORE INC.	78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$74.95
		78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$74.95
		78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$74.95
		78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$37.48
	CUMMING MANAGEMENT GROUP	77955	3/24/2026	186059	ON-CALL LABOR COMPLIANCE SERVI	$2,085.00
	DEPARTMENT OF CONSERVATION	77961	3/24/2026	030926	DEPARTMENT OF CONSERVATION - ACCOUNTING OFFICE (SM	$1,810.80
	DEPT OF HOUSING & COMMUNITY DEVELOPMENT	77962	3/24/2026	HCD_PAL 2026-27	REGISTRATION RENEWAL	$249.00
	DUTRA, JIMMY	78195	4/8/2026	TRVL - 3/26/26	COUNCIL-COMMUNITY LEADERSHIP VISIT SPRING 2026	$19.60
		78109	3/25/2026	TRVL FINAL 3/15/26	COUNCIL-NLC CONGRESSIONAL CITY CONFERENCE	$157.10
		78109	3/25/2026	TRVL FINAL 3/15/26	COUNCIL-NLC CONGRESSIONAL CITY CONFERENCE	$95.12
	EMILY RODRIGUEZ	77968	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	FIRST ALARM, INC.	78111	3/25/2026	923816	ALARM MONITORING	$32.85
		78111	3/25/2026	942045	ALARM MONITORING	$32.85
	GIOVANNI MELGOZA	77981	3/24/2026	TAC Q2 STIPEND	TAC Q2 STIPEND	$150.00
	GRIFFIN STRUCTURES, INC.	77990	3/24/2026	GSI-WRPCM-54	Project Managment Services for	$10,540.14
	GROCERY OUTLET	77991	3/24/2026	0108-3/6/26	NUCLEUS WORKSHOP SNACKS	$40.76
		77991	3/24/2026	0242-3/5/26	NUCLEUS WORKSHOP SUPPLIES	$41.51
		77991	3/24/2026	0271-3/3/26	NUCLEUS WORKSHOP SNACKS	$77.65
		77991	3/24/2026	3/12/26	NUCLEUS WORKSHOP	$55.74

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	GUILLERMO GARCIA	78146	4/1/2026	01600	SERVICE GYM EQUIPT AT STATION 1	$570.00
	HARRIS & ASSOCIATES INC.	77993	3/24/2026	71431	ON-CALL PROFESSIONAL ENGINEERI	$15,571.00
	HOPE SERVICES, INC.	77994	3/24/2026	S179648	LITTER REMOVAL FROM CITY ROADW	$5,004.00
	INGRAM LIBRARY SERVICES	77995	3/24/2026	3/1/26	BOOKS	$671.96
	INNOVATIVE INTERFACES INC.	77874	3/18/2026	INV-INC41190	VEGA PREMIUM DISCOVER 3/1/26-2/28/27	$17,540.30
	ISABELLA NICOLE ALVARADO	77998	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	K & D LANDSCAPING INC.	78002	3/24/2026	20017	2023-2026 Landscape Maintenanc	$8,062.67
		78002	3/24/2026	20017	2023-2026 Landscape Maintenanc	$4,190.00
	LEHR	78008	3/24/2026	SI129417	OUTFITTING OF POLICE VEHICLE	$22,650.33
		78008	3/24/2026	SI130013	OUTFITTING OF PATROL VEHICLE	$22,650.33
	LEILAH I. CHAVEZ	78009	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	LIBRARY IDEAS	78012	3/24/2026	124919	VOX BOOKS	$242.61
	LIEBERT CASSIDY WHITMORE	78013	3/24/2026	312061	LIBRARY SUBSCRIPTION	$900.00
	MID VALLEY SUPPLY	78024	3/24/2026	3/3/2026	PURCHASES	$232.50
		78024	3/24/2026	3/3/2026	PURCHASES	$371.26
		78024	3/24/2026	3/3/2026	PURCHASES	$1,087.17
		78024	3/24/2026	3/3/2026	PURCHASES	$756.62
		78024	3/24/2026	3/3/2026	PURCHASES	$389.30
	MIDWEST TAPE	78025	3/24/2026	3/2/26	BOOKS	$942.07
	MISSION LINEN SUPPLY	77879	3/18/2026	322220-2/28/26	UNIFORM RENTAL SERVICES	$191.52
	MONTESINO, EDUARDO	78206	4/8/2026	TRVL-4/21/26	COUNCIL-CITY LEADERS SUMMIT 2026	$216.50

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	MONTESINO, EDUARDO	78113	3/25/2026	TRVL FINAL - 3/15/26	COUNCIL-NLC CONGRESSIONAL CITY CONFERENCE	$190.33
	NAOMI BRUNELLI	78031	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	NEW IMAGE LANDSCAPE COMPANY	78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$73.79
		78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$147.06
	OVERDRIVE	78036	3/24/2026	00910SV26069341	SUBSCRIPITON - CRAFTSY	$5.98
		78036	3/24/2026	00910SV26069358	SUBSCRIPTION - INDIEFLIX	$2.99
		78036	3/24/2026	00910SV26069385	SUBSCRIPTION - GCLC	$11.96
	PACIFIC CREST ENGINEERING, INC	78039	3/24/2026	16040	Ramsay Park renaissance Projec	$14,193.75
		78039	3/24/2026	15844	Ramsay Park renaissance Projec	$5,740.00
	PACIFIC GAS & ELECTRIC	78208	4/8/2026	0418334151-2-3/25/26	0418334151-2-3/25/26	$2,108.01
		78211	4/8/2026	9491368495-0-3/23/26	9491368495-0-3/23/26	$1,824.26
		78211	4/8/2026	9491368495-0-3/23/26	9491368495-0-3/23/26	$1,824.26
		78157	4/1/2026	3820804447-9-3/23/26	240 AIRPORT BLVD	$1,456.73
		78158	4/1/2026	8480030300-4-3/22/26	114 E 5TH ST	$1,424.48
		78159	4/1/2026	4829825447-4-3/23/26	HARKINS SLOUGH RD @ W END OF BRIDGE	$109.08
		78162	4/1/2026	4287605895-1-3/20/26	75 HOPE DR	$11.93
		78151	4/1/2026	5060076049-5-3/24/26	WEST BEAC ST AND MAIN	$1,460.08
		78153	4/1/2026	6718133522-4-3/22/26	6718133522-4-3/22/26	$1,836.06

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	**PACIFIC GAS & ELECTRIC**	78154	4/1/2026	0458151262-3-3/23/26	370 AIRPORT BLVD STE 100	$801.93
		78148	4/1/2026	5740377546-3-3/24/26	280 MAIN ST #A	$49.64
		78122	3/25/2026	4048670603-5-3/19/26	52 ARISTA CT	$10.09
		78123	3/25/2026	9925942904-3-3/19/26	37 DAVIS AVE	$321.80
		78125	3/25/2026	9656517006-3-3/17/26	651 OHLONE PARKWAY IRRIGATION	$15.46
		78117	3/25/2026	7523404092-3-3/16/26	7523404092-3-3/16/26	$3,620.28
		78121	3/25/2026	3653340008-5-3/19/26	201 PACIFICA BLVD	$20.51
		78043	3/24/2026	1540833758-0-3/12/26	1110 W BEACH ST	$160.67
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$975.13
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$366.73
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$249.88
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$2,719.27
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1,047.23
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$10.55
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1.45

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	PACIFIC GAS & ELECTRIC	77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$47.05
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$14.13
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1,879.07
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$839.64
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$7,034.27
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$4,018.91
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$26.28
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1.58
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1,124.31
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$30.35
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$7.69
	PAJARO VALLEY LOCK SHOP	78046	3/24/2026	139977	KEYS	$4.87
	PAJARO VALLEY PRINTING	78047	3/24/2026	50489	MONTHLY NEWSLETTER	$7,572.75
		78047	3/24/2026	50429	BUSINESS CARDS	$685.94
	PARKER, ARI	78130	3/25/2026	TRVL FINAL - 3/15/26	COUNCIL-NLC CONGRESSIONAL CITY CONFERENCE	$128.50
	POSTMASTER	78218	4/8/2026	FUN GUIDE - 2026	FUN GUIDE - SPRING/SUMMER 2026	$5,768.54
	QUENCH USA, INC.	78057	3/24/2026	INV10358210	WATER	$450.82

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	QUENCH USA, INC.	78057	3/24/2026	INV10373095	INV#INV10373095; 03/01/2026; DEPT WATER SERVICE	$69.30
	RICOH USA, INC	78062	3/24/2026	5072830060	EQUIPMENT RENTAL	$409.38
		78062	3/24/2026	5072860710	EQUIPMENT RENTAL	$39.94
		78062	3/24/2026	5072860844	EQUIPMENT RENTAL	$48.41
		78062	3/24/2026	5072860844	EQUIPMENT RENTAL	$48.41
		78062	3/24/2026	5072860844	EQUIPMENT RENTAL	$32.27
		78062	3/24/2026	5072860844	EQUIPMENT RENTAL	$32.27
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$27.72
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$1,364.33
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$26.75
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$18.15
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$31.73
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$31.73
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$21.15
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$21.15
		78062	3/24/2026	5072860944	EQUIPMENT RENTAL	$7.07
		78062	3/24/2026	5072859994	EQUIPMENT RENTAL	$75.17
		78062	3/24/2026	5072860528	EQUIPMENT RENTAL	$199.26
	RUFF RUFF PET PRODUCTS	78064	3/24/2026	3709	TUNA ROLL BAGS	$531.82
	SAFEGUARD BUSINESS SYSTEMS	78067	3/24/2026	9010158322	PRINTING	$536.13
	SALCIDO, KRISTAL	78133	3/25/2026	TRVL FINAL 3/15/26	COUNCIL-NLC CONGRESSIONAL CITY CONFERENCE	$128.50

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	SAVE MART SUPERMARKET	78071	3/24/2026	TRD-2/22/26	PURCHASES	$96.15
		78071	3/24/2026	TRD-2/22/26	PURCHASES	$111.11
	SELBERT PERKINS DESIGN INC.	78076	3/24/2026	251515	Wayfinding System Design & Imp	$1,625.00
	SHRED-IT USA	78078	3/24/2026	8013494937	MONTHLY SERVICE	$58.29
		78078	3/24/2026	8013494937	MONTHLY SERVICE	$136.13
		78078	3/24/2026	8013494937	MONTHLY SERVICE	$83.44
	SLAVIC AMERICAN CULTURAL ORGANIZATION	78220	4/8/2026	SACO DINNER 4/18	EVENT TICKET SACO ANNUAL LAMB DINNER 4/18	$50.00
		78220	4/8/2026	SACO DINNER 4/18	EVENT TICKET SACO ANNUAL LAMB DINNER 4/18	$50.00
	SOFIA IBARRA BUCIO	78080	3/24/2026	TAC Q2 Stipend	TAC Q2 STIPEND	$300.00
	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$43.43
		78134	3/25/2026	7008882191	PURCHASES	$230.24
		78134	3/25/2026	7008882191	PURCHASES	$37.23
		78134	3/25/2026	7008882191	PURCHASES	$567.30
		78134	3/25/2026	7008882191	PURCHASES	$371.82
		78134	3/25/2026	7008882191	PURCHASES	$176.36
		78134	3/25/2026	7008882191	PURCHASES	$259.95
		78134	3/25/2026	7008882191	PURCHASES	($172.63)
		78134	3/25/2026	7008882191	PURCHASES	$182.67
		78134	3/25/2026	7008882191	PURCHASES	$96.54
		78134	3/25/2026	7008882191	PURCHASES	$219.49
	STEPHANIE BARRAZA	78084	3/24/2026	EMPLOYEE REIMB 2/20	SPANISH LANGUAGE BOOK FAIR MILEAGE REIMBURSEMENT	$96.42

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	STURDY OIL COMPANY	78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$142.06
	TAMARA VIDES	78221	4/8/2026	TRVL FINAL - 3/15/26	CM-NLC CONGRESSIONAL CITY CONFERENCE	$1,421.40
		78221	4/8/2026	TRVL FINAL - 3/15/26	CM-NLC CONGRESSIONAL CITY CONFERENCE	$3,337.78
		78165	4/1/2026	TRVL - 3/26/26	CM-COMMUNITY LEADERSHIP VISIT SPRING 2026	$29.00
	TERRA X PEST SERVICE, INC.	78088	3/24/2026	29294	CITY HALL, MSC & WASTE & RECYC	$442.00
	U S BANK CORPORATE PAYMENT SYSTEM	78166	4/1/2026	6167-2/23/26	OFFICE SUPPLIES	$100.27
		78166	4/1/2026	6167-2/23/26	CLEANING SUPPLIES	$60.19
		78166	4/1/2026	6167-2/23/26	OFFICE SUPPLIES	$9.75
		78166	4/1/2026	6167-2/23/26	JOSE ROCHA CPSI TRAINING PARKS SAFETY INSPECTOR	$750.00
		78166	4/1/2026	6167-2/23/26	JOSEPH MEDINA CPSI TRAINING PARKS SAFETY INSPECTOR	$750.00
		78166	4/1/2026	6167-2/23/26	JOSE ROCHA CPRS FLIGHT	$406.80
		78166	4/1/2026	6167-2/23/26	NICOLAS CALUBAQUIB CPRS FLIGHT	$406.80
		78166	4/1/2026	6167-2/23/26	CPRS FLIGHT CHRISTOPHER KRISHNA	$369.80
		78166	4/1/2026	6167-2/23/26	FUN GUIDE MARKETING	$31.83
		78166	4/1/2026	6167-2/23/26	FUN GUIDE MARKETING	$31.83
		78166	4/1/2026	6167-2/23/26	ANNUAL REPORT MATERIALS	$31.82
		78166	4/1/2026	6167-2/23/26	2026 MEMBERSHIP	$50.00
		78166	4/1/2026	6167-2/23/26	SALINAS SEMINAR	$240.00
		78166	4/1/2026	6167-2/23/26	EASTER EGG HUNT SUPPLIES	$375.08

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	U S BANK CORPORATE PAYMENT SYSTEM	78166	4/1/2026	6167-2/23/26	RETURN	($39.99)
		78166	4/1/2026	6167-2/23/26	SNR CTR TRIP	$249.40
		78166	4/1/2026	6167-2/23/26	STRAWBERRY FESTIVAL MERCH	$31.83
		78166	4/1/2026	6167-2/23/26	STRAWBERRY FESTIVAL MERCH	$31.83
		78166	4/1/2026	6167-2/23/26	EVENT SUPPLIES - GENERAL	$39.48
		78166	4/1/2026	6167-2/23/26	EVENT SUPPLIES - GENERAL	$106.75
		78166	4/1/2026	6167-2/23/26	JOSEPHE MEDINA CPRS FLIGHT	$269.80
		78166	4/1/2026	6167-2/23/26	LEAK DETECTION TOOL	$895.00
		78166	4/1/2026	6167-2/23/26	AIRPORT PARKING	$32.36
		78166	4/1/2026	6167-2/23/26	EGG HUNT SUPPLES	$626.64
		78166	4/1/2026	6167-2/23/26	JOSE ROCHA CPRS FLIGHT	$76.01
		78166	4/1/2026	6167-2/23/26	RISING STAR & GUIDING LIGHT BRUNCH	$70.00
		78166	4/1/2026	6167-2/23/26	RISING STARS & GUIDING LIGHTS BRUNCH	$70.00
		78166	4/1/2026	6167-2/23/26	CHRISTOPHER RISING STAR BRUNCH	$70.00
		78166	4/1/2026	6167-2/23/26	RISING STAR BRUNCH	$70.00
		78166	4/1/2026	6167-2/23/26	RISING STAR BRUNCH	$70.00
		78166	4/1/2026	6167-2/23/26	RISING STAR BRUNCH	$70.00
		78166	4/1/2026	6167-2/23/26	JASON HALL CPRS FLIGHT	$369.80
		78166	4/1/2026	6167-2/23/26	JASON HALL CPRS FLIGHT REFUND	($37.00)
		78135	3/25/2026	5738-2/23/26	IPHONE SCREEN & CASE PROTECTOR FOR FLD SVC STAFF	$93.26

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	5738-2/23/26	USB FLASH DRIVES FOR PROPERTY	$164.60
		78135	3/25/2026	5738-2/23/26	USB-C CHARGING FOR CABLE FOR IPHONE L.GLAD	$20.85
		78135	3/25/2026	5738-2/23/26	POWER ADAPTER FOR IPHONE L.GLAD	$20.85
		78135	3/25/2026	5738-2/23/26	IPHONE SCREEN PROTECTOR FOR L.GLAD IPHONE	$26.88
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES REFUND	($16.20)
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$58.02
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$19.18
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$46.14
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$119.33
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$89.13
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$269.57
		78135	3/25/2026	0540-2/23/26	PAL SUPPLIES	$109.73
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$70.08
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$177.10
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$21.91
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$44.95
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$33.85
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$68.02
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$43.85
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$18.65
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$213.84

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$131.64
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	($98.73)
		77885	3/18/2026	5486-2/23/26	CLA MEMBERSHIP	$230.00
		77885	3/18/2026	5486-2/23/26	ONLINE SERVICE	$5.00
		77885	3/18/2026	5486-2/23/26	STAFF DAY	$209.87
		77885	3/18/2026	5486-2/23/26	BOOKS	$154.48
		77885	3/18/2026	5486-2/23/26	PRIME BUSINESS RENEWAL	$141.58
		77885	3/18/2026	5486-2/23/26	DOMAIN RENEWAL	$16.18
		77885	3/18/2026	5486-2/23/26	BOOKS	$57.48
		77885	3/18/2026	5486-2/23/26	BOOKS	$232.00
		77885	3/18/2026	5486-2/23/26	BOOKS	$170.20
		77885	3/18/2026	9366-2/23/26	ANNUAL MEMBERSHIP CITY CLERK ORTIZ	$300.00
		77885	3/18/2026	9366-2/23/26	ANNUAL CONFERENCE REGISTRATION	$675.00
		77885	3/18/2026	9366-2/23/26	COUNCIL MEETING DESSERT	$37.95
		77885	3/18/2026	9366-2/23/26	COUNCIL MEETING DINNER	$576.15
		77885	3/18/2026	9366-2/23/26	FRAMES FOR PROCLAMATION	$118.55
		77885	3/18/2026	0566-2/23/26	LABOR LAW POSTERS	$1,135.81
		77885	3/18/2026	6703-2/23/26	ONLINE NEWSPAPER SUBSCRIPTION	$25.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE:NEW MAYOR AND COUNCILMEMBER ACADEMY	$534.24
		77885	3/18/2026	6703-2/23/26	BUSINESS CARDS-ALVARO MADRIGAL ZACHARY BICKEL	$127.28

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	U S BANK CORPORATE PAYMENT SYSTEM	77885	3/18/2026	6703-2/23/26	CONFERENCE COMMUNITY LEADERSHIP VISIT - JIMMY DUTR	$616.21
		77885	3/18/2026	6703-2/23/26	CONFERENCE COMMUNITY LEADERSHIP VISIT JIMMY DUTRA	$183.79
		77885	3/18/2026	6703-2/23/26	CONFERENCE COMMUNITY LEADERSHIP VISIT KRISTAL SALC	$800.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE CITY LEADERS SUMMIT 2026 - EDUARDO MONT	$650.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE COMMUNITY LEADERSHIP VISIT TAMARA VIDES	$800.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE CITY LEADERS SUMMIT 2026 TAMARA VIDES	$650.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE NLC CONGRESSIONAL CITY MARIA OROZCO REF	($755.00)
		77885	3/18/2026	6703-2/23/26	VIDEO EDITING SOFTWARE FOR COMMUNITICATION TEAM	$22.00
		77885	3/18/2026	6703-2/23/26	EVENT TICKET MONARCH SERVICES WINGS OF HOPE GALA	$150.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE 2026 CAL CITIES CITY MANAGERS CONFERENC	$597.26
		77885	3/18/2026	6703-2/23/26	CONFERENCE 2026 CAL CITIES CITY MANAGERS - NICK C	$597.26
		77885	3/18/2026	6703-2/23/26	CONFERENCE 2026 CAL CITIES CITY MANAGER NATHALIE M	$597.26
		77885	3/18/2026	6703-2/23/26	BUSINESS CARDS ANNIE FINCH	$56.73
		77885	3/18/2026	6703-2/23/26	EVENT SUPPLIES POLICE AND FIRE CHIEF MEET AND GREE	$4.11
		77885	3/18/2026	6703-2/23/26	EVENT SUPPLIES POLICE AND FIRE CHIEF MEET AND GREE	$20.84
		77885	3/18/2026	6703-2/23/26	OFFICE SUPPLIES	$20.66

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	U S BANK CORPORATE PAYMENT SYSTEM	77885	3/18/2026	6703-2/23/26	FIRE SERVICES LUNCH MEETING COUNTY AND CITY OFFICI	$118.00
		77885	3/18/2026	6703-2/23/26	BUSINESS SPOTLIGHT SUPPLIES	$26.08
		77885	3/18/2026	6703-2/23/26	EVENT SUPPLIES POLICE AND FIRE CHIEF MEET AND GREE	$46.95
		77885	3/18/2026	6703-2/23/26	EVENT TICKET NATIONAL AG DAY SPRING LUNCHEON MARA	$81.88
		77885	3/18/2026	6703-2/23/26	EVENT TICKET MONARCH SERVICES WINGS OF HOPE GALA	$150.00
		77885	3/18/2026	6703-2/23/26	EVENT TICKET NATIONAL AG SPRING LUNCHEON	$81.88
		77885	3/18/2026	6703-2/23/26	BUSINESS CARD LINCOLN GALD	$43.04
		77885	3/18/2026	6703-2/23/26	EMPLOYEE APPRECIATION BREAKFAST DECOR	$62.25
		77885	3/18/2026	6703-2/23/26	EMPLOYEE APPRECIATION BREAKFAST DECOR	$26.09
		77885	3/18/2026	6703-2/23/26	EVENT MATERIALS FOOD STORAGE	$67.35
		77885	3/18/2026	6703-2/23/26	COMMUNICATIONS TEAM RECRUIT CAMPAIGN REFUND	($0.25)
		77885	3/18/2026	6703-2/23/26	CITY MANAGER MEMBERSHIP CCMF	$400.00
		77885	3/18/2026	6703-2/23/26	CONFERENCE 2026 CAL CITIES MANAGERS CAR CHARGING	$24.42
		77885	3/18/2026	6703-2/23/26	CONFERENCE 2026 CAL CITIES CITY MANAGER CAR CHARGI	$81.43
		77885	3/18/2026	6703-2/23/26	DIGITAL NEWSPAPER SUBSCRIPTION	$19.96
		77885	3/18/2026	6703-2/23/26	BUSINESS SPOTLIGHT SUPPLIES	$39.12
		77885	3/18/2026	6703-2/23/26	TRAINING FEB 24 WEBINAR - ACCESIBLE VIDEO IN PRACTI	$45.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	U S BANK CORPORATE PAYMENT SYSTEM	77885	3/18/2026	6703-2/23/26	ONLINE NEWSPAPER SUBSCRIPTION	$25.00
		77885	3/18/2026	8119-1/22/26.2	MANAGEMENT MEMBERSHIP	$155.00
		77885	3/18/2026	8119-1/22/26.2	GAAP UPDATE	$93.59
		77885	3/18/2026	8119-1/22/26.2	COA APPLICATION	$670.00
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$26.77
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$39.38
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$44.24
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$21.50
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$170.00
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$51.50
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$54.19
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$52.83
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$18.66
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$40.15
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$95.43
	UNIFIED CLEANING SERVICES INC	78094	3/24/2026	12620	Janitorial Services for Recrea	$600.00
		78094	3/24/2026	12588	Janitorial Services for Recrea	$11,090.00
	UNIQUE MANAGEMENT SERVICES, INC.	78095	3/24/2026	6151887	COLLECTION AGENCY FEES	$198.05
	UPS STORE	78096	3/24/2026	19711	FRINGERPRINTING	$874.00
	VERDE DESIGN, INC.	78097	3/24/2026	42-2106300	Architectural Desig for Ramsay	$24,621.37
		78097	3/24/2026	37-2106300	Architectural Desig for Ramsay	$51,400.44

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0150	VISIT SANTA CRUZ COUNTY	78069	3/24/2026	2ND QTR 10/25-12/31	2ND QTR 10/1/25-12/31/25 TOURISM ASSESSMENT	$47,985.45
	WATSONVILLE FIREFIGHTERS LOCAL #1272	78101	3/24/2026	04 REISSUE	SHIELDS - SCHWANDER & G. NAVARRO	$270.00
	WATSONVILLE PAJARONIAN	78103	3/24/2026	146186	PH NOTICE 6/13-20	$1,255.60
		78103	3/24/2026	167897	PH NOTICE 3/3/26	$510.96
	Fund Total					$741,832.10
0201	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$27.43
		78137	4/1/2026	2/28/26	PURCHASES	$77.87
		77868	3/18/2026	1/31/26	PURCHASES	$43.89
	BETTER BRAND FOODS	77928	3/24/2026	860348	COFFEE BAR	$579.74
	C & N TRACTOR	77934	3/24/2026	113334	TRIMMER	$249.04
		77935	3/24/2026	113366	WEEDCUTTER	$253.90
	CDW GOVERNMENT, INC.	77945	3/24/2026	AH2QA9J	BLUEBEAM RENEWALS FOR VARIOUS DEPTS	$421.43
	DIXON & SONS TIRES INC.	77963	3/24/2026	100621-2/27/26	PURCHASES	$26.00
		77963	3/24/2026	100621-2/27/26	PURCHASES	$26.00
	JAM SERVICES, INC.	77999	3/24/2026	199950	LED SL MODULES & SMART PHOTOCONTROLS	$254,713.29
	K & D LANDSCAPING INC.	78002	3/24/2026	20017	2023-2026 Landscape Maintenanc	$8,333.33
	KALEO INDIGO	78147	4/1/2026	2127	Taiji Classes for Older Adults	$300.00
		78147	4/1/2026	2128	Taiji Classes for Older Adults	$300.00
	MID VALLEY SUPPLY	78024	3/24/2026	3/3/2026	PURCHASES	$19.65
		78024	3/24/2026	3/3/2026	PURCHASES	$127.16

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0201	MONTEREY BAY F.C. , LLC	78028	3/24/2026	1929-2	Youth Center 5.23 Field Trip	$720.00
	SAVE MART SUPERMARKET	78071	3/24/2026	TRD-2/22/26	PURCHASES	$75.10
		78071	3/24/2026	TRD-2/22/26	PURCHASES	$327.71
	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$346.18
		78134	3/25/2026	7008882191	PURCHASES	$408.15
	U S BANK CORPORATE PAYMENT SYSTEM	78166	4/1/2026	6167-2/23/26	COFFEE BAR SUPPLIES	$41.69
		78166	4/1/2026	6167-2/23/26	CLEANING SUPPLIES	$27.53
		78166	4/1/2026	6167-2/23/26	VALENTINES DANCE SUPPLIES	$143.98
		78166	4/1/2026	6167-2/23/26	VALENTINES DANCE SUPPLIES	$481.15
		78166	4/1/2026	6167-2/23/26	VALENTINES DANCE SUPPLIES	$141.48
		78166	4/1/2026	6167-2/23/26	CPRS FLIGHT SARA JEWELL	$369.80
		78166	4/1/2026	6167-2/23/26	CPRS FLIGHT JOSE BARRERA	$369.80
		78166	4/1/2026	6167-2/23/26	YC PROGRAM SUPPLIES	$193.89
		78166	4/1/2026	6167-2/23/26	YC PROGRAM SUPPLIES	$87.75
		78166	4/1/2026	6167-2/23/26	YC PROGRAM SUPPLIES	$128.90
		78166	4/1/2026	6167-2/23/26	COFFEE BAR SUPPLIES	$37.30
		78166	4/1/2026	6167-2/23/26	VALENTINES DANCE SUPPLIES	$9.75
		78166	4/1/2026	6167-2/23/26	CROCHET CLUB	$76.62
		78166	4/1/2026	6167-2/23/26	SNR CTR SUPPLIES	$121.34
		78166	4/1/2026	6167-2/23/26	JOSE BARRERA - CPRS FLIGHT REFUND	($369.80)
		78166	4/1/2026	6167-2/23/26	CROCHET CLUB	$98.24
		78166	4/1/2026	6167-2/23/26	RISING STAR BRUNCH	$70.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0201	Fund Total					$269,405.29
0202	CHARTER COMMUNICATIONS	78108	3/25/2026	170045401031426-3/14	INTERNET	$95.37
	Fund Total					$95.37
0204	RICOH USA, INC	78062	3/24/2026	5072830060	EQUIPMENT RENTAL	$201.28
	Fund Total					$201.28
0215	AMERICAN RED CROSS	77917	3/24/2026	RC00107705	PROVIDE RELOCATION ASSISTANCE	$1,064.22
	Fund Total					$1,064.22
0221	BURKE, WILLIAMS & SORENSEN, LLP	77932	3/24/2026	360870	CITY ATTORNEY SERVICES	$56.00
		77932	3/24/2026	360843	CITY ATTORNEY SERVICES	$1,372.00
	RICOH USA, INC	78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$18.15
	U S BANK CORPORATE PAYMENT SYSTEM	77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$19.48
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$77.10
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$26.58
		77885	3/18/2026	8119-2/23/26	MISC PURCHASES	$36.19
	Fund Total					$1,605.50
0246	PACIFIC GAS & ELECTRIC	78116	3/25/2026	0498528361-5-3/16/26	275 MAIN STREET	$38,012.98
	Fund Total					$38,012.98
0250	BABMAR CORPORATION	78168	4/2/2026	10626-50% DEPOSIT	ROOFTOP FURNITURE	$38,347.70
	COUNTY OF SANTA CRUZ LIBRARY OF JOINT POWERS	77951	3/24/2026	04/2026-WATS	1/12TH OF CONTRIBUTION	$45,140.33
	GROCERY OUTLET	77991	3/24/2026	0122-2/24/26	PROGRAM SUPPLIES	$17.77

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0250	GROCERY OUTLET	77991	3/24/2026	0124-2/17/26	PROGRAM SUPPLIES	$7.96
	INGRAM LIBRARY SERVICES	77995	3/24/2026	3/1/26	BOOKS	$75.05
	JOYA WINWOOD	78001	3/24/2026	0326	MOTHERSONG - 3/6/26	$95.00
	KPA GROUP	78005	3/24/2026	005-2/28/26	Design Services for Library Ro	$17,997.50
	Fund Total					$101,681.31
0260	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$43.86
		77868	3/18/2026	1/31/26	PURCHASES	$37.27
		77868	3/18/2026	1/31/26	PURCHASES	$14.81
		77868	3/18/2026	1/31/26	PURCHASES	$36.21
		77868	3/18/2026	1/31/26	PURCHASES	$21.94
	CREME DE CANNA COLLECTIVE	78194	4/8/2026	CANNABIS EQUITY 3RD	LOCAL CANNABIS EQUITY GRANT PR	$56,250.00
	ECOLOGY ACTION OF SANTA CRUZ	77966	3/24/2026	69008	ICARP PLANNING GRANT SERVICES	$14,164.04
	FARALLON STRATEGIES, LLC	77972	3/24/2026	INV 1081	REGIONAL CLIMATE ADAPTATION FU	$11,940.00
	HARBOR FREIGHT TOOLS	77873	3/18/2026	A854BD7E	SUPPLIES	$42.77
		77873	3/18/2026	5E64CC7B	SUPPLIES	$87.79
		77873	3/18/2026	C3F64454	SUPPLIES	$362.14
	L C ACTION POLICE SUPPLY	77876	3/18/2026	482598	SUPPRESSORS	$3,539.43
	LEHR	78008	3/24/2026	SI130243	OUTFITTING OF POLICE VEHICLE (CANNABIS GRANT)	$22,665.70
	LEXIS NEXIS RISK DATA MANAGEMENT	78010	3/24/2026	1100281760	LAW ENFORCEMENT DATABASE	$1,250.20
	PACIFIC CREST ENGINEERING, INC	78039	3/24/2026	16135	City Plaza Revitalization Proj	$360.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0260	RAIMI + ASSOCIATES, INC.	78131	3/25/2026	26-7360	HOUSING ELEMENT IMPLEMENTATION	$4,888.64
	ROBERT A. BOTHMAN, INC	78063	3/24/2026	2401221	Ramsay Park Renaissance Projec	$1,429,682.21
	S&S WORLDWIDE, INC.	77884	3/18/2026	IN101714296	NUCLEUS ART AND CRAFT SUPPLIES	$182.60
		77884	3/18/2026	IN101707182	NUCLEUS ART AND CRAFTS	$691.56
		77884	3/18/2026	IN101707880	NUCLEUS ARTS AND SPORTS SUPPLIES	$424.13
		78066	3/24/2026	IN101707880	Nucleus Program Supplies	$424.13
		78066	3/24/2026	IN101728637	Camp WOW program supplies	$329.73
	SAVE MART SUPERMARKET	78071	3/24/2026	TRD-2/22/26	PURCHASES	$370.32
	U S BANK CORPORATE PAYMENT SYSTEM	78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$159.47
		78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$65.70
		78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$135.53
		78166	4/1/2026	6167-2/23/26	CAMP WOW SUPPLIES	$163.35
		78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$294.88
		78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$32.37
		78166	4/1/2026	6167-2/23/26	NUCELUS WORKSHOP SUPPLIES	$40.56
		78166	4/1/2026	6167-2/23/26	STEM ELOP SUPPLIES	$259.96
		78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$53.77
		78166	4/1/2026	6167-2/23/26	STEM ELOP SUPPLIES	$69.14
		78166	4/1/2026	6167-2/23/26	NUCLEUS WORKSHOP SUPPLIES	$231.92
		78166	4/1/2026	6167-2/23/26	RETURN	($6.14)
		78166	4/1/2026	6167-2/23/26	ELOP STEM SUPPLIES	$131.08

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0260	U S BANK CORPORATE PAYMENT SYSTEM	78166	4/1/2026	6167-2/23/26	ELOP STEM SUPPLIES	$58.89
		78135	3/25/2026	0540-2/23/26	REG SERVICE FEE	$15.74
		78135	3/25/2026	0540-2/23/26	REG-GRANT RADAR	$632.00
		78135	3/25/2026	0540-2/23/26	FOOD-ABC GRANT OP	$39.78
		78135	3/25/2026	0540-2/23/26	HOTEL-GRANT ULISES	$843.96
		78135	3/25/2026	0540-2/23/26	HOTEL-GRANT AVALOS	$843.96
		78135	3/25/2026	0540-2/23/26	REG-DUI CHECKPOINT	$318.00
	ULINE	77886	3/18/2026	203314349	NUCLEUS WORKSHOP SUPPLIES	$5,044.91
		77886	3/18/2026	202576780	NUCLEUS STORAGE CABINETS & MISC SUPPLIES	$6,512.05
	Fund Total					$1,563,750.36
0305	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$50.40
		78137	4/1/2026	2/28/26	PURCHASES	$129.45
	ALEJANDRO AYALA	77915	3/24/2026	1ST BOOT REIMB 3/16	1ST BOOT REIMBURSEMENT 3/16/26	$250.00
	BEAR ELECTRICAL SOLUTIONS, LLC	77927	3/24/2026	10198	2023-2026 STREET LIGHT MAINTEN	$130.00
	BIG CREEK LUMBER COMPANY	77930	3/24/2026	2609107	SUPPLIES	$157.62
	FRANCISCO BANDERAS-ARANDA	77976	3/24/2026	1ST BOOT REIMB 3/9	1ST BOOT REIMBURSEMENT 3/9/26	$250.00
	GRANITE ROCK COMPANY	77985	3/24/2026	2275604	INV#2275604 TRAFFIC OPS-BROWN PLASTIC FLEX WEEP, B	$234.04
		77986	3/24/2026	2275605	IN#2275605 TRAFFIC OPS ACETONE PUMP 3 GAK AND FLOA	$327.33
	MAX NEVAREZ	78019	3/24/2026	2ND BOOT REIMB 3/5/2	2ND BOOT REIMBURSEMENT 3/5/26	$250.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0305	MISSION LINEN SUPPLY	78200	4/8/2026	320471-3/31/26	UNIFORM RENTAL SERVICES	$606.25
	PACIFIC GAS & ELECTRIC	78209	4/8/2026	1274173766-7-3/23/26	1274173766-7-3/23/26	$1,287.51
		78161	4/1/2026	7294900587-9-3/20/26	W 5TH AND MAIN ST	$587.77
		78149	4/1/2026	6771895322-6-3/24/26	CENTRAL AVE 200 FT E OF MAIN ST	$519.28
		78150	4/1/2026	0581861689-7-3/24/26	PAJARO LN @ GREEN VALLEY	$90.91
		78129	3/25/2026	0909726970-9-3/17/26	0909726970-9-3/17/26	$20,367.91
		78127	3/25/2026	1965495282-9-3/16/26	1965495282-9-3/16/26	$2,557.67
		78115	3/25/2026	1413903318-8-3/16/26	SW COR OHLONE PKWY AND HARKINS SL	$152.54
		77881	3/18/2026	3009950151-9-3/9/26	1601 FREEDOM BLVD	$160.23
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1,471.82
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$682.46
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$156.80
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$56.62
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$33.42
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$8.82
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$257.30

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0305	PACIFIC GAS & ELECTRIC	77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$96.84
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$47.18
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$14.19
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$171.20
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$62.20
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$13.54
	PKT WELDING & FABRICATION	78054	3/24/2026	1829	MATERIALS	$3,087.27
	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$460.88
	ZUMAR INDUSTRIES, INC.	78107	3/24/2026	56096	INV#56096 SPECIAL-NO PARKING OVERSIZE VEHICLES SIG	$2,549.73
	Fund Total					$37,279.18
0306	GRANITE ROCK COMPANY	77987	3/24/2026	INVOICE NO. 2	2025 PAVEMENT REPAIR PROJECT	$79,161.99
	MNS ENGINEERS, INC.	78026	3/24/2026	93018	INSPECTION SERVICES - BRIDGE S	$3,196.00
	Fund Total					$82,357.99
0309	CRUZIO/THE INTERNET STORE INC.	78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$74.95
	FIRST ALARM, INC.	78111	3/25/2026	923816	ALARM MONITORING	$389.76
		78111	3/25/2026	942045	ALARM MONITORING	$389.76
	PACIFIC GAS & ELECTRIC	78152	4/1/2026	3370611625-9-3/24/26	260 RODRIGUEZ ST	$5,417.27

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0309	PANTHER PROTECTIVE SERVICE	78049	3/24/2026	0002-2026WCG	Beach St and Civic Plaza Garag	$2,100.00
		78049	3/24/2026	0002-2026WCG	Beach St and Civic Plaza Garag	$1,050.00
		78049	3/24/2026	0001-2026WCG	Beach St and Civic Plaza Garag	$2,100.00
		78049	3/24/2026	0001-2026WCG	Beach St and Civic Plaza Garag	$1,050.00
	Fund Total					$12,571.74
0310	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$20.05
		78137	4/1/2026	2/28/26	PURCHASES	$17.54
		78137	4/1/2026	2/28/26	PURCHASES	$15.34
		78137	4/1/2026	2/28/26	PURCHASES	$19.73
		77868	3/18/2026	1/31/26	PURCHASES	$138.22
		77868	3/18/2026	1/31/26	PURCHASES	$10.96
		77868	3/18/2026	1/31/26	PURCHASES	$18.64
		77868	3/18/2026	1/31/26	PURCHASES	$29.60
		77868	3/18/2026	1/31/26	PURCHASES	$14.09
		77868	3/18/2026	1/31/26	PURCHASES	$9.60
		77868	3/18/2026	1/31/26	PURCHASES	$34.00
	AIRTEC SERVICE,INC	77914	3/24/2026	36310	CITYWIDE HVAC MAINTENANCE	$1,647.87
	ALLSTAR FIRE EQUIPMENT, INC	78138	4/1/2026	270081	PPE FOR NEW RECRUITS	$3,416.01
	AT&T MOBILITY LLC	77925	3/24/2026	87322287772X031 02026	CELL & DATA CHARGES PD/FIRE FR 02/03/26-03/02/26	$370.85
		77925	3/24/2026	87322287772X031 02026	CELL & DATA CHARGES PD/FIRE FR 02/03/26-03/02/26	$4,166.31

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0310	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$194.67
	BODY BY HANK	78142	4/1/2026	25983465	VEHICLE REPAIRS	$9,025.67
	BURTON'S FIRE APPARATUS, INC.	77933	3/24/2026	S71056	PARTS	$126.39
	CRUZIO/THE INTERNET STORE INC.	78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$499.00
	DEFENSA PRIVATE SECURITY, INC.	77959	3/24/2026	003/2026CW	Security Services for Facility	$960.00
	DIXON & SONS TIRES INC.	77963	3/24/2026	100621-2/27/26	PURCHASES	$202.68
	LA SELVA	78006	3/24/2026	16472	ON-CALL TREE MAINTENANCE SERVI	$4,975.00
	LEXIS NEXIS RISK DATA MANAGEMENT	78010	3/24/2026	1100281760	LAW ENFORCEMENT DATABASE	$818.24
	LEXIS NEXIS RISK SOLUTIONS FL INC.	78011	3/24/2026	1300252230	DORS	$812.71
	MID VALLEY SUPPLY	78024	3/24/2026	3/3/2026	PURCHASES	$194.09
	SAVE MART SUPERMARKET	78071	3/24/2026	TRD-2/22/26	PURCHASES	$9.42
		78071	3/24/2026	TRD-2/22/26	PURCHASES	$187.70
	SEBASTIAN RESENDIZ	78074	3/24/2026	TUITION REIMB 2/26	INSTRUCTOR 1	$475.00
	SHELLEY RICHARDSON	78219	4/8/2026	2603300	LUNCH FOR AFSS MEETING	$400.00
	SOUTH BAY REGIONAL PUBLIC SAFETY	78081	3/24/2026	226202	BASIC POLICE ACADEMY	$12,567.00
	SOUTH COUNTY INDUSTRIAL EMERGENCY COUNCIL	78112	3/25/2026	INV-006533	BEN AVIS HAZMAT TECH CLASSES	$3,580.00
	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$35.49
		78090	3/24/2026	52800-3/2/26	PURCHASES	$21.62

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0310	TRI COUNTY TROPHY & ENGRAVING	78091	3/24/2026	AFD5174B-0004	PERPETUAL PLAQUE	$164.63
	U S BANK CORPORATE PAYMENT SYSTEM	78166	4/1/2026	6167-2/23/26	YC MAZE FOR EVENTS	$2,673.51
		78135	3/25/2026	0540-2/23/26	DETECTIVE SUPPLIES	$41.28
		78135	3/25/2026	0540-2/23/26	CAR RENTAL CHIEF	$395.77
		78135	3/25/2026	0540-2/23/26	FLIGHT CHANGE CHIEF	$38.19
		78135	3/25/2026	0540-2/23/26	HOTEL - FLEET PICKUP	$225.26
		78135	3/25/2026	0540-2/23/26	OFFICE SIGNS	$197.45
		78135	3/25/2026	0540-2/23/26	REG-CPCA FULGONI	$975.00
		78135	3/25/2026	0540-2/23/26	REG-CPCA CHIEF SHAB	$875.00
		78135	3/25/2026	0540-2/23/26	SPECIALIZED EQUIPMENT	$43.89
		78135	3/25/2026	0540-2/23/26	HOTEL DEPOSIT CHIEF	$540.74
		78135	3/25/2026	0540-2/23/26	HOTEL- DEPOSIT CAPTA	$540.74
		78135	3/25/2026	0540-2/23/26	OFFICE SUPPLY	$13.16
		78135	3/25/2026	0540-2/23/26	FLIGHT CPCA-CHIEF	$290.80
		78135	3/25/2026	0540-2/23/26	FLIGHT - CPCA FULGONI	$236.80
		78135	3/25/2026	0540-2/23/26	OFFICE SUPPLIES	$66.95
		78135	3/25/2026	0540-2/23/26	OFFICE SUPPLIES	$53.66
		78135	3/25/2026	0540-2/23/26	HOTEL-RECORD SEALING	$452.74
		78135	3/25/2026	0540-2/23/26	AGENCY TRAINING PASS	$800.00
		78135	3/25/2026	0540-2/23/26	COMM ENG SUPPLIES	$30.70
		78135	3/25/2026	0540-2/23/26	SUPPLIES	$139.68
		78135	3/25/2026	0540-2/23/26	DOOR SIGNS	$46.35

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0310	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	0540-2/23/26	FOOD-PIT ORIENTATION	$185.20
		78135	3/25/2026	0540-2/23/26	FOOD-PIT ORIENTATION	$87.36
		78135	3/25/2026	0540-2/23/26	FOOD-PIT ORIENTATION	($16.00)
		78135	3/25/2026	0540-2/23/26	INVEST SUPPLIES	$786.75
		78135	3/25/2026	0540-2/23/26	SPECIALIZED EQUIPMENT	$356.69
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$36.12
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$83.90
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$1,400.00
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$760.73
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$623.93
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$5.92
		78135	3/25/2026	2003-2/23/26	MISC PURCHASES	$768.61
	VORTEX VOLLEYBALL	78098	3/24/2026	2025-007	Youth Center Volleyball Progra	$240.00
	WATSONVILLE FORD	78102	3/24/2026	G014	FORD EXPLORER STAFF VEH	$59,871.16
	Fund Total					$119,046.16
0312	U S BANK CORPORATE PAYMENT SYSTEM	77885	3/18/2026	7789-2/23/26	REGIONAL WATER QUALITY CONTROL BOARD FEE	$278.64
	Fund Total					$278.64
0354	PACIFIC GAS & ELECTRIC	78118	3/25/2026	6312050406-1-3/18/26	1180 E LAKE AVE	$5.88
		78119	3/25/2026	0541697410-2-3/18/26	1300 BRIDGE ST	$14.65

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0354	PACIFIC GAS & ELECTRIC	78120	3/25/2026	0519864328-9-3/18/26	150 BIRDGE ST #A	$22.39
	Fund Total					$42.92
0360	K & D LANDSCAPING INC.	78002	3/24/2026	20054	2023-2026 Landscape Maintenanc	$1,967.00
	Fund Total					$1,967.00
0510	US BANK	78167	4/1/2026	3174813	ACCOUNT 294131000	$970,000.00
		78167	4/1/2026	3174813	ACCOUNT 294131000	$272,205.96
	Fund Total					$1,242,205.96
0710	A L LEASE COMPANY, INC	77908	3/24/2026	188352	SUPPLIES	$86.64
		77908	3/24/2026	188353	SUPPLIES	$28.09
		77908	3/24/2026	188356	SUPPLIES	$20.05
		77908	3/24/2026	188266	SUPPLIES	$17.78
		77908	3/24/2026	188168	SUPPLIES	$4.36
	A-1 JANITORIAL SERVICE	77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$268.93
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$268.93
	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$556.22
		78137	4/1/2026	2/28/26	PURCHASES	$26.30
		78137	4/1/2026	2/28/26	PURCHASES	$332.03
		78137	4/1/2026	2/28/26	PURCHASES	$357.70
		78137	4/1/2026	2/28/26	PURCHASES	$30.71
		78137	4/1/2026	2/28/26	PURCHASES	$17.54
		78137	4/1/2026	2/28/26	PURCHASES	$239.09

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$2,799.65
		78137	4/1/2026	2/28/26	PURCHASES	$23.12
		78137	4/1/2026	2/28/26	PURCHASES	$188.02
		78137	4/1/2026	2/28/26	PURCHASES	$17.52
		78137	4/1/2026	2/28/26	PURCHASES	$8.99
		78137	4/1/2026	2/28/26	PURCHASES	$5.86
		78137	4/1/2026	2/28/26	PURCHASES	$37.27
		78137	4/1/2026	2/28/26	PURCHASES	$48.27
		78137	4/1/2026	2/28/26	PURCHASES	$22.56
		77868	3/18/2026	1/31/26	PURCHASES	$21.90
		77868	3/18/2026	1/31/26	PURCHASES	$209.55
		77868	3/18/2026	1/31/26	PURCHASES	$56.99
		77868	3/18/2026	1/31/26	PURCHASES	$29.60
		77868	3/18/2026	1/31/26	PURCHASES	$639.47
		77868	3/18/2026	1/31/26	PURCHASES	$87.76
		77868	3/18/2026	1/31/26	PURCHASES	$329.03
		77868	3/18/2026	1/31/26	PURCHASES	$25.23
		77868	3/18/2026	1/31/26	PURCHASES	$27.40
		77868	3/18/2026	1/31/26	PURCHASES	$17.52
		77868	3/18/2026	1/31/26	PURCHASES	$122.80
	AGILE OCCUPATIONAL MEDICINE, PC	77911	3/24/2026	EM061553	DOT PHYSICAL/ PRE EMPLOYMENT	$30.00
		77911	3/24/2026	EM070425	DOT PHYSICAL	$135.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	AIRGAS USA, LLC	77913	3/24/2026	5523263693	CYLINDER RENTAL	$186.83
	APGN, INC.	77920	3/24/2026	20743	INV#20743 REMOTE SUPPORT	$564.00
		77920	3/24/2026	22605	INV#22605 ROUTINE MAINTENANCE ON TURBO BLOWER	$5,315.00
		77920	3/24/2026	21208	INV#21208 PART ITEM#SRV00014-0010.0	$73.13
		77920	3/24/2026	21207	INV#21207 NEU FILTER FABRIC #MTN03000-001.0	$913.50
	ARRIAGA, JOHN	77923	3/24/2026	8327	State Advocacy and Consulting	$1,750.00
	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$234.76
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$305.82
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$43.88
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$230.31
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$580.66
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$53.97
	BIG CREEK LUMBER COMPANY	77930	3/24/2026	2602766	SUPPLIES	$28.51
	BURKE, WILLIAMS & SORENSEN, LLP	77932	3/24/2026	360859	CITY ATTORNEY SERVICES	$3,701.04
		77932	3/24/2026	360850	CITY ATTORNEY SERVICES	$1,167.50
		77932	3/24/2026	360861	CITY ATTORNEY SERVICES	$952.00
		77932	3/24/2026	360843	CITY ATTORNEY SERVICES	$588.00
	CAPITAL EDGE ADVOCACY, INC.	77940	3/24/2026	26-40	Federal Legislative Advocacy a	$1,000.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	CARLSON CM, INC	77942	3/24/2026	1113	CONSTRUCTION MANAGEMENT - RWF	$2,220.00
		77942	3/24/2026	1112	WWTF ELECT. SYS HAZARD MITIGAT	$17,774.00
	CAROLLO ENGINEERS, INC.	77943	3/24/2026	FB79167	HEADWORKS AND INFLUENT PUMP ST	$3,933.50
	CASTILLO, ANTONIO	77944	3/24/2026	1ST BOOT REIMB 3/3	PW-1ST BOOT REIMBURSEMENT 3/3	$229.37
	CDW GOVERNMENT, INC.	77945	3/24/2026	AI42N3F	BATTERY FOR WRC UPS	$299.51
		77945	3/24/2026	AH2QA9J	BLUEBEAM RENEWALS FOR VARIOUS DEPTS	$2,950.01
	CRISTIAN MAGDALENO	77953	3/24/2026	2ND BOOT REIMB 3/9	PW-2ND BOOT REIMBURSEMENT 3/9/26	$213.99
	CUMMING MANAGEMENT GROUP	77955	3/24/2026	186059	ON-CALL LABOR COMPLIANCE SERVI	$1,691.00
	D&G SANITATION	77956	3/24/2026	318823	PORTABLE TOILET	$131.70
	DAVIS AUTO PARTS	77958	3/24/2026	39941	PARTS	$31.20
	DIXON & SONS TIRES INC.	77963	3/24/2026	100621-2/27/26	PURCHASES	$421.65
	EUROFINS DRINKING WATER AND WASTEWATER WEST	78110	3/25/2026	3800118721	WELLS COMPLIANCE	$2,781.00
		78110	3/25/2026	3800118758	WELLS COMPLIANCE	$3,203.30
		77970	3/24/2026	3800118321	DBP	$1,648.00
		77970	3/24/2026	3800118374	WELLS COMPLIANCE	$2,472.00
	FASTENAL COMPANY	77973	3/24/2026	CAWAT142345	SUPPLIES	$334.24
		77973	3/24/2026	CAWAT142307	SUPPLIES	$107.38
	FEDEX	77974	3/24/2026	9-185-17135	SHIPMENTS	$45.74
	G7EI, INC.	77978	3/24/2026	013125ORG4	PROJECT MANAGEMENT SERVICES	$3,217.50
		77978	3/24/2026	013126LRT26	PROJECT MANAGEMENT SERVICES	$5,265.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	G7EI, INC.	77978	3/24/2026	022826ORG5	PROJECT MANAGEMENT SERVICES	$2,242.50
		77978	3/24/2026	022826LRT27	PROJECT MANAGEMENT SERVICES	$10,627.50
	GARCIA, ADRIAN	77979	3/24/2026	1ST BOOT REIMB 3/4	PW-1ST BOOT REIMBURSEMENT 3/4/26	$250.00
	GRAINGER	77983	3/24/2026	9824495585	HAND SANITIZER	$126.43
		77983	3/24/2026	9828504465	EYE WASH STATION	$327.82
		77983	3/24/2026	9830469863	SUPPLIES	$75.26
		77983	3/24/2026	9835003022	SUPPLIES	$272.34
		77983	3/24/2026	9835003022	SUPPLIES	$272.33
		77983	3/24/2026	9825560122	SUPPLIES	$97.35
		77983	3/24/2026	9825560122	SUPPLIES	$97.34
		77983	3/24/2026	9810252933	SUPPLIES	$88.22
		77983	3/24/2026	9828239898	SUPPLIES	$184.77
		77983	3/24/2026	9828504457	SUPPLIES	$276.79
		77983	3/24/2026	9826859341	SUPPLIES	$92.42
	GREEN RUBBER-KENNEDY AG	77989	3/24/2026	W-594650	SUPPLIES	$201.08
		77989	3/24/2026	W-594478	SUPPLIES	$64.09
		77989	3/24/2026	W-594591	SUPPLIES	$46.89
		77989	3/24/2026	W-593973	SUPPLIES	$880.83
	HACH COMPANY	77992	3/24/2026	14894350	PARTS	$1,898.79
		77992	3/24/2026	14894350	PARTS	$1,898.80
	INORGANIC VENTURES INC	77996	3/24/2026	0353535-IN	INV#0353535-IN W-2-NOX756663 NITRITE AS N 125 ML I	$220.18

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	JOSE DE JESUS GARCIA	78000	3/24/2026	2ND BOOT REIMB 2/10C	PW-2ND BOOT REIMBURSEMENT CORRECTED AMOUNT	$50.00
	KIMBALL MIDWEST	78004	3/24/2026	104221430	SUPPLIES	$241.10
		78004	3/24/2026	104242749	SUPPLIES	$106.93
	LIFE TECHNOLOGIES CORPORATION	78014	3/24/2026	88389450	INV#88389450 ROSS PH ELECTRODE FILL SOLN 5X60ML	$201.44
	MCMASTER CARR	78020	3/24/2026	60794218	SUPPLIES	$1,199.26
	MERCURY METALS INC	78021	3/24/2026	15990	SUPPLIES	$182.12
	MICHAEL K. NUNLEY & ASSOCIATES, INC	78022	3/24/2026	2803	SEWER PUMP STATION NO. 14 IMPR	$840.75
		78022	3/24/2026	2810	ENGINEERING SUPPORT SRVCS FOR	$33,264.75
	MISSION LINEN SUPPLY	78204	4/8/2026	320454-3/31/26	UNIFORM RENTAL SERVICES	$742.85
		78204	4/8/2026	320454-3/31/26	UNIFORM RENTAL SERVICES	$395.25
		78204	4/8/2026	320454-3/31/26	UNIFORM RENTAL SERVICES	$1,388.63
	MNS ENGINEERS, INC.	78026	3/24/2026	93003	CIVIL DESIGN-WWTF ELECTRICAL S	$1,262.71
	MONTEREY BAY ANALYTICAL SERVICES, INC.	78027	3/24/2026	260210_100	INV#260210_100 ANALYSIS SAMPLE ON 2/10/2026	$151.20
		78027	3/24/2026	260210_100	INV#260210_100 ANALYSIS SAMPLE ON 2/10/2026	$181.80
	MONTEREY BAY WATER WORKS ASSOCIATION	77880	3/18/2026	MARCH 2026 TRAINING	MARCH 2026 WATER TREATMENT DISTRIBUTION	$50.00
	NEW IMAGE LANDSCAPE COMPANY	78032	3/24/2026	153530	LANDSCAPE MAINTENANCE FEB 2026	$1,905.22
		78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$94.94
	O'REILLY AUTOMOTIVE INC.	78035	3/24/2026	3446-335599	BATTERIES	$167.58
	PACE ANALYTICAL SERVICES, LLC	78037	3/24/2026	2627B531799	INV#2627B531799 WWTP BELL PRESS BIOSOLIDS LAB ID#2	$521.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	PACIFIC CREST ENGINEERING, INC	78039	3/24/2026	16140	WWTF ELECTRICAL SYSTEM HAZARD	$7,000.00
		78039	3/24/2026	16190	CONSULTANT SERVICES- SPECIAL I	$875.00
	PACIFIC GAS & ELECTRIC	78217	4/8/2026	9335083043-1-4/1/26	401 PANABAKER RD	$3,213.64
		78212	4/8/2026	5314251010-5-3/20/26	5314251010-5-3/20/26	$6,653.52
		78213	4/8/2026	6994615709-1-3/25/26	401 PANABAKER RD	$117,027.11
		78207	4/8/2026	2914465320-0-3/26/26	500 CLEARWATER LN	$2,393.74
		78160	4/1/2026	1283243089-1-3/20/26	401 PANAKAER RD	$40,137.33
		78156	4/1/2026	0998529372-0-3/22/26	W BEACH ST & LEE RD	$118.68
	PAJARO VALLEY LOCK SHOP	78046	3/24/2026	1-13726	DUPLICATE KEY	$140.91
	PAUL RENDON	78051	3/24/2026	1ST BOOT REIMB 3/10	PW-1ST BOOT REIMBURSEMENT 3/10	$250.00
	PG&E CFM/PPC DEPARTMENT	78040	3/24/2026	0008485051-0	INV#0008485051-0 JANUARY 2026 NONBYPASSABLE CHARGE	$3,891.09
	PLATT	78055	3/24/2026	7D62588	SUPPLIES	$44.42
		78055	3/24/2026	7D66391	SUPPLIES	$925.18
		78055	3/24/2026	7D81153	SUPPLIES	$494.91
		78055	3/24/2026	7D23779	SUPPLIES	$172.91
		78055	3/24/2026	7C96514	SUPPLIES	$32.38
	PROVAC SALES,INC.	78163	4/1/2026	47943	PARTS	$2,665.75
	RAFTELIS FINANCIAL CONSULTANTS, INC.	77883	3/18/2026	43977	UTILITIES COST-OF-SERVICE ANAL	$2,705.00
		77883	3/18/2026	44455	UTILITIES COST-OF-SERVICE ANAL	$15,786.25

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	RICOH USA, INC	78062	3/24/2026	5072830060	EQUIPMENT RENTAL	$1,188.40
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$8.60
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$28.47
		78062	3/24/2026	5072859865	RICOH EQUIPMENT	$98.07
	RYAN EATON	78065	3/24/2026	1ST BOOT REIMB 3/4	PW-1ST BOOT REIMBURSEMENT 3/4/26	$250.00
	SANTA CRUZ SENTINEL	78070	3/24/2026	0006948151	INV#0006948151 FEB.2026 NOTICE INVITING BIDS FOR T	$516.45
	SCHAAF & WHEELER, CONSULTING CIVIL	78073	3/24/2026	42728	MILES LANE PUMP STATION UPGRAD	$3,202.50
	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$28.98
		78134	3/25/2026	7008882191	PURCHASES	$67.77
		78134	3/25/2026	7008882191	PURCHASES	$29.16
		78134	3/25/2026	7008882191	PURCHASES	$38.08
	STATE WATER RESOURCES CNTRL BD	78083	3/24/2026	SC-153478	ACCT#2030143 10/1/25-12/31/25 CITY OF WATSONVILLE-	$776.57
	STURDY OIL COMPANY	78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$350.00
	TELLEZ, RUBEN	78086	3/24/2026	EMPLOYEE REIMB 1/28	WEBINAR FOR WCR STAFF 10 EMPLOYEES	$140.00
		78086	3/24/2026	EMPLOYEE REIMB 1/28	WEBINAR FOR WCR STAFF 10 EMPLOYEES	$90.00
		78086	3/24/2026	EMPLOYEE REIMB 1/28	WEBINAR FOR WCR STAFF 10 EMPLOYEES	$60.00
	TENNANT SALES AND SERVICE COMPANY	78087	3/24/2026	US90273641	INV#US90273641 BRUSH SCB, BRUSH ASSY, DISK, STRAP	$1,657.88
	THE HOSE SHOP INC.	78089	3/24/2026	471894	SUPPLIES	$541.39

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$10.31
		78090	3/24/2026	52800-3/2/26	PURCHASES	$16.64
	TROJAN TECHNOLOGIES CORP	78093	3/24/2026	200/50011424	INV#200/50011424 CANISTER ASSY, NIPPLE, GREASE, FA	$3,763.08
	U S BANK CORPORATE PAYMENT SYSTEM	78222	4/8/2026	7771-1/22/26	DESK FOR OFFICE	$350.39
		78222	4/8/2026	7771-1/22/26	MEMBERSHIP FOR COMMUNICATION TEAM	$119.40
		78222	4/8/2026	7771-1/22/26	BULLETIN BOARD	$37.44
		78222	4/8/2026	7771-1/22/26	STANDING DESK	$156.03
		78222	4/8/2026	7771-1/22/26	PART FOR JOHN DEER	$15.85
		78222	4/8/2026	7771-1/22/26	BLADES FOR JOHN DEER	$51.84
		78222	4/8/2026	7771-1/22/26	SUPPLIES FOR WRC SHOP	$278.59
		78222	4/8/2026	7771-1/22/26	COLLECTIONS RENEWAL FEE RUBEN TELLEZ	$129.00
		78222	4/8/2026	7771-1/22/26	CREDIT FOR BULLETIN BOARD	($37.44)
		78222	4/8/2026	7771-1/22/26	PSC CONFERENCE AND EXPO LESLIE RIOS	$955.00
		78222	4/8/2026	7771-1/22/26	OFFICE SUPPLIES	$94.56
		78222	4/8/2026	7771-2/23/26	LAB OFFICE	$37.44
		78222	4/8/2026	7771-2/23/26	PARTS FOR MECHANIC SHOP	$1,312.38
		78222	4/8/2026	7771-2/23/26	LUNCH MEETING	$35.10
		78222	4/8/2026	7771-2/23/26	OFFICE SUPPLIES	$15.32
		78222	4/8/2026	7771-2/23/26	BLADES FOR JOHN DEER	($51.84)
		78135	3/25/2026	5738-2/23/26	AT&T BILL VIA PRINCE PARKER COLLECTION AGENCY	$92.46

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	5738-2/23/26	USB-C CHARGING CABLE FOR IPHONE FLD SVC	$20.85
		78135	3/25/2026	5738-2/23/26	POWER ADAPTER FOR IPHONE FLD SVC	$20.85
		78135	3/25/2026	5738-2/23/26	IPHONE SCREEN & CASE PROTECTOR FOR FLD SVC STAFF	$70.86
		78135	3/25/2026	3458-2/23/26	CAR PARTS	$48.67
		78135	3/25/2026	3458-2/23/26	WATER FILLER SYSTEM	$280.83
		78135	3/25/2026	3458-2/23/26	OFFICE SUPPLIES	$18.04
		78135	3/25/2026	3458-2/23/26	PPE	$98.65
		78135	3/25/2026	3458-2/23/26	PPE	$493.25
		78135	3/25/2026	3458-2/23/26	SUPPLIES	$421.34
		78135	3/25/2026	3458-2/23/26	SUPPLIES	$54.86
		78135	3/25/2026	3458-2/23/26	SUPPLIES	$21.94
		78135	3/25/2026	3458-2/23/26	BOATING SAFETY COURSE	$11.00
		77885	3/18/2026	7789-2/23/26	KEYBOARD & MOUSE	$109.73
		77885	3/18/2026	7789-2/23/26	PRIZES & SUPPLIES FOR ANNUAL EGG DROP	$86.97
		77885	3/18/2026	7789-2/23/26	PRIZES & SUPPLIES FOR ANNUAL EGG DROP COMPETITION	$127.08
		77885	3/18/2026	7789-2/23/26	OFFICE SUPPLIES FOR ANNUAL EGG DROP COMPETITION	$124.57
		77885	3/18/2026	7789-2/23/26	PRESENTATION BOARD & MATERIALS FOR EGG DROP	$40.05
		77885	3/18/2026	7789-2/23/26	LAPTOP BAG	$48.28
	WALLACE GROUP, A CALIFORNIA CORPORATION	78099	3/24/2026	67209	CONSTRUCTION MANAGEMENT - MILE	$5,631.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0710	WESTROCK ENGINEERING	78105	3/24/2026	APPLICATION NO 2	MILES LANE SEWER PUMP STATION	$509,020.45
	Fund Total					$874,717.10
0720	A TOOL SHED RENTALS, INC.	77909	3/24/2026	1783080-6	RENTALS	$119.24
	A-1 JANITORIAL SERVICE	77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$459.78
		77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$622.87
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$459.78
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$622.87
	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$15.34
		78137	4/1/2026	2/28/26	PURCHASES	$14.25
		78137	4/1/2026	2/28/26	PURCHASES	$28.01
		78137	4/1/2026	2/28/26	PURCHASES	$19.73
		78137	4/1/2026	2/28/26	PURCHASES	$38.38
		78137	4/1/2026	2/28/26	PURCHASES	$33.99
		78137	4/1/2026	2/28/26	PURCHASES	$4.61
		78137	4/1/2026	2/28/26	PURCHASES	$61.41
		78137	4/1/2026	2/28/26	PURCHASES	$9.87
		78137	4/1/2026	2/28/26	PURCHASES	$10.95
		78137	4/1/2026	2/28/26	PURCHASES	$105.21
		78137	4/1/2026	2/28/26	PURCHASES	$30.72
		78137	4/1/2026	2/28/26	PURCHASES	$7.67
		78137	4/1/2026	2/28/26	PURCHASES	$5.48
		78137	4/1/2026	2/28/26	PURCHASES	$43.89

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0720	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$18.37
		78137	4/1/2026	2/28/26	PURCHASES	$18.65
		78137	4/1/2026	2/28/26	PURCHASES	$52.66
		77868	3/18/2026	1/31/26	PURCHASES	$61.83
		77868	3/18/2026	1/31/26	PURCHASES	$62.52
		77868	3/18/2026	1/31/26	PURCHASES	$71.33
		77868	3/18/2026	1/31/26	PURCHASES	$49.38
		77868	3/18/2026	1/31/26	PURCHASES	$19.27
		77868	3/18/2026	1/31/26	PURCHASES	$7.64
		77868	3/18/2026	1/31/26	PURCHASES	$25.22
		77868	3/18/2026	1/31/26	PURCHASES	$36.20
		77868	3/18/2026	1/31/26	PURCHASES	$43.83
		77868	3/18/2026	1/31/26	PURCHASES	$99.74
		77868	3/18/2026	1/31/26	PURCHASES	$46.04
	AQUA-METRIC SALES COMPANY	77921	3/24/2026	INV0113007	WATER METERS AND READING EQUIP	$12,015.45
	ARRIAGA, JOHN	77923	3/24/2026	8327	State Advocacy and Consulting	$1,750.00
	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$666.77
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$389.79
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$117.79
	C & N TRACTOR	77936	3/24/2026	113551	SMALL ENGINE LABOR	$30.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0720	CAPITAL EDGE ADVOCACY, INC.	77940	3/24/2026	26-40	Federal Legislative Advocacy a	$1,000.00
	CAROLLO ENGINEERS, INC.	77943	3/24/2026	FB79574	ZONE 2 RESERVOIR PROJECT WA-20	$15,036.50
	CHARTER COMMUNICATIONS	78108	3/25/2026	170045401031426 -3/14	INTERNET	$47.12
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$47.12
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$47.12
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$128.11
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$95.40
	CLARK BROS. INC	77949	3/24/2026	1758.2.2	ZONE 2 WATER RESERVOIR AIRPORT	$479,275.00
	CRUZIO/THE INTERNET STORE INC.	78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$74.95
	CUMMING MANAGEMENT GROUP	77955	3/24/2026	186059	ON-CALL LABOR COMPLIANCE SERVI	$2,483.00
	D&G SANITATION	77956	3/24/2026	318824	PORTABLE TOILET	$25.00
		77956	3/24/2026	318825	PORTABLE TOILET	$50.00
		77956	3/24/2026	318827	PORTABLE TOILET	$50.00
		77956	3/24/2026	318826	PORTABLE TOILET	$50.00
	DARREL VARNI ELECTRIC INC.	77957	3/24/2026	26-COW	INV#26-COW C35' LOOP, D LOOP AND D 20' LOOP	$15,050.00
	DIXON & SONS TIRES INC.	77963	3/24/2026	100621-2/27/26	PURCHASES	$50.00
		77963	3/24/2026	100621-2/27/26	PURCHASES	$26.00
	FASTENAL COMPANY	77973	3/24/2026	CAWAT142387	SUPPLIES	$71.34
	GLOBAL CONCEPTS	77982	3/24/2026	L2021062	CHAIRS	$2,644.31

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0720	GRAINGER	77983	3/24/2026	9831198834	SUPPLIES	$281.04
	GRANITE ROCK COMPANY	77984	3/24/2026	2268169	INV#2268169 PLASTIC FLEX SWEEP, TASKING TAPE, QUAR	$325.92
		77872	3/18/2026	2276743	WATER CONSTRUCTION MATERIALS,	$9,680.20
		78145	4/1/2026	2279124	WATER CONSTRUCTION MATERIALS,	$3,844.61
		78196	4/8/2026	2280791	WATER CONSTRUCTION MATERIALS,	$1,366.75
		78197	4/8/2026	2280234	WATER CONSTRUCTION MATERIALS,	$1,200.37
	GREAT WEST EQUIPMENT, INC.	77988	3/24/2026	26093	INV#26093 PAVING BREAKER	$1,418.63
	GREEN RUBBER-KENNEDY AG	77989	3/24/2026	W-594509	SUPPLIES	$443.73
		77989	3/24/2026	W-594646	SUPPLIES	$65.33
		77989	3/24/2026	W-594544	SUPPLIES	$35.61
	LARGE'S METAL FABRICATION, INC	78007	3/24/2026	137926	PARTS	$871.93
	LINDE GAS & EQUIPMENT INC.	78015	3/24/2026	55056579	CYLINDER RENTAL	$38.58
	LINXUP	78016	3/24/2026	INV0001256322	INV0001256322 CUSTOMER SERVICE PLUGIN DEVICE ATT-G	$189.32
	LUHDORFF & SCALMANINI CONSULTING ENGINEERS, INC.	78017	3/24/2026	44368	ROACH ROAD MUNICIPAL WELL PUMP	$4,558.18
	MAGGIORA BROS DRILLING CO. INC	77877	3/18/2026	M26-008	WELL #3, PUMP REMOVAL AND INST	$2,540.00
		77877	3/18/2026	112315	WELL #3, PUMP REMOVAL AND INST	$39,755.00
		77877	3/18/2026	112314	WELL #3, PUMP REMOVAL AND INST	$25,390.00
	MICHAEL K. NUNLEY & ASSOCIATES, INC	78022	3/24/2026	2916	DESIGN FOR HEXAVALENT CHROMIUM	$55,732.67
	MID COAST ENGINEERS, INC.	78023	3/24/2026	5358	BUENA VISTA/WATSONVILLE AIRPORT	$1,050.00
	MISSION LINEN SUPPLY	77878	3/18/2026	321329-2/28/26	UNIFORM RENTAL SERVICES	$130.58

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0720	MISSION LINEN SUPPLY	78203	4/8/2026	320463-3/31/26	UNIFORM RENTAL SERVICES	$804.36
		78204	4/8/2026	320454-3/31/26	UNIFORM RENTAL SERVICES	$519.57
		78205	4/8/2026	320444-3/31/26	UNIFORM RENTAL SERVICES	$119.35
	MNS ENGINEERS, INC.	78026	3/24/2026	93002	AIRPORT RESERVOIR RECOATING PR	$1,840.75
		78026	3/24/2026	92831	PROFESSIONAL ENGINEERING SERVI	$7,993.00
		78026	3/24/2026	93004	POPPY HILL BOOSTER PUMP STATIO	$8,643.25
	MONTEREY BAY WATER WORKS ASSOCIATION	77880	3/18/2026	TRAINING 3/25/26	WATER SERVICE STAFF MAR 2026 WATER TREATMENT DISTR	$700.00
		77880	3/18/2026	MARCH 2026 TRAINING	MARCH 2026 WATER TREATMENT DISTRIBUTION	$300.00
		77880	3/18/2026	MARCH 2026 TRAINING	MARCH 2026 WATER TREATMENT DISTRIBUTION	$50.00
	NEW IMAGE LANDSCAPE COMPANY	78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$126.42
		78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$168.22
	PACIFIC CREDIT SERVICES INC	78038	3/24/2026	791400000079	COLLECTIONS COMMISSION	$491.79
		78038	3/24/2026	7914000000084	COLLECTIONS COMMISSIONS	$320.04
	PACIFIC GAS & ELECTRIC	78214	4/8/2026	7624842502-7-3/25/26	130 RODRIGUEZ ST	$144.26
		78215	4/8/2026	8999729770-3-3/25/26	127 RIVERSIDE DR	$2.88
		78128	3/25/2026	8693283387-3-3/16/26	8693283387-3-3/16/26	$76,592.70
		78124	3/25/2026	8257828808-4-3/17/26	101 LIGHTHOUSE DR	$12,932.57
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$26.28

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0720	PACIFIC GAS & ELECTRIC	77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1.58
		77882	3/18/2026	1553836670-7-3/6/26	1553836670-7	$1,317.57
	POSTMASTER	78056	3/24/2026	PERMIT 128 2/20/26	USPS MARKETING MAIL PERMIT 128 2/20/26	$370.00
	RDO EQUIPMENT CO.	78059	3/24/2026	P1057839	SUPPLIES	$208.44
		78059	3/24/2026	P1001939	PARTS	$126.89
	REXEL USA, INC	78060	3/24/2026	S144065810	AB SERVICE TRAINING - ROBERTO ALANIS	$4,171.00
	RICOH USA, INC	78062	3/24/2026	5072830060	EQUIPMENT RENTAL	$201.28
		78062	3/24/2026	5072830060	EQUIPMENT RENTAL	$100.63
		78062	3/24/2026	5072859732	EQUIPMENT RENTAL	$15.79
		78062	3/24/2026	5072859616	EQUIPMENT RENTAL	$141.69
		78062	3/24/2026	5072860818	EQUIPMENT RENTAL	$132.89
		78062	3/24/2026	5072860929	EQUIPMENT RENTAL	$23.88
	SBS	78072	3/24/2026	0782702-IN	PURCHASE OF MATERIAL - SAND SL	$1,079.82
		78072	3/24/2026	0782871-IN	PURCHASE OF MATERIAL - SAND SL	$1,262.62
		78072	3/24/2026	0783082-IN	PURCHASE OF MATERIAL - SAND SL	$3,258.36
	SECURITY SHORING AND STEEL PLATES INC.	78075	3/24/2026	164868	INV#164868 3/8" SHORING PINS AND SHORING O-RINGS	$131.10
	SHRED-IT USA	78078	3/24/2026	8013494937	MONTHLY SERVICE	$58.29
		78078	3/24/2026	8013494937	MONTHLY SERVICE	$58.29
	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$435.03
		78134	3/25/2026	7008882191	PURCHASES	$71.63

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0720	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$106.30
		78134	3/25/2026	7008882191	PURCHASES	$59.70
		78134	3/25/2026	7008882191	PURCHASES	$83.53
		78134	3/25/2026	7008882191	PURCHASES	$33.67
		78134	3/25/2026	7008882191	PURCHASES	$76.80
		78134	3/25/2026	7008882191	PURCHASES	$44.09
		78134	3/25/2026	7008882191	PURCHASES	$181.98
		78134	3/25/2026	7008882191	PURCHASES	$201.89
		78134	3/25/2026	7008882191	PURCHASES	$78.99
	STURDY OIL COMPANY	78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,328.82
	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$10.96
		78090	3/24/2026	52800-3/2/26	PURCHASES	$120.80
	U S BANK CORPORATE PAYMENT SYSTEM	78222	4/8/2026	7771-1/22/26	COMPUTER STAND	$38.31
		78222	4/8/2026	7771-2/23/26	PARTS FOR WATER OPS	$3,580.84
		78135	3/25/2026	3458-2/23/26	TRAINING FEE	$1,500.00
		78135	3/25/2026	3458-2/23/26	OFFICE SUPPLIES	$181.93
		78135	3/25/2026	3458-2/23/26	OFFICE SUPPLIES	$104.24
		77885	3/18/2026	7789-2/23/26	BUSINESS CARDS FOR CRISTY CASSEL & MARIO BEJAR	$77.00
	WALLACE GROUP, A CALIFORNIA CORPORATION	78099	3/24/2026	67235	ENGINEERING DESIGN WATER MAIN	$7,309.45
	Fund Total					$823,527.47
0730	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$49.04

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0730	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$5.30
		78137	4/1/2026	2/28/26	PURCHASES	$29.62
		78137	4/1/2026	2/28/26	PURCHASES	$269.96
		77868	3/18/2026	1/31/26	PURCHASES	$5.69
	ARTT PAINT SUPPLIES LLC	78139	4/1/2026	WNXBY	AIRPORT OPERATIONS BUILDINGS	$182.73
		78139	4/1/2026	HD944	TRAFFIC PAINT	$368.74
		78139	4/1/2026	6XXWA	WATER LEAKS	$365.47
	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$395.43
	CAPITOLA PUMP COMPANY INC	77941	3/24/2026	58950	LABOR TO REPLACE CHECK VALVE ON 5HP PUMP	$666.62
	CHARTER COMMUNICATIONS	78143	4/1/2026	0091405032126	INTERNET	$289.89
		78108	3/25/2026	170045401031426 -3/14	INTERNET	$218.15
	CHAZ TOWING	77946	3/24/2026	91397	TOW	$225.00
		77946	3/24/2026	92412	WINCH OUT RECOVERY	$550.00
	DELTA GLASS	77960	3/24/2026	93756	LABOR STOREFRONT DOOR	$160.00
	DONALD WHITESIDE	77964	3/24/2026	REFUND FIRE EXT	REFUND FOR FIRE EXTINGUISHER	$40.00
	FANNIN FENCING	77971	3/24/2026	1831	GATE SERVICE AND REPAIR	$455.00
	FIRST ALARM, INC.	78111	3/25/2026	923816	ALARM MONITORING	$1,357.95
		78111	3/25/2026	923816	ALARM MONITORING	$389.61
		78111	3/25/2026	942045	ALARM MONITORING	$389.61
		78111	3/25/2026	942045	ALARM MONITORING	$1,357.95
		77975	3/24/2026	940469	PERMITS	$357.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0730	KIMLEY-HORN & ASSOCIATES, INC.	77875	3/18/2026	29555835	FIVE-YEAR ON DEMAND CONTRACT	$8,123.00
		77875	3/18/2026	29555835	FIVE-YEAR ON DEMAND CONTRACT	$1,627.00
	MID VALLEY SUPPLY	78024	3/24/2026	3/3/2026	PURCHASES	$365.97
		78024	3/24/2026	3/3/2026	PURCHASES	$184.18
		78024	3/24/2026	3/3/2026	PURCHASES	$164.44
	MISSION LINEN SUPPLY	78202	4/8/2026	320474-4/1/2026	UNIFORM RENTAL SERVICES	$963.53
	MONUMENT LUMBER COMPANY	78029	3/24/2026	2603-013649	SUPPLIES	$46.90
	NUTRIEN AG SOLUTIONS	78034	3/24/2026	58421986	SUPPLIES	$1,125.37
	PACIFIC CREST ENGINEERING, INC	78114	3/25/2026	16186	CONSTRUCTION SUPPORT SERVICES	$190.00
	PACIFIC GAS & ELECTRIC	78216	4/8/2026	3682041072-2-3/24/26	50 AVIATION WAY	$1,112.27
		78155	4/1/2026	9830958081-3-3/23/26	125 AVIATION WAY	$26.98
		78126	3/25/2026	2209323609-3-3/16/26	2209323609-3/16/26	$11,792.17
		78041	3/24/2026	6558284005-7-3/13/26	123 AVIATION WAY	$923.60
		78042	3/24/2026	3823955332-4-3/13/26	AIRPORT BLVD AND HOLM RD	$170.50
		78044	3/24/2026	1506815321-0-3/12/26	150 AVIATION WAY	$214.78
	PAJARO VALLEY PRINTING	78047	3/24/2026	50533	TRANSIENT PARKING FEE	$645.33
	RICOH USA, INC	78062	3/24/2026	5072860530	EQUIPMENT RENTAL	$99.38
	ROBINSON, MITCHELL	78164	4/1/2026	2898	EQUIPMENT COVERS	$375.00
		78164	4/1/2026	2897	VEHICLE GATE SIGNAGE	$1,900.95

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0730	WORLD FUEL SERVICES	77887	3/18/2026	1188010	PURCHASE OF AVIATION GRADE GAS	$41,686.40
		77887	3/18/2026	1188666	PURCHASE OF AVIATION GRADE GAS	$32,470.73
		78136	3/25/2026	1190691	PURCHASE OF AVIATION GRADE GAS	$47,304.85
	Fund Total					$159,642.09
0740	A L LEASE COMPANY, INC	77908	3/24/2026	188377	SUPPLIES	$107.20
	A-1 JANITORIAL SERVICE	77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$350.00
		77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$1,226.62
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$350.00
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$1,226.62
		77910	3/24/2026	9337	JANITORIAL SERVICES AT MSC CY2	$40.00
		77910	3/24/2026	9348	MSC PRESSURE WASH CLEAN	$1,200.00
	AAA BUSINESS SUPPLIES	78048	3/24/2026	2485365-0	MATERIALS	$301.41
	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$44.88
		78137	4/1/2026	2/28/26	PURCHASES	$329.23
		78137	4/1/2026	2/28/26	PURCHASES	$27.38
		78137	4/1/2026	2/28/26	PURCHASES	$140.39
		78137	4/1/2026	2/28/26	PURCHASES	$15.34
		78137	4/1/2026	2/28/26	PURCHASES	$49.38
		78137	4/1/2026	2/28/26	PURCHASES	$96.22
		78137	4/1/2026	2/28/26	PURCHASES	$32.91
		77868	3/18/2026	1/31/26	PURCHASES	$24.78
		77868	3/18/2026	1/31/26	PURCHASES	$21.94

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0740	ACE HARDWARE	77868	3/18/2026	1/31/26	PURCHASES	$50.46
		77868	3/18/2026	1/31/26	PURCHASES	$26.30
	AIR UNLIMITED	77912	3/24/2026	379762	INV#379762 RECYCLING DEPT PROPANE 42 GAL ON 3/3/20	$183.91
		77912	3/24/2026	379872	INV#379872 RECYCLING DEPT PROPANE 26 GAL ON 3/5/20	$113.86
		77912	3/24/2026	380009	INV#380009 RECYCLING DEPT PROPANE 43.50 GAL ON 3/1	$190.49
		77912	3/24/2026	380156	INV#380156 RECYCLING DEPT PROPANE 42 GAL ON 3/13/2	$191.91
	ARRIAGA, JOHN	77923	3/24/2026	8327	State Advocacy and Consulting	$1,750.00
	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$45.49
		77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$213.92
	BIG BELLY SOLAR, LLC	77929	3/24/2026	61744	INV#61744 BUBBLE ASSEMBLY KIT	$1,538.02
	CALIFORNIA DEPARTMENT OF TAX & FEE ADMINISTRATION	77937	3/24/2026	L0034820210	OCTOBER 1, 2025 TO DECEMBER 31, 2025 LATE FEE-INTE	$84.82
	CAMPOS BROS. RECOVERY, INC.	77939	3/24/2026	20923	CERTIFIED APPLIANCE RECYCLER P	$839.00
		77939	3/24/2026	20003	CERTIFIED APPLIANCE RECYCLER P	$685.00
	CAPITAL EDGE ADVOCACY, INC.	77940	3/24/2026	26-40	Federal Legislative Advocacy a	$1,000.00
	CP COMPACTORS & BALERS	77952	3/24/2026	3296653	INV#3296653 COMPACTOR @ 433 UNION ST/23 E BEACH ST	$1,756.37
	CRUZIO/THE INTERNET STORE INC.	78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$37.47
	D&G SANITATION	77956	3/24/2026	318820	PORTABLE TOILET	$104.26
	DIXON & SONS TIRES INC.	77963	3/24/2026	100621-2/27/26	PURCHASES	$55.00

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0740	EL PAJARO COMMUNITY DEV CORP	77967	3/24/2026	P-10773	INV#P-10773 PLAZA VIGIL JANITORIAL SERIVICES FOR J	$473.00
		77967	3/24/2026	P-10772	INV#P-10772 JANITORIAL SERVICES FOR DECEMBER 2025	$473.00
	FASTENAL COMPANY	77973	3/24/2026	CAWAT142406	PPE	$150.91
	KEITH DAY COMPANY, INC.	78003	3/24/2026	77869	MULCH/COMPOST PROCUREMENT FOR	$327.88
	MATHESON TRI-GAS INC.	78018	3/24/2026	0032942152	INV#0032942152 NITROGEN	$502.29
	MISSION LINEN SUPPLY	77878	3/18/2026	321329-2/28/26	UNIFORM RENTAL SERVICES	$130.58
		78199	4/8/2026	320469-3/31/26	UNIFORM RENTAL SERVICES	$496.25
		78201	4/8/2026	320467-3/31/26	UNIFORM RENTAL SERVICES	$1,313.16
	MONTROSE ENVIRONMENTAL SOLUTIONS, INC	77969	3/24/2026	CINV-489095	LANDFILL REGULATORY SERVICES/P	$3,354.63
	NEW IMAGE LANDSCAPE COMPANY	78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$263.16
		78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$84.62
	PACIFIC GAS & ELECTRIC	78210	4/8/2026	1437608399-5-3/20/26	1437608399-5-3/20/26	$3,554.55
	PAJARO VALLEY LOCK SHOP	78046	3/24/2026	1-13690	DUPLICATE KEY	$240.25
	PAJARO VALLEY PRINTING	78047	3/24/2026	50520	RECYCLE SIGNS	$566.31
	PAPE MACHINERY, INC	78050	3/24/2026	1841664	VEHICLE & EQUIPMENT REPAIR SER	$11,290.43
		78050	3/24/2026	1841344	VEHICLE & EQUIPMENT REPAIR SER	$43,377.55
	PETERSON	78052	3/24/2026	SW080079536	INV#SW080079536 REPAIR TO AA 813 #CAT00816KJ6N0014	$1,537.75
	RICARDO CARRILLO	78061	3/24/2026	1ST BOOT REIMB 3/16	PW-1ST BOOT REIMBURSEMENT 3/16	$250.00
	RICOH USA, INC	78062	3/24/2026	5072830060	EQUIPMENT RENTAL	$100.63

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0740	RICOH USA, INC	78062	3/24/2026	5072859616	EQUIPMENT RENTAL	$141.70
	SILKE COMMUNICATIONS	78079	3/24/2026	INV-23003989	INV-23003989 BNC/F SMA/F ADAPTER NMO BLK MAF MNT C	$488.08
	STAPLES BUSINESS CREDIT	78134	3/25/2026	7008882191	PURCHASES	$62.73
		78134	3/25/2026	7008882191	PURCHASES	$61.01
		78134	3/25/2026	7008882191	PURCHASES	$38.17
	STURDY OIL COMPANY	78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,528.56
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$429.13
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,548.21
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,227.95
	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$22.91
	TRI-COUNTY FIRE PROTECTION INC	78092	3/24/2026	66712	ABC SERVICE	$633.29
		78092	3/24/2026	66716	ABC SERVICE	$202.55
	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	3458-2/23/26	SAFETY MEETING LUNCH	$242.59
		78135	3/25/2026	3458-2/23/26	GRIDDLE FOR KITCHEN	$10.74
		78135	3/25/2026	3458-2/23/26	SAFETY MEETING LUNCH	$104.00
		78135	3/25/2026	3458-2/23/26	SWANA SYMPOSIUM	$1,000.00
		78135	3/25/2026	3458-2/23/26	SWANA SYMPOSIUM	$1,000.00
		78135	3/25/2026	3458-2/23/26	N. CA RECYCLING ASSOC. UPDATE	$250.00
		78135	3/25/2026	3458-2/23/26	N. CA RECYCLING ASSOC. UPDATE	$250.00
		78135	3/25/2026	3458-2/23/26	TOLL FEE	$12.70

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0740	WATSONVILLE FORD	78102	3/24/2026	G014WF15208	2026 F350 4x4 Reguar Service Truck	$82,225.95
	WEST COAST RUBBER RECYCLING	78104	3/24/2026	26-0299	INV#26-0299 TIRE DISPOSAL	$856.90
	Fund Total					$175,274.70
0741	SWT ENGINEERING, INC	78085	3/24/2026	20261160	ENGINEERING SRVCS LANDFILL PH.	$570.94
	Fund Total					$570.94
0760	A TOOL SHED RENTALS, INC.	77909	3/24/2026	1783080-6	RENTALS	$119.24
	A-1 JANITORIAL SERVICE	77910	3/24/2026	9347	JANITORIAL SERVICES AT MSC CY2	$268.93
		77910	3/24/2026	9336	JANITORIAL SERVICES AT MSC CY2	$268.93
	ACE HARDWARE	78137	4/1/2026	2/28/26	PURCHASES	$49.38
		78137	4/1/2026	2/28/26	PURCHASES	$41.65
		78137	4/1/2026	2/28/26	PURCHASES	$58.63
		78137	4/1/2026	2/28/26	PURCHASES	$29.62
		78137	4/1/2026	2/28/26	PURCHASES	$47.14
		78137	4/1/2026	2/28/26	PURCHASES	$19.72
		77868	3/18/2026	1/31/26	PURCHASES	$38.38
		77868	3/18/2026	1/31/26	PURCHASES	$3.47
		77868	3/18/2026	1/31/26	PURCHASES	$13.15
	ARATA EQUIPMENT COMPANY	77922	3/24/2026	1-123263	SUPPLIES	$577.47
		77922	3/24/2026	1-123227	HDRH LIFT CYLINDER	$4,543.86
		77922	3/24/2026	1-123019	PARTS	$775.69
		77922	3/24/2026	1-123186	PARTS	$11,948.50
	BURTON'S FIRE APPARATUS, INC.	77933	3/24/2026	S70970	SUPPLIES	$1,172.28

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0760	COAST COUNTIES TRUCK & EQUIP	77950	3/24/2026	002337376P	PARTS	$313.72
		77950	3/24/2026	002337297P	SUPPLIES	($27.95)
		77950	3/24/2026	02336479P	RETURNS	($445.74)
		77950	3/24/2026	02336403P	SUPPLIES	$189.39
		77950	3/24/2026	02336509P	PARTS	$121.80
	EAST BAY TIRE CO.	77965	3/24/2026	2222802	TIRES	$1,759.50
	GCS ENVIRONMENTAL EQUIPMENT SERVICES	77980	3/24/2026	31650	SUPPLIES	$72.31
	GE SOFTWARE, INC	77871	3/18/2026	225472	RR PREBILLED GSS	$240.00
		77871	3/18/2026	225882	EKOS SERVICE & REPAIR	$2,331.20
		77871	3/18/2026	226671	ANCILLARY TELETRAC EQUIPMENT	$100.65
		77871	3/18/2026	224430	RR PREBILLED EV MODULE	$360.00
	GRAINGER	77983	3/24/2026	9840029301	SUPPLIES	$13.92
		77983	3/24/2026	9836332867	SUPPLIES	$151.59
		77983	3/24/2026	9830409729	SUPPLIES	$160.06
	INTERSTATE BATTERY CO	77997	3/24/2026	110010422	BATTERIES	$1,222.46
	KIMBALL MIDWEST	78004	3/24/2026	104242263	SUPPLIES	$962.63
	MISSION LINEN SUPPLY	78198	4/8/2026	320440-4/2/26	UNIFORM RENTAL SERVICES	$316.29
	MUNICIPAL MAINTENANCE EQUIPMENT	78030	3/24/2026	046958	INV#046958. DRIVESHAFT, L/H, INT IV (SHORT) & DRIV	$1,233.72
	NEW IMAGE LANDSCAPE COMPANY	78032	3/24/2026	153529	LANDSCAPE MAINTENANCE FEB 2026	$73.79
	NPM, INC.	78033	3/24/2026	188643	OPERATORS MONTHLY VISUAL	$270.00
	O'REILLY AUTOMOTIVE INC.	78035	3/24/2026	2912-235945	CABIN FILTER	$69.49

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0760	O'REILLY AUTOMOTIVE INC.	78035	3/24/2026	2912-232915	PARTS	$46.07
		78035	3/24/2026	2912-233554	PARTS	$47.01
	PACIFIC TRUCK PARTS	78045	3/24/2026	01P3867	PARTS	$329.55
		78045	3/24/2026	01P3672	PARTS	$585.99
		78045	3/24/2026	01P3647	PARTS	$227.48
	PETERSON TRUCKS, INC.	78053	3/24/2026	4566745	INV#4566745. 2035007C2 SWITCH, PRESSURE OPEN @ 2-6	$290.12
	PLATT	78055	3/24/2026	7D88384	SUPPLIES	$392.70
	QUINTERO TIRES WHEEL SERVICE	78058	3/24/2026	21691	WHEEL ALIGNMENT	$120.00
	RICOH USA, INC	78062	3/24/2026	5072860430	RICOH EQUIPMENT	$3.06
	SALINAS VALLEY FORD LINCOLN	78068	3/24/2026	69420	PARTS	$122.03
		78068	3/24/2026	69583	INV#69583. OUTER TIE ROD END (RIMZ*3A130*C).	$72.87
		78068	3/24/2026	69540	INV#69540. TIE ROD END (RIMZ*3A130*B).	$72.87
		78068	3/24/2026	69369	INV#69369 OIL COOSPO, END-SSPO, ARM ASYSPO-MSC VEH	$564.11
		78068	3/24/2026	69438	INV#69438. TIE END ROD (RIMZ*3a130*B).	$72.87
	SHIRAISHI, SCOT	78077	3/24/2026	EMPLOYEE REIMB 11/25	TOOL REIMBURSEMENT 11/25/25	$2,000.00
	SOUTHERN TIRE MART, LLC	78082	3/24/2026	7350017100	INV#7350017100. TIRES (LT245/75R17/10 TRNSFRCE AT2	$362.27
	STURDY OIL COMPANY	78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$886.01
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$26,711.37

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0760	STURDY OIL COMPANY	78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,175.99
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$258.73
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,004.67
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$31,643.07
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,053.56
		78169	4/2/2026	3050-2/28/26	PETROLEUM PRODUCTS FOR CITYWID	$1,673.77
	THE HOSE SHOP INC.	78089	3/24/2026	471864	SUPPLIES	$1,044.83
		78089	3/24/2026	471839	PARTS	$267.15
		78089	3/24/2026	471737	PARTS	$236.69
	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$43.88
		78090	3/24/2026	52800-3/2/26	PURCHASES	$76.02
		78090	3/24/2026	52800-3/2/26	PURCHASES	($148.17)
		78090	3/24/2026	52800-3/2/26	PURCHASES	$1,008.68
		78090	3/24/2026	52800-3/2/26	PURCHASES	$43.43
		78090	3/24/2026	52800-3/2/26	PURCHASES	$110.97
		78090	3/24/2026	52800-3/2/26	PURCHASES	$3.07
		78090	3/24/2026	52800-3/2/26	PURCHASES	$62.62
		78090	3/24/2026	52800-3/2/26	PURCHASES	$148.73
		78090	3/24/2026	52800-3/2/26	PURCHASES	$24.87
		78090	3/24/2026	52800-3/2/26	PURCHASES	$24.87

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0760	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$391.12
		78090	3/24/2026	52800-3/2/26	PURCHASES	$24.98
		78090	3/24/2026	52800-3/2/26	PURCHASES	$10.98
		78090	3/24/2026	52800-3/2/26	PURCHASES	$3.15
		78090	3/24/2026	52800-3/2/26	PURCHASES	$181.59
		78090	3/24/2026	52800-3/2/26	PURCHASES	$99.93
		78090	3/24/2026	52800-3/2/26	PURCHASES	$63.21
		78090	3/24/2026	52800-3/2/26	PURCHASES	$39.15
		78090	3/24/2026	52800-3/2/26	PURCHASES	$5.45
		78090	3/24/2026	52800-3/2/26	PURCHASES	$13.05
		78090	3/24/2026	52800-3/2/26	PURCHASES	$48.42
		78090	3/24/2026	52800-3/2/26	PURCHASES	$23.34
		78090	3/24/2026	52800-3/2/26	PURCHASES	$46.59
		78090	3/24/2026	52800-3/2/26	PURCHASES	$9.76
		78090	3/24/2026	52800-3/2/26	PURCHASES	$15.12
		78090	3/24/2026	52800-3/2/26	PURCHASES	$296.05
		78090	3/24/2026	52800-3/2/26	PURCHASES	$23.90
		78090	3/24/2026	52800-3/2/26	PURCHASES	($23.90)
		78090	3/24/2026	52800-3/2/26	PURCHASES	$194.23
		78090	3/24/2026	52800-3/2/26	PURCHASES	$45.39
		78090	3/24/2026	52800-3/2/26	PURCHASES	$99.83
		78090	3/24/2026	52800-3/2/26	PURCHASES	$17.37

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0760	TOWNSEND AUTO PARTS	78090	3/24/2026	52800-3/2/26	PURCHASES	$34.75
		78090	3/24/2026	52800-3/2/26	PURCHASES	$95.28
		78090	3/24/2026	52800-3/2/26	PURCHASES	$22.38
		78090	3/24/2026	52800-3/2/26	PURCHASES	$130.25
		78090	3/24/2026	52800-3/2/26	PURCHASES	($19.76)
		78090	3/24/2026	52800-3/2/26	PURCHASES	$100.96
		78090	3/24/2026	52800-3/2/26	PURCHASES	$63.90
		78090	3/24/2026	52800-3/2/26	PURCHASES	($21.95)
		78090	3/24/2026	52800-3/2/26	PURCHASES	$7.45
	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	5738-2/23/26	RTA IPAD COVER	$81.20
		78135	3/25/2026	3458-2/23/26	TOLL FEE	$13.30
	WATSONVILLE CHRYSLER DODGE JEEP RAM	78100	3/24/2026	49269	PARTS	$230.91
	WORLD OIL ENVIRONMENTAL SERVICES	78106	3/24/2026	I500-01323733	INV#I500-01323733. USED OIL/MIXED OILS & USED OIL	$153.00
	Fund Total					$104,649.06
0780	BURKE, WILLIAMS & SORENSEN, LLP	77932	3/24/2026	360844	CITY ATTORNEY SERVICES	$229.35
		77932	3/24/2026	360865	CITY ATTORNEY SERVICES	$134.00
		77932	3/24/2026	360868	CITY ATTORNEY SERVICES	$33.50
		77932	3/24/2026	360847	CITY ATTORNEY SERVICES	$2,100.00
	RICHARD D JONES, A PROFESSIONAL LAW CORP	78132	3/25/2026	139522	PROFESSIONAL SERVICES	$810.00
		78132	3/25/2026	139897	PROFESSIONAL SERVICES	$19.61
	Fund Total					$3,326.46

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0787	BENEFIT COORDINATORS CORP.	78193	4/8/2026	B0M9XK	DENTAL CLAIMS	$9,012.04
		78193	4/8/2026	B0MD2D	DENTAL CLAIMS	$10,461.30
		78193	4/8/2026	B0MNQF	DENTAL CLAIMS	$10,257.71
		78193	4/8/2026	B0MDG7	DENTAL CLAIMS	$5,784.42
		78193	4/8/2026	B0MP6G	DENTAL CLAIMS	$11,909.67
		78193	4/8/2026	B0MPRC	DENTAL CLAIMS	$7,773.62
		78193	4/8/2026	B0LV03	DENTAL CLAIMS	$9,075.52
		78193	4/8/2026	B0LVM8	DENTAL CLAIMS	$7,414.90
		78193	4/8/2026	B0LWD9	DENTAL CLAIMS	$9,016.04
		78193	4/8/2026	B0M0FH	DENTAL CLAIMS	$12,718.00
		78193	4/8/2026	B0M0S2	DENTAL CLAIMS	$5,774.07
		78193	4/8/2026	B0M953	DENTAL CLAIMS	$5,145.07
		78193	4/8/2026	B0LFML	DENTAL CLAIMS	$13,580.14
		78193	4/8/2026	B0LFXJ	DENTAL CLAIMS	$8,601.56
		78193	4/8/2026	B0LHYP	DENTAL CLAIMS	$6,189.77
		78193	4/8/2026	B0LL7Z	DENTAL CLAIMS	$7,246.53
		78141	4/1/2026	B0MNMV	HEALTH BENEFITS FOR 2026 APRIL	$845,127.25
	Fund Total					$985,087.61
0790	AIRTEC SERVICE,INC	77914	3/24/2026	36310	CITYWIDE HVAC MAINTENANCE	$290.80
		77914	3/24/2026	36490	CITYWIDE HVAC MAINTENANCE	$118.80
	AT&T MOBILITY LLC	77924	3/24/2026	87320260154X031 02026	CELL & DATA CHARGES FOR CITY FRM 02/03/26-03/02/26	$174.96

Fund #	Vendor Name	Check #	Invoice Date	Invoice	Invoice Description	Amount
0790	AT&T-CAL NET 2	78140	4/1/2026	000024872590	1GB INTERNET LINE FOR FEB. 2026 acct# 2857222	$1,773.06
	CRUZIO/THE INTERNET STORE INC.	78144	4/1/2026	N29135-196	WIRELESS PRO FOR APRIL 2026	$1,499.00
	FUSION LLC	77977	3/24/2026	10237898	TELEPHONE SUPPORT APRIL PLUS LATE CHARGE FEB INV	$6,038.58
	MID VALLEY SUPPLY	78024	3/24/2026	3/3/2026	PURCHASES	$34.25
	RICOH USA, INC	78062	3/24/2026	5072860541	EQUIPMENT RENTAL	$7.03
	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	5738-2/23/26	WHITEBOARD FOR GIS STAFF	$73.16
		78135	3/25/2026	5738-2/23/26	PACIFIC ARC RULER FOR GIS STAFF	$34.68
		78135	3/25/2026	5738-2/23/26	CUTTING MAT FOR GIS STAFF	$41.68
		78135	3/25/2026	5738-2/23/26	EXACTO KNIFE FOR GIS STAFF	$4.97
		78135	3/25/2026	5738-2/23/26	ASSET TAG FOR CITY OF WATSONVILLE DEVICES	$408.31
	Fund Total					$10,499.28
0825	U S BANK CORPORATE PAYMENT SYSTEM	78135	3/25/2026	0540-2/23/26	SPECIALIZED EQUIPMENT	$2,698.35
		78135	3/25/2026	0540-2/23/26	SPECIALIZED EQUIPMENT	$650.00
		78135	3/25/2026	0540-2/23/26	SPECIALIZED EQUIPMENT	$2,291.17
		78135	3/25/2026	0540-2/23/26	SWAT-SPECIAL EQUIPT	$188.07
	Fund Total					$5,827.59
Total	Total					$9,216,685.81

MISCELLANEOUS DOCUMENTS REPORT
APRIL 14, 2026

1.0 PROCLAMATIONS

--C.A.R. Day of Service
April 5, 2026

--K&D Landscaping
Outstanding Large Business of the Year
April 9, 2026

--Manny Escarcega
West Coast Community Bank
Ambassador of the Year
April 9, 2026

--Erica Padilla-Chavez
2026 Strong, Smart, and Bold Award
April 11, 2026

Proclamation

C.A.R. Day of Service

April 5, 2026

WHEREAS, the National Society of the Children of the American Revolution (N.S.C.A.R) is the nation's oldest and largest patriotic youth organization, founded April 5, 1895; and

WHEREAS, the N.S.C.A.R. focuses on patriotism, service and education about our American heritage; and

WHEREAS, the local society, N.S.C.A.R. is active in our local community promoting this vision to the residents of our City and surrounding community; and

WHEREAS, the local society is dedicated to helping the youth in our community thru the Kids Helping Kids program committee.

NOW, THEREFORE, I, Kristal Salcido, Mayor of the City of Watsonville, in the State of California, on behalf of the City Council hereby recognize C.A.R. Day of Service and commend them for their important work.

IN WITNESS WHEREOF, I have hereunto set my hand and caused the Seal of the City of Watsonville to be affixed this 5th day of April, Two thousand and twenty-six.

Kristal Salcido, Mayor

WATSONVILLE, CALIFORNIA

Proclamation

K&D Landscaping
Outstanding Large Business of the Year
April 9, 2026

WHEREAS, founded in 1986 as a humble, small family operation, K&D Landscaping has grown into a $20 million regional leader without losing its core values; and

WHEREAS, driven by deep local roots, K&D Landscaping launched its Community Beautification Projects in 2016 to give back to the region that built them; and

WHEREAS, since then, they have beautified over 35 nonprofits, investing more than $200,000 last year alone to ensure the community thrives; and

WHEREAS, K&D Landscaping is redefining the industry with California's first Level 5 autonomous commercial fleet and 100% electric handheld tools; and

WHEREAS, amidst this rapid technological advancement, K&D Landscaping fiercely protects a supportive, people-first company culture, allowing them to sustain an 85% employee retention rate; and

WHEREAS, looking ahead, K&D Landscaping is expanding toward the Bay Area and San Luis Obispo County with a vision to become a $1 billion company by 2035; and

WHEREAS, as they build a path to a $100,000 minimum salary for their team, the ultimate mission of K&D Landscaping remains clear: to raise the bar in landscaping.

NOW, THEREFORE, I, Kristal Salcido, Mayor of the City of Watsonville, in the State of California, on behalf of the City Council hereby congratulate K&D Landscaping for receiving the Outstanding Large Business of the Year Award from the Salinas Valley Chamber of Commerce.

IN WITNESS WHEREOF, I have hereunto set my hand and caused the Seal of the City of Watsonville to be affixed this 9th day of April, Two thousand and twenty-six.

Kristal Salcido, Mayor

Proclamation

Manny Escarcega
West Coast Community Bank
Ambassador of the Year
April 9, 2026

WHEREAS, Manny Escarcega has proudly served as a Chamber Ambassador for over four years, representing the organizations he's been part of with professionalism and heart; and

WHEREAS, with over 20 years in banking, currently with West Coast Community Bank as a Treasury Management Advisor and previously a Branch Manager with Bay Federal Credit Union, Manny brings strong financial expertise and a relationship-focused approach to his role; and

WHEREAS, Manny is a consistent presence at mixers, ribbon cuttings, signature events, and volunteer initiatives, always supporting members and Chambers efforts; and

WHEREAS, Manny recently served as Co-Chair of the Chamber Foundation's Children's Shopping Tour, helping lead one of the Chamber's most impactful community programs; and

WHEREAS, his leadership, organization, and dedication were instrumental in creating a meaningful experience for local children and families; and

WHEREAS, Manny supports his family's restaurant, Tacos Al Fuego, reflecting his passion for small business and local entrepreneurship; and

WHEREAS, a devoted family man, Manny is a proud father of four children, ages 4, 10, 11, and 25, and shares his life with his fiancée Evelyn; and

WHEREAS, Manny exemplifies the spirit of ambassadorship, engaged, dependable, and always willing to serve and step forward.

NOW, THEREFORE, I, Kristal Salcido, Mayor of the City of Watsonville, in the State of California, on behalf of the City Council hereby congratulate Manny Escarcega for receiving the Ambassador of the Year Award from the Salinas Valley Chamber of Commerce.

IN WITNESS WHEREOF, I have hereunto set my hand and caused the Seal of the City of Watsonville to be affixed this 9th day of April, Two thousand and twenty-six.

Kristal Salcido, Mayor

Watsonville
CALIFORNIA

Proclamation

Erica Padilla-Chavez
2026 Strong, Smart, and Bold Award
April 11, 2026

WHEREAS, Erica Padilla-Chavez, a proud Watsonville native, graduated from Watsonville High School and was the first in her family to attend college, earning her Bachelor of Arts in Sociology from University of California Berkely and later receiving her Master's in Public Administration from Golden State University in San Francisco; and

WHEREAS, Erica has dedicated her career to advancing health and wellness for all, with over two decades of experience in the health and human services field; and

WHEREAS, her career spans diverse administrative roles, and most notably, Erica served as CEO of Pajaro Valley Prevention & Student Assistance, Inc., where she spearheaded the development of a cutting edge integrated behavioral health facility, providing vital services to children, youth, and families; and

WHEREAS, in July 2022, Erica became CEO of Second Harvest Food Bank Santa Cruz County, making her only the second leader in the organization's history; and

WHEREAS, Erica is committed to ending food insecurity in the community through a collaborative approach that unites private, public, and community centered partnerships; and

WHEREAS, in her brief tenure, Erica has launched the Healthy Food Box Program, a Medi-Cal reimbursable service under the State's CalAIM initiative, established an on-site pantry at a community hospital, and created closed-loop referral systems with all federally qualified health clinics in the county; and

WHEREAS, Erica serves on Dominican Hospital's Community Board, the California Association of Food Banks Board, as a Task Force member in Feeding America's Health Care Partnership, and is a founding member of the RISE Together Santa Cruz County Race Equity Initiative; and

WHEREAS, Erica is married to Alejandro Chavez, a UCSC alum, and they share two children, Emileo and Maya, who were both born in Santa Cruz.

NOW, THEREFORE, I, Kristal Salcido, Mayor of the City of Watsonville, in the State of California, on behalf of the City Council hereby congratulate Erica Padilla-Chavez for receiving the 2026 Strong, Smart, and Bold Award from Girls Inc.

SEAL OF THE CITY OF WATSONVILLE, CAL. PAJARO RECOGNIZED MAY 14TH 1868

IN WITNESS WHEREOF, I have hereunto set my hand and caused the Seal of the City of Watsonville to be affixed this 11th day of April, Two thousand and twenty-six.

Kristal Salcido, Mayor

Conference/Seminar Summary

City of Watsonville
275 Main St 4th Floor
Watsonville, CA 95076
(831)768-3008

To:	The Honorable Mayor & City Council
Council Meeting Date:	04/14/2026
City Council Member:	Jimmy Dutra
Conference/Seminar:	NLC Congressional City Conference
Location:	Washington D.C
Dates of Travel:	03/15/26 – 03/18/26

Please provide a brief report on the conference, seminar, or meeting you attended.

This year's congressional conference offered us the opportunity to hear from federal agency experts and other advocacy professionals on the federal-local connections and the impact of federal policy on local governments. It allowed for us to strengthen our partnerships with policy experts and other local government advocates. It also provided an opportunity to network with federal agencies to leverage federal programs and funding. We also got to lobby our federal leaders with potential local projects.

Conference/Seminar Summary

City of Watsonville
275 Main St 4th Floor
Watsonville, CA 95076
(831)768-3008

To: The Honorable Mayor & City Council
Council Meeting Date: 04/14/2026

City Council Member: Ari Parker
Conference/Seminar: 2026 NLC Congressional City Conference
Location: Washington D.C
Dates of Travel: 03/16/2026 – 03/18/2026

Please provide a brief report on the conference, seminar, or meeting you attended.

I attended the National League of Cities Congressional Cities Conference in Washington D.C. from March 16-18 representing the City of Watsonville. In addition to attending and gathering information from Conference workshops such as "Public Safety and Tech for Local Leaders We also participated in policy roundtables with strategic partners from California and other states. Supported by our federal Lobbyists we also advocated in meetings on Capitol Hill with Senator Padilla and Schiff in a California Cities Roundtable and had individual meetings with Congressman Jimmy Panetta and our Congresswoman, Zoe Lofgren regarding the advancement of Public Safety and Quality of Life in Watsonville through funding of the following: Wastewater Treatment Plant Improvements, Developing more open space in our city, Modernizing Emergency Communication systems for Public Safety, Pavement Management in improving Watsonville's Streets & Transportation, and addressing critical infrastructure needs of our city.

At the conclusion of the event, a brief report on the conference or seminar attended at the expense of the City must be presented to the City Council at the next regularly scheduled City Council Meeting.
Government Code Section 53234

Docusign Envelope ID: D0F5EF33-B573-4F6F-B1B4-9A2405D1BA7B

Conference/Seminar Summary

City of Watsonville
275 Main St 4th Floor
Watsonville, CA 95076
(831)768-3008

To:	The Honorable Mayor & City Council
Council Meeting Date:	04/14/2026

City Council Member:	Kristal Salcido
Conference/Seminar:	National League of Cities 2026 Congressional City Conference
Location:	Washington D.C
Dates of Travel:	03/16/2026 – 03/18/2026

Please provide a brief report on the conference, seminar, or meeting you attended.

We attended programming specific to.city issues at the National League of Cities conference. We met with Congresswomn Loftgren and Panetta for requests that would improve our city. Topics for the conference were extensive, including public safety, FEMA, infrastructure, funding for targeted programs for youth, and community development.

At the conclusion of the event, a brief report on the conference or seminar attended at the expense of the City must be presented to the City Council at the next regularly scheduled City Council Meeting.
Government Code Section 53234

Commissioner Attendance Log 2026

Library Commission

	January	February	March	April	May	June	July	August	September	October	November	December
District 1 *VACANT*												
District 2 *Pedro Reynoso*	PRESENT	ABSENT	PRESENT									
District 3 *Ruth Landmann*	PRESENT	PRESENT	PRESENT									
District 4 *Jesus Vega*	PRESENT	PRESENT	PRESENT									
District 5 *Don Brown*	PRESENT	PRESENT	PRESENT									
District 6 *Tony Camargo*	PRESENT	PRESENT	PRESENT									
District 7 *Wayne Hayashibara*	ABSENT	PRESENT	PRESENT									

Parks & Recreation Commission

	January	February	March	April	May	June	July	August	September	October	November	December
District 1 Araseli Campos	PRESENT	PRESENT	CANCELLED									
District 2 *Francisco Estrada*	PRESENT	PRESENT	CANCELLED									
District 3 *Fabian Leonor*	PRESENT	PRESENT	CANCELLED									
District 4 *Jennifer Schacher*	PRESENT	PRESENT	CANCELLED									
District 5 *Celeste DeWald*	PRESENT	PRESENT	CANCELLED									
District 6 *Noe Ibarra*	PRESENT	PRESENT	CANCELLED									
District 7 *Emiko Stewart*	PRESENT	PRESENT	CANCELLED									

Personnel Commission

	January	February	March	April	May	June	July	August	September	October	November	December
District 1 *Angel Zuniga*	N/A	N/A	PRESENT									
District 2 *Tony Camargo*	N/A	N/A	PRESENT									
District 3 *VACANT*	N/A	N/A	N/A									
District 4 *Sylvia Margaret Mendez*	N/A	N/A	ABSENT									
District 5 *Eric Sturm*	N/A	N/A	PRESENT									
District 6 *Alicia Danna*	N/A	N/A	PRESENT									
District 7 *Joyce Parr*	N/A	N/A	ABSENT									

Planning Commission SPECIAL MTG

	January	February	March	April	May	June	July	August	September	October	November	December
District 1 *Daniel Dodge*	N/A	ABSENT	PRESENT									
District 2 *Brando Sencion - Vice Chair*	N/A	UNEXCUSED	UNEXCUSED									
District 3 *Jenni Veitch-Olson*	N/A	PRESENT	PRESENT									
District 4 *Lowell Hurst*	N/A	PRESENT	PRESENT									
District 5 *Peter Radin - Chair*	N/A	PRESENT	PRESENT									
District 6 *Lucy Rojas*	N/A	PRESENT	PRESENT									
District 7 *VACANT*	N/A	VACANT	VACANT									

MINUTES
REGULAR JOINT CITY COUNCIL, SUCCESSOR HOUSING AGENCY, & SUCCESSOR AGENCY MEETING

March 24, 2026

City of Watsonville
Council Chambers
275 Main Street, Top Floor

Pursuant to Government Code Section 54953(b), Mayor Pro Tempore Clark was scheduled to participate in the meeting via teleconferencing from: 751 Larkin Valley Road, Watsonville, CA 95076. Council Member Montesino participated from Hotel El Carmen, Calle de Eduardo Ruiz 63, Centro Historico de Morelia, 58000 Morelia, Michoacan, Mexico.

4:31 p.m.

1. ROLL CALL

Mayor Salcido, Mayor Pro Tempore Clark and Council Members Dutra (arrived at 4:35 p.m.), Montesino (arrived at 6:58 p.m.) Orozco, Parker, and Quiroz-Carter (arrived at 4:43 p.m.) were present.

Staff members present were City Manager Vides, City Attorney Zutler, City Clerk Ortiz, Interim Public Works & Utilities Director Green, Police Chief Shab, Fire Chief Schaefer, I.T. Director Gill, Deputy City Manager/ Interim Community Development Director Manning, Assistant Public Works & Utilities Director Fontes, Assistant Community Development Director Orbach, Wastewater Division Manager Tellez, Associate Planner Madrigal, Engineering Associate Espinosa, Senior Financial Analyst Diaz, Police Officer Bañuelos, Deputy City Clerk Pacheco and Interpreter Landaverry.

1.a. MOTION TO EXCUSE ABSENT COUNCIL MEMBER(S) – None

2. PLEDGE OF ALLEGIANCE

3. INFORMATION ITEMS

3.a. REPORT OF DISBURSEMENTS

3.b. MISCELLANEOUS DOCUMENTS REPORT

4. CONSENT AGENDA

PUBLIC INPUT – None

MOTION: It was moved by Member Orozco, seconded by Mayor Pro Tempore Clark and carried by the following vote to approve the Consent Agenda.

AYES:	MEMBERS:	Clark, Dutra, Orozco, Salcido
NOES:	MEMBERS:	None
ABSENT:	MEMBERS:	Montesino, Parker, Quiroz-Carter

4.a. MOTION APPROVING MARCH 10, 2026, MEETING MINUTES

4.b. RESOLUTION NO. 46-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE AWARDING CONSTRUCTION CONTRACT TO SELDEN & SON, A PARTNERSHIP, FOR PHASE 1 OF THE WATSONVILLE CITY PLAZA REVITALIZATION PROJECT, NO. PK 25-09053, IN THE AMOUNT OF $1,180,800; AUTHORIZING A TEN PERCENT (10%) CONTINGENCY FOR UNFORESEEN CIRCUMSTANCES; AND AUTHORIZING AND DIRECTING CITY MANAGER TO EXECUTE THE SAME AND ANY AMENDMENTS THERETO OF A NON-SUBSTANTIVE NATURE SUBJECT TO LEGAL APPROVAL

4.c. RESOLUTION NO. 47-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING CONTRACT CHANGE ORDER NUMBER 8, IN THE AMOUNT OF $357,694.67 WITH ROBERT A BOTHMAN CONSTRUCTION FOR THE RAMSAY PARK RENAISSANCE PROJECT, NO. PK-22-01, AUTHORIZING AND DIRECTING THE CITY MANAGER TO EXECUTE SAME

4.d. RESOLUTION NO. 48-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING FOURTH AMENDMENT TO CONTRACT FOR PROFESSIONAL SERVICES BETWEEN THE CITY OF WATSONVILLE AND BEAR ELECTRICAL SOLUTIONS, LLC, A LIMITED LIABILITY COMPANY, FOR CITY-WIDE STREETLIGHT MAINTENANCE, PROJECT NO. TR-23-14011, INCREASING CONTRACT COMPENSATION IN THE AMOUNT OF $60,000 FOR A REVISED TOTAL CONTRACT AMOUNT OF $510,000; AND AUTHORIZING AND DIRECTING THE CITY MANAGER TO EXECUTE SAME

4.e. RESOLUTION NO. 49-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING FIRST AMENDMENT TO CONTRACT BETWEEN THE CITY OF WATSONVILLE AND PACIFIC CREST ENGINEERING, INC., A CORPORATION, FOR CONTINUED ON-CALL AND AS-NEEDED SPECIAL INSPECTION AND TESTING SERVICES ON THE WWTF ELECTRICAL SYSTEM HAZARD MITIGATION PROJECT, ADDING AN AMOUNT NOT TO EXCEED $20,000 FOR A TOTAL REVISED CONTRACT AMOUNT OF $107,000; AUTHORIZING AND DIRECTING THE CITY MANAGER TO EXECUTE SAME

4.f. RESOLUTION NO. 50-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING A PURCHASE WITH CORE & MAIN, LP, A LIMITED PARTNERSHIP, FOR THE PURCHASE OF WATER MAIN REPLACEMENT MATERIALS, IN THE AMOUNT OF $571,944.20 PLUS ANY ADJUSTMENTS FOR THE ACTUAL COSTS OF FREIGHT, DELIVERY AND TAXES WHICH ARE CALCULATED AT THE TIME OF FINAL SHIPMENT FOR THE FREEDOM BOULEVARD (GREEN VALLEY TO

COMPTON TERRACE) PROJECT; AND AUTHORIZING AND DIRECTING CITY MANAGER TO NEGOTIATE AND EXECUTE PURCHASE ORDER INCLUDING ANY EXTENSIONS OR AMENDMENTS THEREOF IN ORDER TO IMPLEMENT THE PURCHASE

4.g. RESOLUTION NO. 51-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE ACCEPTING $1,248,000 IN GRANT FUNDS FROM THE SANTA CRUZ COUNTY REGIONAL TRANSPORTATION COMMISSION (SCCRTC) FOR THE SAFE ROUTES TO DOWNTOWN WATSONVILLE PROJECT; AUTHORIZING THE CITY MANAGER TO NEGOTIATE AND EXECUTE ALL AGREEMENTS AND ANY AMENDMENTS NECESSARY; AND APPROPRIATING SUCH FUNDS TO THE SPECIAL GRANTS FUND [0260]

4.h. RESOLUTION NO. 52-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE NEW JOB CLASSIFICATION AND POSITION FOR CUSTOMER SERVICE LEAD TECHNICIAN (MID-MANAGEMENT) AT THE ESTABLISHED SALARY RANGE OF $36.19-$48.50 PER HOUR OR $6,273.72-$8,407.38 PER MONTH AND ELIMINATING THE CUSTOMER SERVICE MANAGER POSITION

4.i. RESOLUTIONS APPROVING NEW & REVISED LIBRARY CLASSIFICATIONS & SALARIES

1) **RESOLUTION NO. 53-26 (CM)**
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE REVISED JOB CLASSIFICATION AND JOB DESCRIPTION FOR CIRCULATION MANAGER (MID-MANAGEMENT) AT THE ESTABLISHED SALARY RANGE OF $33.29-$44.62 PER HOUR OR $5,770.98-$7,733.64 PER MONTH

2) **RESOLUTION NO. 54-26 (CM)**
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE REVISED JOB DESCRIPTION FOR LIBRARIAN (MID-MANAGEMENT) AT THE ESTABLISHED SALARY RANGE OF $33.31-$44.64 PER HOUR OR $5,774.02-$7,737.73 PER MONTH

3) **RESOLUTION NO. 55-26 (CM)**
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE REVISED JOB DESCRIPTION FOR SENIOR LIBRARIAN (MID-MANAGEMENT) AT THE ESTABLISHED SALARY RANGE OF $36.62-$49.08 PER HOUR OR $6,347.58-$8,506.36 PER MONTH

4) **RESOLUTION NO. 56-26 (CM)**
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE REVISED JOB DESCRIPTION FOR PRINCIPAL LIBRARIAN (MANAGEMENT) AT THE ESTABLISHED SALARY RANGE OF $42.11-$56.43 PER HOUR OR $7,299.28-$9,781.76 PER MONTH

5) RESOLUTION NO. 57-26 (CM)
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE NEW JOB CLASSIFICATION AND JOB DESCRIPTION FOR ASSISTANT LIBRARY DIRECTOR (MANAGEMENT) AT THE ESTABLISHED SALARY RANGE OF $48.59-$65.12 PER HOUR OR $8,422.72-$11,287.27 PER MONTH

5. ITEMS REMOVED FROM CONSENT AGENDA – None

6. REPORT TO COUNCIL

6.a. PRESENTATION BY ASSISTANT PUBLIC WORKS & UTILITIES DIRECTOR FONTES REGARDING CURRENT & PLANNED IMPROVEMENTS TO THE FREEDOM BOULEVARD CORRIDOR

Interim Public Works & Utilities Director Green was also available for questions.

Council Clarifying & Technical Questions
In answering Member Orozco, Assistant Public Works & Utilities Director Fontes stated he did not believe business owners along a section of Freedom Boulevard would be open to giving the City the necessary right of way to build a complete sidewalk on that side of the Boulevard.

Member Dutra requested staff speak to business owners again to verify whether they would allow the City the access needed to construct a sidewalk. He spoke about potential concerns from residents should sidewalks be constructed on only one side of Freedom Boulevard.

In answering Member Dutra, Assistant Public Works & Utilities Director Fontes spoke about available funding and the status of an improvement project along Freedom Boulevard.

City Manager Vides stated staff would re-engage with business owners and stated improvements on Freedom Boulevard would be part of a phased project. She stated she did not have details regarding why the project was not taken to Council for review sooner.

In answering Member Parker, Assistant Public Works & Utilities Director Fontes stated the City would work with property owners to determine whether installation of rolled curbs was the best option. He spoke about the potential need for right-of-way acquisition.

Interim Public Works & Utilities Director Green spoke about the process for acquiring right-of-way. She spoke about the importance of making as much progress as possible with improvements and exploring right-of-way acquisition in the future.

Member Parker expressed her desire for constructing sidewalks on both sides of Freedom Boulevard and collaborating with the County of Santa Cruz on potential grant funding opportunities.

Assistant Public Works & Utilities Director Fontes spoke about challenges and potential delays on the project due to staffing levels. He spoke about exploring options for obtaining

the necessary right-of-way to construct sidewalks on one side of Freedom Boulevard. Mayor Salcido requested staff speak to all property owners before exploring other options.

Member Orozco clarified that Council was in favor of moving forward with the project.

In answering Member Dutra, Assistant Public Works & Utilities Director Fontes spoke about improvements made by a business owner on Freedom Boulevard and stated they had dedicated the right of way to the City.

Member Dutra suggested enlisting a business owner along Freedom Boulevard to help convince other property owners to dedicate right of way to the City, which would allow for sidewalk construction.

City Manager Vides, in response to Member Parker, stated Council would have an opportunity to provide input on further improvements to Freedom Boulevard in the future.

In answering Member Orozco, Interim Public Works & Utilities Director Green provided an approximate timeframe for the traffic light improvement project on Freedom Boulevard.

Mayor Salcido recessed the meeting at 5:25 p.m.

CITY COUNCIL RESUMED AT 6:00 p.m.

7. ORAL COMMUNICATIONS

7.a. ORAL COMMUNICATIONS FROM THE PUBLIC – None

7.b. ORAL COMMUNICATIONS FROM THE COUNCIL

Member Orozco spoke about various events she participated in over the past weeks and the highlighted the work of the organizations involved in the events.

Member Parker spoke about her participation at the 50th Wildcat Relay and provided background information. She stated she traveled to Washington D.C. along with other Council members and met with legislators to advocate for Watsonville.

Member Dutra spoke about his participation at various events including local business inaugurations. He spoke about new lighting installed around the City.

Mayor Salcido spoke about her participation at various events over the weekend. She congratulated the Girls' and Boys' Watsonville High School soccer teams on their accomplishments this past season.

8. PRESENTATIONS

8.a. MAYOR'S PROCLAMATION RECOGNIZING MEALS ON WHEELS' 50TH ANNIVERSARY

8.b. MAYOR'S PROCLAMATIONS/CERTIFICATES RECOGNIZING WATSONVILLE HIGH

SCHOOL BOYS' & GIRLS' SOCCER TEAMS & THEIR COACHES

Mayor Salcido recessed the meeting at 6:43 p.m. The meeting resumed at 6:49 p.m.

8.c. UPDATE ON PAJARO VALLEY ARTS BY LYNNE KARST, BOARD PRESIDENT, & MIRIAM ANTON, EXECUTIVE DIRECTOR

Presentation was given by Executive Director Miriam Anton and Board of Directors Member Aurelio Gonzalez.

Member Parker suggested involving community members to assist with capital campaign efforts.

In answering Member Dutra, Executive Director Anton spoke about funding being pursued through their capital campaign efforts.

PVA Board of Directors Member Gonzalez, in answering Member Dutra, spoke about plans for using the second floor of their building.

In answering Member Dutra, Parks & Community Services Director Calubaquib spoke about evaluating the status of the building previously occupied by Pajaro Valley Arts and searching for a new tenant.

9. NEW BUSINESS

9.a. CONSIDERATION OF UTILITY RATE STUDY RESULTS FOR THE WATER, WASTEWATER, & SOLID WASTE ENTERPRISE FUNDS, & AUTHORIZATION TO PROCEED WITH PUBLIC NOTIFICATION SETTING A PUBLIC HEARING FOR THE ADOPTION OF NEW UTILITY RATES

1) Staff Report by Interim Public Works & Utilities Director Green, Raftelis Manager Tamargo, & Raftelis Senior Manager Kostiuk

2) City Council Clarifying & Technical Questions

In answering Member Dutra, Interim Public Works & Utilities Director Green spoke about the status of financial reserves and about the hexavalent chromium treatment project. She spoke about potential cost increases, funding opportunities for the hexavalent chromium treatment project, and reasons why rate increases had been deferred.

Raftelis Manager Tamargo spoke about staff efforts to mitigate impacts of rate increases and potential impacts of continuing to defer them.

In answering Member Dutra, City Manager Vides spoke about street sweeping in compliance with stormwater regulations and the possibility of retaining a consultant to explore increased efficiency.

Interim Public Works & Utilities Green, in answering Member Montesino, provided an explanation regarding what PFAS is and what products contain it. She spoke about the importance of the headworks project that was part of the wastewater treatment plan.

She also spoke about the State revolving fund loan program and pursuing grant opportunities to potentially revise the loan amount.

Raftelis Manager Tamargo provided additional details regarding how grant funding could impact the loan amount.

In answering Mayor Salcido, Interim Public Works & Utilities Director Green spoke about an ongoing project to improve the Wastewater electrical facility to include flood protection.

Interim Public Works & Utilities Director Green, in answering Mayor Pro Tempore Clark, spoke about the potential impacts of Water and Wastewater projects not being completed.

Raftelis Manager Tamargo spoke about the benefits of proactive maintenance versus emergency repairs.

In answering Mayor Pro Tempore Clark, Interim Public Works & Utilities Director Green spoke about efforts to plan for the cost of future projects and increases needed to fund them. Raftelis Manager Tamargo stated rate increases could only be set for five years.

Interim Public Works & Utilities Director Green, in answering Member Parker, spoke about the Clean Water Act which provided loans to assist with waterway cleanup. She stated water treatment plants received that funding. She spoke about funding pursued and received for Water-related projects.

City Manager Vides added that Congresswoman Lofgren had allocated funding the past two years for the City's Wastewater Treatment Plant. She stated funding requests had been submitted to various legislators.

In answering Member Parker, City Manager Vides spoke about efforts to anticipate future funding needs for projects. She stated Council could decide not to increase rates as much if grant funding was received.

Raftelis Manager Tamargo, in answering Member Parker stated Proposition 218 required each customer to pay their cost of service. He spoke about utilizing non-rate revenues to offset costs. Interim Public Works & Utilities Director Green spoke about establishing payment plans for residents should they be unable to make payments.

Member Parker requested hosting another screening of the *Unless Something Goes Terribly Wrong* documentary exploring implications of aging wastewater infrastructure throughout the nation.

Mayor Salcido suggested adding online resources to provide residents information regarding the importance of Water and Wastewater projects.

3) Public Input

? male, Watsonville resident, inquired whether the Water Department was a public entity. He stated there were ways to save money without affecting public safety or

quality of life and spoke about in opposition to high salaries of administrative officials.

Wastewater Division Manager Tellez spoke about building a culture of stewardship, caring for City assets, and planning for timely maintenance.

4) **MOTION:** It was moved by Member Orozco, seconded by Member Parker to approve the resolutions listed under Items 9.a.6. and 9.a.7. below.

5) **City Council Deliberation on Motion**
Member Dutra spoke about the need for sufficient staff to allow projects to be completed in a timely manner.

MOTION: The above motion was carried by the following vote.

AYES:	MEMBERS:	Clark, Dutra, Montesino, Orozco, Parker, Quiroz-Carter, Salcido
NOES:	MEMBERS:	None
ABSENT:	MEMBERS:	None

6) **RESOLUTION NO. 58-26 (CM)**
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE ACCEPTING THE RESULTS OF THE FINANCIAL ANALYSIS AND UTILITY RATE RECOMMENDATIONS, DIRECTING STAFF TO PROVIDE PUBLIC NOTIFICATION OF THE PROPOSED UTILITY RATES, AND DIRECTING THE CITY CLERK TO GIVE NOTICE THEREOF AND FIXING THE TIME FOR PUBLIC HEARING FOR MAY 26, 2026, PURSUANT TO CALIFORNIA GOVERNMENT CODE SECTION 54354.5 CALIFORNIA CONSTITUTION ARTICLE 13D SECTION 6, AND THE UTILITY RATE SETTING PROCEDURES RESOLUTION

7) **RESOLUTION NO. 59-26 (CM)**
A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE ESTABLISHING UTILITY RATE SETTING PROCEDURES FOR WATER, SEWER, AND SOLID WASTE RATES UNDER PROPOSITION 218, AND ASSEMBLY BILL 2257 (GOVERNMENT CODE SECTIONS 53750 THROUGH 53759.2)

10. REPORTS TO COUNCIL (Continued) – No Action Required

10.a. CITY MANAGER'S UPDATE REPORT

In answering Member Dutra, City Manager Vides spoke about road improvements planned for Freedom Boulevard. She stated staff were working on a plan to make improvements to a median near Crestview Drive. She also stated she would send all Council members information regarding closure of City roads due to Caltrans work.

10.b. PRESENTATION BY INTERIM PUBLIC WORKS & UTILITIES DIRECTOR GREEN REGARDING THE CITY'S PUBLIC WORKS BIDDING PROCESS

In answering Mayor Salcido, Interim Public Works & Utilities Director Green stated bids for the Safer Access to Pajaro Valley High School and Beyond Project had not been received yet and explained that many prospective bidders waited until the end the process to submit their bid.

Interim Public Works & Utilities Director Green, in answering Mayor Pro Tempore Clark,

stated the bidding process had largely remained the same over previous years except the addition of the online bidding portal. She spoke about other local agencies' bid process for comparison, the City's bid success rate, the Department of Industrial Relations' (DIR) role in ensuring contractors follow requirements.

Interim Public Works & Utilities Director Green answered Member Parker's questions regarding contractors with violations with the DIR and at what point the City would be made aware of issues.

City Attorney Zutler agreed with Member Parker's statement that the City could not take back a bid it had awarded to a contractor should issues with the DIR be discovered. Interim Public Works & Utilities Director Green stated such issues were rare.

In answering Member Parker, Interim Public Works & Utilities Director Green spoke about how the City's labor compliance consultant conducted assessments at job sites during unannounced visits. She also spoke about review of pay stubs and reports, public availability of certified payroll records, and the City's course of action should contractors be found in non-compliance.

City Attorney Zutler added that the State could fine non-compliant contractors and the City could file a lawsuit should terms of a contract be breached.

In answering Mayor Pro Tempore Clark, Interim Public Works & Utilities Director Green stated she was not aware of any instance in which the City needed to file a complaint with the DIR.

Member Orozco suggested hiring a consultant agreed upon by both City and the Trades Council to review the City's bidding requirements for possible improvements.

In answering Member Parker, Interim Public Works & Utilities Director Green stated the OpenGov online bidding portal took care of requirements to keep an open bidder list and notify them of bid openings. She spoke about additional notification requirements and OpenGov's system for sending notifications.

Interim Public Works & Utilities Director Green, in answering Member Parker, stated the City relied on its labor compliance consultant to handle matters relating to contractor requirements related to apprentices on job sites. She spoke about the request for proposal process through which the labor compliance consultant was selected.

Member Parker agreed with Member Orozco's suggestion regarding hiring a consultant to review the City's bidding requirements.

11. EMERGENCY ITEMS ADDED TO AGENDA – None

12. REQUESTS & SCHEDULING FUTURE AGENDA ITEMS – None

13. ADJOURNMENT

The meeting was adjourned at 9:12 p.m.

_____

Kristal Salcido, Mayor

ATTEST:

_____

Irwin I. Ortiz, City Clerk

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Monday, April 14, 2025**
TO:	**CITY COUNCIL**
WRITTEN BY:	Accountant II Getreu
RECOMMENDED BY:	**ADMINISTRATIVE SERVICES DIRECTOR DURAN**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**ADOPTING THE CITY OF WATSONVILLE INVESTMENT POLICY FOR CALENDAR YEAR 2026**

RECOMMENDATION:

It is recommended that the City Council approve a Resolution Adopting the Calendar Year 2026 City of Watsonville Investment Policy.

DISCUSSION:

- The City's Investment Policy and State law recommend that the City Council annually review the Investment Policy. The City of Watsonville Investment Policy was last reviewed and adopted by the City Council in 2025. We have added the California Asset Management Program (CAMP) as a permitted investment to the policy since its adoption by the City Council in 2022. CAMP is a permitted investment to local agencies and provides a short-term cash reserve portfolio rated at AAAm. It further provides same-day liquidity, competitive yield and interest is paid monthly.
- The purpose of the policy is to provide guidelines to the City Treasurer and staff for the investment of idle cash. Funds are invested in manner that will earn a competitive yield in accordance with the City's needs for liquidity and safety while at the same time maximizing investment earnings. The Investment Policy intends to ensure and promote investment practices that are consistent with the policy, prudent and that provide for the financial operational needs of the City.
- In accordance with the policy the City Treasurer is delegated Investment authority by the Council. In this delegated capacity, the City Treasurer may conduct Investment Committee meetings with staff to discuss investment options and provide direction for the investment of idle cash. A quarterly

Investment report is prepared by the Finance Department and submitted to the City Council at a regularly scheduled council meeting.

STRATEGIC PLAN:

The recommendation supports the principles of the Strategic Plan by focusing on the most effective utilization of resources.

Fiscal Health

FINANCIAL IMPACT:

None.

ALTERNATIVE ACTION:

The City Council could recommend other investment types or change the portfolio investment percentage limits, but making percentage change limits would deviate from the ones allowed in the Government Code Section 53600 et seq.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

None.

RESOLUTION NO.___(CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE ADOPTING AND CONFIRMING THE CITY OF WATSONVILLE INVESTMENT POLICY FOR CALENDAR YEAR 2026 AND DIRECTING THE ADMINISTRATIVE SERVICES DIRECTOR TO IMPLEMENT THE POLICY

BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. Adopting a Resolution adopting and confirming the City's Investment Policy for 2026 does not meet CEQA's definition of a "project", because the action does not have the potential for resulting in either a direct physical change in the environment or a reasonably foreseeable indirect physical change in environment.

2. That the City Council does hereby adopt, confirm, and approve the City of Watsonville Investment Policy for Calendar Year 2026, a copy of which is attached hereto and incorporated by this reference as its policy for the investment of funds not required for immediate necessities of the City for the Period January 1, 2026, to December 31, 2026.

3. That the Administrative Services Director, in their additional role as City Treasurer[1], is hereby directed to comply with and is authorized to do all things necessary to implement such Policy for calendar year 2026.

****

[1] Watsonville Municipal Code § 2-3.404

CITY OF WATSONVILLE

INVESTMENT POLICY FOR CALENDAR YEAR 2026

CITY OF WATSONVILLE
INVESTMENT POLICY

Introduction

The investment objective of the City of Watsonville is to ensure the safety and liquidity, while maintaining a competitive yield, of the City's temporarily idle funds.

The purpose of this policy is to provide guidelines to the officers of the City charged with responsibility for investments. This policy and State law (government section 53600 et seq.) govern the execution of the investment responsibility.

The City Council, after each annual review, delegates investment authority to the City's Treasurer (Finance Director). The Treasurer (Finance Director), under the direction of the City Manager, is responsible for administering the City's investments.

Scope

This policy applies to the investment of all City funds not required for immediate expenditure, excluding proceeds from certain bond issues that are covered by bond documents. The City will concentrate cash and reserve balances from all funds to maximize investments earnings. Investment income will be allocated to funds, other than the General Fund, as required by the funds restrictions, based upon their respective pool participation and in accordance with general accepted accounting principles.

Objectives

Funds of the City will be invested in accordance with California Government code Sections 53600 et. seq. The objectives of the Investment Policy are to meet the short and long-term cash flow demands of the City. The portfolio will be structured to provide the following (in priority order):

1) Safety: The safety and risk associated with an investment refers to the potential loss of principal, interest or combination of these items. The City controls credit risk by investing only in specified, quality investments listed in the City's investment policy, which have little chance of principal loss. Interest rate risk or market risk refers to potential economic risk, which occurs when interest rates increase, devaluing the principal of fixed income investments. To limit this risk, the City normally invests in securities with an ultimate maturity of 5 years or less, except as authorized by City Council.

2) Liquidity: This concept refers to the ability to raise cash for City operations at any moment. Liquidity achieved by purchasing securities, which are traded by a large number of market makers and have relatively short maturities.

3) Yield: Refers to the potential dollar earnings an investment can provide from both interest payments and capital appreciation. To obtain the highest yield, Finance will seek competitive quotes on like investments when purchasing an

investment. Yields of investments are to be independently calculated and verified by Finance on all transactions.

It is the City's intent, at the time of purchase, to hold all investments until maturity. However, investments may be sold prior to maturity for cash flow purposes or to take advantage of principal appreciation.

Prudence

The standard of prudence to be used by the City Treasurer (Finance Director) or designee shall be the "prudent person" standard and shall be applied in the context of managing an overall portfolio. The City Treasurer (Finance Director) or designee acting in accordance with this investment policy and exercising due diligence shall be relieved of personal responsibility for an individual security's credit risk or market price changes, provided deviations from expectations are reported to the City Council in a timely fashion and the liquidity and the sale of securities are carried out in an accordance with the terms of this policy.

The "prudent person" standard state that, "Investments shall be made with judgment and care, under circumstances then prevailing, which persons of prudence, discretion and intelligence exercise in the management of their own affairs, not for speculation, but for investment, considering the probable safety of their capital as well as the probable income to be derived from the investment."

Ethics and Conflicts of Interest

Officers or employees involved in the investment process shall refrain from personal business activity that could conflict with the proper execution and management of the investment program, or that could impair their ability to make impartial decisions. Employees and investment officials shall disclose any personal financial/investment positions that could be related to the performance of the investment portfolio. Employees and officers shall refrain from undertaking personal investment transactions with the same individual with which business is conducted on behalf of the City.

Delegation of Authority

The Director of Finance, in the capacity of City Treasurer, is designated as the Chief Investment Officer of the City and is responsible for investment decisions and activities, under the direction of the City Manager. The Director of Finance shall develop and maintain written administrative procedures for the operation of the investment program by qualified Finance Department staff, consistent with the Statement of Investment and Portfolio Policy.

No person may engage in an investment transaction except as provided under the terms of this policy and the procedures established by the Director of Finance. The Director of Finance shall be responsible for all transactions undertaken and shall establish a system of controls to regulate the activities of subordinate officials. Use of an investment advisor shall be only under contract approved by City Council.

Investment Committee
There is hereby created an Investment Committee, consisting of the City Manager or their designee, the Director of Finance, Assistant Director of Finance, and investment staff. Members of the Investment Committee shall serve without compensation, and shall meet as needed. The Investment Committee shall include in its deliberations such topics as: economic outlook, portfolio diversification, maturity structure, potential risks to the City's funds, authorized depositories, and selection of banks and primary dealers.

Safekeeping
All securities shall be kept in the custody of the City or by a qualified safekeeping institution. If securities are kept by a safekeeping institution, the City shall have access to buy and sell such securities independently of any broker.

Delivery vs. Payment
All trades of market securities will be executed by delivery versus payment (DVP) to ensure that securities are deposited in an eligible institution prior to the release of funds.

Authorized Financial Dealers and Institutions
The City shall transact business only with banks, associations, and with broker/dealers licensed by the State of California.

Authorized Investment Types
This approach affords the City a broad spectrum of investment opportunities allowable under current State of California law (Government Code 53600 et seq.). Investments shall be made only in securities for which market value information is generally available. Investments may be made in the following instruments:

Portfolio Limit	Investment Type
No limit	Securities of the US government or its agencies
No limit	Local Agency Investment Fund (State Pool) demand deposits
No limit	Passbook savings account demand deposits
No limit	Debt of the City of Watsonville
No limit	California Asset Management Program (CAMP JPA)
20%	Money Market Mutual Fund – (funds containing securities issued or guaranteed by the U.S. Government; fund dollar-weighted average maturity of ninety (90) days or less, with no single instrument with more than thirteen (13) months, and consist only of dollar-

	denominated securities)
20%	Repurchase agreements (repos) for a term of one year or less
30%	Certificates of Deposit (or time deposits) placed with commercial banks or like institutions such as credit unions. Certificates of deposit in financial institutions with local branches shall be made only to the extent warranted by the offered yield, liquidity and safety compared to that available from other institutions.
30%	Negotiable Certificates of Deposits issued by nationally or state-chartered commercial banks, federally insured credit unions, or the state licensed branch of a foreign bank.
40%	Bankers Acceptances not to exceed 180 days maturity; no more than 30 percent of the City's surplus funds may be invested in any one commercial bank.
25%	Commercial Paper of corporations having total assets of $500 million or more and having an "A" or higher rating for the issuer's debt from Moody's or Standard & Poor's, not to exceed 270 days in maturity and the City shall not purchase more than 10% of the outstanding commercial paper of any one issuer.
30%	Medium term corporate notes, with a maximum 5-year maturity.

Prohibited Investment Types

In accordance with Section 53601.6 of the California Government Code, the City shall not invest any funds in inverse floaters, range notes, or mortgage-derived interest only strips. In addition, the City shall not invest any funds in any security that could result in zero interest accrual if held to maturity.

Diversification

Investments shall be diversified among institutions, type of securities and maturities to maximize safety and yield with changing market conditions; investments with a maturity at purchase of more than 5 years shall be approved by City Council.

Reporting

The Treasurer (Finance Director) shall report quarterly to the City Manager and City Council the following information on investments owned by the City:

- Investment	- Coupon	- Yield
- Face Value	- Purchase Price	- Market Value
- Purchase Date	- Maturity Date	- Portfolio Yield
- Portfolio Maturity		

This policy shall be reviewed each calendar year by City Council.

First Investment Policy adopted by Council Resolution No. 18-89 (CM). Replaced by Resolution No. 244-92 (CM), 388-96 (CM), 296-97 (CM), 216-98 (CM), 295-99 (CM), 129-00 (CM), 262-01 (CM), 280-02 (CM), 87-03 (CM), 254-04 (CM), 242-05 (CM), 36-07 (CM), 16-08 (CM), 13-09 (CM), 202-11 (CM), 143-12 (CM), 167-13 (CM), 155-15 (CM), 174-15 (CM), 165-17 (CM), 1-19 (CM), 96-20 (CM), 44-21 (CM), 6-22 (CM), 195-23 (CM) 25-24 (CM), and 83-25 (CM).

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Monday, April 14, 2025**
TO:	**CITY COUNCIL**
WRITTEN BY:	**PROJECT MANAGER PERALTA**
RECOMMENDED BY:	**DEPUTY CITY MANAGER CALUBAQUIB**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**APPROVE THIRD AMENDMENT TO CONTRACT WITH GRIFFIN STRUCTURES, INC. FOR THE RAMSAY PARK RENAISSANCE PROJECT, NO. PK-22-01, INCREASING THE AMOUNT BY $87,450 AND EXTENDING THE CONTRACT TERM TO DECEMBER 31, 2026**

RECOMMENDATION:

It is recommended that the City Council adopt a resolution approving the third amendment to a consultant contract with Griffin Structures, Inc., for project management services on the Ramsay Park Renaissance Project, No. PK-22-01, increasing the compensation by $87,450, and extending the contract term to December 31, 2026; and authorizing and directing the City Manager to execute same.

BACKGROUND:

On August 24, 2021, the City Council adopted Resolution No. 218-21 awarding a contract to Griffin Structures, Inc., for project management services for the implementation of the Ramsay Park Master Plan (Ramsay Park Improvement Project).

On February 21, 2023, the City Council adopted Resolution No. 39-23 approving a First Amendment adding to the scope of work, extending the contract term to December 31, 2024, and increasing compensation for a cumulative total of $433,700.00.

On December 10, 2024, the City Council adopted Resolution No. 242-24 approving a Second Amendment, extending the contract term to March 31, 2026, and increasing compensation amount by $142,000 for a cumulative total of $575,700.

DISCUSSION:

Griffin Structures, Inc. is a consultant firm providing construction project management services on the Ramsay Park Improvements Project ("project"). Construction progress on the project has been impacted by multiple unforeseen conditions and several supplemental directives requested by the city. Consequently, additional project management services are needed to continue progress on the project's construction.

Since additional time will be added to the construction schedule, and the project is expected to be completed in Summer 2026, there is a need to extend this contract's term date to December 31, 2026, and increase compensation by eighty-seven thousand four hundred and fifty ($87,450).

Attachment 1 contains a detailed fee proposal with an allocation schedule for further review. This amendment covers all services based on an anticipated project completion in July of 2026 with closeout in September 2026.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

An Initial Study/ Mitigated Negative Declaration was prepared for the Project, in accordance with the provisions of the California Environmental Quality Act (CEQA) to disclose the potential impacts of the Project and suggest methods to minimize those impacts. The Zoning Administrator, in the exercise of his/her independent judgment as the decision-maker of the City of Watsonville for this Project, found there is no substantial evidence that the Project will have a significant effect on the environment, and a Mitigated Negative Declaration has been prepared for the Project in accordance with CEQA requirements. A Mitigation Monitoring and Reporting Program (MMRP) was also prepared for the Project, in accordance with CEQA Guidelines, to ensure all identified mitigation measures are incorporated as conditions of approval.

No additional CEQA review is required because amending the scope of the Contract is consistent with the CEQA documentation prepared for the Project and approved by the City Council. The City Council finds and determines that (i) the CEQA documentation prepared for the Ramsay Park Renaissance Project serves as the appropriate environmental documentation for proposed Second Amendment to Contract and satisfies all requirements of CEQA; and (ii) no supplemental environmental documentation is required by CEQA at this time pursuant to CEQA Guidelines section 15162, because no substantial changes are proposed to the Project with this Second Amendment and no new information of substantial importance has been identified. Additionally, no addendum is required because no technical changes or additions are proposed through this Third Amendment to the Contract.

STRATEGIC PLAN:

This recommendation is consistent with the following council strategic goals:

Community Engagement & Well-being
Infrastructure & Environment

FINANCIAL IMPACT:

The cost of contract Amendment No. 3 will be $87,450.00. This Amendment shall be funded from the following Capital Improvement Plan (CIP) project expense account number:

Ramsay Park Master Plan: 150-901-7820-15020

ALTERNATIVE ACTION:

The Council may choose not to accept this amendment, and the project will not have the additional professional services needed to be completed.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

Attachment 1: Griffin Structures Fee Proposal - Dated January 29, 2026

GRIFFIN STRUCTURES

GRIFFIN STRUCTURES FEE PROPOSAL – ASR 03r1

Ramsay Park Improvements Project

January 29, 2026

Griffin Structures' Fee Proposal is based on all reasonable costs necessary to perform Project Management services for the Ramsay Park Improvements project. For these requisite services Griffin Structures proposes the following **Time and Materials** Fee:

Project Management:	$	56,886
Submittal Exchange Extensions	$	2,750
Reimbursable Expenses:	$	25,284
Total	**$**	**87,450**

All proposed hourly rates are fully burdened and include overhead, profit, taxes, and benefits. The hours identified for each individual employee and task are estimates only and are not to be construed as not to exceed hours for any individual task, phase, or time period. **We reserve the right to reallocate hours between staff members and tasks, in consultation with City staff, in order to accomplish the overall objectives and requirements of the project.**

SCOPE OF SERVICES

This amendment covers all services based on an anticipated project completion in July of 2026 with closeout in September 2026. Due to changes in scope and unforeseen circumstances, the project schedule has extended.

Addition of Certified Playground Inspector is included in the Reimbursable Expenses line item.

APPROACH TO STAFFING & PROJECT TEAM

To bring the highest level of efficiency and value to the City, Griffin Structures has assembled following team:

Jon Hughes will continue to support the project as Principal-In-Charge**.**

Robert Echavarria will remain as the Project Manager**.**

QUALIFICATIONS & EXCLUSIONS

1. Hourly rates are valid through December 31st, 2026 and will escalate by CPI annually thereafter.

2. Insurance costs are included as a reimbursable expense and will be billed monthly at the rate of $10 per $1,000.

3. On-site trailer rental, furniture, utilities, and sanitary facilities for our field staff (Project Management team) are excluded. We assume that offices will be provided as part of the construction site trailer(s) being provided by the City or its contractor.

4. Costs for all permits required for the project are excluded. It is assumed that the City will pay for all permitting fees, assessments, easements, school fees, and other agency or governmental fees or costs to support the design and construction the project. We have not included any permit related fees within our fee proposal. Permits will be pulled by others.

5. Costs for construction staking, environmental and hazardous materials surveys, and all environmental and hazardous materials transportation and remediation costs are excluded.

6. Software licenses or user fees and all software training costs for specific project management software being required by either the City or their contractor(s) are excluded.

7. Cost of bulk blueprinting for plans and specifications for use by the contractors and subcontractors is excluded. Funds included in reimbursable expenses are for Griffin printing costs alone.

8. Independent or third-party testing companies such as Roofing, Peer Reviews, LEED, or other specialized third-party oversight services other than those listed herein are excluded.

9. No FF&E or OS&E procurement is included in this proposal.

10. Construction Site Security is excluded.

11. This proposal does not include a formal independent Inspector of Record (IOR); it is assumed that any Building Department inspections will be performed by the City's Building Department inspections staff. It does include an Add Alternate for a Quality Assurance Inspector.

12. Construction Manager will review all RFI's, Submittals, and Substitutions only for completeness. Approvals shall be executed by the architect of record.

13. Construction Cost Estimates, when provided, are based on standard industry practice, professional experience, and knowledge of market conditions. Griffin has no control over material and labor costs, contractor's methods of establishing prices or the market and bidding conditions at the time of bid. Therefore, Griffin does not guarantee that bids received will not vary from the cost estimate provided and Griffin is not liable for any costs, liabilities, or damages incurred by the City arising from Griffin's opinion of cost, the actual project cost to the City, delays caused by events outside the control of Griffin, or any labor or material cost increases.

14. Griffin is not responsible for, and the City will hold Griffin harmless from, any schedule delays and/or any losses, damages, or liabilities resulting therefrom that are caused by (1) events or conditions that are outside of Griffin's control or (2) the acts or omissions of parties for whom Griffin is not legally liable (collectively, "Non-Consultant Delays"). The schedule for completion will be extended for any Non-Consultant Delays. If Griffin incurs additional costs or expenses due to Non-Consultant Delays, then Griffin's fee compensation will be equitably adjusted to cover such additional costs or expenses.

15. For document tracking control, Griffin has included the use of Submittal Exchange for managing construction documentation, and based the hours allocated in this proposal accordingly. The cost of this system is included here as a reimbursable expense.

16. FF&E services are included and management and oversight of the effort to be performed by the selected design team professionals.

17. Move management services are included as oversight only. Griffin will nonetheless oversee the solicitation, negotiation, and oversight of the move management consultant, but will not be providing the service itself.

18. Commissioning requirements are understood as per California Building Cod / Cal Green (Title 24) only. LEED Commissioning is excluded.

City of Watsonville
Ramsay Park Improvements Project
Resource Allocation Schedule
ASR 03

Watsonville Ramsay Park



PROJECT PHASE																																					
	2021												2022												2023											
	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
DESIGN MANAGEMENT																																					
30% Schematic Design																																					
65% Design Development																																					
95% Construction Documents																																					
Staff Review																																					
100% Construction Documents																																					
PG&E Palyground Design Change																																					
CONTRACTOR BIDDING																																					
Solicitation Period																																					
Interviews and Staff Report																																					
Council Agendize and Award																																					
CONSTRUCTION																																					
Preliminary NTP																																					
Construction																																					
Establishment & Maintenance																																					
Project Closeout																																					
								PHASE 1: DESIGN & PERMITTING												**PHASE 2: BIDDING & CONSTRUCTION**															
Principal In Charge - Jon Hughes								16	16	10	10	16	16	16	16	16	16	16	16	15	15	15	15		10	10	6	0	4	5	6			8	8	8
Project Manager - Robert Echavarria								20	20	20	20	20	20	32	30	30	30	60	60	45	35	25	15	26	30	50	15	16	28	20	28	11	30	24	21	
Principal In Charge - Jon Hughes	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ 3,360	$ 3,360	$ 2,100	$ 2,100	$ 3,360	$ 3,360	$ 3,360	$ 3,360	$ 3,360	$ 3,360	$ 3,360	$ 3,360	$ 3,150	$ -	$ 3,150	$ 3,150	$ -	$ 2,100	$ 2,100	$ 1,260	$ -	$ 900	$ 1,125	$ 1,350	$ -	$ 1,800	$ 1,800	$ 1,800	
Project Manager - Robert Echavarria	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ 3,900	$ 3,900	$ 3,900	$ 3,900	$ 3,900	$ 3,900	$ 6,240	$ 5,850	$ 5,850	$ 5,850	$ 11,700	$ 11,700	$ 8,775	$ 6,825	$ 4,875	$ 2,925	$ 5,070	$ 5,850	$ 9,750	$ 2,925	$ 3,300	$ 6,160	$ 4,400	$ 6,160	$ 2,420	$ 6,600	$ 5,280	$ 4,620	
	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	
	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	
	$ -	**$ -**	**$ -**	**$ -**	**$ -**	**$ -**	**$ -**	**$ -**	**$ 7,260**	**$ 7,260**	**$ 6,000**	**$ 6,000**	**$ 7,260**	**$ 7,260**	**$ 9,600**	**$ 9,210**	**$ 9,210**	**$ 9,210**	**$ 15,060**	**$ 15,060**	**$ 11,925**	**$ 6,825**	**$ 8,025**	**$ 6,075**	**$ 5,070**	**$ 7,950**	**$ 11,850**	**$ 4,185**	**$ 3,300**	**$ 2,060**	**$ 10,525**	**$ 7,510**	**$ 2,420**	**$ 8,400**	**$ 7,080**	**$ 6,420**	



PROJECT PHASE																																					
	2024												2025												2026											
	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
Principal In Charge - Jon Hughes	6	5	6	7	10	6	6.5	7	6	6	6	9	5	6	6	6	10	10	10	10	10	10	10	12	10	10	10	10	10	10	10						**321**
Project Manager - Robert Echavarria	31	25	21	17	40	50	45	60	62	50	40	50	37	40	40	48	40	40	40	40	40	45	30	40	50	50	50	50	50	50	50	50					**1,694**
																																					0
Principal In Charge - Jon Hughes	$ 1,350	$ 1,125	$ 1,350	$ 1,575	$ 2,250	$ 1,350	$ 1,463	$ 1,575	$ 1,350	$ 1,350	$ 1,350	$ 2,025	$ 1,160	$ 1,392	$ 1,392	$ 1,392	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,784	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ 2,320	$ -	$ -	$ -	$ -	$ -	**120,198**
Project Manager - Robert Echavarria	$ 6,820	$ 5,500	$ 4,620	$ 3,740	$ 8,800	$ 11,000	$ 9,900	$ 13,200	$ 13,640	$ 11,000	$ 8,800	$ 11,000	$ 8,140	$ 8,800	$ 9,080	$ 10,896	$ 9,080	$ 9,080	$ 9,080	$ 9,080	$ 9,080	$ 10,215	$ 6,810	$ 9,080	$ 11,350	$ 11,350	$ 11,350	$ 11,350	$ 11,350	$ 11,350	$ 11,350	$ -	$ -	$ -	$ -	$ -	**475,116**
	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	**0**
	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	$ -	**0**
	$ 8,170	**$ 6,625**	**$ 5,970**	**$ 5,315**	**$ 11,050**	**$ 12,364**	**$ 11,363**	**$ 14,775**	**$ 14,990**	**$ 12,350**	**$ 10,150**	**$ 13,025**	**$ 9,300**	**$ 10,192**	**$ 10,472**	**$ 12,288**	**$ 11,400**	**$ 11,400**	**$ 11,400**	**$ 11,400**	**$ 11,400**	**$ 12,535**	**$ 9,130**	**$ 11,864**	**$ 13,670**	**$ 13,670**	**$ 13,670**	**$ 13,670**	**$ 13,670**	**$ 13,670**	**$ 13,670**	**$ 11,350**	**$ 11,350**	**$ -**	**$ -**	**$ -**	**595,327**

	PHASE 1 & 2 TOTALS
Principal In Charge - Jon Hughes	**321**
Project Manager - Robert Echavarria	**1,694**
	0
Principal In Charge - Jon Hughes	**120,198**
Project Manager - Robert Echavarria	**475,116**
	0
	0
	595,327

	CONTRACT	(OVER) UNDER
	$ 538,441	($56,886)

Sub. Ex.	$ 5,280
Reimburseables	$ 22,084
TOTAL	**$ 84,250**

BSAFE Playground Inspection Services, Inc.
10349 Ormond Street
Sunland, CA 91040
(916) 850-5071 (c)
admin@bsafeinspection.com

Integrity . Respect
Expertise . Responsiveness

Quote

10/17/2025

Client	Quote #	Project
Griffin Structures Attn Robert Echavarria 498 1850 Warburton Avenue Santa Clara California 95050		Watsonville Ramsey Park Griffin Structures Attn Robert Echavarria 1301 Main Street, CA 95076 Watsonville California 95076

Description	Qty	Unit Price	Total Price
Inspection & Report	2	$650.00	$1,300.00
Impact Test & Report	2	$650.00	$1,300.00
Travel	1	$175.00	$175.00

Notes: *Payment Terms: Net15*

Total **$2,775.00**

Please let us know if you have any questions.
Our team is always happy to help however we can.
Thank you.

Chris Tait & the BSAFE team

Comments:

RESOLUTION NO._____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING A THIRD AMENDMENT TO CONSULTANT CONTRACT BETWEEN THE CITY OF WATSONVILLE AND GRIFFIN STRUCTURES, INC.; A CORPORATION, FOR PROJECT MANAGEMENT SERVICES FOR THE RAMSAY PARK RENAISSANCE PROJECT, NO. PK-22-01; INCREASING CONTRACT COMPENSATION BY $87,450; EXTENDING THE TERM OF THE CONTRACT TO DECEMBER 31, 2026; AND AUTHORIZING CITY MANAGER TO EXECUTE SAME

WHEREAS, on August 24, 2021, City Council adopted Resolution No. 218-21 (CM) awarding a Professional Services Contract to Griffin Structures, Inc., a California corporation, to provide Project Management Services for the implementation of the Ramsay Park Master Plan (Ramsay Park Improvement Project), in an amount not to exceed $150,000; and

WHEREAS, on February 21, 2023, City Council adopted Resolution No. 39-23 (CM) approving a First Contract Amendment adding to the scope of work, extending the contract term to December 31, 2024, and increasing compensation by $283,700.00 for a cumulative total of $433,700.00; and

WHEREAS, on December 10, 2024, City Council adopted Resolution No. 242-24 (CM) approving a Second Contract Amendment extending the contract term to March 31, 2026, and increasing compensation amount by $142,000 for a cumulative total of $575,700.00; and

WHEREAS, this Third Contract Amendment extends the contract term to December 31, 2026, and increases compensation amount by $87,450 for a cumulative

total of $663,150.00 with Griffin Structures, Inc. to provide Project Management Services on the Ramsay Park Renaissance Project, NO. PK-22-01; and

WHEREAS, an Initial Study/ Mitigated Negative Declaration was prepared for the Project, in accordance with the provisions of the California Environmental Quality Act (CEQA) to disclose the potential impacts of the Project and suggest methods to minimize those impacts. The Zoning Administrator, in the exercise of his/her independent judgment as the decision-maker of the City of Watsonville for this Project, found there is no substantial evidence that the Project will have a significant effect on the environment, and a Mitigated Negative Declaration has been prepared for the Project in accordance with CEQA requirements. A Mitigation Monitoring and Reporting Program (MMRP) was also prepared for the Project, in accordance with CEQA Guidelines, to ensure all identified mitigation measures are incorporated as conditions of approval.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. No additional CEQA review is required because amending the scope of the Contract is consistent with the CEQA documentation prepared for the Project and approved by the City Council. The City Council finds and determines that (i) the CEQA documentation prepared for the Ramsay Park Renaissance Project serves as the appropriate environmental documentation for proposed Second Amendment to Contract and satisfies all requirements of CEQA; and (ii) no supplemental environmental documentation is required by CEQA at this time pursuant to CEQA Guidelines section 15162, because no substantial changes are proposed to the Project with this Second Amendment and no new information of substantial importance has been identified.

Additionally, no addendum is required because no technical changes or additions are proposed through this Third Amendment to the Contract.

2. This Third Amendment to Professional Services Contract between the City of Watsonville and Griffin Structures, Inc., for Project Management Services, a copy of which Third Amendment is attached hereto and incorporated herein by this reference, is hereby approved.

3. The City Manager is hereby authorized and directed to execute said Amendment for and on behalf of the City of Watsonville with minor revisions that may be approved by the City Manager and the City Attorney.

****

Docusign Envelope ID: 5327C188-B256-46F8-A195-2CD97D5D1E43

THIRD AMENDMENT TO CONSULTANT SERVICES CONTRACT BETWEEN THE CITY OF WATSONVILLE AND GRIFFIN STRUCTURES, INC

THIS THIRD AMENDMENT TO CONTRACT for consultant services is entered into by and between the **City of Watsonville** ("City") and **Griffin Structures, Inc.** (“Consultant”) this 6th day of April, 2026. The City and Consultant agree as follows:

RECITALS

WHEREAS, the City and Consultant have previously executed a Consultant Services Contract for Project Management Services for the Ramsay Park Master Plan Implementation dated August 24, 2021;

WHEREAS, the City has added additional tasks to the work program of the Consultant causing additional cost and time to the project completion; and

WHEREAS, the amendment of the Contract for Consultant Services is in the best interest of the City of Watsonville.

NOW, THEREFORE, the City and the Consultant agree that the Contract shall be amended as follows:

Section 2 is hereby amended to add the following:

"Section 2. Term of Contract. Contract end date to extend to December 31, 2026.

Section 4 is hereby amended to read:

Docusign Envelope ID: 5327C188-B256-46F8-A195-2CD97D5D1E43

"Section 4 and Exhibit "C" both entitled "Compensation" of the Contract, are hereby amended to provide an additional amount of compensation of eighty-seven thousand, four hundred fifty dollars and zero cents. ($87,450) for professional services.

All other terms and conditions of the Contract dated August 24, 2021, as amended, shall remain in full force and effect.

IN WITNESS WHEREOF, the parties hereto have executed this First Amendment to Consultant Services Contract the day and year first hereinabove written.

CITY OF WATSONVILLE

By_____
Tamara Vides, City Manager

GRIFFIN STRUCTURES, INC.

By DocuSigned by: Jon Hughes ED4FD8218B3F49D_____
Jon Hughes, President

ATTEST:

By_____
Irwin Ortiz City Clerk

APPROVED AS TO FORM:

By_____
Samantha Zutler, City Attorney

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Tuesday, April 14, 2026**
TO:	**CITY COUNCIL**
WRITTEN BY:	Sr. Civil Engineer Schneider
RECOMMENDED BY:	**INTERIM PUBLIC WORKS & UTILITIES DIRECTOR GREEN**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**APPROVE CHANGE ORDER NO. 2 WITH KJ WOODS CONSTRUCTION INC. FOR THE WATER LINE REPLACEMENT PROJECT – BEACH ST., UNION ST., LINCOLN ST. ADDING $388,000 TO THE COMPENSATION AND AUTHORIZE A $210,000 BUDGET APPROPRIATION FROM THE WATER ENTERPRISE FUND (0720)**

RECOMMENDATION:

Adopt a resolution approving Change Order No. 2 to the Contract with K.J. Woods Construction, Inc. for the Water Line Replacement – Beach St., Union St., Lincoln St. Project, No. WA-25-14834, in the amount of $388,000, and authorizing a budget appropriation of $210,000 from the Water Enterprise Fund [0720] to budget account 0720-913-7831-14834; and authorizing and directing City Manager to execute same.

BACKGROUND:

On July 8, 2025, the City Council adopted Resolution No. 186-25 (CM) and awarded contract to K.J. Woods Construction, Inc., for the Water Line Replacement Beach St., Union St., and Lincoln St. Project, No. WA-25-14834, in the amount of $4,938,000.

On March 30, 2026, the City executed Contract Change Order No. 1 to account for minor adjustments to the waterline vertical alignment due to unforeseen conflicts with existing utilities. The change order is in the amount of $40,726.75, therefore increasing the contract amount to $4,978,726.75.

The City has an ongoing goal of replacing approximately 2.5 miles of existing water main per year. The City's in-house Water Services crew replaces approximately 1.5 miles per year, requiring additional main replacements supported by contractors to stay on top of replacing the most critically aging pipelines

throughout the water distribution area. Staff is recommending additional scope to the Beach St., Union St., Lincoln St. project to add an additional section of water main replacement, requiring Council action.

DISCUSSION:

K.J. Woods Construction, Inc. is nearing completion of the Water Line Replacement–Beach St., Union St., Lincoln St. project. The County will be performing a road replacement project on nearby Lee Road in the summer of 2026, for which the City's water services crew will be performing the replacement and continuing on with the main line replacement on Lee Road. However, a section of Lee Road requiring replacement has a railroad crossing which will require specialty construction unable to be performed by the City's crew. In order to allow this water main replacement work to proceed expediently, staff requested a quote from K.J. Woods to install this section of casing and piping under the railway so it will be ready ahead of the planned City water services crew work. Adding this scope of work will result in a cost savings to the City compared to bidding this work separately at a later date because the contractor is already mobilized in Watsonville and possesses the necessary skill and equipment to perform this relatively small amount of work in quick order. The contractor provided a detailed lump sum cost proposal for this added scope of work, which staff reviewed and found reasonable.

Therefore, staff recommends Council approve this Change Order No 2 with K.J. Woods in the amount of $388,000 for the added steel casing and piping installation under the railway crossing on Lee Road.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

This project and the recommended additional scope of work is exempt from the California Environmental Quality Act ("CEQA") pursuant to Section 15302 Class 2(c), because it involves the replacement of an existing public water utility pipeline with negligible or no expansion of capacity. Further, none of the exceptions to the CEQA exemption in Section 15300.2 apply. This is because the project will have no impact on environmental resources of hazardous or critical concern and will not result in or contribute to cumulative impacts. There are no unusual circumstances associated with the project that would result in a significant effect on the environment, nor would the project impact on scenic resources. The project is not situated on a hazardous waste site and would not impact on any historic resource. Therefore, the project is exempt from CEQA.

STRATEGIC PLAN:

This project is consistent with the following Strategic Plan Goal(s):

Infrastructure & Environment

FINANCIAL IMPACT:

The total negotiated contract change order amount is $388,000. The original based bid amount of $4,938,000 combined with change orders no. 1 & no. 2, for a revised total contract amount of $5,366,726.75. The cumulative change order percentage increase is 8.68%.

There is not sufficient budget available in Water Enterprise Fund Budget account 072-913-7831-14834 to cover the full cost of Change Order No. 2. Therefore, a budget appropriation in the amount of $210,000 from the Water Fund [0720] to budget account 0720-913-7831-14834 is requested.

ALTERNATIVE ACTION:

The Council could elect not to approve this change order and instead bid the added scope at a later date which would likely result in added costs due to material cost escalation, mobilization for a separate project, and additional design costs to develop a detailed bid package.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

None.

RESOLUTION NO._____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING CHANGE ORDER NO. 2 WITH K.J. WOODS CONSTRUCTION, INC., A CORPORATION, FOR THE WATER LINE REPLACEMENT BEACH ST., UNION ST., LINCOLN ST. PROJECT, NO. WA-25-14834, IN THE AMOUNT OF $388,000 FROM THE WATER ENTERPRISE FUND FOR A REVISED TOTAL CONTRACT AMOUNT OF $5,366,726.75; AND AUTHORIZING A $210,000 BUDGET APPROPRIATION FROM THE WATER ENTERPRISE FUND [0720] TO BUDGET ACCOUNT 0720-913-7831-14834; AND AUTHORIZING CITY MANAGER TO EXECUTE SAME

WHEREAS, on July 8, 2025, the City Council adopted Resolution No. 186-25 (CM) and awarded contract to K.J. Woods Construction, Inc., a corporation, for the Water Line Replacement Beach St., Union St., Lincoln St. Project, No. WA-25-14834, in the amount of $4,938,000**;** and

WHEREAS, on March 30, 2026, the City executed Change Order No. 1, and added tasks to the scope of work, and increased compensation, in the amount of $40,726.75 for a revised total contract amount of $4,978,726.75; and

WHEREAS, Change Order No. 2 will add tasks to the scope of work and increase the contract compensation, in the amount of $388,000 for a revised total contract amount of $5,366,726.75.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. This project and the recommended added scope is exempt from the California Environmental Quality Act ("CEQA") pursuant to Section 15302 Class 2(c), because it involves the replacement of an existing public water utility pipeline with negligible or no expansion of capacity. Further, none of the exceptions to the CEQA exemption in Section 15300.2 apply. This is because the project will have no impact on environmental resources of hazardous or critical concern and will not result in or

contribute to cumulative impacts. There are no unusual circumstances associated with the project that would result in a significant effect on the environment, nor would the project impact on scenic resources. The project is not situated on a hazardous waste site and would not impact on any historic resource. Therefore, the project is exempt from CEQA.

2. That the Contract Change Order No. 2 between the City of Watsonville and K.J. Woods Construction, Inc., a copy of which is attached, is hereby approved.

3. That the budget appropriation of $210,000 from the Water Enterprise Fund [0720] to budget account 0720-913-7831-14834 is hereby authorized.

4. The City Manager is hereby authorized and directed to execute said Change Order No. 2 for and on behalf of the City of Watsonville with minor revisions that may be approved by the City Manager and the City Attorney.

****

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

CITY OF WATSONVILLE
Public Works and Utilities Department

CONTRACT CHANGE ORDER No. 2 **Contract No.** 3508

Project Name: Union Beach Lincoln WMR **City Project No.** WA-25-14834

Contractor: KJ Woods Construction, Inc.

Description of Work:

PCO 5 - Lee Road Waterline Railroad Crossing

Contract Price Increase/(Decrease): $388,000.00
Contract Time Increase/(Decrease): ~~15 Days~~ 25 Days

As requested by the City, the attached change order request provides full compensation, at a lump sum price, to install approximately 75LF of 12" C900 PVC waterline under the SCCRTC spur line at Lee Road, approximately 500LF north of Beach St. The installation includes, but is not limited to, 20" steel casing installed via jack and bore; dewatering; waterline installation, testing, and disinfection; annular casing infill; and associated site restoration. Additional requirements, provided by the forthcoming permit from SCCRTC, will be considered as included in this change order (the attached SCCRTC Encorahcment Guidelines are provided as a sample framework of final permit conditions to be anticipated). This change order provides for 25 additional working days to be added to the contract.

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

CITY OF WATSONVILLE
Public Works and Utilities Department

CONTRACT CHANGE ORDER No. 2 **Contract No.** 3508

Project Name: Union Beach Lincoln WMR **City Project No.** WA-25-14834

Contractor: KJ Woods Construction, Inc.

1	Pipe Fitting Substitution Credit and Beach St Realignment	$388,000.00
	Total Amount of Change Order:	**$388,000.00**

By reason of this order the time of completion will be adjusted as follows: 25 Working Days

This change order constitutes full and complete compensation for all labor, equipment, materials, overhead, profit, any and all indirect costs and time adjustment required to perform the above described change. All work shall be completed in accordance with the applicable provisions of the Contract Documents.

Accepted By Contractor: Jack Raftery 4/1/2026
KJ Woods Construction, Inc. Date

Recommended by Construction Manager: Signed by: Matt Scholfield 4/8/2026 | 8:23 AM PDT
60F2EA7C5A7D4... Matt Scholfield, PE Date

City Approval:

Project Manager Date

Director Public Works & Utilities Date

If Cumulative Change Order Percentage is Greater Than 15% the Following Signatures are also required:

Director of Administrative Service Date

City Manager Date

Contract Summary:

The Original Contract Sum:	$4,938,000.00
Net Change by Previously Authorized Change Orders	$40,726.75
The Contract Sum Prior to this Change Order:	$4,978,726.75
Amount of this Change Order:	**$388,000.00**
The New Contract Sum Including this Change Order:	**$5,366,726.75**
Cumulative Change Order Percentage Increase	**7.86%**

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

KJ WOODS CONSTRUCTION INC.
General Engineering Contractor
CSLB # 701797

P.O. Box 947
South San Francisco, CA 94083
PH (415) 759-0506
FAX (415) 468-1359
OFFICE@KJWOODS.COM

Rev 2 / March 24, 2026

Attn: Robert Schneider RE
City of Watsonville
250 Main St.
Watsonville, CA 95076

Subject: **Lee Rd. Water Line RR Crossing**
Jack & Bore 12" PVC Water Main Installation w/20" Steel Casing

KJ Woods Construction, Inc. (KJ Woods) appreciates the opportunity to provide our quotation for the above-mentioned work.

SCOPE OF WORK:

Installation of 12" Water Main Pipe in 20" Casing:

- Grade And Install 10' X 85' AC Paved Shoulder to Assist with Traffic Control Around the Boring Pit.
- Excavate and Shore Approx. 10' X 36' X 10'D Jack & Bore Launch Pit
- Excavate and Shore Approx. 10' X 10' X 10'D Jack & Bore Receiving Pit
- Provide Dewatering as Needed to Complete the Work.
- Installation Of Approx. 75LF 12" PVC Main Inside 20" Steel Casing.
- Install 75LF 20" Steel Casing W/Min .344" Wall Thickness by Jack & Bore
- Install 12" PVC C900 with Pipe Spacers to Centralize Pipe Location Within the Casing.
- Fill And Seal Pipe Casing Annular Space with Blown Sand
- Backfill And Compact Excavations.
- Asphalt Patch Launch and Receiving Pit Locations.
- All Work Will Be Completed in Accordance with The City of Watsonville Specifications.

Clarifications / Assumptions:

1. Dewatering will be discharged into the existing Sanitary Sewer Manhole on the West Side of Lee Road.
2. KJ Woods assumes 1 mobilization. Additional mobs will be billed $10,000/EA.
3. KJ Woods will use area adjacent to the work site for equipment storage and staging.
4. KJ Woods includes traffic control for our work.
5. **The work needs start prior to us completing the Waterline Replacement project that KJ Woods is currently working on.**
6. **If our crew demobilizes from the current project, we will require a Change Order for Remobilizing.**

Exclusions:

1. Payment of all fees, permits, survey, layout, engineering, and/or testing costs and inspections if required.
2. Dewatering Permit
3. Hazardous/Contaminated Materials Testing and/or Disposal.

LUMP SUM - $388,000

Thank you for the opportunity to provide this pricing. If you have any questions or require any further information, please contact me.

Thank you,

David Metzger

David Metzger Estimator

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7



GRAPHIC SCALE
0 5' 10' 20'
(IN FEET)
1 IN = 10 FT

A RR CASING PLAN

SCALE: 1" = 10'



B RR CROSSING PROFILE

SCALE: 1" = 10'



NOTES:

1. END SEAL, MOLDED AND CENTERED TYPE WITH SS HARDWARE, ADVANCED PRODUCTS & SYSTEMS, LLC OR APPROVED EQUAL.
2. TYPICAL DETAIL FOR BOTH ENDS OF CASING PIPE.
3. SEAL CASING PIPE ENDS AFTER FILLING ANNULUS WITH SAND. SEE DETAIL D.

C RR CASING END SEAL DETAIL

SCALE: NTS



NOTES:

1. CARRIER PIPE SPACER W/ SS BAND. MIN 8" WIDTH, 14 GAUGE T-304 SS, 1" MIN. WIDE RUNNERS. ADVANCED PRODUCTS & SYSTEMS, LLC OR APPROVED EQUAL. MAX 6' SPACING ALONG PIPELINE OR AS SPECIFIED BY MFG, WHICHEVER IS MORE STRINGENT.
2. SAND SHALL HAVE SAND EQUIVALENT OF 30 OR GREATER. FIELD VERIFY THAT CASING ANNULUS IS COMPLETELY FILLED WITH SAND, PROVIDE CALCULATION OF VOLUME TO BE FILLED, AND COMPARE TO QUANTITY OF SAND BLOWN INTO INTERIOR OF CASING. PROVIDE VENT AS REQUIRED TO ENSURE GOOD PLACEMENT OF SAND MATERIAL. AFTER SUCCESSFUL PLACEMENT OF SAND, AND CONCURRENCE FROM ENGINEER THAT ANNULUS IS SATISFACTORILY FILLED WITH SAND, REMOVE VENT AND RE-WELD VENT HOLE SHUT TO ENSURE CASING PIPE IS WATER-TIGHT.

D RR CASING CROSS SECTION

SCALE: NTS



NOTES:

1. VENT PIPE SHALL BE 2" SCH. 40 STEEL WITH WELDED DOWN-TURNED ELBOW.

E CASING VENT DETAIL

SCALE: NTS

CITY OF WATSONVILLE, CALIFORNIA
PUBLIC WORKS, ENGINEERING DEPARTMENT

WATER LINE REPLACEMENT
LEE RD
WATER UTILITY AND RR CASING

Approved by
Date 03/13/2026
ROBERT S. SCHNEIDER

Designed by ESR
Drawn by ONW
Checked by -
Job No. XX-25-XXX
Scale
SHEET E-1
1 of 1

WATER LINE REPLACEMENT LEE ROAD

FOR REDUCED PLANS ORIGINAL SCALE IS IN INCHES
0 1 2 3 4

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

SCCRTC Santa Cruz County Regional Transportation Commission

GENERAL PROCEDURES

10/01/2021

RAILPROS

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

NOTICE

This guide is provided under the sponsorship of the Santa Cruz County Regional Transportation Commission ("SCCRTC") for the purpose of information exchange. The SCCRTC assumes no liability for the accuracy of the contents of this guide or use thereof. Information provided herein may be superseded at the sole discretion of SCCRTC.

The contents of this guide do not necessarily reflect the official policy of SCCRTC.

This guide does not constitute a standard, specification, or regulation.

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

1.0 Introduction

This guide is intended to provide the basic requirements for a utility occupying the property of SCCRTC, commonly referred to as Right of Way (“ROW”) This guide is not meant to be comprehensive in nature. For a more thorough guide the reader should refer to Chapter 1, Part 5, of the AREMA Manual for Railway Engineering However, some SCCRTC-specific requirements differ from those od AREMA.

2.0 Utility

For the purposes of this guide, the definition of a utility is taken from Title 23, CFR, Part 645, Subpart A. Utility—a privately, publicly, or cooperatively owned line, facility or system for producing, transmitting, or distributing communications, cable television, power, electricity, light, heat, gas, oil, crude products, water, steam, waste, storm water not connected with highway drainage, or any other similar commodity, including any fire or police signal system or street lighting system, which directly or indirectly serves the public. The term utility shall also mean the utility company inclusive of any wholly owned or controlled subsidiary (“Utility”).

Such utilities occupying the SCCRTC ROW that may involve overhead, underground or surface individually or in combinations shall require a license agreement.

3.0 License Agreement

A license agreement is required for all utilities occupying SCCRTC ROW. Such an agreement between SCCRTC and the Utility will define the terms of the occupancy. Some of the terms may include items such as fees, geographic region, means of occupancy, time-period of licensure, maintenance responsibilities and termination clause.

4.0 Approval Process for Licensure

Approval process for licensure will require both legal and engineering review of the terms of occupancy.

Legal terms will be defined by SCCRTC’s standard agreements that are typically used for such occupancy.

Engineering review and acceptance of the means and method of occupancy will be subject to SCCRTC’s internal review.

Approval for licensure can be time consuming depending on the complexity of the project. Utilities should apply for licensure preferably during the planning phase of their project where there is still the opportunity to make adjustments in the nature and means of occupancy to satisfy both parties.

5.0 Engineering Documents Required for Licensure

Typical engineering documents required for licensure will generally include the following. Additional information may be requested at the discretion of SCCRTC.

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

1. Plan view layout of the occupancy shown in relation to the SCCRTC facility.
2. Profile view layout of the occupancy shown in relation to the SCCRTC facility.
3. Details and specifications of the pipeline or wireline involved.
4. Construction means and method description of the installation.
5. Impacts to SCCRTC operations due to the installation. Typically, no interruptions are expected.

6.0 Engineering Review Criteria

Engineering review of utility occupancy drawings, specifications and means & method of installation will primarily be done using the following documents as a guide.

1. Chapter 1, Part 5, of the AREMA Manual for Railway Engineering.
2. NFPA 70, National Electrical Safety Code.
3. National Electrical Safety Code by IEEE.
4. OSHA Standards – 29 CFR, Part 1926, Safety and Health Regulations for Construction.
5. SCCTRC specific requirements.

7.0 Typical Requirements for Utility Crossings

Typical crossings may include pipelines for transporting substances which may be flammable or non-flammable. Contents of pipelines may be under pressure or non-pressurized. Wireline crossings may include telecommunication or electric. For the purpose of this guide, the requirements are discussed by classifying the utility as discussed below.

a. Pipeline Requirement for Non-flammable Liquid crossing underground

Utilities carrying non-flammable liquids may include watermains, sanitary sewers, storm sewers or liquid chemical waste. The choice of pipeline material is typically the responsibility of the Utility. The pipe material provided may be steel, concrete or plastic.
In all cases the stress on the pipe from internal pressure and external loads must not exceed the minimum allowable stress. Documentation showing that this criteria is met must be provided by the Utility. More information on acceptable material and thickness can be found in AREMA, MRE, Chapter 1, Part 5.

Typical requirements for non-flammable pipelines include:

1. Minimum depth below base of rail is 5½ft.
2. Minimum depth not under track loading zone is 4ft.
3. Minimum depth below bottom of ditch is 3ft.
4. Transverse crossing under pressure require encasement in a leakproof pipe within limits of ROW.
5. Pipelines under pressure require emergency shut-off valves in case of leaks.
6. Longitudinal placement within 25ft of centerline of track to be encased.
7. Angle of track crossing close to 90deg. as practicable but no less than 45deg.
8. Do not place within railroad culverts or attach to railroad bridges.

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

9. Longitudinal placement within ROW to be as far as practical from tracks and close to the ROW.
10. Manholes along pipeline should be outside the ROW and if not practical, make top of manhole flush with top of ground and or outside service roads.
11. Pipelines may require insulation from underground conduits carrying electric wires.
12. The requirements may be more stringent than above if required by others having jurisdiction.
13. Maintenance and repair procedures of pipeline should be non-interfering with railroad operations.

b. Pipeline Requirement for Flammable Liquid

Utilities carrying flammable liquids may include petroleum or other flammable products flowing under pressure. The pipeline material must be steel and must conform to the requirements of ASME B 31.4 Pipeline Transportation Systems for Liquids and Slurries. In all cases the stress on the pipe from internal pressure and external loads must not exceed the minimum allowable stress. Documentation showing that this criteria is met must be provided by the Utility. More information on acceptable material can be found in AREMA, MRE, Chapter 1, Part 5.

Typical requirements for flammable pipelines include.

1. Pipelines in general shall be encased in a steel casing pipe.
2. Minimum depth below base of rail for casing pipe is 5½ft.
3. Minimum depth not under track for casing pipe is 3ft.
4. Casing may be waived under secondary or industry track if depth is not less than 10ft from base of rail nor less than 6ft from ground surface or bottom of ditches.
5. Casing pipe extends from ROW to ROW.
6. Angle of track crossing close to 90deg. as practicable but no less than 45deg.
7. Cross tracks through railroad embankments.
8. Emergency shut off valves either side of SCCRTC ROW.
9. Seals and vents at end of casing pipe is required.
10. Longitudinal placement within ROW to be as far as practical from tracks but not less than 25ft from any track with minimum 6ft of ground cover.
11. Markers on each side of ROW for transverse crossing and every 500ft along pipeline for longitudinal crossing, indicating pipeline content and emergency contact information.
12. Emergency response procedures for potential leaks or leaks due to accidents.
13. Protection from corrosion and insulation from underground electric sources.
14. Inspection and maintenance program.

c. Pipeline Requirement for Flammable or Non-Flammable Gas

For Utilities carrying flammable and non-flammable gas flowing under pressure, the pipeline material must be steel and conform to the requirements of ASME B 31.8 and other

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

ASEM codes. In all cases the stress on the pipe from internal pressure and external loads must not exceed the minimum allowable stress. Documentation showing that this criteria is met must be provided by the Utility. More information on acceptable material can be found in AREMA, MRE, Chapter 1, Part 5.

Typical requirements for flammable pipelines include.

1. Pipelines in general can be encased in a steel casing pipe or uncased.
2. Minimum depth below base of rail for carrier pipe is 10ft.
3. Minimum depth not under track for carrier pipe is 6ft.
4. Where the above depths cannot be met, a casing may be used at minimum depths of 5½ft.
5. Casing pipe extends from ROW to ROW.
6. Angle of track crossing is close to 90deg. as practicable but no less than 45deg.
7. Cross tracks through railroad embankments.
8. Emergency shut off valves either side of SCCRTC ROW.
9. Seals and vents at end of casing pipe is required.
10. Longitudinal placement within ROW to be as far as practical from tracks but not less than 25ft from any track with minimum 6ft of ground cover.
11. Markers on each side of ROW for transverse crossing and every 500ft along pipeline for longitudinal crossing, indicating pipeline content and emergency contact information.
12. Emergency response procedures for potential leaks or leaks due to accidents.
13. Protection from corrosion and insulation from underground electric sources.
14. Inspection and maintenance program.

d. Overhead Pipeline Crossings

Overhead pipelines are generally not preferred. Where circumstances warrant it, they may be attached to overhead structures not owned or maintained by the Railroad provided the owner of the structure has issued a permit for the facility.

The following are some of the typical requirements.

1. For utility pipeline supported on existing facility, the dimensional clearances provided by the facility to the nearest track shall not be reduced.
2. Angle of track crossing is close to 90deg. as practicable but no less than 45deg.
3. The design should provide for protection such as a leak by means of a casing that directs the leak off the railroad property.
4. In case a new pipe bridge is used to support the crossing, the following are the clearance requirements:
    a. Minimum vertical clearance for a bridge above top of rail is 25ft.
    b. Minimum vertical clearance for cable supported span above top of rail is 50ft.
    c. Minimum horizontal clearance from the centerline of nearest track is 25ft.
    d. Bridge Pier protection will be required for horizontal clearance less then 25ft.

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

5. Emergency response procedures for potential leaks or leaks due to accidents.
6. Inspection and maintenance program.

e. Wireline Transverse Crossings and Parallel Occupancies

Wireline crossings will typically include electric power and tele-communication with all associated supports and equipment. Transverse crossings and parallel occupancies may be underground or overhead. The National Electrical Safety Code is referenced for controlling requirements. Underground crossings should be encased in a steel or HDPE conduit.

The following are some typical requirements.

1. Angle of track crossing is close to 90deg. as practicable but no less than 45deg.
2. Poles should be set outside the ROW or as close to the property line as possible.
3. Minimum vertical clearance for proposed aerial transverse crossing measured at 60 deg. Fahrenheit is as follows.

Guy wires, messenger cables, and telecommunication cables	Electric supply lines and neutral wires (voltage is measured phase-to-ground) *		
27-feet	Less than 750-V	750-V to 15-KV	15-KV to 50-KV
	30-feet	31-feet	33-feet

* For electric supply lines or neutral wires carrying greater than 50-KV, use a vertical clearance of 33-feet plus ½-inch per 1-KV above 50-KV.

4. Vertical clearance between proposed aerial wire crossings and aerial communications lines is as follows:

Guy wires, messenger cables, and telecommunication cables	Electric supply lines and neutral wires (voltage is measured phase-to-ground) *		
2-feet	Less than 750-V	750-V to 15-KV	15-KV to 50-KV
	2-feet	4-feet	6-feet

* For electric supply lines or neutral wires carrying greater than 50-KV, use a vertical clearance of 33-feet plus ½-inch per 1-KV above 50-KV.

5. For underground crossings minimum depth of installation is as follows:

Material	Bore & Jack	HDD-Wet	HDD-Dry
Steel	5.5-ft	10-ft	5.5-ft
Plastic	15-ft*		
Parallel Occupancy	4-ft		

* Within 25-feet of centerline of the closest track and a minimum depth of 10-feet anywhere else on ROW. HDD-Wet = installation using drilling fluids.

6. Minimum horizontal clearance from overhead wireline crossing to track supporting structure is 300ft.
7. Minimum horizontal clearance from overhead wireline crossing to any switch or other railroad infrastructure is 50ft.
8. Minimum horizontal clearance from wireline support structure to nearest track is 50ft.
9. Unguyed support structure should be located a minimum of distance equal to the height of the structure from railroad signal and communication lines.
10. Unguyed support structure should be located a minimum of distance equal to the height of the structure plus 10ft from centerline of track. Increase clearance by 6inch minimum or

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

1.5inch for every degree of curve.

11. Guy wires should be placed outside the ROW or when inside the ROW place parallel to ROW line.

8.0 Methods of Construction

Methods of construction will require review by SCCRTC to understand the impacts to operations. Typically, all installations shall be completed without interference to rail operations and without conflict to existing facilities and/or utilities.

Pipeline construction is done using various methods depending on suitability. Some of the more commonly used methods are:

1. Jack and Bore method.
2. Horizontal directional drilling wet method using a drilling fluid.
3. Horizontal directional drilling dry method.
4. Microtunneling using a tunnel boring machine.

In all cases, the contractor is required to submit a full description of the means and method of construction including any excavation and shoring that may be required. Once the contractor submittal is approved for construction, the work may proceed with adequate protection such as flaggers and construction monitors on site.

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

APPENDIX A

DRAWING CHECKLIST

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

Aerial Wireline Occupancy Checklist

Plan View of Crossing

- ☐ All railroad tracks shown
- ☐ Indicates distance (in feet) to SCCRTC milepost or grade crossing
- ☐ Angle of crossing relative to railroad track(s)
- ☐ Dimensioned property lines
- ☐ Location of poles and distance from edge of pole to nearest railroad track centerline
- ☐ Location of all existing railroad communications lines and all utility lines
- ☐ Indicate span length across tracks from pole to pole
- ☐ If within highway limits or in the vicinity of a grade crossing, location and type of grade crossing traffic control devices (flashers, gales, etc.) and clearance from existing devices to proposed wire line/poles

Profile View of Crossing

- ☐ All railroad tracks shown
- ☐ Dimensioned property lines
- ☐ Location of poles and distance from edge of pole to nearest railroad track centerline
- ☐ Vertical clearance from top of rail to bottom of sag for all tracks
- ☐ Location of all existing railroad communications lines and all utility lines
- ☐ Vertical clearance between existing railroad pole fines and proposed wire line
- ☐ Indicate span length across tracks from pole to pole
- ☐ If within highway limits or in the vicinity of a grade crossing, location and type of grade crossing traffic control devices (flashers, gales, etc.) and clearance from existing devices to proposed wire line/poles

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

Underground Wireline Occupancy Checklist

All underground conduit applications shall include a conduit data sheet, plan, and profile view of the proposed facility. See the SCC guidelines for the required format. Below is a suggested check-list for your plan development and the Conduit Data Sheet.

Plan View of Crossing

- ☐ All railroad tracks, including distance to any track switches or turnouts from proposed conduit
- ☐ Indicates distance (in feet) to SCCRTC Milepost or grade crossing
- ☐ Angle of crossing relative to railroad track(s)
- ☐ Dimensioned property lines
- ☐ Location of conduit marker signs (preferably located at edge of property or right of way lines)
- ☐ Location of all existing railroad communications lines and all utility lines
- ☐ Location of any fiber-optic cables parallel to tracks
- ☐ Conduit casing pipe length
- ☐ If within highway limits or in the vicinity of a grade crossing, location and type of grade crossing traffic control devices (flashers, gates, etc.) and clearance from existing devices to proposed wire line
- ☐ Location of launching and receiving pits

Profile View of Crossing

- ☐ All railroad tracks
- ☐ Profile of ground above crossing
- ☐ Dimensioned property lines
- ☐ Theoretical railroad embankment lines
- ☐ Proposed location and elevations of launching and receiving pits
- ☐ Casing pipe length
- ☐ Bottom of rail elevation
- ☐ Depth of cover between bottom of rail and top of conduit or casing pipe
- ☐ Location of and the minimum depth of cover from ground line to top of conduit or casing pipe on right of way (including ditches)

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

Conduit Data Sheet - For Telecom and Power Conduits only, 6" in diameter or less

	CONDUIT
NOMINAL SIZE OF PIPE	
MATERIAL*	
OUTSIDE DIAMETER	
INSIDE DIAMETER	
WALL THICKNESS - **must be at least 0.188"**	
TYPE OF COATING	

* STEEL conduits required at least 10' depth below base of rail HDPE conduits will be considered at least 15' depth below base of rail

Proposed method of installation:

- ☐ Jack & Bore
- ☐ Directional Boring Method "A" – *must have at least 10' depth below base of rail*
- ☐ Directional Boring Method "B" – *only for casings 6 inches or less in diameter*
- ☐ Open Cut – *All installations directly under any track must be designed as a bored installation. Open cut installations will be considered on a case-by-case basis by SCCRTC.*
- ☐ Other – Please Specify: _____

MULTIPLE INNERDUCTS
NUMBER OF INNERDUCTS WITHIN CASING PIPE:

- Provide a detail or cross section of the casing pipe with innerducts (see below).
- Clearly mark the type of facility that will be installed within each innerduct. If innerduct will be left spare or empty, please identify as such.



Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

Pipeline Occupancy Checklist

All pipeline applications shall include a pipe data sheet, plan, and profile view of the proposed facility. Below is a suggested check-list for your plan development and a Pipe Data Sheet.

Plan View of Crossing

- ☐ All railroad tracks, including distance to any track switches or turnouts from proposed pipeline
- ☐ Indicates distance (in feet) to SCCRTC Milepost or grade crossing
- ☐ Angle of crossing relative to railroad track(s)
- ☐ Dimensioned property lines
- ☐ Location of valves
- ☐ Location of vents
- ☐ Location of pipeline marker signs (preferably at edge of property or right of way lines)
- ☐ Location of all existing railroad communications lines and all utility lines
- ☐ Location of any fiber-optic cables parallel to tracks
- ☐ If within highway limits or in the vicinity of a grade crossing, location and type of grade crossing traffic control devices (flashers, gates, etc.) and clearance from existing devices to proposed pipe
- ☐ Casing pipe length
- ☐ Location of launching and receiving pits

Profile View of Crossing

- ☐ All railroad tracks
- ☐ Profile of ground above crossing
- ☐ Distance to valves
- ☐ Distance to vents and height above ground
- ☐ Distance to pipeline marker signs
- ☐ Dimensioned property lines
- ☐ Theoretical railroad embankment lines
- ☐ Proposed location and elevations of launching and receiving pits
- ☐ Casing pipe length
- ☐ Bottom of rail elevation
- ☐ Depth of Cover between bottom of rail and top of casing pipe (or carrier pipe if casing pipe not required)
- ☐ location of and the minimum depth of cover from ground line to top of casing pipe (or carrier pipe if casing not required) on right of way (inducing ditches)

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

General Notes (all plans shall include the following General Notes)

1. Contractor shall follow al requirements of SCCRTC Design and Construction Specifications
2. Pipeline and crossing to be installed and maintained in accordance with last approved American Railway Engineering and Maintenance of way Association Specifications for Pipelines Conveying Flammable and Non-flame Substances
3. Blasting not permitted

Pipe Data Sheet

	CARRIER PIPE	CASING PIPE
CONTENTS TO BE HANDLED		
MAX. ALLOWABLE OPERATING PRESSURE		
NOMINAL SIZE OF PIPE		
OUTSIDE DIAMETER		
INSIDE DIAMETER		
WALL THICKNESS		
WEIGHT PER FOOT		
MATERIAL		
PROCESS OF MANUFACTURE		
SPECIFICATION		
GRADE OR CLASS (Specified Minimum Yield Strength)		
TEST PRESSURE		
TYPE OF JOINT		
TYPE OF COATING		
DETAILS OF CATHODIC PROTECTION		
DETAILS OF SEALS OR PROTECTION AT END OF CASING		
CHARACTER OF SUBSURFACE MATERIAL		
APPROXIMATE GROUND WATER LEVEL		
SOURCE OF INFORMATION ON SUBSURFACE CONDITIONS		

Docusign Envelope ID: 6AF97AB3-E64C-4F9E-B29E-7E12670BE4F7

Proposed method of installation:

- ☐ Bore & Jack
- ☐ Jacking
- ☐ Tunneling (with Tunnel Liner Plate)
- ☐ Directional Bore/Horizontal Direction Drilling – Method A
- ☐ Directional Bore/Horizontal Direction Drilling – Method B
- ☐ Open Cut – *All installations directly under any track must be designed as a bored installation. Open cut installations will be considered on a case-by-case basis.*
- ☐ Other – Please Specify: _____

CITY COUNCIL AGENDA REPORT

MEETING DATE: **Tuesday, April 14, 2026**
TO: **CITY COUNCIL**
WRITTEN BY: SENIOR FINANCIAL ANALYST DIAZ
RECOMMENDED BY: **INTERIM PUBLIC WORKS & UTILITIES DIRECTOR GREEN**
APPROVED BY: **TAMARA VIDES, CITY MANAGER**

SUBJECT: **AUTHORIZATION TO INCREASE OPEN PURCHASE ORDERS WITH PAJARO VALLEY FABRICATION, INC, ARATA EQUIPMENT COMPANY AND FASTENAL COMPANY BY $50,000.01, FOR AN AMOUNT NOT TO EXCEED $150,000 EACH**

RECOMMENDATION:

It is recommended that the City Council adopt a resolution authorizing the increase of open purchase orders with Pajaro Valley Fabrication, Inc, Arata Equipment Company and Fastenal Company by $50,000.01, for an amount not to exceed $150,000 each.

BACKGROUND:

City operations require immediate purchases and occasional small jobs. Pajaro Valley Fabrication, Inc, Arata Equipment Company and Fastenal Company have been identified as vendors commonly used to facilitate small jobs throughout many departments. The City established open purchase orders with Pajaro Valley Fabrication, Inc, Arata Equipment Company and Fastenal Company, in an amount not to exceed $99,999.99 per open purchase order.

DISCUSSION:

The current open purchase orders with Pajaro Valley Fabrication, Inc, Arata Equipment Company and Fastenal Company are running out of funds and will be exceeding the amount of $99,999.99. Purchases and services in excess of $100,000 require Council approval per Section 3-5 460 of Chapter 5 (Purchasing Procedure) of Title 3 (Finance) of the Watsonville Municipal Code. Staff is requesting the increase of "not-to-exceed" open purchase orders with Pajaro Valley Fabrication, Inc, Arata Equipment Company and

Fastenal Company by $50,000.01 per open purchase order, for an amount not to exceed $150,000 each to pay for purchases and services for the remainder of the fiscal year.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

This action is exempt from the requirements of the California Environmental Quality Act (CEQA) in accordance with CEQA Guidelines Section 15378(b)(5), in that adopting a Resolution authorizing open purchase orders with Pajaro Valley Fabrication Inc. Arata Equipment Company and Fastenal Company, does not meet CEQA's definition of a "project," because the action does not have the potential for resulting in either a direct physical change in the environment or a reasonably foreseeable indirect physical change in the environment and if a "project," is exempt under the "common sense" exception (14 Cal. Code Regs. § 15061(b)(3)) because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment.

STRATEGIC PLAN:

These open purchase orders support the following Strategic Plan:
Infrastructure & Environment

FINANCIAL IMPACT:

Funds for these open purchase orders will be paid through the supplies and materials and repair accounts in the operational budgets of the respective departments.

ALTERNATIVE ACTION:

No reasonable alternatives are known at this time.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

None.

RESOLUTION NO._____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE AUTHORIZING THE INCREASE OF OPEN PURCHASE ORDERS WITH PAJARO VALLEY FABRICATION, INC., ARATA EQUIPMENT COMPANY AND FASTENAL COMPANY BY $50,000.01 IN AN AMOUNT NOT TO EXCEED $150,000 EACH TO FACILITATE PURCHASES $10,000 AND SMALLER

WHEREAS, City operations require immediate purchases from time to time to facilitate small jobs under $10,000; and

WHEREAS, Pajaro Valley Fabrication Inc., Arata Equipment Company, and Fastenal Company have been identified as vendors commonly used to facilitate small jobs throughout many departments; and

WHEREAS, the City established open purchase orders with Pajaro Valley Fabrication Inc, Arata Equipment Company, and Fastenal Company, in an amount not to exceed $99,999.99; and

WHEREAS, the current open purchase orders with Pajaro Valley Fabrication Inc, Arata Equipment Company, and Fastenal Company will be exceeding the $99,999.99 amount and an increase of $50,000.01 is requested to pay for the purchases and services for the remainder of the fiscal year; and

WHEREAS, purchases in excess of $100,000 require Council approval per Section 3-5.460 of Chapter 5 (Purchasing Procedures) of Title 3 (Finance) of the Watsonville Municipal Code.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, AS FOLLOWS:

1. This action is exempt from the requirements of the California Environmental Quality Act (CEQA) in accordance with CEQA Guidelines Section 15378(b)(5), in that

adopting a Resolution authorizing open purchase orders with Pajaro Valley Fabrication Inc. Arata Equipment Company and Fastenal Company, does not meet CEQA's definition of a “project,” because the action does not have the potential for resulting in either a direct physical change in the environment or a reasonably foreseeable indirect physical change in the environment and if a “project,” is exempt under the “common sense” exception (14 Cal. Code Regs. § 15061(b)(3)) because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment.

2. The City Council hereby authorizes the increase of the Open Purchase Orders by $50,000.01, per open purchase order, for the following vendors:

- Pajaro Valley Fabrication Inc,
- Arata Equipment Company
- Fastenal Company

With the additional amount, each of the above Open Purchase Orders will not exceed $150,000.

****

CITY COUNCIL AGENDA REPORT

MEETING DATE: Tuesday, April 14, 2026
TO: CITY COUNCIL
WRITTEN BY: GIS Coordinator Hanley
RECOMMENDED BY: INNOVATION & TECHNOLOGY DIRECTOR GILL
APPROVED BY: TAMARA VIDES, CITY MANAGER

SUBJECT: RENEWAL OF 3-YEAR ENTERPRISE LICENSE AGREEMEN WITH ESRI

RECOMMENDATION:

Staff recommends Council approve the renewal of a 3-year enterprise license agreement with ESRI for $60,300 per year, for a three-year total of $180,900.

BACKGROUND:

GIS (geographic information system) technology has long been an essential tool for the effective functioning of cities and local governments. As the foundation for all GIS mapping and data management at the City of Watsonville, ESRI software is a critical tool that supports operations at nearly every level across almost every department, including asset management; regulatory compliance; short and long-range planning; capital improvement planning; the provision of data and information to staff, residents, partners, and consultants; informed decision-making; emergency preparedness and response; and citizen engagement and an open, transparent government.

As the City of Watsonville continues its transition to becoming a fully digitally enabled ‘smart city,’ GIS will serve as the cornerstone of a connected, integrated suite of business systems and information that will continue to improve the City’s level of service. The future is decidedly more digital, more connected, and more dependent on technology like GIS to empower this transformation.

DISCUSSION:

The City has been an ESRI customer for decades. The contract referenced by this memo is a 3-year renewal of our most recent 3-year contract.

STRATEGIC PLAN:

The application of GIS technology and methods is well-suited to support the entire scope and range of the City's strategic plan, including planning, analysis, presentation/visualization through to implementation, tracking, and reporting.

FINANCIAL IMPACT:

The most recent contract with ESRI (2023-2026) was based on 2023 pricing at $55,000 for the first year, and $56,700 for each of the next 2 years. That represented a 3.1% price increase from our previous contract signed in 2020. This new contract will include a 6.3% increase to $60,300 in the first year, but will remain at $60,300 each year for the remainder of the agreement. The terms of the contract will expire after year 3 on May 31, 2029. Software licensing is paid for out of the IT budget.

ALTERNATIVE ACTION:

There are no reasonable alternatives, ESRI software is ubiquitous in city and local government. ESRI has more than 30,000 city and local government customers including the City of Watsonville, City of Santa Cruz, City of Salinas, City of Gilroy, Santa Cruz County, Monterey County, San Benito County, and Santa Cruz Regional 911.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

None.

RESOLUTION NO. _____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING SOLE SOURCE PURCHASE WITH ENVIRONMENTAL SYSTEMS RESEARCH INSTITUTE (ESRI), INC., A CORPORATION, FOR THE PURCHASE OF GEOGRAPHIC INFORMATION SYSTEMS SOFTWARE, IN AN AMOUNT NOT TO EXCEED $180,900; AND AUTHORIZING CITY MANAGER TO EXECUTE A SERVICES AND PURCHASING AGREEMENT (FUNDED FROM 285-7226 IT SOFTWARE FUND)

WHEREAS, competitive bidding requirements for the purchase of supplies, equipment and non-personal contractual services and the sale ,of personal property are set forth in Chapter 5 of Title 3 of the Municipal Code; and

WHEREAS, subdivision (c) of § 3-5.210 exempts Equipment, supplies, or nonprofessional services that have been uniformly adopted or otherwise standardized in the City, available only from one source, or sought to match existing equipment or supplies already in use (also known as a sole source purchase); and

WHEREAS, ESRI is the manufacturer of the software and has limited reselling partners of which are assigned to the city account.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. Adopting a Resolution approving a sole source purchase agreement for Geographic Information Systems does not meet CEQA's definition of a “project,” because the action does not have the potential for resulting in either a direct physical change in the environment or a reasonably foreseeable indirect physical change in the environment, and because the action constitutes organizational or administrative activities of governments that will not result in direct or indirect physical changes in the environment and if a “project,” is exempt under the “common sense” exception (14 Cal. Code Regs. § 15061(b)(3))

because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment.

2. The Council finds that the purchase of Geographic Information Systems is available from one source that meets the needs of the City (also known as a sole source purchase).

3. This purchase is exempt from the purchasing procedures of Chapter 5 of Title 3 of the Municipal Code as a sole source purchase under subdivision (d) of § 3-5.210 of the Municipal Code.

4. That the Council hereby approves the Small Enterprise Agreement between the City of Watsonville and ESRI for the purchase of Geographic Information Systems, in an amount not to exceed $180,900.

5. That the City Manager is hereby authorized and directed to execute said Agreement for and on behalf of the City of Watsonville in the form attached hereto and incorporated herein by this reference, with minor revisions that may be approved by the City Manager and the City Attorney.

****

Quotation # Q-560100

Date: March 10, 2026

Environmental Systems Research Institute, Inc.
380 New York St
Redlands, CA 92373-8100
Phone: (909) 793-2853
DUNS Number: 06-313-4175 CAGE Code: 0AMS3

Customer # 107393 **Contract #**

City of Watsonville
Innovation & Technology Dept
215 Union St
Watsonville, CA 95076-5009

ATTENTION: Charles Hanley
PHONE: (831) 768-3430
EMAIL: charles.hanley@watsonville.gov

To expedite your order, please attach a copy of this quotation to your purchase order.
Quote is valid from: 12/9/2025 To: 6/7/2026

Material	Qty	Term	Unit Price	Total
193206	1	Year 1	$60,300.00	$60,300.00
Populations of 50,001 to 100,000 Small Government Enterprise Agreement Annual Subscription				
193206	1	Year 2	$60,300.00	$60,300.00
Populations of 50,001 to 100,000 Small Government Enterprise Agreement Annual Subscription				
193206	1	Year 3	$60,300.00	$60,300.00
Populations of 50,001 to 100,000 Small Government Enterprise Agreement Annual Subscription				

Subtotal:	$180,900.00
Sales Tax:	$0.00
Estimated Shipping and Handling (2 Day Delivery):	$0.00
Contract Price Adjust:	$0.00
Total:	$180,900.00

Esri may charge a fee to cover expenses related to any customer requirement to use a proprietary vendor management, procurement, or invoice program.

For questions contact:	Email:	Phone:
Michael Arias	marias@esri.com	(909) 793-2853

The items on this quotation are subject to and governed by the terms of this quotation, the most current product specific scope of use document found at https://assets.esri.com/content/dam/esrisites/media/legal/product-specific-terms-of-use/e300.pdf, and your applicable signed agreement with Esri. If no such agreement covers any item quoted, then Esri's standard terms and conditions found at https://go.esri.com/MAPS apply to your purchase of that item. If any item is quoted with a multi-year payment schedule, Esri may invoice at least 30 days in advance of each anniversary date without the issuance or a Purchase Order, and Customer is required to make all payments without right of cancellation. Third-party data sets included in a quotation as separately licensed items will only be provided and invoiced if Esri is able to provide such data and will be subject to the applicable third-party's terms and conditions. If Esri is unable to provide any such data set, Customer will not be responsible for any further payments for the data set. US Federal government entities and US government prime contractors authorized under FAR 51.1 may purchase under the terms of Esri's GSA Federal Supply Schedule. Supplemental terms and conditions found at https://www.esri.com/en-us/legal/terms/state-supplemental apply to some US state and local government purchases. All terms of this quotation will be incorporated into and become part of any additional agreement regarding Esri's offerings. Acceptance of this quotation is limited to the terms of this quotation. Esri objects to and expressly rejects any different or additional terms contained in any purchase order, offer, or confirmation sent to or to be sent by buyer. Unless prohibited by law, the quotation information is confidential and may not be copied or released other than for the express purpose of system selection and purchase/license. The information may not be given to outside parties or used for any other purpose without consent from Esri. Delivery is FOB Origin for customers located in the USA.

ARIASM **This offer is limited to the terms and conditions incorporated and attached herein.**

Quotation # Q-560100

Date: March 10, 2026

Environmental Systems Research Institute, Inc.
380 New York St
Redlands, CA 92373-8100
Phone: (909) 793-2853
DUNS Number: 06-313-4175 CAGE Code: 0AMS3

Customer # 107393 **Contract #**

City of Watsonville
Innovation & Technology Dept
215 Union St
Watsonville, CA 95076-5009

ATTENTION: Charles Hanley
PHONE: (831) 768-3430
EMAIL: charles.hanley@watsonville.gov

To expedite your order, please attach a copy of this quotation to your purchase order.
Quote is valid from: 12/9/2025 To: 6/7/2026

If you have made ANY alterations to the line items included in this quote and have chosen to sign the quote to indicate your acceptance, you must fax Esri the signed quote in its entirety in order for the quote to be accepted. You will be contacted by your Customer Service Representative if additional information is required to complete your request.

If your organization is a US Federal, state, or local government agency; an educational facility; or a company that will not pay an invoice without having issued a formal purchase order, a signed quotation will not be accepted unless it is accompanied by your purchase order.

In order to expedite processing, please reference the quotation number and any/all applicable Esri contract number(s) (e.g. MPA, ELA, SmartBuy, GSA, BPA) on your ordering document.

BY SIGNING BELOW, YOU CONFIRM THAT YOU ARE AUTHORIZED TO OBLIGATE FUNDS FOR YOUR ORGANIZATION, AND YOU ARE AUTHORIZING ESRI TO ISSUE AN INVOICE FOR THE ITEMS INCLUDED IN THE ABOVE QUOTE IN THE AMOUNT OF $_____, PLUS SALES TAXES IF APPLICABLE. DO NOT USE THIS FORM IF YOUR ORGANIZATION WILL NOT HONOR AND PAY ESRI'S INVOICE WITHOUT ADDITIONAL AUTHORIZING PAPERWORK.

Please check one of the following:

___ I agree to pay any applicable sales tax.

___ I am tax exempt, please contact me if exempt information is not currently on file with Esri.

_____ _____
Signature of Authorized Representative **Date**

_____
Name (Please Print)

_____
Title

The quotation information is proprietary and may not be copied or released other than for the express purpose of system selection and purchase/license. This information may not be given to outside parties or used for any other purpose without consent from Environmental Systems Research Institute, Inc. (Esri).

Any estimated sales and/or use tax reflected on this quote has been calculated as of the date of this quotation and is merely provided as a convenience for your organization's budgetary purposes. Esri reserves the right to adjust and collect sales and/or use tax at the actual date of invoicing. If your organization is tax exempt or pays state tax directly, then prior to invoicing, your organization must provide Esri with a copy of a current tax exemption certificate issued by your state's taxing authority for the given jurisdiction.

Esri may charge a fee to cover expenses related to any customer requirement to use a proprietary vendor management, procurement, or invoice program.

For questions contact:	**Email:**	**Phone:**
Michael Arias	marias@esri.com	(909) 793-2853

The items on this quotation are subject to and governed by the terms of this quotation, the most current product specific scope of use document found at https://assets.esri.com/content/dam/esrisites/media/legal/product-specific-terms-of-use/e300.pdf, and your applicable signed agreement with Esri. If no such agreement covers any item quoted, then Esri's standard terms and conditions found at https://go.esri.com/MAPS apply to your purchase of that item. If any item is quoted with a multi-year payment schedule, Esri may invoice at least 30 days in advance of each anniversary date without the issuance or a Purchase Order, and Customer is required to make all payments without right of cancellation. Third-party data sets included in a quotation as separately licensed items will only be provided and invoiced if Esri is able to provide such data and will be subject to the applicable third-party's terms and conditions. If Esri is unable to provide any such data set, Customer will not be responsible for any further payments for the data set. US Federal government entities and US government prime contractors authorized under FAR 51.1 may purchase under the terms of Esri's GSA Federal Supply Schedule. Supplemental terms and conditions found at https://www.esri.com/en-us/legal/terms/state-supplemental apply to some US state and local government purchases. All terms of this quotation will be incorporated into and become part of any additional agreement regarding Esri's offerings. Acceptance of this quotation is limited to the terms of this quotation. Esri objects to and expressly rejects any different or additional terms contained in any purchase order, offer, or confirmation sent to or to be sent by buyer. Unless prohibited by law, the quotation information is confidential and may not be copied or released other than for the express purpose of system selection and purchase/license. The information may not be given to outside parties or used for any other purpose without consent from Esri. Delivery is FOB Origin for customers located in the USA.

ARIASM **This offer is limited to the terms and conditions incorporated and attached herein.**

Esri Use Only:
Cust. Name _____
Cust. # _____
PO # _____
Esri Agreement # _____

SMALL ENTERPRISE AGREEMENT
COUNTY AND MUNICIPALITY GOVERNMENT
(E214-3)

This Agreement is by and between the organization identified in the Quotation (**"Customer"**) and **Environmental Systems Research Institute, Inc.** (**"Esri"**).

This Agreement sets forth the terms for Customer's use of Products and incorporates by reference (i) the Quotation and (ii) the Master Agreement. Should there be any conflict between the terms and conditions of the documents that comprise this Agreement, the order of precedence for the documents shall be as follows: (i) the Quotation, (ii) this Agreement, and (iii) the Master Agreement. This Agreement shall be governed by and construed in accordance with the laws of the state in which Customer is located without reference to conflict of laws principles, and the United States of America federal law shall govern in matters of intellectual property. The modifications and additional rights granted in this Agreement apply only to the Products listed in Table A.

Table A
List of Products

Uncapped Quantities (annual subscription)

ArcGIS Enterprise Software and Extensions ArcGIS Enterprise (Advanced and Standard) ArcGIS Monitor ArcGIS Enterprise Extensions: ArcGIS 3D Analyst, ArcGIS Spatial Analyst, ArcGIS Geostatistical Analyst, ArcGIS Network Analyst, ArcGIS Data Reviewer	**ArcGIS Enterprise Additional Capability Servers** ArcGIS Image Server **ArcGIS Online User Types** ArcGIS Online Viewer User Type **ArcGIS Enterprise User Types** ArcGIS Enterprise Viewer User Type

Capped Quantities (annual subscription)

ArcGIS Online User Types		**ArcGIS Enterprise User Types**	
ArcGIS Online Contributor User Type	30	ArcGIS Enterprise Contributor User Type	30
ArcGIS Online Mobile Worker User Type	150	ArcGIS Enterprise Mobile Worker User Type	150
ArcGIS Online Creator User Type	150	ArcGIS Enterprise Creator User Type	150
ArcGIS Online Professional User Type	40	ArcGIS Enterprise Professional User Type	40
ArcGIS Online Professional Plus User Type	40	ArcGIS Enterprise Professional Plus User Type	40
ArcGIS Pro (Add-on Apps) for ArcGIS Online Creator or Professional User Type		**ArcGIS Pro (Add-on Apps) for ArcGIS Enterprise Creator or Professional User Type**	
ArcGIS 3D Analyst, ArcGIS Data Reviewer, ArcGIS Geostatistical Analyst, ArcGIS Network Analyst, ArcGIS Publisher, ArcGIS Spatial Analyst, ArcGIS Workflow Manager, ArcGIS Image Analyst	40 each	ArcGIS 3D Analyst, ArcGIS Data Reviewer, ArcGIS Geostatistical Analyst, ArcGIS Network Analyst, ArcGIS Publisher, ArcGIS Spatial Analyst, ArcGIS Workflow Manager, ArcGIS Image Analyst	40 each
ArcGIS Online Apps and Other		**ArcGIS Enterprise Apps and Other**	
ArcGIS Location Sharing for ArcGIS Online	40	ArcGIS Location Sharing for ArcGIS Enterprise	40
ArcGIS Online Service Credits	100,000	ArcGIS Advanced Editing User Type Extension for ArcGIS Enterprise	30

Other Benefits

Number of Esri User Conference registrations provided annually	4
Number of Tier 1 Help Desk individuals authorized to call Esri	4
Five percent (5%) discount on all individual commercially available instructor-led training classes at Esri facilities purchased outside this Agreement	

Customer may accept this Agreement by signing and returning the whole Agreement with (i) the Quotation attached, (ii) a purchase order, or (iii) another document that matches the Quotation and references this Agreement ("**Ordering Document**"). **ADDITIONAL OR CONFLICTING TERMS IN CUSTOMER'S PURCHASE ORDER OR OTHER DOCUMENT WILL NOT APPLY, AND THE TERMS OF THIS AGREEMENT WILL GOVERN.** This Agreement is effective as of the date of Esri's receipt of an Ordering Document, unless otherwise agreed to by the parties ("**Effective Date**").

Term of Agreement: Three (3) years

This Agreement supersedes any previous agreements, proposals, presentations, understandings, and arrangements between the parties relating to the licensing of the Products. Except as provided in Article 4—Product Updates, no modifications can be made to this Agreement.

Accepted and Agreed:

_____
(Customer)

By: _____
Authorized Signature

Printed Name: _____

Title: _____

Date: _____

CUSTOMER CONTACT INFORMATION

Contact: _____

Address: _____

City, State, Postal Code: _____

Country: _____

Quotation Number (if applicable): _____

Telephone: _____

Fax: _____

E-mail: _____

1.0—Additional Definitions

In addition to the definitions provided in the Master Agreement, the following definitions apply to this Agreement:

"Case" means a failure of the Software or Online Services to operate according to the Documentation where such failure substantially impacts operational or functional performance.

"Deploy", "Deployed" and "Deployment" mean to redistribute and install the Products and related Authorization Codes within Customer's organization(s).

"Fee" means the fee set forth in the Quotation.

"Maintenance" means Tier 2 Support, Product updates, and Product patches provided to Customer during the Term of Agreement.

"Master Agreement" means the applicable master agreement for Esri Products incorporated by this reference that is (i) found at https://www.esri.com/en-us/legal/terms/full-master-agreement and available in the installation process requiring acceptance by electronic acknowledgment or (ii) a signed Esri master agreement or license agreement that supersedes such electronically acknowledged master agreement.

"Product(s)" means the products identified in Table A—List of Products and any updates to the list Esri provides in writing.

"Quotation" means the offer letter and quotation provided separately to Customer.

"Technical Support" means the technical assistance for attempting resolution of a reported Case through error correction, patches, hot fixes, workarounds, replacement deliveries, or any other type of Product corrections or modifications.

"Tier 1 Help Desk" means Customer's point of contact(s) to provide all Tier 1 Support within Customer's organization(s).

"Tier 1 Support" means the Technical Support provided by the Tier 1 Help Desk.

"Tier 2 Support" means the Esri Technical Support provided to the Tier 1 Help Desk when a Case cannot be resolved through Tier 1 Support.

2.0—Additional Grant of License

2.1 Grant of License. Subject to the terms and conditions of this Agreement, Esri grants to Customer a personal, nonexclusive, nontransferable license solely to use, copy, and Deploy quantities of the Products listed in Table A—List of Products for the Term of Agreement (i) for the applicable Fee and (ii) in accordance with the Master Agreement.

2.2 Consultant Access. Esri grants Customer the right to permit Customer's consultants or contractors to use the Products exclusively for Customer's benefit. Customer will be solely responsible for compliance by consultants and contractors with this Agreement and will ensure that the consultant or contractor discontinues use of Products upon completion of work for Customer. Access to or use of Products by consultants or contractors not exclusively for Customer's benefit is prohibited. Customer may not permit its consultants or contractors to install Software or Data on consultant, contractor, or third-party computers or remove Software or Data from Customer locations, except for the purpose of hosting the Software or Data on Contractor servers for the benefit of Customer.

3.0—Term, Termination, and Expiration

3.1 Term. This Agreement and all licenses hereunder will commence on the Effective Date and continue for the duration identified in the Term of Agreement, unless this Agreement is terminated earlier as provided herein. Customer is only authorized to use Products during the Term of Agreement. For an Agreement with a limited term, Esri does not grant Customer an indefinite or a perpetual license to Products.

3.2 No Use upon Agreement Expiration or Termination. All Product licenses, all Maintenance, and Esri User Conference registrations terminate upon expiration or termination of this Agreement.

3.3 Termination for a Material Breach. Either party may terminate this Agreement for a material breach by the other party. The breaching party will have thirty (30) days from the date of written notice to cure any material breach.

3.4 Termination for Lack of Funds. For an Agreement with government or government-

owned entities, either party may terminate this Agreement before any subsequent year if Customer is unable to secure funding through the legislative or governing body's approval process.

3.5 Follow-on Term. If the parties enter into another agreement substantially similar to this Agreement for an additional term, the effective date of the follow-on agreement will be the day after the expiration date of this Agreement.

4.0—Product Updates

4.1 Future Updates. Esri reserves the right to update the list of Products in Table A—List of Products by providing written notice to Customer. Customer may continue to use all Products that have been Deployed, but support and upgrades for deleted items may not be available. As new Products are incorporated into the standard program, they will be offered to Customer via written notice for incorporation into the Products schedule at no additional charge. Customer's use of new or updated Products requires Customer to adhere to applicable additional or revised terms and conditions in the Master Agreement.

4.2 Product Life Cycle. During the Term of Agreement, some Products may be retired or may no longer be available to Deploy in the identified quantities. Maintenance will be subject to the individual Product Life Cycle Support Status and Product Life Cycle Support Policy, which can be found at https://support.esri.com/en/other-resources/product-life-cycle. Updates for Products in the mature and retired phases may not be available. Customer may continue to use Products already Deployed, but Customer will not be able to Deploy retired Products.

5.0—Maintenance

The Fee includes standard maintenance benefits during the Term of Agreement as specified in the most current applicable Esri Maintenance and Support Program document (found at https://www.esri.com/en-us/legal/terms/maintenance). At Esri's sole discretion, Esri may make patches, hot fixes, or updates available for download. No Software other than the defined Products will receive Maintenance. Customer may acquire maintenance for other Software outside this Agreement.

a. Tier 1 Support

1. Customer will provide Tier 1 Support through the Tier 1 Help Desk to all Customer's authorized users.

2. The Tier 1 Help Desk will be fully trained in the Products.

3. At a minimum, Tier 1 Support will include those activities that assist the user in resolving how-to and operational questions as well as questions on installation and troubleshooting procedures.

4. The Tier 1 Help Desk will be the initial point of contact for all questions and reporting of a Case. The Tier 1 Help Desk will obtain a full description of each reported Case and the system configuration from the user. This may include obtaining any customizations, code samples, or data involved in the Case.

5. If the Tier 1 Help Desk cannot resolve the Case, an authorized Tier 1 Help Desk individual may contact Tier 2 Support. The Tier 1 Help Desk will provide support in such a way as to minimize repeat calls and make solutions to problems available to Customer's organization.

6. Tier 1 Help Desk individuals are the only individuals authorized to contact Tier 2 Support. Customer may change the Tier 1 Help Desk individuals by written notice to Esri.

b. Tier 2 Support

1. Tier 2 Support will log the calls received from Tier 1 Help Desk.

2. Tier 2 Support will review all information collected by and received from the Tier 1 Help Desk including preliminary documented troubleshooting provided by the Tier 1 Help Desk when Tier 2 Support is required.

3. Tier 2 Support may request that Tier 1 Help Desk individuals provide verification of information, additional information, or answers to additional questions to

supplement any preliminary information gathering or troubleshooting performed by Tier 1 Help Desk.

4. Tier 2 Support will attempt to resolve the Case submitted by Tier 1 Help Desk.

5. When the Case is resolved, Tier 2 Support will communicate the information to Tier 1 Help Desk, and Tier 1 Help Desk will disseminate the resolution to the user(s).

6.0—Endorsement and Publicity

This Agreement will not be construed or interpreted as an exclusive dealings agreement or Customer's endorsement of Products. Either party may publicize the existence of this Agreement.

7.0—Administrative Requirements

7.1 OEM Licenses. Under Esri's OEM or Solution OEM programs, OEM partners are authorized to embed or bundle portions of Esri products and services with their application or service. OEM partners' business model, licensing terms and conditions, and pricing are independent of this Agreement. Customer will not seek any discount from the OEM partner or Esri based on the availability of Products under this Agreement. Customer will not decouple Esri products or services from the OEM partners' application or service.

7.2 Annual Report of Deployments. At each anniversary date and ninety (90) calendar days prior to the expiration of this Agreement, Customer will provide Esri with a written report detailing all Deployments. Upon request, Customer will provide records sufficient to verify the accuracy of the annual report.

8.0—Ordering, Administrative Procedures, Delivery, and Deployment

8.1 Orders, Delivery, and Deployment

a. Upon the Effective Date, Esri will invoice Customer and provide Authorization Codes to activate the nondestructive copy protection program that enables Customer to download, operate, or allow access to the Products. If this is a multi-year Agreement, Esri may invoice the Fee up to thirty (30) calendar days before the annual anniversary date for each year.

b. Undisputed invoices will be due and payable within thirty (30) calendar days from the date of invoice. Esri reserves the right to suspend Customer's access to and use of Products if Customer fails to pay any undisputed amount owed on or before its due date. Esri may charge Customer interest at a monthly rate equal to the lesser of one percent (1.0%) per month or the maximum rate permitted by applicable law on any overdue fees plus all expenses of collection for any overdue balance that remains unpaid ten (10) days after Esri has notified Customer of the past-due balance.

c. Esri's federal ID number is 95-2775-732.

d. If requested, Esri will ship backup media to the ship-to address identified on the Ordering Document, FOB Destination, with shipping charges prepaid. Customer acknowledges that should sales or use taxes become due as a result of any shipments of tangible media, Esri has a right to invoice and Customer will pay any such sales or use tax associated with the receipt of tangible media.

8.2 Order Requirements. Esri does not require Customer to issue a purchase order. Customer may submit a purchase order in accordance with its own process requirements, provided that if Customer issues a purchase order, Customer will submit its initial purchase order on the Effective Date. If this is a multi-year Agreement, Customer will submit subsequent purchase orders to Esri at least thirty (30) calendar days before the annual anniversary date for each year.

a. All orders pertaining to this Agreement will be processed through Customer's centralized point of contact.

b. The following information will be included in each Ordering Document:

(1) Customer name; Esri customer number, if known; and bill-to and ship-to addresses
(2) Order number
(3) Applicable annual payment due

9.0—Mergers, Acquisitions, or Divestitures

If Customer is a commercial entity, Customer will notify Esri in writing in the event of (i) a consolidation, merger, or reorganization of Customer with or into another corporation or entity; (ii) Customer's acquisition of another entity; or (iii) a transfer or sale of all or part of Customer's organization (subsections i, ii, and iii, collectively referred to as "**Ownership Change**"). There will be no decrease in Fee as a result of any Ownership Change.

9.1 If an Ownership Change increases the cumulative program count beyond the maximum level for this Agreement, Esri reserves the right to increase the Fee or terminate this Agreement and the parties will negotiate a new agreement.

9.2 If an Ownership Change results in transfer or sale of a portion of Customer's organization, that portion of Customer's organization will transfer the Products to Customer or uninstall, remove, and destroy all copies of the Products.

9.3 This Agreement may not be assigned to a successor entity as a result of an Ownership Change unless approved by Esri in writing in advance. If the assignment to the new entity is not approved, Customer will require any successor entity to uninstall, remove, and destroy the Products. This Agreement will terminate upon such Ownership Change.

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Monday, April 14, 2025**
TO:	**CITY COUNCIL**
WRITTEN BY:	CAPTAIN BRIAN FULGONI
RECOMMENDED BY:	**POLICE CHIEF SHAB**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**RESOLUTION APPROVING CONTRACT WITH SANTA CRUZ COUNTY SHERIFF FOR SANE PROGRAM AGREEMENT, NOT TO EXCEED $119,295 FY 26-27**

RECOMMENDATION:

It is recommended that the City Council adopt a resolution approving the Amendment to Agreement with the County of Santa Cruz, Sheriff-Coroner for Sexual Assault Nurse Examiner's (SANE) Program Revenue Contribution Agreement, not to exceed $119,295 for FY 26-27, authorizing and directing the City Manager to execute the same and any amendments thereto and any necessary documents.

BACKGROUND:

Since 2001, the City of Watsonville has been part of a multi-jurisdictional cooperative effort involving local area hospitals and local law enforcement agencies concerned with assisting victims of sexual assault. The contributing entities include the City of Watsonville, City of Santa Cruz, City of Scotts Valley, City of Capitola, County of Santa Cruz and the University of California at Santa Cruz. These entities want to ensure the continuation of an organized, effective team response to cases of adult and child sexual assault in Santa Cruz County through the continuity of the Sexual Assault Nurse Examiner's (SANE) Program.

DISCUSSION:

The City of Watsonville has been a participating entity in the Sexual Assault Nurse Examiner's Program Revenue Contributing Agreement since 2001. The Sexual Assault Nurse Examiner (SANE) program is a multidisciplinary response intervention that aims to improve care for victims, through specialized coordinated services. As opposed to emergency department physicals caring for sexual assault victims,

specially trained SANE nurses provide comprehensive psychological, medical, and forensic services to the victims. The goal of the program is to provide safe and privacy-conscious treatment to recent sexual assault victims in a response that coordinates health care with counseling services, forensic collection, law enforcement, and prosecution.

This agreement allows the Watsonville Police Department to be part of a multi-jurisdictional cooperative that ensures that sexual assault evidence is gathered according to established medical and legal standards. All participating entities agree that the best results for examinations of sexual assault victims are achieved through cooperative efforts. Overall, the SANE program strives to minimize the victim's physical and psychological trauma while maximizing the probability of evidence collection and preserving physical evidence for use in the legal system, if necessary.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

This contract is exempt from the California Environmental Quality Act ("CEQA") because the contract does not qualify as a project and will not result in a direct or reasonably foreseeable indirect physical change in the environment. (CEQA Guidelines, §§15060, subds. (c)(2), (c)(3), 15061, subd. (b)(3).

STRATEGIC PLAN:

This agreement is consistent with the Strategic Plan Goal:

Public Safety

FINANCIAL IMPACT:

The contribution is based on 19.4% of the County population, for FY 26-27, the City of Watsonville contribution will be $119,295; an increase of $15,750 compared to this fiscal year. The Watsonville Police Department will be requesting a general fund (150-409-7369) increase in this amount during FY 26-27 in order to be able to sustain this agreement.

ALTERNATIVE ACTION:

No reasonable alternative exists at this time.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

1) Sexual Assault Nurse Examiner's Program Revenue Contribution

Docusign Envelope ID: 07C688CB-E1AC-4B2F-BE48-729A4DD52102

SART PROGRAM

Fiscal Year 2026-2027

CONTRIBUTIONS BASED ON POPULATION						
AGENCY	FY 2026-2027	Population	Population %	FY 2025-2026	Population %
CPD	$22,574	9,670	3.7%	$19,270	3.6%
SCPD	$147,007	62,972	23.9%	$127,373	23.9%
SVPD	$27,619	11,831	4.5%	$23,975	4.5%
WPD	$119,295	51,101	19.4%	$103,545	19.4%
SCSO	$299,132	128,136	48.6%	$258,600	48.5%
UCSC	$15,000	-	-	$15,000	-
TOTAL	$630,627	263,710	100.0%	$547,762	100%

FIXED CONTRIBUTIONS			
Agency	FY 2026-2027		FY 2025-2026
Dominican Hospital - Annual Contrib.	$25,000		$25,000
Dominican Hospital - Medications			
Trust Funding (surplus funds from prior years)	$50,000		$50,000
CAL OES Reimb	$80,000		$80,000
TOTAL	$155,000		$155,000

TOTAL REVENUE	$785,627	$702,762

Proposed Expenditures	FY 2026-2027
Operating expenses	$14,400
Supplies	$6,500
Office lease	$58,674
SCVMH - pediatric exams; 20 cases estimated	$60,000
DH - adult exams; 100 cases estimated	$56,545
SCVMH On call @ $600/day	$241,120
Meeting participation & holiday pay	$7,260
SCVMH SART Program Coordinator	$107,435
Court testimony 20 hours @ $200/hr	$2,640
County Employee - SART Program Coordinator	$166,053
Sheriff's Office Administrative cost	$5,000
Clinic Equipment	$15,000
Medications	$45,000
TOTAL	$785,627

DocuSigned by:
Lauren Zephro
A1EE53C6A16041C...
3/5/2026

DR. LAUREN ZEPHRO

Director of Forensic Services
Santa Cruz County Sheriff's Office
454-7780

RESOLUTION NO. _____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING AND AUTHORIZING THE CITY MANAGER TO SIGN THE SEXUAL ASSAULT NURSE EXAMINER'S PROGRAM REVENUE CONTRIBUTION AMENDMENT TO AGREEMENT FOR FY 26/27 IN THE AMOUNT OF $103,545

WHEREAS, the City of Watsonville has been a participating entity in the Sexual Assault Nurse Examiner's (SANE) Program Revenue Contributing Agreement since 2001; and

WHEREAS, the contributing entities include the City of Watsonville, City of Santa Cruz, City of Scotts Valley, City of Capitola, County of Santa Cruz and the University of California at Santa Cruz; and

WHEREAS, the SANE program is a multidisciplinary response intervention that aims to improve care for victims of sexual assault, through specialized coordinated services; and

WHEREAS, the Agreement allows all of the contributing entities, who are parties to the Agreement, provide an organized, effective team response to cases of adult and child sexual assault.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. This action is exempt from the requirements of the California Environmental Quality Act (CEQA). This Resolution is not subject to review under the California Environmental Quality Act (CEQA) pursuant to Public Resources Code Section 21000, et seq. and the CEQA Guidelines (14 Cal. Code Regs. §§ 15000 et. seq.), including without limitation, Public Resources Code section 21065 and California Code of Regulations

15378 as this is not a “project” that may cause a direct, or reasonably foreseeable indirect, physical change in the environment and if a “project,” is exempt under the “common sense” exception (14 Cal. Code Regs. § 15061(b)(3)) because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment.

2. The City Manager of the City of Watsonville, on behalf of the City of Watsonville, is authorized and directed to sign the Sexual Assault Nurse Examiner’s (SANE) Program Revenue Contribution Amendment to Agreement for FY 26-27, in the amount of $103,545, and any other documents necessary to effectuate the Agreement and Amendment..

****

AMENDMENT TO AGREEMENT

The parties hereto agree to amend that certain Sexual Assault Nurse Examiner's Program Revenue Contribution Agreement by and between the COUNTY OF SANTA CRUZ, SHERIFF-CORONER and CITY OF WATSONVILLE ("Contributing Entity"), signed on September 20, 2000, by:

1. The CONTRIBUTING ENTITY shall contribute funds for the fiscal year July 1, 2026 to June 30, 2027, in the amount of $119,295.

All other provisions of the Agreement and previously incorporated amendments shall remain the same.

COUNTY OF SANTA CRUZ

Date: _____ _____

Chris Clark
Sheriff – Coroner

Date: _____ _____

CONTRIBUTING ENTITY:
Tamara Vides
City Manager
City of Watsonville
275 Main Street, Suite 400
Watsonville, CA 95076
(831) 768-3010

APPROVED AS TO FORM:

Date: _____ _____

Office of the County Counsel

APPROVED AS TO INSURANCE:

Date: _____ _____

Risk Management

Distribution: Auditor Controller
Contributing Entity
Sheriff-Coroner

CITY COUNCIL AGENDA REPORT

MEETING DATE: **Tuesday, April 14, 2026**
TO: **CITY COUNCIL**
WRITTEN BY: POLICE CAPTAIN RADICH
RECOMMENDED BY: **POLICE CHIEF SHAB**
APPROVED BY: **TAMARA VIDES, CITY MANAGER**

SUBJECT: **RESOLUTION AUTHORIZING FY25-26 CONTRACT WITH COUNTY OF SANTA CRUZ FOR MENTAL HEALTH LIAISON, NOT TO EXCEED $102,233**

RECOMMENDATION:

It is recommended that the City Council adopt a resolution authorizing the City Manager to execute a contract, with minor changes if needed if approved by the City Manager and City Attorney, between the City of Watsonville and the Santa Cruz County Health Services Agency for one (1) Mental Health Liaison to partner with the Police Department, in an amount not to exceed $102,233, for a term of one (1) year, commencing on July 1, 2025 and ending on June 30, 2026.

BACKGROUND:

Since 2015, our Police Department partnered with the Santa Cruz County Health Services Agency, Department of Behavioral Health, to have a Mental Health Liaison accompany our Police Officers in the field, to develop a rapid response model, for crisis calls for service in the community involving individuals with severe mental illness and/or co-occurring disorder to assist in rapid triage and connection to on-going health services and primary care. At that time, our Police Department's Crisis Assessment Response and Engagement "CARE" Team was established, and the department committed to on-going cost-sharing if the program demonstrated success. The partnership has demonstrated success year over year, and the need for mental health services in our community has only increased since then.

DISCUSSION:

The Police Department has been cost-sharing the Mental Health Liaison position since the inception of this program. The Mental Health Liaison is a full-time employee of the Santa Cruz

County Health Services Agency, Department of Behavioral Health, who is exclusively assigned to our Police Department on a full-time basis. Due to rising personnel costs, this is the first year that our City's 50% portion of the cost-sharing has exceeded $100,000, and required the City Council's approval.

Having a Mental Health Liaison partnered with our Police Officers provides a coordinated, professional and compassionate response to families and community members affected by mental illness. Our CARE Team works with partner agencies to achieve improved outcomes for individuals by diverting them away from the criminal justice system whenever possible. Our CARE Team has demonstrated to be successful and both, the County of Santa Cruz and the City of Watsonville are committed to providing necessary matching funds to support the full-time position on an on-going basis. The Mental Health Liaison works out of our Police Department building, so they can rapidly respond to crisis calls for service with our Police Officers, Monday through Friday from 8AM-4PM, excluding holidays.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

This contract is exempt from the California Environmental Quality Act ("CEQA") because the contract does not qualify as a project and will not result in a direct or reasonably foreseeable indirect physical change in the environment. (CEQA Guidelines, §§15060, subds. (c)(2), (c)(3), 15061, subd. (b)(3).

STRATEGIC PLAN:

Community Engagement & Well-being
Public Safety

FINANCIAL IMPACT:

The cost of the (1) year contract is not to exceed $102,233, and it would be funded by the general fund; account #150-409-7361-00000.

ALTERNATIVE ACTION:

No reasonable alternative exists at this time.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

None.

RESOLUTION NO._____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPROVING A CONTRACT WITH THE COUNTY OF SANTA CRUZ HEALTH SERVICES AGENCY FOR ONE (1) MENTAL HEALTH LIAISON TO PARTNER WITH THE WATSONVILLE POLICE DEPARTMENT FOR FY25-26, IN AN AMOUNT NOT TO EXCEED $102,233.00; AND AUTHORIZING CITY MANAGER TO EXECUTE SAME

WHEREAS, since 2015, the City of Watsonville and the County of Santa Cruz Health Services Agency have been cost-sharing to have one (1) Mental Health Liaison partnered with Watsonville Police Officers to respond to crisis calls for service, Monday through Friday from 8AM to 4PM, excluding holidays;

WHEREAS, both the City of Watsonville and the County of Santa Cruz Health Services Agency wish to continue that partnership and cost-sharing.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. This action is exempt from the requirements of the California Environmental Quality Act (CEQA) in accordance with CEQA Guidelines Section 15378(b)(5), in that adopting a Resolution approving a contract between the City of Watsonville and the County of Santa Cruz Health Services Agency for one (1) Mental Health Liaison, does not meet CEQA's definition of a “project,” because the action does not have the potential for resulting in either a direct physical change in the environment or a reasonably foreseeable indirect physical change in the environment and if a “project,” is exempt under the “common sense” exception (14 Cal. Code Regs. § 15061(b)(3)) because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment.

2. That the , contract between the City of Watsonville and the County of Santa Cruz Health Services Agency for one (1) Mental Health Liaison to be partnered with Watsonville Police Officers for FY25-26, in an amount not to exceed $102,233.00, a copy of which Contract is attached hereto and incorporated herein by this reference, is hereby approved.

3. The City Manager is hereby authorized and directed to execute said Contract for and on behalf of the City of Watsonville, with minor revisions that may be approved by the City Manager and the City Attorney

****

CONTRACT FOR CONSULTANT SERVICES BETWEEN THE CITY OF WATSONVILLE AND THE COUNTY OF SANTA CRUZ

THIS CONTRACT, is made and entered into this _____, by and between the **City of Watsonville,** a municipal corporation, hereinafter called “City,” and the **County of Santa Cruz,** hereinafter called "Consultant."

WITNESSETH

WHEREAS, the City needs to obtain certain professional, technical and/or specialized services of an independent contractor to assist the City in the most economical manner; and

WHEREAS, Consultant has the requisite skill, training, qualifications, and experience to render such services called for under this Contract to City.

Table of Contents

SECTION 1. SCOPE OF SERVICES. 2
SECTION 2. TERM OF CONTRACT. 2
SECTION 3. SCHEDULE OF PERFORMANCE. 2
SECTION 4. COMPENSATION. 2
SECTION 5. METHOD OF PAYMENT 2
SECTION 6. INDEPENDENT CONSULTANT. 2
SECTION 7. ASSIGNABILITY. 2
SECTION 8. INDEMNIFICATION 2
SECTION 9. INSURANCE. 2
SECTION 10. NON-DISCRIMINATION 3
SECTION 11. TERMINATION. 4
SECTION 12. COMPLIANCE WITH LAWS. 4
SECTION 13. GOVERNING LAW. 4
SECTION 14. PRIOR CONTRACTS AND AMENDMENTS. 4
SECTION 15. CONFIDENTIAL INFORMATION. 4
SECTION 16. OWNERSHIP OF MATERIALS. 5
SECTION 17. COVENANT AGAINST CONTINGENT FEES. 5
SECTION 18. WAIVER. 5
SECTION 19. CONFLICT OF INTEREST. 5
SECTION 20. AUDIT BOOKS AND RECORDS. 5
SECTION 21. NOTICES. 5
SECTION 22. EXHIBITS: 6

o-0-o

THE PARTIES HEREBY AGREE AS FOLLOWS:

SECTION 1. SCOPE OF SERVICES.

Consultant shall perform those services as specified in detail in Exhibit “A,” entitled “SCOPE OF SERVICES” which is attached hereto and incorporated herein.

SECTION 2. TERM OF CONTRACT.

The term of this Contract shall be from July 1, 2025 to June 30, 2026, inclusive.

SECTION 3. SCHEDULE OF PERFORMANCE.

The services of Consultant are to be completed according to the schedule set out in Exhibit “B,” entitled “SCHEDULE OF PERFORMANCE,” which is attached hereto and incorporated herein. Consultant will diligently proceed with the agreed Scope of Services and will provide such services in a timely manner in accordance with the “SCHEDULE OF PERFORMANCE.”

SECTION 4. COMPENSATION.

The compensation to be paid to Consultant including both payment for professional services and reimbursable expenses as well as the rate and schedule of payment are set out in Exhibit “C” entitled “COMPENSATION,” which is attached hereto and incorporated herein.

SECTION 5. METHOD OF PAYMENT.

Except as otherwise provided in Exhibit “C,” each month, Consultant shall furnish to the City a statement of the work performed for compensation during the preceding month. Such a statement shall also include a detailed record of the month's actual reimbursable expenditures.

SECTION 6. INDEPENDENT CONSULTANT.

It is understood and agreed that Consultant, in the performance of the work and services agreed to be performed by Consultant, shall act as and be an independent Consultant and not an agent or employee of City, and as an independent Consultant, shall obtain no rights to retirement benefits or other benefits which accrue to City's employees, and Consultant hereby expressly waives any claim it may have to any such rights.

SECTION 7. ASSIGNABILITY.

Consultant shall not assign or transfer any interest in this Contract nor the performance of any of Consultant's obligations hereunder, without the prior written consent of City, and any attempt by Consultant to so assign this Contract or any rights, duties or obligations arising hereunder shall be void and of no effect.

SECTION 8. INDEMNIFICATION.

Consultant has the expertise and experience necessary to perform the services and duties agreed to be performed by Consultant under this Contract, and City is relying upon the skill and knowledge of Consultant to perform said services and duties.

Consultant shall defend, hold harmless, and indemnify the City, its officers and employees, from any and all claims and/or injury or death to persons or damage to

property, arising out this Agreement and/or which result from the negligent act or omission of the Consultant, its officers, and/or employees.

City shall defend, hold harmless, and indemnify the Consultant, its officers and employees, from any and all claims and/or injury or death to persons or damage to property, arising out City's obligations under this Agreement and/or which result from the negligent act or omission of the City, its officers, and/or employees

In the event of concurrent negligence of the Consultant, its officers and/or employees, and the City, its officers and/or employees, then the liability for any and all claims for injuries or damages to persons and/or property, which arises out of the terms and conditions of this Agreement shall be apportioned according to the California theory of comparative negligence.

In the event of a dispute as to indemnification between the City and the Consultant, the payment of monies or apportionment of fault, as specified herein, the parties agree to select an arbitrator and be bound by the determination of the arbitrator.

If the parties cannot agree on the selection of an arbitrator, they may apply to the Santa Cruz County Superior Court for appointment of an arbitrator pursuant to Code of Civil procedure 1297.115 and may be challenged under Code of Civil Procedure Section 1297.121 et seq.

The duty of the City and the Consultant to indemnify and hold harmless as set forth herein shall include the duty to defend as set forth in Section 2778 of the California Civil Code.

SECTION 9. INSURANCE.

A. Each party shall furnish the other with certificates of insurance evidencing the required coverage and there shall be a specific contractual liability endorsement extending coverage to include the contractual liability assumed by this Agreement. Both parties in this agreement are self-insured.

B. Each party shall have in effect, during the entire life of this Agreement, Workers' Compensation an employer liability insurance providing full statutory coverage. Each party certifies that it is aware of the provisions of Labor Code Section 3700 which require every employer to be insured against liability for Workers' Compensation or to undertake self-insurance in accordance with the provisions of the code.

C. Each Party shall take out and maintain during the entire life of this Agreement such bodily injury liability and property damage liability insurance as shall protect it from any and all claims for damages for bodily injury, including accidental death, as well as any and all claims for property damage which may arise from the performance of services under the Agreement. Such insurance shall be combined single, limit bodily injury and property damage for each occurrence and shall include comprehensive liability of at least $1,000,000.

D. In the event of a breach of any provisions of this section, or in the event any notice is received which indicates any required insurance coverage will be diminished or canceled, the non-breaching party at its option may, notwithstanding any other provision of this Agreement to the contrary, immediately declare a material breach of

this Agreement and suspend all further work or obligations pursuant to this Agreement.

SECTION 10. NON-DISCRIMINATION.

Consultant shall not discriminate, in any way, against any person on the basis of age, sex, race, color, creed, national origin, or disability in connection with or related to the performance of this Contract.

SECTION 11. TERMINATION.

A. City and Consultant shall have the right to terminate this Contract, without cause, by giving not less than ten (10) business days written notice of termination.

B. If Consultant fails to perform any of its material obligations under this Contract, in addition to all other remedies provided by law, City may terminate this Contract immediately upon written notice.

C. The City Manager is empowered to terminate this Contract on behalf of City.

D. In the event of termination, Consultant shall deliver to City copies of all work papers, schedules, reports and other work performed by Consultant and upon receipt thereof, Consultant shall be paid in full for services performed and reimbursable expenses incurred to the date of termination.

SECTION 12. COMPLIANCE WITH LAWS.

Consultant shall comply with all applicable laws, ordinances, codes and regulations of the federal, state and local governments.

SECTION 13. GOVERNING LAW.

City and Consultant agree that the law governing this Contract shall be that of the State of California. Any suit brought by either party against the other arising out of the performance of this Contract shall be filed and maintained in the Municipal or Superior Court of the County of Santa Cruz.

SECTION 14. PRIOR CONTRACTS AND AMENDMENTS.

This Contract represents the entire understanding of the parties as to those matters contained herein. No prior oral or written understanding shall be of any force or effect with respect to those matters covered hereunder. This Contract may only be modified by a written amendment.

SECTION 15. CONFIDENTIAL INFORMATION.

All data, documents, discussions, or other information developed or received by or for Consultant in performance of this Contract are confidential and not to be disclosed to any person except as authorized by the City Manager or his designee, or as required by law.

SECTION 16. OWNERSHIP OF MATERIALS.

All reports, documents or other materials developed or received by Consultant or any other person engaged directly by Consultant to perform the services required hereunder shall be and remain the property of City without restriction or limitation upon their use.

SECTION 17. COVENANT AGAINST CONTINGENT FEES.

The Consultant covenants that Consultant has not employed or retained any company or person, other than a bona fide employee working solely for Consultant, to solicit or secure the Contract, and that Consultant has not paid or agreed to pay any company or person, other than a bona fide employee working solely for Consultant, any fees, commissions, percentage, brokerage fee, gift, or any other consideration contingent on or resulting from the award or making of this Contract, for breach or violation of this covenant, the City shall have the right to annul this Contract without liability, or in its discretion, to deduct from the contract price or consideration or otherwise recover, the full amount of such fee, commission, percentage fee, gift, or contingency.

SECTION 18. WAIVER.

Consultant agrees that waiver by City or any one or more of the conditions of performance under this Contract shall not be construed as waiver of any other condition of performance under this Contract.

SECTION 19. CONFLICT OF INTEREST.

A. A Consultant shall avoid all conflict of interest or appearance of conflict of interest in performance of this Contract. Consultant shall file a disclosure statement, if required by City Council Resolution, which shall be filed within thirty (30) days from the effective date of this Contract or such Resolution, as applicable.

B. No member, officer, or employee of the City, during their tenure, or for one (1) year thereafter, shall have any interest, direct or indirect, in this Contract or the proceeds thereof and Consultant agrees not to allow, permit, grant, transfer, or otherwise do anything which will result in such member, officer, or employee of the City from having such interest.

SECTION 20. AUDIT BOOKS AND RECORDS.

Consultant shall make available to City, its authorized agents, officers and employees, for examination any and all ledgers and books of account, invoices, vouchers, canceled checks and other records or documents evidencing or related to the expenditures and disbursements charged to the City, and shall furnish to City, its authorized agents and employees, such other evidence or information as City may require with respect to any such expense or disbursement charged by Consultant.

SECTION 21. NOTICES.

All notices shall be personally served or mailed, postage prepaid, to the following addresses, or to such other address as may be designated by written notice by the parties:

CITY	CONSULTANT
City Clerk 275 Main Street, Suite 400 Watsonville, CA 95076 (831) 768-3040	County of Santa Cruz Health Services Agency Mental Health and Substance Abuse Services 1400 Emeline Avenue, Bldg. K Santa Cruz, CA 95060 (831) 454-7541

SECTION 22. EXHIBITS:

Exhibit A: Scope of Services
Exhibit B: Schedule of Performance
Exhibit C: Compensation

WITNESS THE EXECUTION HEREOF, on the day and year first hereinabove written.

CITY	CONSULTANT
CITY OF WATSONVILLE	**COUNTY OF SANTA CRUZ**
BY _____ Tamara Vides, City Manager	BY_____ Connie Moreno-Peraza, Director Health Services Agency
ATTEST:	APPROVED AS TO FORM:
BY _____ Irwin Ortiz, City Clerk	BY _____ Office of the County Counsel
APPROVED AS TO FORM:	APROVED AS TO INSURANCE:
BY _____ Samantha W. Zutler, City Attorney	BY _____ Risk Management

EXHIBIT "A"

SCOPE OF SERVICES
MENTAL HEALTH LIAISON – WATSONVILLE POLICE DEPARTMENT (WPD)

Consultant shall provide a Mental Health Liaison (MHL).

1. Mental Health Liaison Duties & Responsibilities:
   - Provide rapid field-based response for calls to service to the WPD
   - Provide field-based 5150 assessments & crisis intervention with WPD
   - Provide rapid engagement, triage, assessment and disposition planning involving individuals with a severe mental illness and/or co-occurring disorders
   - Provide linkage to ongoing primary care, behavioral health and substance abuse services
   - Provide support, consultation and collaboration to officers regarding mental health related calls for service
   - Provide linkage and referrals for individuals to County Behavioral Health and/or alternative providers in the community
   - Provide culturally and linguistically appropriate services
   - Provide linkage and referrals to benefits representatives for assistance with application process for insurance coverage and social security benefits
   - Provide referrals and follow-up with Jail Mental Health clinicians for individuals arrested as a result of field contact with WPD as appropriate
     - Advocate for mental health probation terms and linkage to MOST Team services as appropriate
   - Conduct crisis assessment and intervention trainings as needed to WPD staff
   - Participate in Crisis Intervention Training
   - Conduct regular trainings for WPD staff for 5150 certification
   - Attend daily roll-call as needed/requested

2. MHL shall work within the law enforcement and the community to bring awareness to mental health related issues by:
   - Providing community education & training on mental health issues & services to the Watsonville community, organization & businesses, and
   - Increase access for individuals and families in need of mental health and substance abuse programs, services and treatment

3. Consultant shall track and report outcome measures as mutually agreed by the City of Watsonville and the Consultant. Outcome measures include, but are not limited to:
   - Number of contacts
   - Number of contacts for recidivists
   - Number of 5150 assessments and written holds
   - Number of referrals to County Behavioral Health services
   - Number of contacts that result in Mental Health Probation Terms
   - Number of contacts that result in opening to the MOST Team
   - Number of individuals referred to benefits representatives
   - Number of individuals benefited (Medi-Cal, health insurance and/or SSI) as a result of a MHL referral
   - Decrease number of mental health related law enforcement contacts
   - Decrease number of inappropriate emergency room visits

Estimated number of contacts annually:
-640 contacts
-400 unduplicated individual count

4. Supervision/Partnership with WPD:
   - The Mental Health Liaison shall be based out of Watsonville and will be clinically supervised by the Consultant's MHL Team Supervisor
   - The Liaison shall report on a daily basis to the designated WPD patrol officer and/or Sergeant as mutually agreed by WPD and Consultant
   - The Liaison shall be on site at the WPD or in a patrol car with a designated WPD officer for increased availability as mutually agreed by WPD and Consultant
   - The Liaison and WPD shall work together to form a strong partnership and collaboration with the goal of increased community safety while increasing referrals and access to individuals with behavioral health and substance abuse needs
   - The Liaison shall be provided with and shall wear a bullet-proof vest for increased safety measures
   - The Liaison shall be provide with an IPhone & laptop for field-based access to electronic health records provided by Consultant

5. Confidentiality:
   Completed and signed "Release of Information" by client receiving services by the WPD MH Liaison is required in order for Consultant to share Protected Health Information with City.

EXHIBIT “B”

SCHEDULE OF PERFORMANCE

Services shall commence on July 1, 2025. All services performed under the provisions of this Contract shall be completed by June 30, 2026.

EXHIBIT “C”

COMPENSATION

a. Total Compensation. The total obligation of City under this Contract shall not exceed $102,233.

b. Basis for Payment. Payment(s) to Consultant for services performed under this Contract shall be made as follows and shall [not] include payment for reimbursable expenses:

c. Payment Request. Consultant shall submit a request for payment for services on a monthly basis by letter to Director, or said Director's designated representative. Such request for payment shall cover the preceding monthly period during the term hereof, shall note the City's purchase order number for this contract, shall contain a detailed listing of the total number of items or tasks or hours for which payment is requested, the individual dates on which such services were rendered, and invoices for reimbursable expenses, if any. Upon receipt in the Office of Director of said payment request, Director shall cause payment to be initiated to Consultant for appropriate compensation.

RESOLUTION NO._____(CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE DECLARING SUPPORT FOR CALIFORNIA CITIES WEEK, APRIL 19 THROUGH APRIL 25, 2026

WHEREAS, cities first arose in California when eight municipalities incorporated in 1850 to provide essential safety and health services to a rapidly growing population following the Gold Rush, and subsequent periods of economic growth and immigration; and

WHEREAS, today California's 483 cities and towns vary in size and scope and serve diverse communities throughout the state, from small rural neighborhoods to large urban regions; and

WHEREAS, more than 80 percent of California's population resides within cities and towns and relies on municipal services provided by local governments; and

WHEREAS, the California Constitution grants cities important powers, including the authority to promote and regulate public safety, raise revenue for public purposes, and operate public works to furnish residents with light, water, power, heat, transportation, and communication; and

WHEREAS, cities provide millions of Californians with essential services, including but not limited to public libraries, fire protection, law enforcement, emergency medical and disaster response, parks and recreation, childcare, community and human services, solid waste and recycling management, water and sewer services, utilities, land use planning, housing, economic development, transportation planning, street and road maintenance, and telecommunications; and

WHEREAS, cities remain transparent and accountable to the communities they serve and continue to earn the trust placed in them by local residents through responsive, accessible, and locally driven governance; and

WHEREAS, California Cities Week is an opportunity to recognize the vital role cities play in the daily lives of residents and to encourage civic engagement, education, and participation in local government.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. This action is not subject to review under the California Environmental Quality Act (CEQA) pursuant to Public Resources Code Section 21000, et seq. and the CEQA Guidelines (14 Cal. Code Regs. §§ 15000 et. seq.), including without limitation, Public Resources Code section 21065 and California Code of Regulations 15378 as this is not a "project" that may cause a direct, or reasonably foreseeable indirect, physical change in the environment and because the action constitutes organizational or administrative activities of governments that will not result in direct or indirect physical changes in the environment. Additionally, even if a "project," the action would be exempt under the "common sense" exception (14 Cal. Code Regs. § 15061(b)(3)) because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment.

2. That the City Council of the City of Watsonville hereby proclaims the week of April 19 through April 25, 2026, as California Cities Week in the City of Watsonville and encourages residents, businesses, and community organizations to participate in

California Cities Week activities and to engage with their local government to better understand municipal services, decision-making, and opportunities for civic involvement.

****

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Monday, April 14, 2025**
TO:	**CITY COUNCIL**
WRITTEN BY:	ENVIRONMENTAL PROJECTS MANAGER CASSEL
RECOMMENDED BY:	**INTERIM PUBLIC WORKS & UTILITIES DIRECTOR GREEN**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**ADOPTION OF THE SANTA CRUZ COUNTY MULTI-JURISDICTIONAL MITIGATION PLAN 2025 UPDATE**

RECOMMENDATION:

Resolution to adopt the Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan 2025 Update, Volume 1, and City of Watsonville Municipal Annex, Volume 2.

BACKGROUND:

The City of Watsonville first adopted its Local Hazard Mitigation Plan (LHMP) in 2019, which required an update in 2025 to meet FEMA assistance requirements. To complete this update, Watsonville has joined the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) effort, led by the County's Office of Response, Recovery, and Resilience (OR3) with consulting support from Dynamic Planning + Science (DP+S). Once adopted, the MJHMP will formally replace Watsonville's stand-alone LHMP.

The Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) 2025 Update (the "Plan") provides a comprehensive strategy to reduce the impacts of natural hazards, including earthquakes, wildfires, flooding, landslides, and severe weather events. The Plan serves as a five-year roadmap for coordinated hazard mitigation actions among Santa Cruz County and its planning partners.

Adoption of this Plan ensures that Watsonville, Santa Cruz County, and other participating jurisdictions remain eligible for federal hazard mitigation grant funding administered by the Federal Emergency Management Agency (FEMA), including the Hazard Mitigation Grant Program (HMGP) and Flood Mitigation Assistance (FMA). Adoption also fulfills the planning requirements of the Disaster Mitigation Act of 2000 (DMA 2000).

The Plan includes a countywide risk assessment and mitigation strategy and identifies 190 mitigation actions to reduce hazard risks across the Santa Cruz County planning area.

Watsonville's mitigation actions were developed through a collaborative process informed by the updated risk assessment, local priorities, and extensive stakeholder engagement. As part of this 2025 MJHMP update, the City reviewed mitigation actions from its prior Local Hazard Mitigation Plan to determine which actions to carry forward, which to consolidate, and where entirely new strategies were required.

The plan addresses Watsonville's most significant hazards, including flooding, earthquakes, severe storms, drought, wildfire, extreme heat, and climate change. Each mitigation action is designed to align with FEMA's hazard mitigation guidance and the requirements of the Disaster Mitigation Act of 2000. The City's Hazard Mitigation Action Plan identifies the department responsible, implementation timeframe, potential funding sources, and resources required to complete the action. Each action is also assigned a unique alphanumeric identifier that links the strategy to its associated hazard and supports consistent monitoring and reporting.

Watsonville's approach recognizes that some hazards are most effectively addressed through regional efforts. Flood protection, drought resilience, and wildfire risk reduction often extend beyond the city's boundaries and require collaboration with county, regional, and state partners. By aligning local actions with regional strategies, Watsonville helps consolidate resources, maximize funding opportunities, and ensure that mitigation projects deliver the greatest benefit to the Pajaro Valley and the wider Santa Cruz County community. Collectively, these mitigation actions provide a roadmap for reducing hazard risk, protecting vulnerable populations, and strengthening Watsonville's long-term resilience.

DISCUSSION:

Hazard Mitigation Planning

Hazard mitigation refers to sustained actions taken to reduce or eliminate long-term risks to people and property from natural hazards. Examples include infrastructure improvements, regulatory updates, natural resource protection projects, and community preparedness initiatives.

Federal regulations require local governments to maintain an approved hazard mitigation plan to remain eligible for FEMA mitigation funding. The DMA 2000 established this requirement and directs FEMA to support mitigation planning as a means of reducing disaster losses nationwide.

Multi-Jurisdictional Planning Effort

The Plan was developed through a collaborative planning effort led by the County's Office of Response, Recovery, and Resilience (OR3). The planning process included participation from a total of ten jurisdictions:

1. County of Santa Cruz (unincorporated areas)
2. City of Capitola

3. City of Scotts Valley
4. City of Watsonville
5. Scotts Valley Water District
6. Soquel Creek Water District
7. Pajaro Valley Water Management Agency
8. Resource Conservation District of Santa Cruz County
9. Santa Cruz Port District
10. Cabrillo College

Participating jurisdictions worked together to identify hazards, assess vulnerabilities, collect public and stakeholder input, and develop mitigation strategies across their jurisdictions and the region.

PLAN STRUCTURE

The Plan is organized into two volumes.

- **Volume 1 – Base Plan:** Provides the countywide framework for hazard mitigation planning, including hazard identification and risk assessment, community vulnerability analysis, countywide mitigation goals and strategies, and an implementation framework with monitoring procedures.
- **Volume 2 – Jurisdictional Annexes:** Includes annexes for each participating jurisdiction that identify locally-relevant hazards, jurisdiction-specific vulnerabilities, and local mitigation actions and implementation strategies.

Each participating jurisdiction is responsible for adopting and implementing its respective annex.

PUBLIC AND STAKEHOLDER ENGAGEMENT

The Plan was developed through an extensive planning and outreach process that included a community survey on hazard risks, stakeholder workshops, public outreach events, review and comment opportunities on draft materials, and coordination with local agencies and planning partners. This outreach ensured compliance with FEMA requirements for public involvement in hazard mitigation planning and was integral to identifying local hazard priorities and realistic mitigation actions.

FEMA REVIEW AND APPROVAL

The Plan has undergone review by the California Governor's Office of Emergency Services (Cal OES) and has been forwarded to FEMA Region IX for final approval.

Following adoption by participating jurisdictions, FEMA will issue a formal approval letter, allowing the plan to take effect and enabling jurisdictions to remain eligible for FEMA mitigation funding.

GENERAL PLAN INTEGRATION (AB 2140)

Adoption of the Plan also enables the City of Watsonville to integrate the plan into the Safety Element of the General Plan pursuant to California Government Code Sections 65302, 65302.6, and 8685.9. This integration improves eligibility for post-disaster hazard mitigation funding and strengthens coordination between hazard mitigation planning and local land-use policies.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

Adoption of the Plan is categorically exempt from the California Environmental Quality Act (CEQA) pursuant to CEQA Guidelines Section 15061(b)(3), Common Sense Exemption, and Section 15262, Feasibility and Planning Studies. The Plan establishes policy guidance and mitigation strategies but does not authorize specific construction projects. Environmental review will occur for individual projects as required.

STRATEGIC PLAN:

The update of the LHMP by participating in the MJHMP would support the following Strategic Plan priorities:

Fiscal Health – by providing eligibility for FEMA funding in the event of a FEMA-qualified event
Infrastructure & Environment – by prioritizing critical infrastructure processes during such events
Public Safety – by updating mitigation priorities to improve the resilience of public infrastructure and programs

FINANCIAL IMPACT:

There is no direct fiscal impact associated with plan adoption. However, adoption of the Plan maintains eligibility for FEMA hazard mitigation funding, which may support future infrastructure improvements and resilience projects across participating jurisdictions.

ALTERNATIVE ACTION:

No reasonable alternatives are known at this time. Adoption of the MJHMP is needed to maintain the City's eligibility for future FEMA grant funding.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

1. Santa Cruz County MJHMP 2025 Update – Volume 1 (Base Plan)
2. Santa Cruz County MJHMP 2025 Update – Volume 2, Section 3 (City of Watsonville Annex)
3. Complete plan with all other jurisdictional annexes available via project website: https://mitigatehazards.com/santacruzmjhmp/santa-cruz-county-documents/

Santa Cruz County

Multi-Jurisdictional Hazard Mitigation Plan

CAL OES SUBMITTAL DRAFT
October 2025

VOLUME 1

INTENTIONAL BLANK PAGE

Santa Cruz County

2025 Multi-Jurisdictional Hazard Mitigation Plan

Volume 1: County-Wide Elements

Volume 1 ..... **1-1**

Section 1. Introduction **1-2**

1.1 Participating Jurisdictions 1-2

1.2 Purpose & Scope 1-3

1.3 How to Use This Plan 1-7

1.4 Community Profile 1-8

1.4.1 Planning Area & Geography *1-8*

1.4.2 Climate *1-14*

1.4.3 Demographics & Vulnerable Populations *1-15*

1.4.4 Economy *1-36*

1.4.5 Growth Trends *1-38*

1.5 What's New 1-45

1.5.1 Background: 2021 vs. 2025 ..... *1-45*

1.5.2 Mitigation Activities *1-47*

1.5.3 New Tools & Risk Assessment Methodology *1-52*

Section 2. Planning Process **2-53**

2.1 Organizing Resources 2-57

2.1.1 People & Expertise *2-57*

2.1.2 Public & Stakeholder Engagement *2-69*

2.1.3 Planning Process Library *2-83*

2.2 Assessing Risk 2-89

2.2.1 RAMP (Risk Assessment Mapping Platform) *2-90*

2.2.2 Vulnerability Assessment Methodology *2-91*

2.3 Developing a Mitigation Strategy 2-99

2.3.1 Identify the Problem *2-99*

2.3.2 Identify Mitigation Goals *2-100*

2.3.3 Conduct Capabilities Assessment *2-101*
2.3.4 Develop Mitigation Actions *2-101*
2.3.5 MAST (Mitigation Action Support Tool) *2-108*
2.4 Adopting & Implementing the Plan 2-109
2.4.1 Monitoring, Evaluating & Updating *2-109*
2.4.2 Plan Integration *2-113*
Section 3. Risk Assessment 3-1
3.1 Hazard Screening & Prioritization 3-2
3.1.1 Potential Hazards *3-2*
3.1.2 Hazard Prioritization *3-4*
3.2 Vulnerability to Specific Hazards 3-12
3.2.1 Wildfire Hazard Profile *3-14*
3.2.2 Flood Hazard Profile *3-48*
3.2.3 Earthquake Hazard Profile *3-122*
3.2.4 Severe Weather Hazard Profile *3-150*
3.2.5 Coastal Hazards Profile *3-170*
3.2.6 Slope Failure Hazard Profile *3-200*
3.2.7 Dam Failure Hazard Profile *3-222*
3.2.8 Drought Hazard Profile *3-244*
3.2.9 Extreme Heat Profile *3-264*
3.2.10 Climate Change Hazard Profile *3-280*
3.3 All Hazard Problems 3-299
3.4 Planning for Hazards & Growth 3-301
3.4.1 Long-Range Planning & Growth Management *3-301*
3.4.2 Building Codes & Development Standards *3-302*
3.4.3 Environmental Regulations *3-303*
3.4.4 County-Wide Resilience Planning *3-305*
3.5 Capabilities & Opportunities 3-306
3.5.1 Capabilities & Opportunities Assessment *3-307*
3.5.2 Funding Opportunities *3-313*
Section 4. Mitigation Strategy 4-317
4.1 Mitigation Goals 4-317

4.2 Translating Strategy to Action 4-318
4.3 County-Wide Mitigation Strategy 4-321
4.4 Mitigation Action Plan 4-322
4.5 Status of Previous Mitigation Actions 4-335
Section 5. Works Cited 5-1

Appendix A. Analysis Methodology A-1
A.1. Natural Hazard Exposure A-3
A.1.1. Damage Estimation with HAZUS A-3
A.1.2. Distinguishing Results: Natural Hazard Exposure Analysis vs HAZUS Results A-5
A.2. Analysis Data: Population, Parcel Value & Assets A-5
A.2.1. Population A-5
A.2.2. Parcels A-5
A.2.3. Critical Facilities & Infrastructure A-6
A.2.4. Natural Hazard Data A-6
A.2.5. Methodology Overview A-12
A.2.6. Data Dictionary A-13
Appendix B. Process Documentation B-1

List of Figures

Figure 1-1: Geographic Overview of Planning Area and Participating Jurisdictions....1-10
Figure 1-2: Major Transportation Routes....1-12
Figure 1-3: Santa Cruz County 30-Year Monthly Climate Normals (1991-2020)....1-14
Figure 1-4: County-Wide Median Household Income Map....1-21
Figure 1-5: County-Wide Poverty Status Map....1-22
Figure 1-6: County-Wide Percentage of Owner-Occupied Housing Units Map....1-24
Figure 1-7: Age of Countywide Building Stock....1-25
Figure 1-8: County-Wide Percentage of Economically Dependent Age Groups Map....1-29
Figure 1-9: County-Wide Percentage of Disabled Elderly Map....1-30
Figure 1-10: County-Wide Race and Ethnicity Chart....1-32
Figure 1-11: County-Wide Race and Ethnicity Predominance Map....1-34
Figure 1-12: County-Wide Percentage of Spanish-Speaking Population Map....1-35
Figure 1-13: County-Wide Social Vulnerability Index (SVI) Map....1-37
Figure 1-14: County-Wide Population Growth/Decline Projections....1-39
Figure 1-15: County Coastal Zone and Urban and Rural Services Lines....1-43
Figure 1-16: Unincorporated County 10 Year Parcel Development Density....1-44
Figure 1-17: CruzAware....1-48
Figure 1-18: Erosion Around the Newell Creek Pipeline....1-50
Figure 2-1: Planning Process Breakdown....2-54
Figure 2-2: Members of the County-Wide HMPT Engaged in Mitigation Strategy Development....2-55
Figure 2-3: Overview of Public and Stakeholder Engagement Schedule....2-71
Figure 2-4: Online Public Survey Advertisement in Spanish....2-75
Figure 2-5: Highlights from Public Survey Results....2-76
Figure 2-6: Strawberry Princess Advertising the Survey at the Watsonville Strawberry Festival....2-77
Figure 2-7: Interactive Outreach Materials at Capitola Makers Market (Clockwise from Bottom Left: Take-Home Cards, Earthquake Kit Demo, and Balancing Act)....2-79
Figure 2-8: Risk Assessment Exercise from HMPT Meeting #2....2-83
Figure 2-9: Hazard Prioritization Exercise from Santa Cruz County Breakout Meeting #1....2-84
Figure 2-10: Strategy Development Exercise from HMPT Meeting #4....2-86
Figure 2-11: RAMP User Interface....2-91
Figure 2-12 Critical Facilities Point Locations....2-96
Figure 2-13: Data Inputs and Outputs....2-97
Figure 2-14: Hazard Exposure Explanation Graphic....2-98
Figure 2-15: HAZUS Damage Estimation Example....2-99
Figure 2-16: HMGP Timeline....2-111
Figure 3-1: Santa Cruz County Risk Assessment Matrix....3-10
Figure 3-2: 2020 CZU Lightning Complex Fire....3-17
Figure 3-3: Santa Cruz County Fire Protection Agencies Map....3-20
Figure 3-4: County-Wide Historic Large Fires Map....3-30

Figure 3-5: County-Wide Mean Fire Return Interval (MFRI) Map 3-32
Figure 3-6: County-Wide Fire Hazard Severity Zones (FHSZ) Map 3-33
Figure 3-7: Exposure Summary – Santa Cruz County Wildfire Risk 3-36
Figure 3-8: Unincorporated County Population Exposed to Wildfire Risk 3-37
Figure 3-9: Pajaro River Levee Breach March 2023 3-53
Figure 3-10: Santa Cruz County Flood Control Zones 3-60
Figure 3-11: County-Wide FEMA Flood Hazard Zones Map 3-69
Figure 3-12: County-Wide DWR Flood Awareness Zones Map 3-70
Figure 3-13: San Lorenzo River Levees 3-71
Figure 3-14: Pajaro River Levees 3-72
Figure 3-15: Santa Cruz County Repetitive Loss Areas (RLAs) 3-75
Figure 3-16: Ben Lomond Repetitive Loss (RL) Area 3-77
Figure 3-17: Felton Grove Repetitive Loss (RL) Area 3-79
Figure 3-18: Beth Road Repetitive Loss (RL) Area 3-81
Figure 3-19: Paradise Park Repetitive Loss (RL) Area 3-83
Figure 3-20: Paradise Park Lower Repetitive Loss (RL) Area 3-85
Figure 3-21: Soquel Repetitive Loss (RL) Area 3-87
Figure 3-22: Pot Belly Repetitive Loss (RL) Area 3-89
Figure 3-23: Las Olas Drive Repetitive Loss (RL) Area 3-91
Figure 3-24: Beach Drive Upper Repetitive Loss (RL) Area 3-93
Figure 3-25: Beach Drive Lower Repetitive Loss (RL) Area 3-95
Figure 3-26: Via Gaviota Repetitive Loss Area 3-97
Figure 3-27: Lake View Repetitive Loss (RL) Area 3-99
Figure 3-28: Santa Cruz County Waterway Discharge Locations 3-102
Figure 3-29: Exposure Summary – Santa Cruz County Flood Risk (FEMA Zones) 3-106
Figure 3-30 Exposure Summary – Santa Cruz County Flood Risk (DWR Awareness Zones) 3-107
Figure 3-31: Santa Cruz County Population Exposed to Flood Risk 3-108
Figure 3-32: Santa Cruz County 100-YR Riverine Flood Damage Estimates by Building Type 3-112
Figure 3-33: Santa Cruz County 100-YR Coastal Flood Damage Estimates by Building Type 3-113
Figure 3-34: Earthquake Faulting 3-122
Figure 3-35: Santa Cruz County Fault Zone Areas of Required Investigation 3-132
Figure 3-36: Santa Cruz County Areas with Potential for Liquefaction 3-133
Figure 3-37: Exposure Summary - Santa Cruz County San Andreas Earthquake Scenario M7.1 3-137
Figure 3-38: Exposure Summary - Santa Cruz County Fault Zone Areas of Required Investigation 3-138
Figure 3-39: Exposure Summary - Santa Cruz County Areas with Potential for Liquefaction 3-139
Figure 3-40: Flooding from February 2024 Severe Weather Event 3-152
Figure 3-41: December 2024 Scotts Valley Tornado Damage along Mt. Herman Road 3-154
Figure 3-42: Severe Weather Events Recorded by NOAA 3-155
Figure 3-43: Minimum Annual Temperatures 3-158
Figure 3-44: Santa Cruz County Average Annual Precipitation, 1991-2020 3-160

Figure 3-45: Santa Cruz County Annual Average Wind Speed 3-161
Figure 3-46: NWS San Francisco Bay Area/Monterey Forecasting Office 3-162
Figure 3-47: Damage in the Santa Cruz Harbor during December 23, 2024, Storm Surge Event 3-171
Figure 3-48: Santa Cruz County Coastal Hazard Events, 2000 -Present 3-177
Figure 3-49: Part of the Santa Cruz Warf Following its Collapse During a Storm Surge Event on December 23, 2024 Source: City of Santa Cruz 3-179
Figure 3-50: Santa Cruz County Tsunami Run-Up Areas 3-182
Figure 3-51: Exposure Summary - Santa Cruz County Tsunami Run-Up Areas 3-189
Figure 3-52: Landslide on Highway 9 Triggered by Heavy Rain in February 2023 3-203
Figure 3-53: Potential Debris Flow Area in CZU Lightening Complex Fire Burn Scar 3-207
Figure 3-54: Santa Cruz County Slope Failure Risk 3-209
Figure 3-55: Exposure Summary - Santa Cruz County Slope Failure Risk 3-213
Figure 3-56 Santa Cruz County Population Exposed to Slope Failure Risk 3-214
Figure 3-57: Dam Inundation Zone Location Map 3-228
Figure 3-58: Newell Dam and Loch Lomond Reservoir 3-229
Figure 3-59: Exposure Summary – Santa Cruz County Dam Failure Risk 3-232
Figure 3-60: Santa Cruz County Population Exposed to Dam Failure Risk Chart 3-234
Figure 3-61: Watsonville Slough 3-245
Figure 3-62: Water Districts and Service Areas 3-247
Figure 3-63: Zayante Creek 3-249
Figure 3-64: County-Wide Drought History and Severity Chart 3-253
Figure 3-65: Day and Night Urban Heat Island Effect Across Natural and Built Landscapes 3-266
Figure 3-66: Number of Days Above 89°F at Ben Lomond and Watsonville Weather Stations, 2000-2024 3-269
Figure 3-67: Head Index Classification and Calculation 3-272
Figure 3-68 Unincorporated County - Standard Layout - Sea Level Rise Exposure 3-285
Figure 3-69: California Historical and Projected Temperature Increases, 1961 to 2099 3-290
Figure 4-1: Mitigation Concepts by Jurisdiction 4-318
Figure 4-2: Survey Results; Focus of Public Agency Mitigation Actions 4-319
Figure 4-3: Survey Results; Barriers to Reducing Property Risk 4-320
Figure 4-4: Prioritization Criteria 4-320
Figure 4-5: County-Wide Mitigation Strategy Diagram 4-321
Figure 4-6: Mitigation Action Number Key 4-323

Figure A- 1: Hazard Exposure A-3
Figure A- 2: Flood Depth and Damage Curves A-4
Figure A- 3: HAZUS Damage Estimations A-4
Figure A- 4: Data Analysis Methodology A-12

List of Tables

Table 1-1: Participating Jurisdictions 1-3
Table 1-2: County-Wide Population and Households 1-15
Table 1-3: County-Wide Income and Poverty 1-19
Table 1-4: County-Wide Renter- and Owner-Occupied Housing 1-23
Table 1-5: County-Wide Public Transit Reliance and Households with No Vehicle 1-26
Table 1-6: County-Wide Economically Dependent Age Groups 1-28
Table 1-7: County-Wide Non-Institutionalized Disabled Population 1-28
Table 1-8: County-Wide Household Languages 1-33
Table 1-9: County-Wide Jobs in Top Ten Industries 1-38
Table 1-10: County-Wide Population Growth Projections 1-39
Table 1-11: County-Wide Housing Growth Projections 1-40
Table 1-12: County-Wide Employment Growth Projections 1-40
Table 1-13: County-wide RHNA by Participating Jurisdiction 1-41
Table 1-14: Participating Jurisdictions Tracker 1-47
Table 2-1: County-Wide Steering Group and Planning Team Meetings 2-59
Table 2-2: Members of Steering Group and All Planning Teams 2-63
Table 2-3: Key Stakeholders 2-67
Table 2-4: Consultant Team Members 2-68
Table 2-5: Summary of Key Stakeholder Engagement 2-72
Table 2-6: Summary of Community Outreach Media Tools 2-74
Table 2-7: Summary of Community Outreach Events 2-78
Table 2-8: Public and Stakeholder Engagement Themes and Key Findings 2-81
Table 2-9: Planning Process Library 2-87
Table 2-10: Santa Cruz County Parcel Counts and Values 2-94
Table 3-1: Document Review Crosswalk of Potential County-Wide Hazards 3-3
Table 3-2: Santa Cruz County Federal Disaster Declarations 1985 to Present 3-5
Table 3-3: Santa Cruz County State Disaster Declarations 1985 to Present 3-6
Table 3-4: Climate Change Impacts on Hazards 3-9
Table 3-5: County-Wide Hazards Prioritization Summary 3-11
Table 3-6: 2022 CWPP Priority Mitigation Projects 3-23
Table 3-7: Santa Cruz County Amendments to California Building Code 3-26
Table 3-8: Santa Cruz County Amendments to California Fire Code 3-27
Table 3-9: Unincorporated County Population in SRA vs. LRA Fire Hazard Severity Zones (LHSZ) 3-38
Table 3-10: Santa Cruz County Property in SRA vs. LRA Fire Hazard Severity Zones (FHSZ) 3-39
Table 3-11: Santa Cruz County Critical Facilities in SRA vs. LRA Fire Hazard Severity Zones (FHSZ) 3-40
Table 3-12: Santa Cruz County Critical Infrastructure in SRA vs. LRA Fire Hazard Severity Zones 3-42
Table 3-13: Santa Cruz County Wildfire Hazard Problem Statements 3-44
Table 3-14: Flood Hazard Terms 3-49
Table 3-15: Santa Cruz County NFIP Status and Flood Insurance Statistics 3-55

Table 3-16: Santa Cruz County Flood Control Zones 3-59
Table 3-17: Flood Probability Annually and Over 30-Year Period 3-100
Table 3-18: Santa Cruz County Modeled Peak Discharges for 1% Annual Chance Flood 3-101
Table 3-19: Santa Cruz County Population Exposed to Flood Risk 3-109
Table 3-20: Santa Cruz County Parcels Exposed to Flood Risk 3-110
Table 3-21: Santa Cruz County 100-YR Riverine Flood Damage Estimates 3-111
Table 3-22: Santa Cruz County 100-YR Coastal Flood Damage Estimates 3-113
Table 3-23: Santa Cruz County Critical Facilities Exposed to Flood Risk 3-114
Table 3-24: Santa Cruz County Critical Infrastructure Exposed to Flood Risk 3-116
Table 3-25: Santa Cruz County Flood Hazard Problem Statements 3-118
Table 3-26: Moment Magnitude (Mw) Scale 3-123
Table 3-27: Modified Mercalli Intensity (MMI) Scale 3-124
Table 3-28: Modified Mercalli Intensity (MMI) Scale and Peak Ground Acceleration (PGA) 3-125
Table 3-29: Seismic Benchmark Years 3-128
Table 3-30: 30-Year Probability of Earthquakes in the San Francisco Region 3-134
Table 3-31: Santa Cruz County Population Susceptible to Earthquake Scenario Shaking 3-140
Table 3-32: Santa Cruz County Population Susceptible to Faults and Liquefaction 3-140
Table 3-33: Santa Cruz County Parcels Susceptible to Earthquake Scenario Shaking 3-141
Table 3-34: Santa Cruz County Parcels Susceptible to Faults and Liquefaction 3-141
Table 3-35: Building Stock and Benchmark Years 3-142
Table 3-36: Santa Cruz County Critical Infrastructure Susceptible to Earthquake Scenario Shaking 3-143
Table 3-37: Santa Cruz County Critical Facilities Susceptible to Earthquake Scenario Shaking 3-144
Table 3-38: Santa Cruz County Critical Infrastructure Susceptible to Faults and Liquefaction 3-145
Table 3-39: Santa Cruz County Critical Facilities Susceptible to Faults and Liquefaction 3-145
Table 3-40: Santa Cruz County Earthquake Hazard Problem Statements 3-147
Table 3-41: Classes of Wind Power 3-151
Table 3-42: Santa Cruz County Severe Weather Hazard Problem Statements 3-166
Table 3-43: Santa Cruz County Population Exposed to Tsunami Risk 3-190
Table 3-44: Santa Cruz County Parcels Exposed to Tsunami Risk 3-191
Table 3-45: Santa Cruz County Critical Infrastructure Exposed to Tsunami Risk 3-192
Table 3-46: Santa Cruz County Critical Facilities Exposed to Tsunami Risk 3-192
Table 3-47: Santa Cruz County Coastal Hazard Problem Statements 3-196
Table 3-48: Slope Failure Susceptibility Classifications 3-208
Table 3-49: Santa Cruz County Population Exposed to Slope Failure Risk 3-214
Table 3-50: Santa Cruz County Parcels Exposed to Slope Failure Risk 3-215
Table 3-51: Santa Cruz County Critical Infrastructure Exposed to Slope Failure Risk 3-216
Table 3-52: Santa Cruz County Critical Facilities Exposed to Slope Failure Risk 3-217
Table 3-53: Santa Cruz County Slope Failure Hazard Problem Statements 3-219
Table 3-54: Dams in or Adjacent to Santa Cruz County 3-226
Table 3-55: FEMA Dam Hazard Potential Classifications 3-230

Table 3-56: Santa Cruz County Population Exposed to Dam Failure Risk 3-233
Table 3-57: Santa Cruz County Parcels Exposed to Dam Failure Risk 3-234
Table 3-58: Santa Cruz County Critical Infrastructure Exposed to Dam Failure Risk 3-235
Table 3-59: Santa Cruz County Critical Infrastructure Exposed to Dam Failure Risk by Dam 3-236
Table 3-60: Santa Cruz County Critical Facilities Exposed to Dam Failure Risk 3-237
Table 3-61: Santa Cruz County Critical Facilities Exposed to Dam Failure Risk by Dam 3-238
Table 3-62: Santa Cruz County Dam Failure Hazard Problem Statements 3-240
Table 3-63: Santa Cruz County Water Supplier Summary 3-244
Table 3-64: Drought Classifications and Impacts for California 3-254
Table 3-65: Santa Cruz County Drought Hazard Problem Statements 3-261
Table 3-66: Cal-Adapt Extreme Heat Terms 3-271
Table 3-67: Heat-Related Illnesses 3-273
Table 3-68: NWS HeatRisk Categories and Related Impacts 3-274
Table 3-69: NWS Heat Forecast Terms and Definition 3-274
Table 3-70: Santa Cruz County Extreme Heat Hazard Problem Statements 3-277
Table 3-71: Population Susceptible to Sea Level Rise 3-293
Table 3-72: Population Susceptible to Sea Level Rise 3-294
Table 3-73: Critical Facilities Susceptible to Sea Level Rise 3-296
Table 3-74: Detailed Inventory of Critical Facilities Susceptible to Sea Level Rise 3-296
Table 3-75: Santa Cruz County Climate Change Hazard Problem Statements 3-298
Table 3-76: Santa Cruz County Capabilities Assessment 3-308
Table 3-77: Federal, State, and Local Funding Opportunities 3-313
Table 4-1: County-Wide Hazard Mitigation Action Plan 4-325
Table 4-2: Santa Cruz County Hazard Mitigation Action Plan 4-327

Table A- 1: GIS Data Dictionary A-13

INTENTIONAL BLANK PAGE

Volume 1

SANTA CRUZ COUNTY
MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Section 1. Introduction

The Santa Cruz County 2025 Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) involves the participation of multiple local planning partners and geographically covers the entire area within Santa Cruz County's boundaries (the "planning area"). This MJHMP was prepared to guide officials in protecting the people, infrastructure, and property within Santa Cruz County from the effects of natural disasters and hazard events. This plan demonstrates a commitment to reducing risk from natural hazards through strategic mitigation actions and serves as a tool to help decision-makers direct available administrative, technical, and financial resources toward the most effective actions.



The term "hazard mitigation" refers to actions or strategies that reduce or eliminate long-term risks from natural hazards. Mitigation activities can be implemented before or after a disaster occurs. Too often, disaster recovery focuses only on restoring property and infrastructure to pre-disaster conditions; returning to "normal" but leaving communities vulnerable to the same cycle of damage and repair. Hazard mitigation planning in Santa Cruz County is intended to break this repetitive cycle by reducing vulnerability to hazards through resilient construction, thoughtful land use, and proactive planning for future development and critical infrastructure.

Since 2017, Santa Cruz County has faced eight federally declared disasters, including winter storms, flooding, coastal wave damage, wildfires, and the COVID-19 pandemic, as well as numerous other hazard events such as landslides, straight-line winds, tornadoes, and tsunamis. These experiences have significantly affected our communities and infrastructure, shaping local priorities and underscoring the need for coordinated resilience efforts. In response, this planning cycle emphasizes a multi-jurisdictional approach to hazard mitigation.

To prepare its first MJHMP, Santa Cruz County formed a planning partnership with several cities, special districts, local agencies, and community-based organizations to develop and steer the contents of this plan. Together, these partners developed the goals, objectives, strategies, and implementation measures that will guide efforts to reduce risk from natural hazards across the planning area.

1.1 Participating Jurisdictions

The 2025 Santa Cruz County MJHMP includes Santa Cruz County, three municipalities, and six special districts and agencies, collectively referred to as "participating jurisdictions." Any local government or agency with the authority to regulate building or infrastructure development can participate in the hazard mitigation planning process; however, to receive Federal Emergency Management Agency (FEMA) approval, participating jurisdictions must also meet FEMA's planning requirements detailed in the Code of Federal Regulations (CFR). (44 C.F.R. § 201.6 *et seq.*) Throughout the development of this plan, all

participating jurisdictions adhered to FEMA's recommended process and fulfilled the necessary requirements for FEMA approval, as outlined in Volume 1 and in the individual jurisdiction annexes of Volume 2.

Together, the participating jurisdictions established shared goals, objectives, and mitigation strategies while also identifying jurisdiction-specific actions to reduce risk. This collaborative approach ensures that hazard mitigation efforts are coordinated across the county, while also reflecting the unique needs and priorities of each community. The jurisdictions listed in Table 1-1 formally participated in and completed this plan update process.

Table 1-1: Participating Jurisdictions

Jurisdiction Name
Municipalities
Santa Cruz County
City of Capitola
City of Scotts Valley
City of Watsonville
Special Districts and Agencies
Soquel Creek Water District
Scotts Valley Water District
Pajaro Valley Water Management Agency
Resource Conservation District of Santa Cruz County
Santa Cruz Port District
Cabrillo College

1.2 Purpose & Scope

Each year in the United States, natural disasters claim lives, cause injuries, and result in billions of dollars in damages. In 2024, the nation experienced 27 different billion-dollar or more weather and climate disasters, trailing only the record-setting 28 events recorded in 2023. (NOAA, 2025) Nationwide, residents contribute billions of their tax dollars to help communities, organizations, businesses, and individuals recover from disasters. Many residents also face the individual recovery journey from these disasters nationwide with limited financial resources to recover. Insurance companies absorb some of these financial losses but often pass on the cost of recovery through rate increases and dropped policies. Many non-governmental organizations, small private utilities, or other private infrastructure also absorb significant losses and are not reimbursed by state or federal tax dollars for their rebuild and recovery costs. While natural hazards cannot be prevented, much of the resulting damage can be reduced or even avoided through proactive mitigation.

The primary purpose of this 2025 MJHMP is to guide hazard mitigation planning to better protect the people, property, and assets of Santa Cruz County from the effects of natural hazard events. This MJHMP was also developed to ensure continued eligibility for certain federal disaster assistance. More specifically, the plan meets eligibility requirements for FEMA Hazard Mitigation Assistance (HMA) grants, including the Hazard Mitigation Grant (HMGP), Building Resilient Infrastructure and Communities (BRIC), and Flood Mitigation Assistance (FMA) programs.

Planning Objectives

This plan documents the hazard mitigation planning process undertaken by the participating jurisdictions to increase natural hazard resilience in Santa Cruz County. The effort was initiated for several key purposes. The planning area faces significant exposure to multiple hazards that have caused hundreds of millions of dollars in historical damages and that will continue to impact the area. Since limited local resources make it difficult to fully implement proactive risk reduction measures, federal and state financial assistance is essential to successful hazard mitigation.

The elements and strategies outlined in this plan were selected to best address the participating jurisdictions' specific needs. Collectively, the following planning objectives aim to enhance resilience, reduce vulnerability, and safeguard the well-being of Santa Cruz County community.

- Meet or exceed Federal Disaster Mitigation Act of 2000 (DMA 2000), California Senate Bill (SB) 379, and other state and federal requirements for hazard mitigation planning.
- Integrate climate adaptation strategies into hazard mitigation planning.
- Maintain eligibility for federal mitigation funding.
- Meet the planning requirements of FEMA's Community Rating System (CRS) program, allowing those jurisdictions that participate in CRS to maintain or enhance their classifications.
- Ensure the plan fulfills the needs of participating jurisdictions while complying with local, state, and federal regulations.
- Coordinate existing plans and programs to align priorities and maximize the impact of mitigation projects.
- Conduct a comprehensive risk assessment focused on hazards most relevant to the planning area.
- Incorporate and address additional goals and priorities identified through the involvement of community members and other stakeholders.
- Provide actions aligned with the local and state funding measures for building a more resilient community.

What is Hazard Mitigation?

Hazard mitigation refers to long- and short-term actions which reduce or alleviate the loss of life, personal injury, and property damage that can result from a disaster FEMA defines hazard mitigation as "any sustained action taken to reduce or eliminate long-term risk to human life and property from a hazard event." Mitigation strategies can take many forms such as planning efforts, policy changes, programs,

projects, and other activities that can mitigate the impacts of hazards. These activities can be planned and implemented either before or after a disaster occurs. Too often, post-disaster recovery and repairs aim to restore property to its pre-disaster state, which may lead to repeated cycles of damage and rebuilding. Independent analysis by the National Institute of Building Sciences (NIBS) has demonstrated that hazard mitigation is highly cost-effective; on average, every dollar invested in mitigation saves society six dollars in future disaster losses, alongside preventing casualties and injuries. (NIBS, 2019)

Hazard mitigation planning is the structured process of identifying hazards, assessing potential impacts, setting goals, and developing strategies to reduce risk. This MJHMP identifies and describes hazards that could affect the Santa Cruz County planning area and evaluates their potential impacts and highlights "problem statements" or areas of concern where people and property are most vulnerable due based on social and geographic relationships to hazards. Most importantly, the mitigation strategy presented in this MJHMP responds to those identified vulnerabilities and outlines specific "mitigation actions" to achieve the greatest risk reduction available resources. Together, Santa Cruz County and other participating jurisdictions aim to save lives, reduce injuries and property damage, and protect natural resources for future generations through the mitigation actions identified and described herein.

Why Have a Hazard Mitigation Plan?

Enshrined in Public Law No. 106-390 of the United States Code (USC), DMA 2000 mandates that state and local governments develop hazard mitigation plans to qualify for federal disaster grant assistance. (42 USC § 5121 *et seq.*) Before DMA 2000, federal disaster funding primarily focused on post-disaster relief and recovery under the Robert T. Stafford Act, with limited support for proactive hazard mitigation planning. DMA 2000 shifted its focus by prioritizing pre-disaster planning and preparedness.

This MJHMP outlines the prevalent hazards in Santa Cruz County and examines how these hazards may impact the population and property differently across the planning area. It includes detailed information on natural hazard threats, identifying risks to vulnerable people, property, and assets. The plan's mitigation strategy addresses specific vulnerabilities and prescribes actions aimed at achieving the greatest reduction in these vulnerabilities, leading to quicker allocation of funds and more cost-effective projects aimed at reducing risks.

This approach ultimately leads to saving lives, minimizing injuries, reducing property damage, and protecting the environment during natural hazard events. Furthermore, the MJHMP ensures participating jurisdictions' ongoing eligibility for federal disaster assistance, specifically FEMA's HMA grants, including programs like the Hazard Mitigation Grant Program (HMGP) and FMA.

Why Update the Plan?

Local jurisdictions must maintain an active, approved hazard mitigation plan to pursue funding under the Robert T. Stafford Act. This requirement, established by DMA 2000, mandates that the plan be updated every five years to comply with federal mitigation grant conditions. Federal regulations stipulate that hazard mitigation plans must include a process for monitoring, evaluating, and updating the plan. This update process enables the reassessment of recommendations, the evaluation of completed actions' impacts, and the identification of necessary adjustments to mitigation strategies over time. Compliance with grant requirements hinges on meeting the plan update criteria specified in the CFR.

Santa Cruz County's previous LHMP was last updated and approved by FEMA in 2021. This current plan is the first multi-jurisdictional plan for Santa Cruz County and was comprehensively updated in 2025 to include nine additional participating jurisdictions. This update reflects extensive data analysis, public input, and guidance from a multi-disciplinary group of stakeholders. Throughout the planning process, all participating jurisdictions adhered to FEMA's recommended four-step process to develop this 2025 plan update. This comprehensive update includes:

- A robust and inclusive planning process
- Clear delineation of jurisdictional information
- Development of a new risk assessment
- Reevaluation of goals and objectives
- Creation of new mitigation actions
- New enhancements for implementing mitigation actions
- Updates to all sections of participating jurisdictions' previous plans
- A new project website (mitigatehazards.com/santacruzcountymjhmp) for stakeholder involvement and public information

This thorough approach ensures that the updated plan addresses current risks and mitigation needs effectively for the entire planning area.

Who Benefits from this Plan?

The 2025 Santa Cruz County MJHMP is a cornerstone for enhancing safety and resilience among residents, businesses, and visitors alike; all the community members in Santa Cruz County are the ultimate beneficiaries of this plan.

Hazard mitigation is a shared responsibility. Private property owners, businesses, industries, and all levels of government (local, federal, state) play a role in reducing risk. A key benefit of multi-jurisdictional planning is the ability to pool resources and eliminate redundant activities within a planning area that has common risk exposures and vulnerabilities. This plan will help guide and coordinate mitigation activities throughout Santa Cruz County.

By consolidating resources and coordinating efforts, the MJHMP planning process optimizes the allocation of resources to Santa Cruz County's most vulnerable areas. This approach not only enhances efficiency but also amplifies the effectiveness of mitigation efforts, ultimately benefiting the community by reducing the overall impact from natural hazards based upon available resources.

1.3 How to Use This Plan

The 2025 Santa Cruz County MJHMP is structured into two volumes to effectively manage elements that apply broadly across the planning area and to the county, specifically (Volume 1), and those elements unique to other participating jurisdictions (Volume 2). All participating jurisdictions within the county adopted Volume 1 in its entirety. Additionally, each jurisdiction adopted its own specific annex within Volume 2, ensuring that both county-wide and local needs are addressed comprehensively. This structured approach facilitates effective coordination, resource allocation, and implementation of hazard mitigation strategies across the entire planning area.

VOLUME 1
(County-Wide Elements)

Volume 1 covers all federally required elements of a hazard mitigation plan that apply to the entire planning area. This includes:

- **Section 1 – Introduction:** Describes the overall purpose of the MJHMP, its structure, and characteristics of the county-wide planning area, and provides an overview of previous hazard mitigation efforts conducted and highlights updates made in this plan.
- **Section 2 – Planning Process:** Details how the plan was developed according to FEMA's four-step process, including stakeholder engagement and public involvement strategies, and outlines procedures for updating and maintaining the plan over time.
- **Section 3 – County-Wide Hazard Risk Assessment:** Provides an assessment of the natural hazards affecting the entire planning area and the unincorporated county specifically, including their characteristics and potential impacts.
- **Section 4 – County-Wide Mitigation Strategy:** Presents mitigation goals, strategies, and actions aimed at reducing risks and enhancing resilience across the entire planning area and for the unincorporated county specifically, matched with local capabilities.
- **Section 5 – Works Cited –** Citations to sources used.
- **Appendix A – Analysis Methodology:** Details the methods used for hazard and risk assessments.
- **Appendix B – Planning Process Documentation:** Provides documentation of the planning process, including meeting summaries and stakeholder input.

VOLUME 2 (Jurisdiction-Specific Annexes)	**Jurisdiction-Specific Annexes:** Each annex contains detailed information specific to that participating jurisdiction within the planning area, including elements mandated by state and federal regulations for each jurisdiction such as tailored hazard profiles and risk assessments; relevant supporting documentation and maps; jurisdiction-specific mitigation strategies and actions; and implementation schedules and responsibilities. Vol. 2 Jurisdictional Annexes include the following:	
	City of Capitola	**Pajaro Valley Water Management Agency**
	City of Scotts Valley	**Resource Conservation District of Santa Cruz County**
	City of Watsonville	**Santa Cruz Port District**
	Soquel Creek Water District	**Cabrillo College**
	Scotts Valley Water District	

1.4 Community Profile

The Community Profile for Santa Cruz County establishes the foundation for assessing risks and vulnerabilities across the planning area. By pairing the hazard-specific vulnerability assessments (Section 3.2) local geography, demographic characteristics, and economic conditions, mitigation strategies and actions can be more effectively directed toward key populations and areas. The Hazard Mitigation Planning Team reviewed geographic and demographic data as part of the risk prioritization and assessment process. By linking known community vulnerabilities to natural hazard risk the planning process ensures that mitigation efforts are tailored to address the most critical vulnerabilities first.

1.4.1 Planning Area & Geography

The Santa Cruz County MJHMP geographically covers the entire 446-square-mile area within the county's boundaries (the "planning area") with the exception of the City of Santa Cruz. The planning area includes the cities of Capitola, Scotts Valley, and Watsonville; several special districts; and all of the unincorporated areas. The county is located in the Governor's Office of Emergency Services Coastal Region and Mutual Aid Region II.

Approximately 49% of the county's population resides within unincorporated Santa Cruz County. Another 28% resides in the cities of Capitola, Scotts Valley, and Watsonville. The remaining 23% resides in the City of Santa Cruz. Figure 1-1 provides an overview of the planning area and participating jurisdictions.

Santa Cruz County is located on the northern stretch of the Monterey Bay, 70 miles south of San Francisco. It is one of the three Monterey Bay Area counties, the other two being Monterey and San Benito. Contiguous counties include San Mateo (north), Santa Clara (east), San Benito (southeast), and Monterey (south). The

landscape is topographically diverse and features coastal bluffs, beaches, deep mountain canyons, open meadows, and redwood, oak and madrone forests. Santa Cruz County has three distinct geographic regions: The Pacific Coast, the Santa Cruz Mountains, and the Pajaro Valley.

The coast extends the full length of the county along the Monterey Bay National Marine Sanctuary from Swanton in the north to Pajaro Dunes in the south. The cities of Capitola and Santa Cruz and the unincorporated communities of Davenport, Live Oak, Soquel, Aptos, Rio Del Mar, La Selva Beach, and Pajaro Dunes are located along the Pacific Coast and its coastal plain. Its location along the Pacific Coast provides valuable natural resources and economic opportunities, as well as threats from natural hazards such as coastal bluff erosion, storm surge, and tsunami.

The Santa Cruz Mountains occupy the central portion of the county and reach upwards of 3,000 feet above mean seal level, with the highest point being Mount Bielawski at 3,232 feet. Coast redwood and Douglas-fir forests are prevalent throughout the mountains. The City of Scotts Valley and the unincorporated communities of Ben Lomond, Bonnie Doon, Boulder Creek, Felton, Lompico, and Mount Hermon are located in the Santa Cruz Mountains. Many of these mountainous areas are subject to slope failure and wildfire hazards, and the entire county is subject to seismic shaking from nearby active earthquake faults.

The Pajaro Valley extends east to west across the southern portion of Santa Cruz County along the Pajaro River and serves as the county's primary agricultural region. Portions of the valley are subject to riverine flood hazards, particularly in low-lying areas near the river and its tributaries, where flood risks can be compounded by coastal storms and tidal influences. The City of Watsonville, along with the unincorporated communities of Corralitos and Freedom, are located within the Pajaro Valley and have experienced recurring flood impacts.



Figure 1-1: Geographic Overview of Planning Area and Participating Jurisdictions

Transportation Routes

Understanding transportation routes in the planning area is crucial for hazard mitigation planning. Several key roadways in Santa Cruz County provide important linkages and access during a hazard event, including functioning as critical evacuation routes, and other forms of transportation may also be utilized to assist in emergency ingress and egress.

Five major state highways connect Santa Cruz County with adjacent counties. State Route 1 (SR-1) is located along the coast and extends from San Francisco, through San Mateo County along the coast, south to the cities of Santa Cruz, Capitola, and Watsonville, and then on to Monterey County. State Route 9 (SR-9) traverses the county from the City of Santa Cruz through the rural villages of Felton, Ben Lomond, and Boulder Creek, before descending into Santa Clara County at Saratoga Gap. State Route 17 (SR-17) crosses the Santa Cruz Mountains into Santa Clara County passing through the City of Scotts Valley. To the south, State Route 129 (SR-129) and State Route 152 (SR-152) connect the City of Watsonville with neighboring Santa Clara County and San Benito County, respectively. State Route 236 (SR-236) provides access to Big Basin State Park in the Santa Cruz Mountains from SR-9.

The Santa Cruz Branch Rail Line, owned by the Santa Cruz County Regional Transportation Commission (RTC), extends 32 miles along the coast from Watsonville Junction to Davenport. The northern portion of this rail line has been out of service for years and may be developed as a multi-modal recreational trail in the future. The RTC has studied the possibility of operating passenger rail service between the City of Santa Cruz and Watsonville Junction. Additionally, the Roaring Camp & Big Trees Narrow Guage Railroad operates passenger excursion trains between Felton and Santa Cruz.

Watsonville Municipal Airport (WVI) is the only airport in Santa Cruz County. The airport has two 4,000-foot runways and supports general aviation. There is no scheduled commercial passenger service at WVI.

In addition to these major transportation routes, areas across the county are connected by a network of publicly maintained roads (arterials, collectors, and local public roads); recreational trails for hiking, horseback riding, and biking; and an extensive network of privately owned and -maintained roads. Within the mountainous areas of the county, in particular, many of these secondary and tertiary travelways are geographically isolated along steep slopes, ridgelines, and canyons, complicating emergency ingress and egress. This condition is exemplified by the numerous single egress (i.e., one-way-in; one-way-out) neighborhoods in the Santa Cruz Mountains.

While major transportation routes are pivotal for evacuation planning, emergency response, and general transportation needs, as outlined in this MJHMP, alternate transportation modes and secondary and tertiary travelways can also be utilized to wholistically address emergency access deficiencies. Figure 1-2 provides a geographic overview of the planning area highlighting major transportation routes.



Transportation Routes

Source: Santa Cruz County

Figure 1-2: Major Transportation Routes

County Service Areas (CSAs)

Santa Cruz County administers a number of County Service Areas (CSAs) that provide locally initiated and voter-approved services beyond the baseline responsibilities of the county. There are currently 36 private road CSAs, which allow residents to collectively fund the maintenance and improvement of private mountain roads through a Benefit Assessment fee added to their property tax bills. This mechanism represents a viable local mitigation strategy by ensuring long-term upkeep of critical access routes, particularly in areas vulnerable to wildfire, landslides, and storm damage. In addition to road maintenance, CSAs also exist to support other community needs such as waste disposal, police and fire protection, streetscape improvements, and street lighting, allowing neighborhoods to tailor services to their specific priorities.

Water Resources

Nearly all of Santa Cruz County's domestic water supply comes from local sources, with approximately 20 percent from streams and reservoirs and 80 percent from groundwater. The county does not import significant amounts of water. Major agencies include the San Lorenzo Valley Water District, Scotts Valley Water District, City of Santa Cruz Water Department, Soquel Creek Water District, Central Water District, City of Watsonville, and the Pajaro Valley Water Management Agency, several of which participate directly in this plan. Outside of these systems, many residents rely on small water systems and private wells, which are often more vulnerable to disaster impacts. Water supply challenges, vulnerabilities, and long-term sustainability are addressed in greater detail in the Drought Hazard Profile Section 3.2.8.

County Sanitation

The Sanitation Unit, within the Community Development and Infrastructure (CDI) Department's Division of Public Works Special Services, is responsible for managing wastewater collection, treatment, and environmental compliance across multiple service areas. The unit oversees three sanitation districts: the Santa Cruz County Sanitation District, the Davenport Sanitation District, and the Freedom Sanitation District. It also manages five Sanitation CSAs. In addition to wastewater responsibilities, the Davenport Sanitation District also provides treated drinking water to its community. The Sanitation Unit ensures compliance with state and federal water quality standards, operates and maintains collection system infrastructure, and supports capital improvement projects to reduce the risk of overflows and protect public health and the environment. These services are critical to hazard mitigation, as wastewater systems are vulnerable to flooding, power outages, and storm damage, and their proper functioning is essential for maintaining community resilience during disasters.

1.4.2 Climate

Santa Cruz County's climate can generally be described as Mediterranean, with mild, wet winters and warm, dry summers. However, the county's coastal mountain terrain and proximity to the Pacific Ocean create distinct microclimates. Along the coast, the presence of a marine layer moderates temperature extremes and fog is common throughout the summer. By contrast, inland valleys and the uppermost elevations of the Santa Cruz Mountains experience much warmer conditions, with summer highs often exceeding 90 degrees Fahrenheit (°F) and occasionally over 100°F. The warmest portion of Santa Cruz County has historically been the San Lorenzo Valley and high-elevation inland-facing valleys throughout the Santa Cruz Mountains. At the highest peaks (over 3,500 feet in elevation), snowfall can occur during winter months.

Warm temperatures and low precipitation are the norm from approximately April through October, while cooler temperatures and heavy rains dominate November through March. Though winters are typically mild, colder winds from inland regions with more continental climates can result in short-term cold snaps. According to the National Oceanic and Atmospheric Administration (NOAA), the annual mean temperature in Santa Cruz is approximately 57°F, with an annual mean high of almost 62°F and mean low of around 52°F. Extreme heat and cold were historically rare threats to the community with both summer and winter temperatures moderated by marine influences, climate change is shifting local norms toward more frequent and severe extremes.

Figure 1-3 presents the county-wide 30-year monthly climate normals from 1991 to 2020 for precipitation and minimum and maximum temperatures.



Figure 1-3: Santa Cruz County 30-Year Monthly Climate Normals (1991-2020)

Source: gridMET (UC Merced)

Prevailing winds are generally northwesterly during most of the year, shaped by marine conditions and topography. The Santa Cruz Mountains form a natural barrier to winds from the north and from the hot interior valleys. In summer and early fall, **offshore** (east and northeast) wind events can occur—producing dry, downslope adiabatic warming that dries fuels and heightens wildfire danger. For the remainder of the year, **onshore** winds from the Pacific bring moist, marine air that moderates temperatures and maintains the county's coastal fog cycle.

Most of the county's annual rainfall arrives from November to March and comes in heavy bursts from Pacific frontal systems and atmospheric rivers, which can produce intense short-term flooding and landslide risk. Rainfall varies widely throughout the county, from approximately 80 inches per year in Bonny Doon, to approximately 22 inches per year in the Watsonville area. According to NOAA, the mean annual precipitation in Santa Cruz is approximately 29 inches but increasingly frequent and severe drought conditions in recent years have resulted in annual precipitation as low as five inches.

1.4.3 Demographics & Vulnerable Populations

This section provides an overview of Santa Cruz County's social and economic landscape to inform hazard mitigation planning. Natural disasters affect communities both physically and socially, and their impacts are not distributed evenly. Certain populations may face greater challenges in preparedness, response, and recovery, which can magnify the overall consequences of a disaster. By examining demographic characteristics alongside the built environment, this section supports a better understanding of potential social costs from damage to housing, industry, public facilities, essential services, and transportation.

The demographic data for Santa Cruz County and the other participating jurisdictions discussed in this MJHMP is derived from the U.S. Census Bureau's American Community Survey 5-Year Estimates (ACS 5-Year) from 2018 to 2023. The figures presented are intended to highlight broader regional trends relevant to hazard mitigation planning efforts rather than inform specific decision-making or administrative actions.

The U.S. Census Bureau estimated Santa Cruz County's total population to be 266,021 in 2023, with around 49% living outside incorporated areas. Unincorporated Santa Cruz County's population represents 49% of the county-wide population, while the incorporated cities of Capitola, Scotts Valley, and Watsonville collectively total 28%. The City of Santa Cruz accounts for the remaining 23 Table 1-2 summarizes population and household characteristics for Santa Cruz County, including the unincorporated county and the incorporated cities that participated in this MJHMP.

Table 1-2: County-Wide Population and Households

Jurisdiction	Total Population	Total Households	Average Household Size
Unincorporated Santa Cruz County	131,149	56,539	-
City of Capitola	9,813	5,086	1.89
City of Santa Cruz	60,953	23,778	2.12

City of Scotts Valley	12,138	5,440	2.18
City of Watsonville	51,968	15,792	3.24
Santa Cruz County (Total)	**266,021**	**106,635**	**2.36**

Notes: Limited data available for unincorporated Santa Cruz County. City of Santa Cruz population provided for comparison only; not a participating jurisdiction.

Source: ACS 5-Year, 2018-2023

1.4.3.1 Introduction to Vulnerable Populations

Exploring local demographic data is crucial for identifying groups and geographic areas vulnerable to hazard events. Certain populations face heightened risks following disasters due to factors such as age, economic status, mobility limitations, physical or mental disabilities, and geographic location. Vulnerable residents are not always aggregated in any single area or high enough concentration to be recognized by census derived geographies. However, the county development history and demographics reflect that elderly and low-income residents are spread throughout the county and within every jurisdiction. Vulnerability is not static; individuals may be more at risk from some hazards than others. For instance, a low-income family without transportation may struggle during rapid evacuations for wildfires or floods but could be adequately prepared for an earthquake event. Mitigation efforts can reduce personal vulnerability for some but not all individuals, especially those reliant on caregiving networks like children, the elderly, and persons with disabilities. Further, environmental risk often disproportionately burdens lower-income and marginalized communities, who typically reside in hazard-prone areas with fewer mitigation resources. (National Center for Disaster Preparedness, 2020)

In all-hazards preparedness and response planning, at-risk individuals, often synonymous with vulnerable populations, are federally defined as "children, pregnant women, senior citizens, and others with access or functional needs during public health emergencies." (42 USC § 2802(b)(4)(B)) These include those who are economically disadvantaged, have chronic medical conditions, belong to historically marginalized groups, face language barriers, lack transportation, or experience homelessness. Prioritizing resources where they are most effective, such as cost-sharing for wildfire or flood mitigation measures and translating emergency information into languages needed by the local community, are prime examples of planning for vulnerable populations in hazard mitigation.

At-Risk Individuals with Access & Functional Needs

Access and functional needs may interfere with the ability for an at-risk individual to access or receive medical care before, during, or after a disaster or emergency event. Irrespective of a specific diagnosis, status, or label, the term “access and functional needs” refers to a broad set of cross-cutting access-based or function-based needs, generally distinguished according to the following:

- **Access-based needs** require that resources are accessible to all individuals to maintain health, such as social services, accommodations, information, transportation, and medications.

- **Function-based needs** refer to restrictions or limitations an individual may have that requires assistance before, during, and after a disaster or public health emergency.

At-risk individuals may have additional needs that must be considered in planning for, responding to, and recovering from a disaster or emergency. An approach recommended by the U.S. Department of Health and Human Services (HHS) for integrating the access and functional needs of at-risk individuals is to consider elements based on the "CMIST" framework:

- **C = Communication:** Individuals with communication needs may have limitations that interfere with the receipt of and response to information, requiring information to be provided in an appropriate and accessible format. This can include individuals who are deaf or hard of hearing, speak American Sign Language, have limited or no English proficiency, are blind or have low vision, or have cognitive or physiological disabilities.
- **M = Maintaining Health:** Individuals may require specific services, supplies, equipment, medication, or nutrition to reduce negative impacts of a disaster or emergency and maintain activities of daily living, such as breathing, eating, dressing, grooming, transferring, and toileting.
- **I = Independence:** Continuity of access to necessary assistive devices, such as wheelchairs, or other aids, like service animals, is crucial to maintaining independence for individuals who rely on these support tools to function autonomously.
- **S = Support:** Tailored, person-centered support may be necessary for individuals who have lost caregiver assistance, find it difficult to cope in a new or strange environment, have difficulty remembering or understanding, or have past trauma experiences. This includes support for victims of abuse, individuals with behavioral health needs, or those who have psychiatric conditions (e.g., Alzheimer's disease, Schizophrenia).
- **T = Transportation:** Individuals may lack access to personal transportation due to a variety of factors, including economic status, age, physical or mental disability, temporary condition or injury, or legal restriction. This requires coordination with mass transit and accessible transportation service providers to ensure access to support and necessary services. (HHS, 2020)

While most individuals with access and functional needs do not have acute medical conditions requiring the support of trained medical professionals, many require additional assistance to maintain health and minimize preventable negative outcomes, especially during a disaster event. These at-risk individuals may also require more time or personnel to assist during an evacuation. Therefore, special attention from planners and emergency managers is crucial for this highly vulnerable population.

Environmental Justice

Environmental justice issues can often exacerbate public health impacts from hazard events, and vice versa. The U.S. Environmental Protection Agency (EPA) defines environmental justice as the "fair treatment and meaningful involvement of all people regardless of race, color, national origin, or income with respect to the development, implementation, and enforcement of environmental laws, regulations, and policies" (EPA, 2021).

As previously discussed, hazard events can disproportionately impact low-income and vulnerable populations. Lower-income populations, for instance, are more likely to live in neighborhoods susceptible to flooding or near industrial areas or hazardous waste sites, increasing their risk to toxic leaks associated with flood and storm damage (Sherwin, 2019). With the increased frequency of wildfires in recent years, populations already living in air quality-impacted areas can be further affected by wildfire smoke. These populations often include agricultural and outdoor workers, children, seniors, and low-income residents who experience disproportionate health impacts from wildfire smoke, as well as other impacts from wildfires such as physical and psychological stress from evacuation, property loss, physical injury, or death (Shahir Masri et al., 2021)

Certain locations within Santa Cruz County are known to be at higher risk of hazard-related impacts to vulnerable populations due to historical development patterns and socioeconomic pressures, as well as changing demographics. For instance, areas along the Pajaro River where many low-income households and small farms are located are at higher risk of flooding, and these populations are more likely to lack adequate resources for effective flood mitigation and recovery. Similarly, rural communities in the Santa Cruz Mountains are often made up of seniors living in older structures and neighborhoods that do not meet modern standards and are at higher risk of wildfires due to overgrown, drought-stressed vegetation. The elderly and others with mobility issues may face additional challenges in conducting fuel management and during evacuation

It is vital that environmental laws and regulations, as well as hazard mitigation planning, meaningfully include these communities in their efforts to account for public health and safety. This approach ensures that vulnerable populations are not overlooked and that their specific needs and risks are addressed comprehensively.

Mental Health Impacts of Hazard Events

Hazard events are associated with many physical impacts on people and property, but they can also have mental health impacts. Specifically, hazards can precipitate anxiety, depression, shock, extreme stress, or Post Traumatic Stress Disorder (PTSD). (Makwana, 2019) Mental health challenges can also result from ongoing impacts after a disaster event, such as socioeconomic losses from damage to housing resulting in displacement. The death or injury of a loved one can lead to substantial and prolonged psychological stress as well. (*Id.*)

The county has also experienced the trauma impacts in major disaster recovery, especially in the aftermath of the San Mateo-Santa Cruz Unit (CZU) lightning Complex Fire in 2020. There is a clear need to ensure that the County and jurisdictions provide trauma informed training for staff in support of disaster recovery victims in the future.

1.4.3.2 Income & Housing

Economic status and mobility strongly predict hazard vulnerability. Low-income households and communities bear disproportionate financial burdens from the costs associated with disaster preparedness, response, and recovery. In the United States, households are expected to rely on private resources to prepare for, respond to, and recover from disasters, placing those in poverty at a distinct disadvantage. Moreover, economically disadvantaged households are more likely not to own their homes and frequently inhabit poorly constructed or inadequately maintained housing.

Disasters often result in unexpected expenses that can push families and individuals living on the brink of poverty or homelessness over the edge. Low-income residents are at significantly higher risk of injury and face greater challenges securing food and shelter during and after an event. Further, those lacking transportation may find it impossible to evacuate during an emergency, while recovery costs can be prohibitively high for households unable to afford hazard mitigation measures in advance. (Krause & Reeves, 2017) Renters and low-income residents are also less likely to purchase insurance, leaving them particularly vulnerable to significant losses during hazard events.

The overall poverty rate across Santa Cruz County is approximately 11% with a median annual income of over $109,000 (Table 1-3). In general, lower-income areas are concentrated within and around urban areas in the middle and southern portion of the county while the northern and mountainous regions, such as Scotts Valley, have higher median incomes and lower poverty rates (Figure 1-4 and Figure 1-5).

Table 1-3: County-Wide Income and Poverty

Jurisdiction	Median Income	Poverty Rate
Santa Cruz County (including municipalities)	**$109,266**	**11.2%**
City of Capitola	$96,412	13.9%
City of Scotts Valley	$140,887	4.8%
City of Watsonville	$74,785	15.1%

Source: ACS 5-Year, 2018-2023

Renters face additional challenges beyond being less likely to have personal property insurance. Decisions about major structural improvements typically rest with property owners, not tenants, and low-income renters may inhabit older, less resilient homes located in areas with greater exposure to hazards. For instance, mobile homes are more susceptible to damage from severe weather and floods compared to other types of residences, while aged homes may lack air conditioning or cooling units needed during heatwaves. Federal disaster recovery services can widen disparities between renters and homeowners, as homeowners generally receive higher payouts through FEMA's Individual Assistance (IA) program. Research spanning 1999 to 2013 indicates that homeowners' wealth tends to increase after local hazard events, while renters' wealth typically decreases. (Howell & Elliot, 2019)

Santa Cruz County has an overall homeownership rate of approximately 60%, which is higher than the state and national averages. Around 30% of occupied units in the unincorporated county are rentals. Many residents find themselves "House Rich" but "Cash Poor," which limits their ability to do proactive hazard mitigation around their homes. Such as wildfire risk reduction.

Cost-Burdened Households

Housing affordability remains one of the most significant challenges facing Santa Cruz County. A household is considered cost-burdened if it spends more than 30% of its income on housing, and severely cost-burdened if more than 50% of income goes toward housing costs. These pressures place households, particularly low-income renters, at higher risk of displacement, eviction, or homelessness.

In the unincorporated areas of the county, disparities in housing cost burden are evident across race, ethnicity, and tenure. Overall, approximately 38% of households experience housing cost burden, with 17% facing severe cost burdens. Renters are disproportionately affected: 51 percent of renters are cost-burdened compared with 30% of homeowners (Santa Cruz County, 2024).

According to the General Plan Housing Element, the highest proportion of cost burdens neighborhoods are concentrated in Rio Del Mar, Twin Lakes, Pleasure Point, Aptos Hills–Larkin Valley, Aptos, Monte Toyon, and the census tract northeast of Interlaken. The southern portion of the unincorporated county also exhibits higher shares of renters, poverty concentrations, and displacement vulnerability.



Figure 1-4: County-Wide Median Household Income Map

Source: ACS 5-Year, 2018-2023



Figure 1-5: County-Wide Poverty Status Map

Source: ACS 5-Year, 2018-2023

Owner vs. Rental Occupancy

Housing tenure is a critical factor in hazard mitigation planning because renters and owners often face different levels of risk, resources, and recovery capacity. Renters may be more vulnerable to displacement following a disaster due to limited insurance coverage, fewer financial resources for temporary housing, and reliance on landlords to implement structural retrofits or repairs. Owner-occupants, while generally more likely to invest in property improvements, may also face significant financial burdens when major repairs or rebuilding are required.

As shown in Table 1-4, Santa Cruz County has close 97,000 occupied housing units, with 40.0% renter-occupied and 60.0% owner-occupied. Within incorporated cities, Watsonville has the highest proportion of renter households (56.4%), while Scotts Valley has the lowest (27.5%). The unincorporated county falls below the statewide average renter rate, with 30 % of units renter-occupied compared to the California statewide average of 44% renter-occupied and 55.8% owner-occupied (ACS 5-Year Estimates, 2018–2023).

These patterns have direct implications for hazard vulnerability. Communities with higher renter populations, such as Watsonville and Capitola, may require additional resources to support disaster preparedness, evacuation, and post-disaster housing recovery. In contrast, areas with predominantly owner-occupied housing stock, such as Scotts Valley, may face different challenges, such as financing mitigation retrofits for older homes. Recognizing these tenure-based differences helps ensure that mitigation strategies are tailored to meet the needs of both renters and homeowners across the county.

Table 1-4: County-Wide Renter- and Owner-Occupied Housing

Jurisdiction	# Occupied Housing Units	# Renter-Occupied	% Renter-Occupied	# Owner-Occupied	% Owner-Occupied
Unincorporated Santa Cruz County	50,423	15,212	30.2%	35,211	69.8%
City of Capitola	4,506	2,241	49.7%	2,265	50.3%
City of Scotts Valley	5,008	1,377	27.5%	3,631	72.5%
City of Watsonville	15,267	8,610	56.4%	6,657	43.6%
Santa Cruz County (Total)	**96,873**	**38,771**	**40.0%**	**58,102**	**60.0%**
California (Statewide)	~13.4 M	~5.9 M	~44.2%	~7.5 M	~55.8%
United States	~126.8 M	~43.6 M	~34.4%	~83.1 M	~65.6%

Source: ACS 5-Year, 2018-2023



Figure 1-6: County-Wide Percentage of Owner-Occupied Housing Units Map

Source: ACS 5-Year, 2018-2023

Age of Building Stock

The age of buildings in Santa Cruz County has direct implications for hazard vulnerability and resilience. Data from the Santa Cruz County Assessor's Office (Figure 1-7) shows that a significant portion of the county's building stock was built between the 1960s and 1980s, prior to many of California's modern building code requirements for seismic safety, energy efficiency, and wildfire resilience.

- **Unincorporated County** - has substantial mid-century housing, with 21% built in the 1970s and 18% in the 1980s.
- **Capitola** - nearly one-quarter (24%) of homes were constructed during the 1970s, with another 18% built in the 1960s.
- **Scotts Valley** - housing is newer overall, with the largest share (24%) constructed in the 1980s, followed by 21% in the 1970s.
- **Watsonville-** the housing stock is more evenly distributed, though 18% was built in both the 1970s and 1980s.

Overall, this distribution means that many homes were constructed before the 1997 Uniform Building Code (UBC) overhaul, which introduced strength-based seismic design, soil amplification factors, and near-source effects. California had already unified its building standards under Title 24 (1978), but homes built in the late 1970s and 1980s still predate the most rigorous seismic provisions later adopted into the California Building Code (CBC) from the International Building Code (IBC). Similarly, widespread



Figure 1-7: Age of Countywide Building Stock

requirements for fire-resistant materials and defensible space did not emerge until after major wildfire losses in the 1990s and 2000s.

The condition and age of housing stock highlight the importance of encouraging voluntary retrofits for older structures, maintaining critical lifelines in aging neighborhoods, and ensuring rental housing — which is often concentrated in older buildings — receives adequate investment to remain safe and habitable after disasters.

1.4.3.3 Access to Transportation

Transportation barriers also contribute to social vulnerability, as some parts of Santa Cruz County lack public transit infrastructure. Families and individuals without personal transportation, including many lower-income households and older adults, face challenges in rapidly evacuating and difficulties accessing essential or medical services due to limited transportation options. Rural communities, in particular, may experience longer travel times to economic centers where most healthcare facilities and emergency shelters are located, further exacerbating disparities in access. In the event of natural disasters or road closures due to earthquake, wildfire, flood, or another disaster, these transportation challenges can hinder evacuation efforts and access to relief services.

Across the county, reliance on public transit and the number of households lacking personal transportation are low, at less than 1% and less than 5%, respectively (Table 1-5). However, more than 3% of households in the unincorporated areas of the county have no personal vehicle, complicating emergency evacuation where there are very few public transit options. The highest rates of transit reliance and households with no vehicle correlate with areas of lower median income and higher poverty in the middle and southern portions of the county, including the City of Watsonville in the Pajaro Valley (Figure 1-4 and Figure 1-5).

Table 1-5: County-Wide Public Transit Reliance and Households with No Vehicle

Jurisdiction	# Persons Reliant on Public Transit	% Population Reliant on Public Transit	# Households w No Vehicle	% Households w No Vehicle
Unincorporated Santa Cruz County	561	0.4%	1,743	3.1%
City of Capitola	57	0.6%	228	4.5%
City of Scotts Valley	21	0.2%	303	5.6%
City of Watsonville	297	0.6%	1,127	7.1%
Santa Cruz County (Total)	**1,857**	**0.7%**	**5,107**	**4.8%**

Source: ACS 5-Year, 2018-2023

1.4.3.4 Dependent & Disabled Populations

Age and disability status play significant roles in vulnerability to natural hazards, as seniors, children, and many who experience disabilities are dependent populations who rely on caregiver networks for support and protection. Seniors and disabled persons may have mobility challenges and increased health concerns, necessitating additional assistance during evacuations and recovery. Similarly, children have limited ability to protect themselves and depend on caregivers to ensure their safety and well-being during emergencies. When combined with factors such as poverty, these vulnerabilities can be further compounded, highlighting the importance of targeted interventions to address the unique needs of dependent and disabled populations.

Although vulnerability among persons in the same age cohort varies significantly based on health and socioeconomic security, seniors as a group have a higher prevalence of physical and financial barriers to response and recovery, both during and after an emergency, and are more prone to health-related consequences, making recovery slower. They are more likely to experience vision, hearing, or mobility impairments, as well as mental impairments. Additionally, many elderly individuals reside in assisted-living facilities where emergency preparedness depends on the facility operators. These facilities are typically identified as “critical facilities” by emergency managers because they require extra notice and resources to implement evacuations. Further, seniors living alone may have difficulty evacuating their homes and could be stranded in dangerous situations. This population often needs special medical attention, which may not be readily available during a disaster event due to isolation. Given the current aging of the American population, specific planning for the elderly is warranted.

People under the age of 18 have little control over their living situation or household actions for hazard preparedness, response, or recovery. Disasters may have detrimental long-term effects on children, both mentally and physically and especially when living in poverty. Those children living in households with a single caregiver may also be more vulnerable due to compounding factors, such as reduced financial resources. Table 1-6 summarizes Santa Cruz County’s economically dependent age groups. Although the county’s population skews older than the state and national averages, with over a third of households composed of persons 65 years of age or older, the percentage of seniors living alone or in poverty is relatively low.

Over a quarter of households across the county include children under the age of 18, approximately 6% of which have a single caregiver. Both the number of households with children and those with a single caregiver are much higher in the southern portion of the county in and around the City of Watsonville compared to other regions. Figure 1-8 identifies concentrations of economically dependent age groups, including seniors and children.

Table 1-6: County-Wide Economically Dependent Age Groups

Jurisdiction	% Households 65+	% Households 65+ Living Alone	% Households 65+ in Poverty	% Households <18	% Households <18 w Single Caregiver
Unincorporated Santa Cruz County	36.5%	9.2%	2.0%	23.0%	4.7%
City of Capitola	35.3%	10.4%	2.3%	19.4%	7.3%
City of Scotts Valley	40.1%	7.8%	2.4%	23.3%	5.3%
City of Watsonville	30.6%	4.2%	5.3%	42.1%	12.9%
Santa Cruz County (Total)	**33.4%**	**7.9%**	**2.7%**	**24.8%**	**6.0%**
California Statewide	31.4%	9.8%	11.8%	32.9%	5.8%
Nationwide	31.3%	7.7%	11.2%	29.9%	6.1%

Source: ACS 5-Year, 2018-2023

Those with access and functional needs may experience more difficulties in preparing for, responding to, or recovering from a disaster or emergency event. This includes persons living with one or more physical or cognitive disabilities such as hearing or vision impairment, reliance on mobility or other medical devices, mental disorders or neurodivergence, and chronic health conditions that increase susceptibility to hazard impacts like wildfire smoke. As such, these at-risk individuals may require additional time or personnel to assist during an evacuation or other emergency and special attention is warranted from planners and emergency managers this highly vulnerable population.

Across the county, approximately 11% of the non-institutionalized population lives with some form of disability (Table 1-7). Figure 1-9 identifies elderly disabled persons, showing that this population is generally located within and adjacent to urban centers where more services are available; however, a significant number of seniors with a disability live in the Santa Cruz Mountains.

Table 1-7: County-Wide Non-Institutionalized Disabled Population

Jurisdiction	# Persons w Disability	% Persons w Disability
Unincorporated Santa Cruz County	13,890	10.6%
City of Capitola	1,631	16.6%
City of Scotts Valley	1,318	10.9%
City of Watsonville	6,109	11.8%
Santa Cruz County (Total)	**29,557**	**11.1%**

Source: ACS 5-Year, 2018-2023



Figure 1-8: County-Wide Percentage of Economically Dependent Age Groups Map

Source: ACS 5-Year, 2018-2023



Figure 1-9: County-Wide Percentage of Disabled Elderly Map

Source: ACS 5-Year, 2018-2023

1.4.3.5 Race, Ethnicity & Language

Natural disasters compound racial disparities; non-white individuals and communities receive less recovery aid from FEMA than their white counterparts, even when the extent of damage is the same. (Howell & Elliot, 2019) (National Advisory Council, 2020) Research indicates that minorities are less likely to participate in pre-disaster planning and experience higher mortality rates during disaster events. Post-disaster recovery for these groups is also often ineffective and can sometimes be culturally insensitive. Since a higher proportion of ethnic minorities live below the poverty line compared to white populations, poverty exacerbates their vulnerability. (Fothergill, 1999)

These disparities illustrate the complex relationship between disaster recovery and overlapping social vulnerabilities such as race, income, language, and health. Black and Latino residents are more likely to be low-income renters, which creates barriers to navigating FEMA's IA programs. Communities with higher proportions of non-white residents may have lower tax revenue and property values, resulting in less investment in mitigation and rebuilding efforts both before and after emergencies. The recent COVID-19 pandemic highlighted these disparities, with non-white persons facing significantly higher morbidity rates from infections—ranging from 70% to 350%—than those of white, non-Hispanic individuals. (CDC, 2020)

It should be noted that U.S. Census Bureau ACS estimates are often less accurate in areas with high concentrations of undocumented persons. Some minority households may avoid participating in Census surveys due to mistrust of government agencies or concerns about immigration status. This can lead to underreporting, further obscuring the true extent of racial, ethnic, language-related vulnerabilities. As such, race and ethnicity are discussed as part of a more comprehensive approach using the Center for Disease Control's Social Vulnerability Index (SVI) in Section 1.4.3.7.

As identified in Figure 1-10 and Figure 1-11, Santa Cruz County is predominantly White and consists of smaller populations of other races and ethnicities compared to statewide averages. However, the Hispanic population, which is more concentrated in the heavily agricultural area of the Pajaro Valley and Watsonville, is significant at approximately 35%.



Figure 1-10: County-Wide Race and Ethnicity Chart

Source: ACS 5-Year, 2018-2023

Non-English speaking or limited-English proficiency individuals may struggle to understand emergency information due to language and literacy barriers, often resulting in confusion about who to trust for accurate information. These individuals may be unable to access up-to-date emergency information and may have difficulty navigating recovery programs. Local governments can take steps to increase equity in disaster preparedness and recovery outcomes by translating preparedness materials and emergency notifications in a timely manner and partnering with local community groups to target outreach more effectively to at-risk populations.

Across the county, around 17% of households speak Spanish and 3% speak little to no English (Table 1-8 and Figure 1-12). Within the Pajaro Valley and City of Watsonville, almost half of households speak Spanish and 15% are limited English. Other areas with concentrations of Spanish-speaking households include the North Coast communities of Davenport and Live Oak. The County also has identified some residents who speak indigenous non-written languages, such as Mixtec and Trique.

Table 1-8: County-Wide Household Languages

Jurisdiction	# Spanish-Speaking Households	% Spanish-Speaking Households	# Limited-English Households	% Limited-English Households	# Other Language Households
Unincorporated Santa Cruz County	6,929	12.3%	719	1.3%	90
City of Capitola	511	10.0%	49	1.0%	0
City of Scotts Valley	319	5.9%	12	0.2%	0
City of Watsonville	7,719	48.9%	2,363	15.0%	0
Santa Cruz County (Total)	**18,325**	**17.2%**	**3,354**	**3.1%**	**90**

Source: ACS 5-Year, 2018-2023

1.4.3.6 Agricultural Workers

Agricultural workers may be particularly vulnerable during a hazard event, especially those who are non-English speaking, working outdoors, or living in temporary worker housing. These characteristics significantly increase exposure to—and compound impacts from—hazards such as extreme heat and wildfire smoke. Further, drought and flood events can damage or destroy crops, causing economic impacts across the agricultural sector and putting agricultural workers at higher risk of poverty and displacement.

The Santa Cruz County Agricultural Commissioner issued a report in June 2025 indicating that agricultural production directly employed 7,231 persons in Santa Cruz County 2023. This employment figure includes a wide range of production-related jobs, not just growing and harvesting. Fruit farming, especially of berries, is the largest agricultural sector in the county, followed by greenhouse, nursery, and floriculture (i.e., flowers and other ornamentals). The California Employment Development Department estimated there were 7,800 workers in the "farm" sector as of June 2025.

The agricultural industry and the workers within it are primarily concentrated in the Pajaro Valley. There is also an agricultural presence in the Davenport area. This area is also home to a significant Hispanic population and large number of limited-English households, many of which are agricultural workers. These characteristics increase overall vulnerability to hazard events due to cultural and language barriers in communicating about risk, preparedness, and available resources.



Figure 1-11: County-Wide Race and Ethnicity Predominance Map

Source: ACS 5-Year, 2018-2023



Figure 1-12: County-Wide Percentage of Spanish-Speaking Population Map

Source: ACS 5-Year, 2018-2023

1.4.3.7 Social Vulnerability Index (SVI)

The U.S. Centers for Disease Control (CDC) developed the Social Vulnerability Index (SVI) to quantify social vulnerability. The SVI ranks Census Tracts, Census County Divisions, or other appropriate statistical divisions based on sixteen variables across four key themes: socioeconomic status, housing and transportation, racial and ethnic minority status, and household characteristics. The SVI measures a community's ability to prepare for and recover from hazardous events. This composite index provides a percentile ranking, with those statistical divisions in the 90th percentile or above identified as having the highest social vulnerability to public health emergencies and natural hazard events.

A map of Santa Cruz County's SVI is provided in Figure 1-13. The greatest social vulnerability is present in the southern portion of the county, in the Pajaro Valley and City of Watsonville, where the SVI is greater than 0.75. Additionally, areas in and around the Cities of Santa Cruz and Capitola have higher social vulnerability than more rural, mountainous regions of the county.

Santa Cruz County's SVI highlights disparities in housing and transportation that disproportionately impact lower-income populations, rural residents, and agricultural worker communities. In Santa Cruz County, these vulnerabilities are shaped by geographic isolation, limited affordable housing, and reliance on personal vehicles for mobility in some areas.

1.4.4 Economy

Hazard events can have a significant impact on the economy of a region, including lost jobs and unemployment following the disaster. Loss of agricultural production and tourism impacts are particularly significant in Santa Cruz County, given that these industries account for approximately 20% of all jobs in the county.

According to the California Employment Development Department, in June 2025 there were close to 112,000 jobs in all industries in Santa Cruz County. Table 1-9 shows the number of jobs in the county within the top ten industries as of June 2025.

Despite being the second smallest county by geographical size in California, agriculture accounts for a significant portion of the Santa Cruz County economy. A 2025 report issued by the Santa Cruz County Agricultural Commissioner indicated that agriculture contributed over $1.5 billion to the county's economy in 2023. (Santa Cruz County, 2025) The report also indicated that the agricultural industry contributed to one in 18 jobs in the county that same year. Santa Cruz is one of the leading counties for berry production, with strawberries, raspberries, and blackberries accounting for approximately $384 million in production value in 2023. (*Id.*)



Figure 1-13: County-Wide Social Vulnerability Index (SVI) Map

Source: ACS 5-Year, 2018-2023

Table 1-9: County-Wide Jobs in Top Ten Industries

Industry	# of Jobs
Government	20,600
Private Education and Health Services	20,000
Trade, Transportation, and Utilities	15,200
Leisure and Hospitality	14,700
Professional and Business Services	9,400
Manufacturing	8,000
Farm	7,800
Mining, Logging, and Construction	5,000
Financial Activities	3,300
Information	700

Source: California Department of Employment Development, 2025.

According to Visit Santa Cruz, tourism is a more than $1.1 billion industry in Santa Cruz County. (Visit Santa Cruz, 2019) Average travel expenditures are more than $600 per trip or $150 per day. The average travel group size is five people, and the length of stay is 2.4 nights. Santa Cruz County tourism originates primarily from the San Francisco Bay Area and the Central Valley regions. (*Id.*)

Industries susceptible to deleterious effects of natural and human caused disasters include trade, transportation, and utilities; leisure and hospitality; farm; and mining, logging, and construction. Collectively, these three industries account for more than 38% of the jobs in Santa Cruz County and, if any one is disrupted by a major hazard event, it would have far-reaching impacts on the county-wide community.

1.4.5 Growth Trends

Understanding population, housing, and employment growth is essential for assessing hazard vulnerability and planning for long-term resilience in Santa Cruz County. Growth patterns influence where people live, how infrastructure is developed, and the extent to which new or existing development may be exposed to hazards such as flooding, wildfires, earthquakes, and coastal storms. The Association of Monterey Bay Area Governments (AMBAG) provides official long-range growth projections for the County and its four cities, which are used by local jurisdictions to guide land use and hazard mitigation planning. These projections, shown in Table 1-10 through Table 1-12, illustrate anticipated changes in population, housing, and employment between 2023 and 2050 and serve as a foundation for evaluating how future growth intersects with hazard-prone areas. Importantly, these trends must be considered within the framework of Measure J,

the County's voter-approved growth management policy, and the California Coastal Act, both of which shape where and how new development can occur.

As shown in Table 1-10, Santa Cruz County's total population is expected to grow by around 18,000 persons between 2023 and 2050. Most of the population growth is expected to occur in the City of Santa Cruz and is largely attributable to planned enrollment growth at the University of California Santa Cruz. Capitola is expected to add approximately 1,800 more people, Scotts Valley is anticipated to add over 1,300 people, and Watsonville is projected to add more than 1,400 people. The unincorporated county is shown as having a decline in population between 2023 and 2030 but then steadily growing again due to shifting age demographics.

Table 1-10: County-Wide Population Growth Projections

Jurisdiction	Projected Population					
	2023	2030	2035	2040	2045	2050
Unincorporated Santa Cruz County	128,159	126,990	127,679	127,747	128,139	128,568
City of Capitola	9,558	10,070	10,635	11,029	11,262	11,395
City of Santa Cruz	62,939	68,057	71,343	74,839	75,583	75,950
City of Scotts Valley	11,872	12,322	12,603	12,887	13,094	13,235
City of Watsonville	50,820	51,475	51,835	52,005	52,180	52,251
Santa Cruz County (Total)	**263,338**	**268,914**	**274,095**	**278,258**	**280,258**	**281,399**

Source: AMBAG, 2025



Figure 1-14: County-Wide Population Growth/Decline Projections

As shown in Table 1-11 and Figure 1-14, Santa Cruz County's total housing inventory is expected to grow by just under 13,000 dwelling units between 2023 and 2050. Capitola is expected to add approximately 1,200 dwelling units, Scotts Valley is anticipated to add just under 1,100 dwelling units, Watsonville is projected to add more than 1,900 dwelling units, and the unincorporated county is predicted to add more than 3,800 dwellings units. As with population, the City of Santa Cruz is expected to account for the most dwelling unit growth as a result of planned enrollment growth at the University of California Santa Cruz.

Table 1-11: County-Wide Housng Growth Projections

Jurisdiction	Projected Housing Units					
	2023	2030	2035	2040	2045	2050
Unincorporated Santa Cruz County	57,550	58,568	60,005	60,609	61,061	61,380
Capitola	5,507	5,887	6,242	6,491	6,634	6,715
Santa Cruz	24,415	26,441	27,499	28,295	28,918	29,267
Scotts Valley	4,994	5,400	5,643	5,844	5,988	6,088
Watsonville	14,699	15,524	16,000	16,331	16,523	16,642
Santa Cruz County (Total)	**107,165**	**111,820**	**115,389**	**117,570**	**119,124**	**120,092**

Source: AMBAG, 2025

As shown in Table 1-12, Santa Cruz County's total employment is expected to grow by more than 8,000 jobs between 2023 and 2050. Capitola is expected to approximately 500 jobs, Scotts Valley is anticipated to add more than 300 jobs, Watsonville is projected to add just under 1,700 jobs, and the unincorporated county is predicted to add more than 3,000 jobs.

Table 1-12: County-Wide Employment Growth Projections

Jurisdiction	Projected Jobs					
	2023	2030	2035	2040	2045	2050
Unincorporated Santa Cruz County	45,533	47,182	47,601	47,967	48,276	48,547
Capitola	12,169	12,485	12,559	12,622	12,662	12,689
Santa Cruz	43,059	44,196	44,649	45,062	45,417	45,737
Scotts Valley	10,206	10,447	10,484	10,504	10,517	10,525
Watsonville	28,125	29,061	29,234	29,456	29,637	29,804
Santa Cruz County (Total)	**139,092**	**143,371**	**144,527**	**145,611**	**146,509**	**147,302**

Source: AMBAG, 2025

Regional Housing Needs Allocation (RHNA)

The State of California requires every city and county to accommodate its share of housing need through the Regional Housing Needs Allocation (RHNA). For the Sixth Cycle (2023–2031), Santa Cruz County and its participating jurisdictions must collectively plan for 9,243 new housing units, distributed as shown in Table 1-13. Meeting these targets is critical for addressing housing needs, but it also requires careful consideration of hazard exposure.

Table 1-13: County-wide RHNA by Participating Jurisdiction

Jurisdiction	6th Cycle RHNA (2023–2031) Units
Unincorporated Santa Cruz County	4,634
City of Capitola	1,336
City of Scotts Valley	1,220
City of Watsonville	2,053
Total Allocated Units	**9,243**

Information from this MJHMP provides community development departments with data to evaluate the siting of future housing units, ensuring new construction avoids the most hazard-prone areas. Aligning RHNA implementation with hazard mitigation strategies not only supports the state's housing goals, but also advances long-term community resilience by reducing risk for future residents and protecting investments in affordable and market rate housing alike.

Growth Management

Santa Cruz County's growth is guided by Measure J, a voter-approved growth management policy adopted in 1978. Measure J established both an Urban Services Line (USL) and a Rural Services Line (RSL) to direct new development into incorporated cities and designated unincorporated communities (Figure 1-15). As a result, the majority of projected population, housing, and employment growth will occur within these service lines. The largest areas inside the USL and RSL include the Santa Cruz–Capitola urban area, Scotts Valley, and Watsonville, which continue to serve as the County's primary growth centers.

Coastal Development

Development in coastal areas is further shaped by the California Coastal Act, which applies to lands within the Coastal Zone (Figure 1-15) and is subject to review by the California Coastal Commission. The Act prioritizes land uses that are dependent on the coast, such as fishing, marine industries, and visitor-serving commercial activities, while restricting development that is not coastal-related. It also places strong emphasis on the preservation of environmentally sensitive habitats. These requirements place additional limits on growth along the coast and help direct new development away from areas that are highly vulnerable to coastal hazards.

Past Development Trends

The past development that most increased hazard risk in Santa Cruz County occurred many decades ago, when homes and infrastructure were constructed without the benefit of modern seismic, flood, and wildfire safety standards. Much of this older housing stock remains in place today, particularly in unincorporated areas, and continues to shape the county's vulnerability profile. In recent decades, however, growth has taken place under a stronger framework of federal, state, and local regulations that require consideration of hazard risk in land use and construction. This has generally reduced the exposure of new development to the most hazardous areas.

Figure 1-15 illustrates where the most recent construction has occurred in the unincorporated county over the last 10 years over based upon assessors' data. The highest concentrations of new development are located along the urban edge near Capitola and Live Oak, with smaller pockets of growth extending inland toward Scotts Valley and the San Lorenzo Valley. Additional development pressure is evident in the Watsonville area, although growth there has been moderated by agricultural land preservation policies.

These patterns confirm that while most hazard-prone areas were established decades ago, new development is subject to far more rigorous planning, zoning, and building standards that significantly reduce exposure to hazards. Current growth along the coast and at the wildland-urban interface is generally safer than past construction, but it still requires careful planning to ensure long-term resilience. Although the county is not experiencing widespread sprawl into the most hazardous areas, the concentration of new housing in already dense coastal and foothill communities underscores the importance of continued investments in infrastructure resilience, defensible space, and public education, as well as the retrofit and maintenance of older structures that remain at higher risk.



Coastal Zone and Urban and Rural Services Line

Source: Santa Cruz County

Figure 1-15: County Coastal Zone and Urban and Rural Services Lines



10 Year Parcel Development Density

Unincorporated County**

*Data sources: Santa Cruz County Parcels Year Built.
**DOES NOT Include Parcel Data within Annexed Jurisdictions

PARCEL DEVELOPEMENT DENSITY

LOW — HIGH

Figure 1-16: Unincorporated County 10 Year Parcel Development Density

1.5 What's New

This section offers an overview of the previous hazard mitigation planning efforts for the planning area and highlights the updates made in this 2025 MJHMP. Mitigation actions from the county's 2021 plan, as well as earlier plans from other jurisdictions, were carefully reviewed, updated, and revised to reflect the new priorities established in this update. Only relevant information and accurate data from the earlier plans were incorporated into the current version.

The following sections describe the comprehensive review and update processes undertaken. The 2025 Santa Cruz County MJHMP profiles ten county-wide hazards, revised from those profiled in the county's 2021 plan.

Wildfire
SECTION 3.2.1

Flood
SECTION 3.2.2

Earthquake
SECTION 3.2.3

Severe Weather
SECTION 3.2.4

Coastal Hazards
SECTION 3.2.5

Slope Failure
SECTION 3.2.6

Dam Failure
SECTION 3.2.7

Drought
SECTION 3.2.8

Extreme Heat
SECTION 3.2.9

Climate Change
SECTION 3.2.10

1.5.1 Background: 2021 vs. 2025

In 2021, Santa Cruz County successfully met all approval requirements outlined in DMA 2000, Title 44 CFR § 201.6, and California SB 379 before officially adopted its 2021 HMP. This plan has been updated from the earlier plan and incorporated elements from the Santa Cruz County 2020 General Plan and other long-range planning mechanisms, as well as those of other participating jurisdictions. Guided by input from hazard mitigation stakeholders, several improvements were implemented for the 2025 update, including:

- **Enhanced Partnerships:** The 2025 plan marks Santa Cruz County's first Multi-Jurisdictional Hazard Mitigation Plan (MJHMP), developed in collaboration with the cities of Capitola, Scotts Valley, and Watsonville, as well as several special districts and local agencies. This broader partnership reflects the reality that hazards cross-jurisdictional boundaries and establishes a stronger foundation for coordinated action.

- **Focused on Priority Hazards:** The hazard mitigation planning teams and key stakeholders continued to prioritize natural hazards over human-caused ones for the 2025 MJHMP update and to exclude soil expansion since it is adequately mitigated by adherence to local building codes.
- **Assessed Local Mitigation Progress:** The 2025 update review progress made in local mitigation efforts since the adoption of previous plans, ensuring continuity and identifying areas for improvement.
- **Incorporated Climate Change and Adaptation:** While the 2021 Local Hazard Mitigation Plan (LHMP) incorporated climate change considerations, the 2025 MJHMP update has been carefully aligned with the latest FEMA and California Office of Emergency Services (Cal OES) guidelines, which emphasize the integration of climate change considerations into hazard mitigation planning. Given the increasing impact of climate change on natural hazards, the updated plan includes comprehensive strategies to address these evolving risks and ensures that climate adaptation and resilience measures are prioritized. This includes assessing the potential impacts of climate change on the frequency and intensity of hazards such as wildfires, floods, and severe weather. The plan also identifies vulnerable populations and critical infrastructure that may be disproportionately affected by climate-related events.
- **Aimed for State and Local Funding:** The plan update acknowledges recent changes in federal funding mechanisms for hazard mitigation by re-aligning the strategy to also target more state and local sources.

These updates reflect a strategic approach to focus resources on the most critical natural hazard threats facing Santa Cruz County while leveraging collaborative efforts and monitoring progress to enhance community resilience and hazard preparedness.

Participating Jurisdictions

This 2025 MJHMP represents the very first joint hazard mitigation planning effort conducted by the county and other local jurisdictions. Some of the participating jurisdictions had existing hazard mitigation plans from previous years. Although many of the jurisdictions have played the role of key stakeholder in past planning efforts, this MJHMP is their first adopted plan. Table 1-14 tracks local jurisdictions that participated in this 2025 MJHMP (or that may participate in the future) and notes the adoption year of their current or previous plan.

Table 1-14: Participating Jurisdictions Tracker

2025 MJHMP Participating Jurisdiction	Previous / Current Plan Year
Local Governments	
Santa Cruz County	2021
City of Capitola[1]	2020
City of Scotts Valley	-
City of Watsonville[1]	2020
Special Districts and Agencies	
Soquel Creek Water District	-
Scotts Valley Water District	-
Pajaro Valley Water Management Agency	-
Resource Conservation District of Santa Cruz County	-
Santa Cruz Port District	-
Cabrillo College[1]	2020

[1] – Jurisdiction previously developed its own stand-alone hazard mitigation plan. With this update cycle, stand-alone plans are being discontinued, and jurisdictions will instead recognize and adopt the Santa Cruz MJHMP.

1.5.2 Mitigation Activities

During the 2025 update process, all mitigation actions from jurisdictions' previous hazard mitigation plans or other organized efforts underwent a thorough review to assess their relevance and potential for future implementation. Each action was evaluated based on its feasibility and alignment with current priorities. Some actions were deemed integral to the MJHMP update process or lacked sufficient detail for local implementation, resulting in their exclusion from this update. Additionally, significant changes were made to other mitigation actions based on updated risk assessments, expanded detail, or adjustments to implementation strategies reflecting current practices or community priorities.

Adjustments to existing mitigation actions that are ongoing or pending from previous plans and remain pertinent are included alongside newly identified actions in the mitigation action plans, including the county's action plan in Table 4-1 and Table 4-2. For the county's previous actions, TABLE contains more specific status updates.

Information regarding mitigation actions specific to other participating jurisdictions can be found in their jurisdictional annex in Volume 2.

Figure 1-17: CruzAware

Source: Santa Cruz County

1.5.2.1 County-Wide Successes Since 2021

The guiding principles, goals, objectives, and many of the mitigation actions outlined in previous hazard mitigation plans have been effectively implemented through ongoing projects, programs, and planning efforts. These successful mitigation activities have resulted in substantial reductions in hazard risks to life and property and significantly enhancing overall emergency response capacity. This section highlights exemplary policies, programs, and projects specific to Santa Cruz County that have achieved notable risk reduction or enhanced hazard resiliency.

CruzAware Alert and Notification System

Santa Cruz County launched CruzAware in 2023 to enhance emergency communication capacity (Figure 1-17). CruzAware is a modern community alert platform developed with Santa Cruz Regional 9-1-1 to replace the outdated CodeRED system. The platform has improved message delivery, accessibility, and public engagement for both emergency and non-emergency notifications.

New Grants & Grant-Funded Projects

Since 2021, Santa Cruz County has advanced a wide range of initiatives through new grant awards and funding partnerships that directly support hazard mitigation, climate adaptation, and community resilience. These investments reflect the County's proactive approach to securing external resources to address local needs and strengthen long-term capacity.

In 2021, the county also advanced drinking water equity and resilience through the Safe and Affordable Funding for Equity and Resilience program and the California Department of Water Resource's Urgent Drinking Water Grant. Administered by the Environmental Health Department, these funds have supported

household water quality testing, bottled water assistance, and treatment device distribution, as well as the creation of a comprehensive Geographic Information System (GIS) database of private wells and targeted outreach for underserved communities. Additional recent funding sources include:

- **County Coordinator Program (California Fire Safe Council / CAL FIRE):** which strengthened local partnerships, expanded emergency preparedness outreach, and addressed barriers to scaling wildfire fuel reduction.
- **Emergency Watershed Protection Program (EWPP):** administered by the Natural Resources Conservation Service (NRCS), which has funded streambank stabilization projects following the 2023 atmospheric river storms.
- **Hazard Mitigation Grant Program (HMGP):** award supporting evacuation route fuels treatment, reducing wildfire risk along key corridors.
- **Building Resilient Infrastructure and Communities (BRIC):** Phase 1 award, which is supporting early design and permitting for wildfire risk reduction.

In the area of sanitation and water infrastructure, the County has also implemented multiple grant-funded projects for the Davenport Sanitation District—a special district within the Community Development and Infrastructure (CDI) Department's Public Works Special Services Division. While this and other special districts under county jurisdiction did not formally participate in this MJHMP, they were represented on the county's Planning Team and their infrastructure is included in the county's critical infrastructure inventory as a part of the Risk Assessment. None of the districts would be direct applicants to HMA; rather, the county functions as a fiscal sponsor and direct Cal OES subapplicant.

Two significant water projects were recently completed in Davenport:

- The **Davenport Water Storage Tank Project**, funded with a $3.4 million grant, constructed two storage tanks providing 720,000 gallons of treated water storage.
- The **Davenport Water Tank Rehabilitation Project**, funded with a $556,000 Department of Water Resources grant, repaired an existing tank and added new process piping to provide 135,000 gallons of backup raw water storage for treatment.

Looking ahead, a $405,000 Proposition 1 grant administered by the Integrated Regional Water Management program will partially fund a project in 2026 to replace the deteriorated 50,000-gallon Equalization Tank at the Boulder Creek wastewater treatment plant with a tank with over twice the storage capacity.

Storm Monitoring System

To strengthen flood preparedness and watershed resilience, the Santa Cruz County Flood Control and Water Conservation District made improvements to its storm monitoring system. The system includes 18 District-maintained rain and/or stream monitoring sites, a flooded road warning system at Beach and Shell Roads, an X-band radar sensor, and the OneRain platform, which provides real-time flood data from District- and partner-maintained monitoring sites to emergency managers and the public.

Key improvements included the integration of several additional partner-maintained monitoring sites into OneRain in 2020 and 2021, enhancing debris flow awareness after the CZU fires. In 2022, the X-band radar was installed and was utilized by emergency managers during the 2022–2023 storm season. Additionally, and in support of monitoring efforts for the 2022-2023 storms, staff developed several new dashboards within the OneRain platform to visualize rainfall and stream levels in real-time. In 2023, the District partnered with United States Geological Survey (USGS) to reactivate the Aptos Creek station in Nisene Marks State Park, now delivering real-time stream data annually from October through April.

Situational Awareness for Emergency Response (S.A.F.E.R)

Santa Cruz County's S.A.F.E.R. (Situational Awareness for Emergency Response) is a dynamic, all-hazards situational awareness tool built by the county's GIS team. It integrates real-time data feeds from ArcGIS Online, web links, and social media platforms into a unified, interactive dashboard designed to support emergency managers, first responders, and the public with timely and actionable information. Embedded within the County's Emergency Operations Plan, the S.A.F.E.R. application helps stakeholders monitor evolving conditions during disasters such as storms, floods, and wildfires in Santa Cruz County.

Newell Creek Pipeline Project

The City of Santa Cruz is advancing a significant infrastructure project to enhance water supply reliability by relocating a 3.7-mile section of the aging Newell Creek Pipeline. Originally constructed in 1960, this 18- to 27-inch diameter pipeline conveys water from the Loch Lomond Reservoir to the Graham Hill Water Treatment Plant and has become increasingly vulnerable to storm damage, particularly within Henry Cowell Redwoods State Park (Figure 1-18). To address this, the pipeline will be rerouted under Graham Hill Road using a new 24-inch diameter pipe to avoid environmentally sensitive areas and reduce geologic risks. Construction is slated to begin in 2025 and is expected to extend over approximately two years.

Figure 1-18: Erosion Around the Newell Creek Pipeline

Source: Santa Cruz County

The City of Santa Cruz serves 100,000 customers, including residents of the unincorporated area, and the project includes interties with neighboring water agencies, which will enhance resilience for the county-wide water resources portfolio.

Pajaro River at Watsonville Project

In March 2023, a levee breach along the Pajaro River inundated nearly 300 homes, displacing residents in Pajaro and causing widespread damage in surrounding agricultural areas. Recognizing the need for enhanced flood protection in the Pajaro Valley, federal, state, and local agencies launched the Pajaro River at Watsonville Project in 2021, a nearly 14-mile levee improvement effort managed by the U.S. Army Corps of Engineers in partnership with the Pajaro Regional Flood Management Agency. (This agency is discussed in detail in Section 3.2.2) With an estimated cost of $600 million, the project is fully funded and will strengthen flood protection for Watsonville, Pajaro, and nearby farmlands. Construction began in 2024 and is expected to continue into the next decade, with initial work focused on Corralitos Creek—the most at-risk reach of the river. Until the new system is complete, however, the Pajaro Valley remains vulnerable to flooding during major storm events. Ongoing operations and maintenance of the levee system is funded by Pajaro Regional Flood Management Agency (PRFMA) member agencies and community assessments.

1.5.2.2 Plan Integration

Plan integration is the process of linking hazard mitigation strategies and data with other local and regional planning mechanisms, such as general plans, capital improvement programs, emergency operations plans, and regulatory codes. A planning mechanism refers to any policy, plan, program, or regulatory tool that guides development, land use, infrastructure, or emergency management. By weaving hazard mitigation into these tools, communities ensure that risk reduction becomes part of everyday decision-making rather than a stand-alone effort.

For Santa Cruz County, the 2021 Local Hazard Mitigation Plan (LHMP) has already been used to inform and strengthen a variety of planning mechanisms. Hazard background information, risk mapping, and exposure analysis have been incorporated into updates of land use policies, infrastructure planning, and emergency management procedures. This integration demonstrates progress toward reducing vulnerability and highlights how hazard mitigation is becoming a cross-cutting element of County planning. The following list provides specific examples of how the 2021 MJHMP was incorporated into other planning mechanisms and which components were most often applied:

- **2022 Santa Cruz County Climate Action and Adaptation Plan:** Climate change-driven hazards risk assessment, vulnerabilities, potential impacts, and mitigation strategy.
- **2023 Santa Cruz County General Plan Housing Element:** Hazard risk assessments, vulnerabilities, and potential impacts affecting housing development and security.
- **2022 San Mateo-Santa Cruz County Community (CZU) Wildfire Protection Plan:** Wildfire hazard risk assessment, vulnerabilities, potential impacts, and mitigation strategy. A plan update will begin in 2026.

This 2025 MJHMP will similarly be incorporated into local and regional planning documents, such as the general and capital improvement plans of participating jurisdictions. For example, the plan will be referenced in and used to help update the Santa Cruz County General Plan Public Safety Element as well as the county's Climate Action and Adaptation Plan.

Section 3.5.1 in Volume 1 outlines county planning mechanisms that have been and will be integrated with the MJHMP and the process for such integration in more detail. Each jurisdictional annex in Volume 2 also describes which planning mechanisms that jurisdiction has been integrating and will integrate with the updated plan, as part of its capabilities assessment.

1.5.3 New Tools & Risk Assessment Methodology

Santa Cruz County strengthened this plan by using new research methods and web-based information systems. Geographic Information Systems (GIS) mapping and analysis provided participating jurisdictions with the tools to develop more comprehensive data sets than those used in previous planning efforts. A web-based mapping tool, called the Risk Assessment Mapping Platform (RAMP), was used to assist and engage the planning teams in this analysis through a highly interactive approach. In addition, an application called the Mitigation Action Support Tool (MAST) was also used to record, update, and track described vulnerabilities (referred to herein as "problem statements") and to create associated mitigation actions. See Sections 2.2 and 2.3 for more information about the new tools and methodology used in developing the mitigation plan and strategy, including RAMP and MAST.

Section 2. Planning Process

This section outlines each stage of the planning process used in the development of this MJHMP. The planning process serves as the framework for document creation and adheres to FEMA's recommended four-step hazard mitigation planning approach.

It is essential to recognize that the MJHMP is a dynamic, living document shaped by community engagement. The participatory planning process holds equal importance to the finalized plan itself, fostering community awareness and ensuring that mitigation efforts are integrated into everyday decision-making processes.

The Robert T. Stafford Disaster Relief and Emergency Assistance Act, as amended by the Disaster Mitigation Act of 2000 (DMA 2000) (42 USC § 5165), mandates the development of hazard mitigation plans to mitigate the impact of natural disasters. These plans are prerequisites for certain non-emergency disaster assistance through FEMA's Hazard Mitigation Assistance (HMA) programs, with regulatory guidance provided in 44 CFR § 201.6 *et seq*.

FEMA outlines the following four major planning steps:

- **Step 1:** Organize Resources
- **Step 2:** Assess Risk
- **Step 3:** Develop a Mitigation Strategy
- **Step 4:** Adopt and Implement the Plan

Santa Cruz County and all other participating jurisdictions adhered to this FEMA four-step planning process and added two additional steps, modeling the process on FEMA's HMP guidelines. The resulting six-phase planning process shown in Figure 2-1 was followed for the development of the 2025 MJHMP. In conjunction with and supplementary to the four-step process, Santa Cruz County and the City of Watsonville conducted the 10-step planning process pursuant to Community Rating System (CRS) program requirements. These additional steps are further described in the county's Flood Hazard Profile (Section 3.2.2) and the city's jurisdictional annex in Volume 2 of this plan.



Figure 2-1: Planning Process Breakdown

Multi-Jurisdictional Planning Process

Multi-jurisdictional hazard mitigation planning offers many benefits, such as increased coordination and efficiency in planning and implementation efforts. At the same time, each jurisdiction has specific hazards and specific mitigation actions that must be individually addressed. This MJHMP balances the benefits of a comprehensive, coordinated approach to hazard mitigation with the specific realities of individual participating jurisdictions. Multi-jurisdictional plans are contemplated under FEMA regulations at 44 CFR § 201.6(4).

While Volume 1 of this MJHMP documents the overall planning process, county-wide elements of the plan, and Santa Cruz County-specific information, Volume 2 documents each participating jurisdiction's unique hazards, assessment of vulnerabilities and capabilities, and mitigation strategy in a stand-alone annex. Each jurisdictional annex was created following the same planning process Santa Cruz County followed, as detailed in this section.

STEP 1: Organize Resources

The first step of the MJHMP planning process was organizing resources, consisting of engaging a wide range of stakeholders with local expertise, conducting extensive community outreach and engagement, reviewing relevant existing documents, and gathering and organizing information. Santa Cruz County and the other participating jurisdictions, assisted by the Consultant Team, used a highly interactive and comprehensive approach in organizing their available resources to ensure that this MJHMP is a living document and will evolve with community needs and priorities. Being flexible in this way will enhance the plan's effectiveness in mitigating local hazards and building resilience in communities across the county.

These various resources are summarized and organized in the following sections of the plan:

- **People and Expertise:** Section 2.1.1
- **Public and Stakeholder Engagement:** Section 2.1.2 and Appendix B
- **Planning Process Library:** Section 2.1.3

STEP 2: Assess the Risk

In accordance with FEMA requirements, the county-wide Hazard Mitigation Planning Team and each of the jurisdictional planning teams identified and prioritized the natural hazards affecting Santa Cruz County as a whole and each participating jurisdiction individually and assessed the vulnerabilities to those identified hazards. Results from the risk assessment aided subsequent identification of appropriate mitigation actions. The real substance of the risk assessment is found in Section 3, with supplemental jurisdiction-specific assessments provided in the annexes of Volume 2.

Figure 2-2: Members of the County-Wide HMPT Engaged in Mitigation Strategy Development

The process and support tools used, and the results of the assessment, are described in the following sections:

- **Priority Hazards:** Section 3.1
- Vulnerabilities to Specific Hazards (Hazard Profiles): Section 3.2
- **Vulnerability Assessment Methodology:** Section 2.2.2 and Appendix A
- **RAMP (Risk Assessment Mapping Platform):** Section 2.2.1

STEP 3: Develop a Mitigation Strategy

The MJHMP was prepared in accordance with DMA 2000 plan update requirements, the California Office of Planning and Research (OPR), and FEMA's mitigation planning guidance. This document provides an explicit strategy and blueprint for reducing potential losses identified in the risk assessment based on existing authorities, policies, programs and resources, and participating jurisdictions' abilities to expand on and improve these existing tools. MJHMP development included identifying goals, assessing existing capabilities, reviewing the 2021 MJHMP goals, and identifying new mitigation actions. The substance of the mitigation strategy is detailed in 3.4.4 of Volume 1 for Santa Cruz County and in the Volume 2 jurisdictional annexes for all other participating jurisdictions.

This process, the tools used to support it, and the county results are found in the following sections of Volume 1:

- **Hazard Problem Statements:** Sections 2.3.1 and 3.2 (within each Hazard Profile)
- **Mitigation Goals:** Sections 2.3.2 and 4.1
- **Assessment of Current Capabilities and Future Opportunities:** Sections 2.3.3 and 3.4.4
- **Mitigation Action Plan:** Sections 2.3.4 and 0
- **Mitigation Action Support Tool (MAST):** Section 2.3.4.4

STEP 4: Adopt & Implement the Plan

Once the risk assessment and mitigation strategy were completed, information, data, and associated narratives were compiled into the MJHMP. The following sections describe the finalization, adoption, implementation, and update processes for the plan:

- **Adoption Proceedings:** See Executive Summary
- **Monitoring, Evaluating, and Updating:** Section 2.4.1
- **Plan Integration:** Section 2.4.2

2.1 Organizing Resources

Santa Cruz County and other participating jurisdictions organized local people and expertise into four main levels and engaged stakeholders throughout the planning process. At the forefront of this effort was the Steering Group, with support from a Consultant Team and county-wide Hazard Mitigation Planning Team (HMPT), as well as the individual jurisdictions' planning teams. In addition, Santa Cruz County engaged with a wide variety of stakeholders and members of communities across the county to inform the development of this 2025 MJHMP. Some participating jurisdictions delegated most outreach efforts to the county while others chose to conduct additional public and stakeholder engagement activities on their own. A summary of the county's public and stakeholder engagement strategy and the results thereof are provided in Section 2.1.2 and documented in Appendix B.

2.1.1 People & Expertise

Organizing the people and expertise needed to develop this MJHMP was implemented by the Steering Group for this plan, which consisted of at least one lead contact for each participating jurisdiction. A six-step stakeholder engagement strategy was used to conduct this complex process within the larger organization task, as detailed in Section 2.1.2. Part of this engagement strategy included inviting neighboring jurisdictions and other regulatory agencies to share information and to discuss public safety and hazard mitigation concerns and priorities in a variety of capacities. Non-governmental stakeholders within the community, such as business leaders, civic groups, academia, non-profit organizations, major employers, and other interested parties, were also invited to participate. While engagement with some of these stakeholders and the general public is described and documented in Section 2.1.2 and Appendix B, this section discusses those stakeholders who took an active and vital role in shaping this MJHMP from beginning to end.

In addition to the Steering Group, the development of this plan involved a county-wide HMPT, ten smaller jurisdictional planning teams (one for each participating jurisdiction), many Key Stakeholders, and a Consultant Team that facilitated and documented the process. All the members of these groups are listed in Table 2-3 through Table 2-5 at the end of this section.



Steering Group

The Steering Group was at the core of the MJHMP planning process and was integral to ensuring its success. This group consisted of staff-level leadership and decision-makers from each participating jurisdiction and worked closely with the Consultant Team throughout the development of this MJHMP, providing direction on the process and major plan components, including public and stakeholder engagement and the plan's future implementation and maintenance. Members of the Steering Group are listed in Table 2-3 and also doubled as members of the planning teams, which are discussed below and in the individual annexes in Volume 2.

Planning Teams

The development of this MJHMP was heavily influenced by the county-wide Hazard Mitigation Planning Team (HMPT or "Planning Team") as well as the smaller, internal planning teams of individual jurisdictions (e.g., City of Capitola Planning Team). These teams consisted of members of the Steering Group, jurisdictional staff, and other stakeholders with specific local expertise to contribute to the planning process from each participating jurisdiction. Planning team members represented public and private organizations within and adjacent to Santa Cruz County that possess knowledge about and regulatory authority over local public safety, development, and hazard conditions, issues, and priorities. They also served as data stewards and liaisons to the greater community.

Planning team members were chosen for their relevant expertise to develop a deeper understanding of hazard vulnerabilities, vulnerable and special needs populations, jurisdictional capabilities, and overall hazard perceptions across the planning area. Each planning team member was responsible for

communicating the direction and status of the planning effort to respective departments and constituents of each jurisdiction and was expected to represent the perspectives of their jurisdiction on the county-wide HMPT. Table 2-3 provides a list of the county-wide HMPT members. The planning team members for each participating jurisdiction are provided in their respective Volume 2 annex. The responsibilities of the HMPT and jurisdictional planning team members generally included:

- Participation in four structured HMPT meetings
- Participating in two jurisdiction-specific breakout meetings
- Contribution of detailed information and assisting in fulfilling data requests, when appropriate
- Input during the hazard selection and prioritization process
- Development of the county-wide and jurisdictional mitigation strategies
- Review and comment on administrative drafts of the plan
- Coordination and promotion of community and stakeholder engagement efforts

Steering Group & Planning Team Meetings

The Steering Group, HMPT, and individual jurisdictional planning teams met throughout the development of the 2025 MJHMP, including a kickoff meeting, four county-wide team meetings, two series of jurisdictional breakout meetings, and a pre-public draft release check-in facilitated by the Consultant Team. Table 2-1 provides details of the county-wide Steering Group and HMPT meetings, including dates, topics discussed, and input goals.

County breakout meetings are summarized in Table 2-2, and details of other jurisdictional breakout meetings are located in the annexes of Volume 2. In addition to the two breakout meetings facilitated by the Consultant Team, the Santa Cruz County Planning Team also conducted a series of focus area breakout meetings, building upon Breakout Meeting #2 to further develop their mitigation strategy. These focus areas included climate resilience, water resources, fire and law enforcement, and public infrastructure.

Meeting documentation, including agendas, sign-in sheets, hazard maps, PowerPoint presentations, minutes, and other relevant handouts, are provided in Appendix B. Not all HMPT members necessarily attended all group meetings; some participated by reviewing draft documents or assisting in individual jurisdictional vulnerability assessments, with public outreach, or at other stages of the process.

Table 2-1: County-Wide Steering Group and Planning Team Meetings

Meeting & Date	Agenda / Topics	Goals / Key Inputs
County-Wide Steering Group Kickoff Meeting December 13, 2024	▪ Welcome and introductions ▪ Review roles and responsibilities ▪ Review project schedule and scope of work ▪ Review expectations of Steering Group, county-wide HMPT, and jurisdictional planning teams	▪ Shared project understanding ▪ Confirm roles and responsibilities

Meeting & Date	Agenda / Topics	Goals / Key Inputs
County-Wide HMPT Meeting #1 January 27, 2025	▪ Welcome and introductions ▪ Hazard mitigation background and basic information ▪ Overview of funding opportunities ▪ Review of previous county plan and changes ▪ Mitigation successes in past 5 years ▪ Community engagement strategy ▪ Project schedule and expectations	▪ Shared project understanding ▪ Confirm roles and responsibilities ▪ Success stories ▪ Data requests
County-Wide HMPT Meeting #2 March 27, 2025	▪ Meeting #1 takeaways ▪ Community engagement progress and results ▪ Review of previous county plan mitigation goals and strategy ▪ Exercise #1: Risk Assessment (review of county-wide hazard risks and exposure and vulnerable populations) ▪ Introduction to Risk Assessment Mapping Platform (RAMP) ▪ Exercise #2: Hazard Prioritization (discussion of county-wide priority hazards and concerns) ▪ Project schedule, updates, and prep for Breakout Meetings Series #1	▪ Identify county-wide hazard problems and areas of concern ▪ Identify and prioritize county-wide hazards ▪ Community engagement volunteers
Jurisdictional Planning Team Breakout Meetings Series #1 April – May 2025		
County-Wide HMPT Meeting #3 June 2, 2025	▪ Meeting #2 and Breakout Meetings Series #1 summary and findings ▪ Community engagement progress and results ▪ Alignment of county-wide mitigation strategy with updated risk assessment and community input ▪ Exercise #2: Hazard Prioritization (finalization of county-wide priority hazards) ▪ Project schedule, updates, and prep for Breakout Meetings Series #2	▪ Consensus on plan goals ▪ Identify county-wide mitigation actions ▪ Community engagement volunteers
Jurisdictional Planning Team Breakout Meetings Series #2 July – August 2025		
County-Wide HMPT Meeting #4 August 4, 2025	▪ Meeting #3 and Breakout Meetings Series #2 summary and findings ▪ Exercise #5: Strategy Development (discussion of collaboration opportunities and county-wide mitigation actions) ▪ Plan maintenance and implementation discussion ▪ Project schedule, updates, and next steps	▪ Consensus on priority county-wide hazard problems ▪ Identification of collaborative county-wide mitigation actions ▪ Consensus on plan maintenance and implementation

Meeting & Date	Agenda / Topics	Goals / Key Inputs
County-Wide Steering Group Check-In Meeting September 22, 2025	▪ Schedule updates ▪ Administrative draft feedback ▪ Final public survey results ▪ Mitigation action prioritization framework ▪ County-wide mitigation strategy ▪ Public draft review and Cal OES submission	▪ Consensus on strategy alignment with public feedback ▪ Consensus on prioritization criteria ▪ Consensus on county-wide strategy

Table 2-2: Santa Cruz County Breakout Meetings

Meeting & Date	Agenda / Topics	Goals / Key Inputs
County-Wide Steering Group and HMPT Meetings #1 & #2 January 27, 2025 – March 27, 2025		
SCC Planning Team Breakout Meeting #1 May 7, 2025	▪ County-wide HMPT meetings #1 and #2 recaps ▪ Community engagement progress and results ▪ Risk assessment and community vulnerability ▪ Demographics and vulnerable populations ▪ Overview of jurisdiction-specific hazard risks and exposure ▪ Introduction to Risk Assessment Mapping Platform (RAMP) ▪ Jurisdiction-specific hazard risk ranking exercise ▪ Project schedule updates and next steps	▪ Consensus on jurisdiction-specific priority hazards ▪ Identify capabilities and potential mitigation actions ▪ Community engagement volunteers
County-Wide HMPT Meeting #3 June 2, 2025		
SCC Planning Team Breakout Meeting #2 July 30, 2025	▪ Breakout Meeting #1 and HMPT #3 recaps ▪ Review capabilities assessment ▪ Review areas of concern and define problem statements ▪ Principles of effective mitigation strategies and actions, and mitigation alternatives ▪ Refine and align jurisdiction-specific mitigation actions exercise ▪ Project schedule updates and next steps	▪ Consensus on jurisdiction-specific capabilities ▪ Consensus on jurisdiction-specific areas of concern ▪ Consensus on priority mitigation actions and collaboration opportunities ▪ Community engagement volunteers
County-Wide HMPT Meeting #4 August 4, 2025		
SCC Planning Team Breakout Meeting #2.5: Climate Resilience, Parks & Facilities Focus August 13, 2025	▪ Continuation of Breakout Meeting #2 work ▪ Mitigation strategy development specifically for climate resilience, parks, and facilities	▪ Strategy development for focus area

Meeting & Date	Agenda / Topics	Goals / Key Inputs
SCC Planning Team Breakout Meeting #2.5: Water Resources & Planning Focus August 13, 2025	▪ Continuation of Breakout Meeting #2 work ▪ Mitigation strategy development specifically for water resources and planning	▪ Strategy development for focus area
SCC Planning Team Breakout Meeting #2.5: Fire, Law & Communications Focus August 14, 2025	▪ Continuation of Breakout Meeting #2 work ▪ Mitigation strategy development specifically for fire, law enforcement, and communications	▪ Strategy development for focus area
SCC Planning Team Breakout Meeting #2.5: Stormwater, Wastewater & Roads Focus August 20, 2025	▪ Continuation of Breakout Meeting #2 work ▪ Mitigation strategy development specifically for stormwater, wastewater, and roads	▪ Strategy development for focus area

Key Stakeholders

Key Stakeholders serve as liaisons to the greater community outside of the Steering Group and planning teams. These are people representing local, regional, state, and federal agencies involved in hazard mitigation or with the authority to regulate development, such as neighboring jurisdictions. Also included were representatives of local businesses, academia, community-based organizations and non-profits, and members of the public. Outreach with Key Stakeholders consisted of email correspondence, informal interviews, and community events, which covered topics such as basic project information, primary hazard concerns and front-line experience, needs and challenges of vulnerable populations, coordinating engagement events, and advertising for the project. Organizations and individuals involved in the planning process as Key Stakeholders are listed in Table 2-4.

Many of the Key Stakeholders engaged represent agencies and organizations that support underserved communities and vulnerable populations, providing channels to those who are often most impacted by hazard events and with the least resources for disaster preparedness, response, or recovery. In particular, Key Stakeholders offered opportunities to engage with community members through known and trusted networks and voices, ensuring that people in all corners of the county and from all backgrounds were provided with opportunities to influence the 2025 MJHMP and mitigation strategy. Key Stakeholders were engaged by Santa Cruz County and the Consultant Team on behalf of each participating jurisdiction at various points during the planning process. These efforts and the findings thereof are summarized in Section 2.1.2 and documented in Appendix B.

Consultant Team

Santa Cruz County enlisted Dynamic Planning + Science (DP+S) as the Consultant Team to assist in the development of the 2025 MJHMP. DP+S was chosen based on its extensive experience and expertise in helping public sector entities with developing hazard mitigation plans. DP+S staff facilitated the planning process from start to finish, collected and analyzed local data, produced materials for and conducted meetings and public engagement events, and developed drafts of the MJHMP for review. The Consultant Team members are listed in Table 2-5 and consisted of a variety of hazard mitigation, data analysis, and certified planning professionals.

Table 2-3: Members of Steering Group and All Planning Teams

Note: Jurisdiction leads in the Steering Group are presented in light blue rows with bold names.

Name	Title	CRS Expertise	Department
Cabrillo College			
Julia Charles	Director, Federal/State Emergency Grants	Emergency Management/Public Safety	President's Office
Luis Toledo	Assistant Director	Public Works/Drainage	Facilities Plan & Plant Operations
Brian Gallagher	Environmental Health & Safety Manager	Environmental Protection/Public Health	Cabrillo College
City of Capitola			
Jessica Kahn	Public Works Director	Public Works/Drainage	Department of Public Works
Katie Herlihy	Community Development Director	Planning/Zoning	Community Development Department
Chloe Woodmansee	Assistant to the City Manager	Public Information	City Manager
Eric Martin	Building Official	Building/Code Enforcement	Community Development Department
Jamie Goldstein	City Manager	Elected Official	City Manager
Jorge Melgoza	Building Services Tech	Building/Code Enforcement	Community Development Department
Matt Kotila	Operations Maintenance Supervisor	Public Works/Drainage	Department of Public Works
Nikki Bryant	Director	Parks and Recreation	Community Services and Recreation
Robin Woodman	Building Official	Building/Code Enforcement	
Sarah Ryan	Chief of Police	Emergency Management/Public Safety	Police Department
City of Scotts Valley			
Carly Blanchard	Senior Administrative Analyst	Public Works/Drainage	Public Works Department
Mindy Esqueda	Senior Administrative Analyst	Public Works/Drainage	Public Works

Name	Title	CRS Expertise	Department
Rodolfo Onchi	Public Works Director/City Engineer	Engineering/Public Works	City of Scotts Valley
Brian Froelich		Emergency Management/Public Safety	
Erin Collins	Interim Deputy Fire Marshal	Emergency Management/Public Safety	Scotts Valley Fire Protection District
Jayson Rutherford	Captain	Public Works/Drainage	Police Department
Jeremy Long	Wastewater Division Manager	Planning/Zoning	Public Works
Josh Wozynski	Associate Planner	Elected Official	Planning
Mali LaGoe	City Manager	Public Works/Drainage	
Matthew Spencer-Cooke	Maintenance Division Manager	Building/Code Enforcement	Public Works
Nelson Alfaro	Building Official	Planning/Zoning	Building Department
Taylor Bateman	Community Development Director	Public Works/Drainage	Community Development
City of Watsonville			
Courtney Lindberg	Public Works Director	Public Works/Drainage	Public Works & Utilities Department
Leslie Rios	Environmental Project Manager	Environmental Protection/Public Health	
Toto Vu-Duc	Environmental Projects Manager	Environmental Protection/Public Health	Public Works & Utilities
Brian Fulgoni	Police Captain	Emergency Management/Public Safety	Watsonville Police Department
Charles Hanley	GIS Coordinator	Public Information	Innovation and Technology
Christopher Gregorio	Assistant Engineer / CRS Coordinator	Engineering	Public Works & Utilities
Cristy Cassel	Conservation Outreach Program Manager	Public Information	Public Works & Utilities
Danielle Green	Assistant Director of Public Works	Public Works/Drainage	Public Works & Utilities
David Rodriguez	Assistant Police Chief	Emergency Management/Public Safety	Police
Ivan Carmona	Planner	Planning/Zoning	Community Development
Joseph DeSante	Chief Building Official	Building/Code Enforcement	Community Development
Justin Meek	Interim Community Development Director	Planning/Zoning	Community Development
Matt Orbach	Assistant Community Development Director	Planning/Zoning	Community Development
Matthew Orbach	Principal Planner	Public Information	Community Development

Name	Title	CRS Expertise	Department
Michelle Pulido	Public Information Officer	Public Information	Police
Nancy Porto	Community Outreach Coordinator	Elected Official	Public Works & Utilities
Nick Culabaquib	Deputy City Manager	Public Works/Drainage	City Manager
Raunel Zavala	Sr. Administrative Analyst	Emergency Management/Public Safety	
Rudy Lopez Sr.	Division Chief/Fire Marshal	Elected Official	Fire
Tamara Vides	City Manager	Emergency Management/Public Safety	City Manager
Tom Avila	Division Chief - Operations	Public Works/Drainage	Fire
Pajaro Valley Water Management Agency (PV Water)			
Brian Lockwood	General Manager / Hydrogeologist	Environmental Protection/Public Health	
Casey Meusel	Associate Hydrologist	Environmental Protection/Public Health	
Isabel Magana	Water Resources Technician	Environmental Protection/Public Health	Operations Division
Marcus Mendiola	Water Conservation & Outreach Specialist	Public Information	Administrative Division
Shinehah Bigham	Operations and Maintenance Manager	Public Works/Drainage	
Resource Conservation District (RCD) of Santa Cruz County			
Cameron McDonald	Ag Program Assistant	Environmental Protection/Public Health	
Lisa Lurie	Executive Director	Public Information	
Angela Gruys	Senior Program and Communications Specialist	Public Information	RCDSCC
Matt Abernathy	Forest Health Senior Program Specialist	Environmental Protection/Public Health	
Santa Cruz County			
Clare Peabody	Emergency Services Analyst	Emergency Management/Public Safety	Office of Response, Recovery & Resilience
Dave Reid	Director	Emergency Management/Public Safety	Office of Response, Recovery & Resilience
Alex Sandoval	Road Superintendent	Public Works/Drainage	Department of Community Development and Infrastructure
Amanda Gullings	Emergency Services Analyst	Emergency Management/Public Safety	Santa Cruz County Office of Response Recovery and Resilience
Annie Puckett	Administrative Analyst	Public Information	

Name	Title	CRS Expertise	Department
Antonella Gentile	Resource Planner – Flood Control	Planning/Zoning	Department of Community Development and Infrastructure
Carolyn Burke	Assistant Director of Public Works	Public Works/Drainage	Department of Community Development and Infrastructure
David Carlson	Resource Planner	Planning/Zoning	Department of Community Development and Infrastructure
David Sanford	Agricultural Commissioner	Environmental Protection/Public Health	Agricultural Commissioner
Elissa Benson	Assistant CAO	Elected Official	County Administrative Office
Elizabeth Byrd	Senior Human Services Analyst	Public Health	Human Services Department
Erin McCarthy	Water Resource Planner	Environmental Protection/Public Health	
Gregory Benson	Senior Health Services Mgr / MHOAC	Environmental Protection/Public Health	Health Services Agency
Jacob Ainsworth	Undersheriff	Emergency Management/Public Safety	Sherriff's Office
Jessica deGrassi	Resource Planner	Planning/Zoning	
Leah MacCarter	Resource Planner (CRS Program Manager)	CRS Coordination / Planning/Zoning	Department of Community Development and Infrastructure
Lun Wang	Health Equity Officer	Public Health	Health Services Agency
Matt Johnston	Principal Planner – Environmental Planning	Planning/Zoning	Department of Community Development and Infrastructure
Matt Machado	Deputy CAO / Director of CDI	Elected Official / Planning	Department of Community Development and Infrastructure
Matt Price	GIS Manager	Public Information	Information Services Department
Megan Reilly	Deputy Director	Public Works/Drainage	General Services
Nicholas Baldridge	Lieutenant	Emergency Management/Public Safety	Sheriffs Office
Rob Tidmore	Park Planner	Parks and Recreation	Parks and Community Services
Jed Wilson	Unit Chief / Fire Chief	Emergency Management/Public Safety	CalFire/Santa Cruz Fire
Sierra Ryan	Water Resources Program Manager	Environmental Protection/Public Health	Department of Environmental Health
Tammie Weigl	Director	Public Information	Information Services
Tatiana Brennan	Administrative Analyst	Public Information	OR3

Name	Title	CRS Expertise	Department
Santa Cruz Port District			
Holland MacLaurie	Port Director	Public Works/Drainage	
Blake Anderson	Harbormaster	Emergency Management/Public Safety	
Carl Wulf	Facilities Maintenance & Engineering Manager	Public Works/Drainage	
Scotts Valley Water District			
Nate Gillespie	Operations Manager	Public Works/Drainage	
Brody Knutson	Engineering Technician	Engineering	
David McNair	General Manager	Public Information / Public Works	
Soquel Creek Water District			
Shelley Flock	Water Resources Manager	Environmental Protection/Public Health	
Skyler Murphy	Water Resources Planner	Environmental Protection/Public Health	
Connor Pollard	Associate Engineer	Engineering	
Melanie Mow Shumacher	General Manager	Public Works/Drainage / Elected Official	
Nicholas Emmert	Operations & Maintenance Manager	Public Works/Drainage	
Taj Dufour	Engineering Manager	Engineering	

Table 2-4: Key Stakeholders

Name	Title
American Red Cross	
Patsy Gasca	Disaster Program Manager
AT&T	
Bettye Saxon	Director of Community and Government Relations
Nathan Cobos	Director of Environmental Sustainability
CalFire	
James Allen	Deputy Chief
Cal OES	
Joelle Mehner	Emergency Services Coordinator
City of Santa Cruz	

Name	Title
Meredith Albert	OES Manager
Tiffany Wise-West	City Manager
Heidi Luckenbach	Water Director
Community Bridges	
Patricia Zamora	Program Coordinator
CSU Monterey Bay	
Peyton Higgs	CSUMB Recovery and Resilience Intern
Fire Safe Council of Santa Cruz County	
Lauren Moody	Communications, Education and Outreach Coordinator
Sally Mack	Board Member
Pajaro Regional Flood Management Agency	
Forrest Revere	Environmental Program manager
Santa Cruz Public Library	
Laura Whaley	Assistant Library Director
University of California Santa Cruz	
Courtney Trask	Storm Water Programs Manager
Erin Johnson	Deputy Fire Marshal
United States Dept. of Agriculture (USDA)	
Rich Casale	District Conservationist
Visit Santa Cruz County	
Denise Harris	Director of Operations
Watsonville Wetlands Watch	
Jonathan Pilch	Director, Operations and Restoration Programs
Zayante Fire Protection District	
Jeff Maxwell	Fire Chief

Table 2-5: Consultant Team Members

Name	Title	Project Role
Ethan Mobley, AICP	Owner / Principal Planner	Project Manager
Brian Greer	Co-Owner / Data Visualization Manager	GIS Lead / Data Analyst

Name	Title	Project Role
Raini Ott, AICP, CFM	Principal Planner	Assistant Project Manager / Outreach Lead / Hazard Mitigation Planner
Cory Schreiner	Fire Prevention Service Manager	Hazard Mitigation Planner
Alex Krebs	Data Visualization Associate	GIS Assistant / Data Analyst
Grant Gruber	Senior Technical Writer	Hazard Mitigation Planner
Christopher Velasco	Senior Planner	Outreach Assistant / Hazard Mitigation Planner
Cassidy Baumann	Planning Associate	Outreach Assistant / Hazard Mitigation Planner / Data Analyst

2.1.2 Public & Stakeholder Engagement

Stakeholder engagement is a critical component in producing any effective and meaningful public planning process and actionable planning document, and public outreach is also a required component of the MJHMP. (44 CFR § 201.6(c)) As such, it is vital that early and continued engagement is facilitated through a diverse range of mediums to ensure community members, neighboring jurisdictions, and other stakeholders have an adequate opportunity to provide input, especially on the mitigation strategy.

The public and stakeholder engagement efforts deployed for this plan exceed the minimum state and federal requirements for outreach. But more than that, the engagement strategy was developed, implemented, and refined over the course of the MJHMP update planning process to ensure an abundance of enhanced opportunities for all types of community members to provide input.

By engaging with stakeholders and members of the public at specific points during the process, perspectives from an array of stakeholder categories were integrated throughout the MJHMP rather than being mentioned as an afterthought or an appendix. This extensive public and stakeholder engagement process and the results thereof are summarized in this section and fully documented in Appendix B.

On behalf of all the participating jurisdictions, Santa Cruz County conducted outreach and engagement following a six-step strategy and work plan with support from the Consultant Team, county-wide HMPT, and jurisdictional planning teams. The outreach strategy for this 2025 MJHMP maximized stakeholder input and public involvement throughout the planning process, utilizing a diverse range of channels, mediums, and formats to ensure residents, business owners, and other community members were solicited for input on the plan from start to finish. Other community stakeholders, such as non-profits serving vulnerable populations, were also engaged using a variety of methods.

Implementation of the six-step strategy and work plan was conducted by the Steering Group and consisted of first identifying goals and the timeframe for engagement followed by identifying the planning team members, key stakeholders, tools, and resources to support the effort. Then a work plan was developed to organize the timeframe, teams, key stakeholders, and engagement tools and resources into a usable framework to guide the process toward accomplishing its stated goals. As the process progressed, it was continually assessed for its effectiveness and adjusted accordingly. This adaptive management approach ensured the engagement process supported the three goals identified in step one. In executing this engagement strategy and work plan, Santa Cruz County accomplished the following three goals:

1. Understand public safety and hazard concerns, problem areas, assets, and policy and mitigation priorities on a neighborhood scale, with intentional outreach to socially vulnerable and underserved populations, including Spanish-speaking residents and people with access and functional needs.
2. Provide accessible, inclusive information and tools — offered in multiple languages and formats — to community members, residents, and businesses to increase safety and decrease hazard risk at the private property-level, ensuring engagement with socially vulnerable populations.
3. Collaborate with adjacent communities, special districts, utility providers, and other local and regional regulatory agencies providing public safety services, while prioritizing coordination that supports underserved and socially vulnerable populations.

The overall timeframe for public and stakeholder engagement stretched across the development of the MJHMP, occurring at regular intervals and important junctures. This schedule is illustrated below in Figure 2-3. A summary of engagement efforts outside of the planning team meetings and breakout sessions discussed in Section 2, Step 1, is provided in Section , including the many community outreach events hosted across the county. The various tools, resources, and efforts undertaken, as well as the feedback gained from stakeholders and community members, are summarized in the following sections. Appendix B fully documents the outreach process, as required by FEMA, Cal OES, and the California Office of Planning and Research (OPR).



Figure 2-3: Overview of Public and Stakeholder Engagement Schedule

2.1.2.1 Outreach Tools & Resources

Members of the public possess valuable local knowledge about their communities and can help identify assets and problem areas, describe issues of concern, narrate safety threats and hazard history, prioritize proposed mitigation and planning policy alternatives, and provide ideas for continuing public involvement. Many public safety planning goals and hazard mitigation actions also affect private property; meaning that the public should be engaged early and often to understand community priorities and policies that might change. As such, the engagement strategy developed and deployed to support the planning process for this MJHMP used a variety of tools, resources, and methods to reach all segments of the county community and populations within other participating jurisdictions.

More than just informing the public of the plan's development, a good community engagement effort educates the public and motivates them to act. It must also be recognized that equal opportunity to participate does not result in equal participation. In every community, there are those who might otherwise engage but go unheard for various reasons, such as lack of internet access, time constraints, or childcare needs which may inhibit in-person engagement. It was Santa Cruz County's goal to identify and overcome these barriers and achieve equitable participation and meaningfully engage with the local community on their terms. The tools and resources discussed in this section aided in achieving this.

Key Stakeholders

Because public safety and hazard issues are not tied to jurisdictional boundaries, Santa Cruz County consulted with a variety of stakeholders throughout the development of this MJHMP, as described in Step 1 of the planning process in Section 2. This included gathering jurisdictional staff and other stakeholders with specific local expertise to contribute to the planning process and forming the county-wide Hazard Mitigation Planning Team (HMPT) as well as internal planning teams for each jurisdiction. In addition, the county consulted directly with a number of Key Stakeholders that represented a broader range of local and regional agencies, including those that work closely with underserved and vulnerable populations.

Key Stakeholders consisted of people from a variety of public and private organizations within Santa Cruz County and the surrounding region that possess knowledge about local public safety and hazard conditions, issues, and priorities. These included representatives of local businesses, community-based and non-profit organizations, academia, and neighborhood groups (see Table 2-4). While some Key Stakeholders were involved in the HMPT or jurisdictional planning teams, others were engaged through different means, such as emails and project announcements, informal interviews and phone calls ("listening sessions"), meetings, and collaboration on community engagement events. These engagement efforts that took place outside of the formal planning teams are summarized in Table 2-6.

Most importantly, Key Stakeholders that work with vulnerable populations and underserved communities provided critical channels and opportunities to meaningfully engage with those groups. Many of the Key Stakeholders consulted are trusted community figures and leaders, with voices that carry across language, cultural, and socioeconomic barriers to reach those who face some of the greatest risks and challenges in preparing for, responding to, and recovering from hazard events. By engaging with these community voices, Santa Cruz County and the other participating jurisdictions were able to develop more comprehensive mitigation strategies that were not only tailored to local hazard conditions and capacities, but that also addressed some of the most pressing needs of their most vulnerable community members. In this way, Key Stakeholders were central in developing the MJHMP goals and mitigation strategies that will make Santa Cruz County safer and more resilient.

Table 2-6: Summary of Key Stakeholder Engagement

Engagement Effort	Date	Location
Stakeholder Listening Sessions		
Fire Safe Council of Santa Cruz County	February 25, 2025	Virtual
Zayante Fire Protection District	February 26, 2025	Virtual
San Lorenzo Valley Water District	February 27, 2025	Virtual
Encompass Community Services	March 11, 2025	Virtual
Pajaro Regional Flood Management Agency	March 13, 2025	Virtual

Engagement Effort	Date	Location
CAL FIRE	March 21, 2025	Virtual
Community Bridges	April 1, 2025	Virtual
USDA Natural Resources Conservation Service	August 4, 2025	Santa Cruz County Emergency Operations Center, Santa Cruz
Other Stakeholder Engagement Efforts		
Meeting on Multi-Benefit Project for Paulsen Road, College Lake, and South County Park	March 3, 2025	District 5 Office, Watsonville
Regional Water Management Group Meeting	March 24, 2025	Community Foundation Santa Cruz County, Aptos
Santa Cruz County Emergency Management Council	May 15, 2025 September 11, 2025	Santa Cruz County Emergency Operations Center, Santa Cruz
Santa Cruz County Water Advisory Commission	August 6, 2025 October 1, 2025	County Government Center, Santa Cruz

Websites, Social & Other Media

Santa Cruz County and the other participating jurisdictions used their websites, social media platforms, and other media to widely advertise the update of the MJHMP and solicit input from a diverse array of community members. In addition, a project portal was created through the Mitigate Hazards website maintained by the Consultant Team (mitigatehazards.com/santacruzmjhmp), which served and will continue to serve as a centralized project information and file-sharing platform throughout the lifecycle of the plan. This website provides a tool for project management, collaborative content, and for mitigation planning resources.

Project participants from each jurisdiction and Key Stakeholders used the website as a project resource for the duration of the planning process and will continue to have access during the five-year cycle and beyond. The page hosts secure information, including a point of contact database and a mapping application built specifically for mitigation planning called the Risk Assessment Mapping Platform (RAMP). RAMP allows for interactive discovery of the robust risk assessment data that was developed for the MJHMP. It displays facilities and buildings overlaid with natural hazards layers to bring interactivity and individual discovery to the GIS analysis performed for the plan. The website also hosts the Mitigation Action Support Tool (MAST) to help each jurisdiction track and update their mitigation strategy. See Sections 2.2.1 and 2.3.4.3 for more information on RAMP and MAST, respectively.

In addition to internal coordination, the project website played a critical role in community engagement throughout the planning process and documenting public involvement, including for the public survey, engagement events, planning team meetings and breakout sessions, and public review of the draft plan.

Resources such as home-based mitigation measures, background documents, RAMP, links to meeting summaries, and the final plan are available to the public via the website.

Jurisdiction-maintained websites and social media are valuable and authoritative resources for the public that were used in addition to the project website to advertise the planning process and ways for community members to get involved. In general, users were directed from the jurisdiction websites and social media posts to the primary project website to avoid inactive or outdated information. Information on the MJHMP update was distributed through multiple social media platforms, such as Instagram, Facebook, and Twitter (X), using visually-oriented posts tailored to that jurisdiction's audience, including posts in Spanish. Local media outlets, such as local radio, were also used to advertise the update and opportunities to participate.

Alongside general project advertising, these websites, social media platforms, and local media outlets were used to publicize project milestones, the public survey, and community engagement events, as documented in Appendix B. The websites and media listed in Table 2-7 were used in the engagement effort, both county-wide and individually, and links to example advertisements of the 2025 MJHMP are provided.

Table 2-7: Summary of Community Outreach Media Tools

Jurisdiction / Agency	Media Tools Used	Example Links
Key Stakeholders and Other Partner Agencies		
KION News Channel 46	TV	March 2025 News Story
Regeneración	Website, Newsletter	March 2025 Newsletter
Participating Jurisdictions		
Santa Cruz County	Website, Press Release, Facebook, Instagram, Twitter (X), Nextdoor	March 2025 Press Release March 2025 Facebook Post March 2025 Twitter (X) Post
City of Capitola	Website, Facebook, Instagram	City of Capitola Public Works Webpage August 2025 Facebook Post
City of Scotts Valley	Website, Newsletter, Facebook, Instagram	April 2025 Facebook Post June 2025 Newsletter
City of Watsonville	Website, Facebook, Instagram, Twitter (X)	March 2025 Facebook Post
Soquel Creek Water District	Website, Facebook, Instagram, Twitter (X)	March 2025 Facebook Post
Scotts Valley Water District	Website, Facebook, Instagram	March 2025 Facebook Post March 2025 Instagram Post
Pajaro Valley Water Management Agency	Website, Facebook	August 2025 Facebook Post

Jurisdiction / Agency	Media Tools Used	Example Links
RCD of Santa Cruz County	Website, Newsletter, Facebook, Instagram	Spring 2025 Newsletter
Santa Cruz Port District	Website, Facebook, Instagram	April 2025 Facebook Post
Cabrillo College	Website, Facebook, Instagram	

Online Public Survey

A primary tool used in informing the development of this MJHMP was an online survey, which provided an easy and powerful way of gathering qualitative and quantitative data to inform plan preparation. The survey was open to the public between February and September 2025, ending just prior to the release of the public draft for review, ensuring as many responses as possible were collected. The survey was distributed in both English and Spanish and was widely advertised across the county through the websites and other platforms of participating jurisdictions, Key Stakeholders, and partner agencies (Figure 2-4). To incentivize greater public participation, Santa Cruz County offered all survey participants the chance to win a home emergency kit and, in addition, many of the individual participating jurisdictions provided small handouts for taking the survey at community outreach events.

Figure 2-4: Online Public Survey Advertisement in Spanish

A total of 450 responses were received, which are summarized in Figure 2-5 and documented in Appendix B. As intended through a series of 16 questions, the results from the survey were used to gauge community members' knowledge of local hazards, perceptions of different hazards, greatest safety concerns, and mitigation priorities. These results were used to ensure that the priorities of Santa Cruz County and the other participating jurisdictions match those of their respective community members.

Figure 2-5: Highlights from Public Survey Results

Community Outreach Events

Community outreach events were hosted across the county during the development of the MJHMP. In-person public engagement events, and in particular events that leveraged existing community events with large attendance, provided opportunities to go beyond other outreach efforts and directly engage with members of the community who might not have otherwise participated in the planning process. Primarily, these events were coordinated with jurisdictional planning teams and Key Stakeholders and consisted of hosting tables and tents at local famers' and art markets, community fairs, cultural events, and other local gatherings. Many of the leveraged events used to boost engagement brought together wide and diverse populations in relatively central locations within participating jurisdictions and across the county, and each event was widely advertised across multiple platforms (Figure 2-6).

A total of eight community outreach events were conducted during the development of the MJHMP and through the public draft review period, which are summarized in Table 2-8.

Figure 2-6: Strawberry Princess Advertising the Survey at the Watsonville Strawberry Festival

Table 2-8: Summary of Community Outreach Events

Outreach Event	Date	Location
Community Wildfire Preparedness Workshop	March 18, 2025	Scotts Valley Community Center, Scotts Valley
Entrenamiento Gratuito de Preparación para Incendios Forestales (Free Wildfire Preparedness Training)	March 29, 2025	Pajaro Middle School, Pajaro
Cultivating Community: Youth & Family Resource Fair	April 4, 2025	Romo Park, Watsonville
Earth Day Santa Cruz	April 19, 2025	Pacific Avenue, Cooper Street and Abbott Square Market, Santa Cruz
Watsonville Earth Day 2025 Celebration	April 27, 2025	Watsonville Plaza, Watsonville
Corralitos Wildfire Resiliency Fair	June 28, 2025	Corralitos Community Center, Corralitos
Watsonville Strawberry Festival	August 2, 2025	Downtown Watsonville, Watsonville
Capitola Makers Market	August 3, 2025	Capitola Esplanade, Capitola

Interactive Meeting & Outreach Materials

Santa Cruz County and the other participating jurisdictions, with assistance from the Consultant Team, conducted a series of county-wide and jurisdiction-specific planning team meetings (see, Step 1) and many community outreach events, as describe in this section. All of these meetings and most of the events were arranged in ways that were conducive to interactive engagement, providing enhanced opportunities for participants to learn and express their perceptions and priorities through a variety of tools.

The stakeholder and community feedback collected through interactive methods is documented in Appendix B. Examples of the tools and meeting materials that were used to create these engagement opportunities include:

- **Take-Home Cards:** Cards with important project information, such as the project website URL and a QR code to the online survey or public draft review page (Figure 2-7).
- **Balancing Act Exercise:** Using scales, collection jars, and dried beans, community and stakeholder feedback was collected on one of the most difficult choices in developing the mitigation strategy: whether to focus on supporting individual mitigation efforts or aim funding toward community-wide actions. This forced community members and stakeholders to weigh the pros and cons of prioritizing a major mitigation project vs individual property owner mitigation (Figure 2-7). Preliminary results could be seen at events by attendees, and the beans were tallied prior to the public draft release. The final result was heavily skewed toward funding community-wide mitigation.

Figure 2-7: Interactive Outreach Materials at Capitola Makers Market (Clockwise from Bottom Left: Take-Home Cards, Earthquake Kit Demo, and Balancing Act)

- **Earthquake Kit Demonstration:** Using a custom display board, several in-home earthquake safety measures were made available for members of the public to interact with. The display board featured different ways to secure furniture and heavy objects like TVs, as well as museum putty to help keep fragile valuables such as glassware in place (Figure 2-7).
- **Feedback Boards:** Prompts on large boards with mapping information or visualized data were provided to help collect stakeholder feedback. Planning team members were able to respond to the information on the board by attaching stickers or post-it notes, or by writing, drawing, or highlighting directly on it.

Public Review Period

After a complete draft of the MJHMP was developed based on the updated risk and capabilities assessments and on feedback from stakeholders and the public, community members across all participating jurisdictions were provided an opportunity to review and comment on the proposed hazard mitigation plan and strategy. This public review period was open for 21 days, between September 29 and October 20, 2025, and widely advertised through community outreach events and jurisdiction websites, social media, and other media platforms.

Reviewers were directed to the project website where the draft MJHMP was provided in a collaborative PDF format to allow quick and easy live commenting. In addition, an online commenting form and direct

emailing to the Steering Group via the Consultant Team were offered as options to give input on the draft. All comments received were reviewed and incorporated into the plan as appropriate, as documented in Appendix B.

2.1.2.2 Reaching Underserved Communities & Vulnerable Populations

As discussed in Section 1.4.3 of the Community Profile, there are populations in Santa Cruz County that are disproportionately impacted by hazard events than others, including Spanish-speakers, agricultural workers, seniors, and people with access and functional needs. Recognizing that traditional engagement methods, such as public hearings or submitting comments in emails or letters, are often inaccessible or intimidating ways to participate in the planning process, the engagement strategy for this MJHMP sought input directly from these communities and populations and from trusted voices within them through different means.

Partnering with Key Stakeholders to reach underserved and vulnerable populations through existing community lifelines and organizations was critical to understanding the concerns, needs, challenges, and priorities of these groups across Santa Cruz County. This was aided by the deployment of intentional outreach efforts using accessible and inclusive tools to engage residents in a variety of ways and on their own terms, including:

- **Translation of Materials:** Santa Cruz County translated all engagement materials into both English and Spanish, including content on the project website, the public survey, and social media posts in order to effectively exchange information with Spanish-speaking residents. Census data was also used to identify locations of linguistically isolated communities and tailor outreach efforts with translation needs.
- **Engagement with Agricultural Workers and Latino Business Owners:** Through Key Stakeholders and partner organizations, Santa Cruz County engaged with agricultural workers and Latino business owners to identify local hazard risks and disseminate risk reduction information. The county's agricultural industry employs a significant Latino workforce, and Latino-owned businesses represent important hubs throughout the county with strong community ties and trusted relationships with residents.
- **Trusted Community Organizations:** As an entity that facilitates, bridges, links, or mediates between groups or persons of differing cultural backgrounds, trusted community organizations provide opportunities to achieve mutual understanding and respect through the planning process. This role was often filled by Key Stakeholders. Translation services were also provided for community outreach events tailored toward linguistically isolated communities.
- **Pop-Up and Community Engagement Events:** Hosting outreach at existing community events proved to be one of the most effective ways to engage Santa Cruz County residents in the hazard mitigation planning process. Pop-up booths at gatherings such as the Watsonville Strawberry Festival and other local fairs, markets, and cultural celebrations created safe, approachable spaces for dialogue. These events allowed the planning team to connect with community members in familiar, trusted settings, reducing barriers for individuals who may feel hesitant to engage with government-led meetings.

- **Hardcopy Materials:** At all in-person events, participants were offered multiple options for taking the survey and providing feedback. This included hardcopy materials for those who may not have access to online resources or be comfortable with technology-based response, such as seniors.
- **Virtual Participation:** Virtual participation options were also offered to provide flexibility for Key Stakeholders and community members who were not able to attend in-person meetings or events due to inconvenience or other constraints. These options included the online public survey, virtual and hybrid meeting formats, and online commenting of the public review draft.

2.1.2.3 Incorporating Public & Stakeholder Feedback

The stakeholder and public feedback gained through the various engagement efforts described in this section and Section 2, Step 1, shaped the development of the MJHMP from start to finish. The Steering Group, county-wide HMPT, and jurisdictional planning teams laid the foundation for and provided critical input on the plan, including the history of hazard events, existing community conditions and hazard concerns, the successes of previous mitigation efforts, current capabilities and improvement opportunities, the overarching plan goals, and the final mitigation strategy. Key Stakeholders representing a range of interests from neighboring jurisdictions to disproportionately impacted communities, were also instrumental in setting the tone and direction of the plan from the beginning.

Building upon the local expertise and experience of these formalized groups, Santa Cruz County and the other participating jurisdictions incorporated comments from the public throughout the plan to tailor the goals and mitigation strategy toward specific community concerns and needs. Public feedback was collected on an ongoing basis and at major injection points, such as during community outreach events and during the public review period. These results are fully documented in Appendix B, and Figure 2-5 provides a summary of the feedback gained from the public survey. Major themes and key findings among the comments collected from members of the public and Key Stakeholders that were incorporated into the MJHMP are summarized in Table 2-9.

Table 2-9: Public and Stakeholder Engagement Themes and Key Findings

Theme	Key Findings		
Top Hazard Risks	▪ Wildfire ▪ Flood ▪ Extreme heat	▪ Earthquake ▪ Slope failure ▪ High wind	▪ Coastal hazards ▪ Drought ▪ Climate change
Top Concerns	▪ Evacuation route vulnerability from substandard design, vegetation overgrowth, drainage issues, and landslide susceptibility ▪ Elderly, farmworker, low-income, and other underserved populations ▪ Lack of sustained mitigation funding or capacity to properly maintain mitigation projects ▪ Older, substandard and unregulated development in high-hazard areas ▪ Inadequate communication infrastructure and coordination ▪ Lack of community trust and outreach ▪ Disaster fatigue, complacency, and unpreparedness among residents		

Theme	Key Findings
Lessons Learned	▪ Importance of inter-agency coordination and legislative support ▪ Past disasters highlight need for infrastructure hardening, increased public education and awareness, and collaboration among agencies and private landowners ▪ Incentives and outreach are more effective than mandates ▪ "One size fits all" approaches don't work; mitigation must be site-specific
County-Wide Challenges	▪ Infrastructure Vulnerability: ○ Concerns about aging infrastructure, limited backup power, and seismic vulnerability ○ Drainage, water, and road infrastructure often degraded in underserved areas ○ Flood-prone areas face repeated damage and access issues ▪ Evolving Conditions: ○ Limited capacity in small jurisdictions to develop and implement mitigation projects ○ More severe storms, rising seas, prolonged and intensified wildfire conditions ▪ Data and Capacity Gaps: ○ Desire for updated hazard maps, especially for flooding, fire, and erosion ○ Challenges coordinating across agencies for multi-jurisdictional hazards ▪ Planning and Policy Needs ○ Need for culturally responsive outreach and coordination across agency lines ○ Need for updated land use policy, public outreach, and regional coordination tools
Mitigation Barriers	▪ Complex, expensive, and delayed permitting processes discourage compliance ▪ Lack of awareness and education, underestimation of risks, and inconsistent incentives ▪ Little dedicated funding or labor support for vulnerable populations (e.g., seniors, low-income households) ▪ Funding, staffing, and other capacity limitations for grant administration, mitigation projects, and outreach programs ▪ Lack of inter-agency coordination and jurisdictional boundary challenges ▪ Language and cultural barriers
Needs	▪ County-wide communication uniformity, trust in local messengers, plain-language alerts, and engagement strategies for unhoused populations ▪ Emphasize both community-scale and large-scale, holistic planning efforts as well as human-centered mitigation

2.1.3 Planning Process Library

During the update process for this MJHMP, the Steering Group, county-wide HMPT, and each jurisdictional planning team engaged in and completed five different exercises to assess risk, prioritize hazards, identify areas of concern and hazard problems, assess existing capabilities and opportunities for improvement, and develop the mitigation strategy. These exercises, facilitated by the Steering Group and Consultant Team, were integral components of the planning team meetings described in Section 2.1.1 and listed in Table 2-1. A description of each exercise and its purpose are provided below.

The outcomes of the five exercises completed by each participating jurisdiction are organized and documented in the form of a Planning Process Library (Table 2-10). Specific results from these exercises are incorporated into Volume 1 for Santa Cruz County; the results for other participating jurisdictions are further described in their Volume 2 annex.

Exercise #1: Risk Assessment

The risk assessment exercise aimed to thoroughly identify both county-wide and jurisdiction-specific vulnerabilities based on the best available data. Hazard overlay maps, demographics reports, and other tools were utilized to educate and engage stakeholders with deep-dive discussions on local hazard concerns and priorities, guiding the development of the risk assessment. This exercise was facilitated by the Steering Group and Consultant Team and engaged all the planning teams in reviewing and discussing the many factors that can impact community hazard risk (Figure 2-8). The Planning Process Library contains the snapshot hazard maps for each participating jurisdiction and a county-wide demographics report that were refined through this exercise and formed the foundation for developing specific, actionable mitigation strategies.



Figure 2-8: Risk Assessment Exercise from HMPT Meeting #2

Exercise #2: Hazard Prioritization

The county-wide HMPT and each of the jurisdictional planning teams considered and screened a broad range of hazards presented in relevant local, regional, and statewide hazard mitigation planning documents. The risk assessment (Exercise #1), past hazard events, and climate change projections also informed the selection of hazards for profiling in this plan. Each jurisdictional planning team then reviewed and prioritized all potential hazards, deciding which are most likely to happen (probability) vs how severe the impacts could be from an event (impact) (Figure 2-9). The crosswalk of documents reviewed, as well as the results of screening and prioritizing relevant hazards, are outlined in Section 3.1. The Planning Process Library contains the completed risk matrixes resulting from this exercise, ranking hazards based on probability in and potential impact on each participating jurisdiction.



Figure 2-9: Hazard Prioritization Exercise from Santa Cruz County Breakout Meeting #1

Exercise #3: Areas of Concern

All of the planning teams engaged in this exercise to identify areas of concern and the potential effects of each of the identified priority hazards on the planning area in terms of impacts, victims, or threats. Problem statements were developed for these areas of concern, which describe the specific nature of the consequences of a hazard occurrence on the community and its assets. This ensured that the mitigation actions developed through the fifth exercise were tailored for each community and to the specific problems created by various hazard scenarios within it. The Planning Process Library contains the resulting problem statements for each jurisdiction.

Exercise #4: Capabilities Assessment

The capabilities assessment exercise involved analyzing the existing planning and regulatory, administrative and technical, financial, and education and outreach resources of each participating jurisdiction. Various tools are used to implement hazard mitigation activities, such as long-range planning documents; building, subdivision, and zoning regulations; trained staff; information systems; various funding mechanisms; and community preparedness education. Each of the Steering Group members, supported by their planning team and the Consultant Team, evaluated their jurisdiction's current capabilities in comparison to previous mitigation planning efforts and provided updated information to reflect recent developments. As part of the exercise, they also explored opportunities to improve capabilities and the various funding options available to support implementation of their mitigation strategy. The Planning Process Library contains the resulting capabilities assessment for each participating jurisdiction.

Review & Incorporation of Existing Documents

In organizing resources for the plan update, one of the initial steps was for each jurisdiction to identify and review their existing community plans, regulations, strategies, studies, and other documents with relevance to local community planning and hazards to help inform the development of the MJHMP. This effort was led by the Steering Group with support from the Consultant Team, county-wide HMPT, and jurisdictional planning teams. Many documents reviewed already incorporate hazard topics and mitigation planning while others, some seemingly unrelated, would be appropriate to integrate in the future. Relevant documents are cited throughout the MJHMP and in each hazard profile of the risk assessment.

As part of Exercises #1 through #4, the planning teams reviewed existing planning, policy, and regulatory documents for their relevance to hazard mitigation planning. The review included many documents into which previous mitigation plans are incorporated into the 4.5 -Works Cited, Capabilities assessment and each the hazard profiles. Since the adoption of its 2021 HMP, Santa Cruz County has incorporated the plan into its 2022 Climate Action and Adaptation Plan, 2022 Community Wildfire Protection Plan, and 2023 County General Plan Housing Element, among others.

The capabilities assessment for each participation jurisdiction identifies the past and current usage of the documents found to be relevant to hazard mitigation, and opportunities for their future integration with the MJHMP directly or indirectly (Table 2-10). The documents were also closely examined as part of the hazard prioritization exercise completed by each jurisdiction's planning team. The objective of this review was to ensure plan alignment with ongoing efforts, identify opportunities for integration, and avoid redundancy.

A summary of county-related documents which were identified, reviewed, and incorporated into this 2025 MJHMP, or that may be integrated with the county's hazard mitigation planning efforts in the future, is provided in the Capabilities and Opportunities Assessment, Section 3.5.1.

Figure 2-10: Strategy Development Exercise from HMPT Meeting #4

Exercise #5: Strategy Development

The final exercise conducted as part of the interactive and comprehensive development of this MJHMP was the creation of the mitigation strategy. Based on the results from all the previous exercises and background information surrounding them, including strategies from past mitigation plans, the Steering Group and Consultant Team led each of the planning teams through the review of potential mitigation actions and a variety of alternatives to consider for their particular jurisdiction during Breakout Meeting Series #2. Following individual strategy development, the HMPT met again to construct a collaborative, county-wide mitigation strategy that leverages resources to address shared needs among jurisdictions (Figure 2-10).

The draft actions were then further refined by the Steering Group and jurisdictional leads to incorporate community feedback received during the public draft review period. The final Mitigation Action Plan for Santa Cruz County is provided in Section 4, and the plans for the other participating jurisdictions are found in the Volume 2 annexes; the final plans are also in the Planning Process Library.

Table 2-10: Planning Process Library

Jurisdiction	Exercise No. / Title		Library Links
County-Wide	**1**	**Risk Assessment**	**County-Wide Demographics Report**
	5	**Strategy Development**	**County-Wide Mitigation Action Plan**
Local Governments			
Santa Cruz County	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
City of Capitola	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
City of Scotts Valley	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
City of Watsonville	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
Special Districts and Agencies			
Soquel Creek Water District	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
Scotts Valley Water District	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix

Jurisdiction	Exercise No. / Title		Library Links
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
Pajaro Valley Water Management Agency (PV Water)	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
Resource Conservation District (RCD) of Santa Cruz County	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
Santa Cruz Port District	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered
Cabrillo College	1	Risk Assessment	Hazard & Demographics Maps
	2	Hazard Prioritization	Risk Matrix
	3	Areas of Concern	Problem Statements
	4	Capabilities Assessment	Capabilities Assessment
	5	Strategy Development	Mitigation Action Plan / Alternatives Considered

2.2 Assessing Risk

This section describes the second major step in the planning process: the comprehensive assessment of risks associated with natural hazards in Santa Cruz County. The county-wide HMPT and each of the jurisdictional planning teams conducted a risk assessment for their planning areas. This involved identifying and prioritizing the natural hazards affecting Santa Cruz County as a whole and each participating jurisdiction individually, followed by assessing vulnerabilities to those identified hazards. Results from this risk assessment process aided the identification of an effective mitigation strategy.

The process for, and results from, identifying and prioritizing which hazards to assess are described in Sections 3.1 and 3.1.2. This section describes the process, methods, and support tools used in assessing the hazard risks to all the planning areas. The hazard-specific vulnerability assessments are documented in the ten hazard profiles.

Wildfire
SECTION 3.2.1

Flood
SECTION 3.2.2

Earthquake
SECTION 3.2.3

Severe Weather
SECTION 3.2.4

Coastal Hazards
SECTION 3.2.5

Slope Failure
SECTION 3.2.6

Dam Failure
SECTION 3.2.7

Drought
SECTION 3.2.8

Extreme Heat
SECTION 3.2.9

Climate Change
SECTION 3.2.10

Assessing risks and vulnerabilities exposes the unique characteristics of individual hazards and begins the process of narrowing down which areas within the county are vulnerable to specific hazard events. The vulnerability assessment included field visits and a Geographic Information System (GIS) overlaying method for examining such vulnerabilities more in depth. The planning teams of participating jurisdictions completed this exercise both singly and jointly with the county-wide HMPT. The hazards ultimately identified and prioritized varied widely depending on the geographic make up of, priorities of, and services provided by the individual participating jurisdiction. Using these methods, participating jurisdictions estimated the potential losses of populations, property, and facilities and infrastructure from their priority hazards.

The risk assessment process was conducted in alignment with FEMA's Local Mitigation Planning Handbook and used best practices to identify vulnerabilities in populations, property and private assets, and critical facilities and infrastructure.

The purpose of the risk assessment in Section 3.2 is to evaluate the locations and causes of the priority natural hazards affecting significant parts of the planning area, as well as the existing regulatory environment around them, their probability, the extent and severity of their potential impacts, and the vulnerabilities within the community. The findings serve as the foundation for developing targeted mitigation strategies that are both proactive and cost-effective. The risk assessment is comprised of the following:

- **Section 1.4, Community Profile:** Providing a geographic and demographic overview of Santa Cruz County as the basis for the assessment, highlighting the populations most vulnerable to hazards in the planning area.
- **Section 3.1, Hazard Identification & Prioritization:** Identifying hazards that pose the most significant threats and prioritizing them based on probability and potential impact in the county and other participating jurisdictions.
- **Section 3.2, Hazard Profiles:** Detailing the characteristics, history, probability, and potential impacts of each hazard, including:
    - Exposure Analysis: Mapping the populations, assets, and critical facilities and infrastructure exposed to each hazard.
    - Vulnerability Analysis: Assessing how susceptible different populations, structures, and other assets are to hazard impacts.

Risk assessment data is provided for all county-wide priority hazards and for Santa Cruz County, specifically, in Section 3 of this volume; all other participating jurisdictions are profiled individually in Volume 2.

2.2.1 RAMP (Risk Assessment Mapping Platform)

A highly interactive, web-based mapping platform was used to assist in the vulnerability assessment. RAMP, the Risk Assessment Mapping Platform, is hosted by and accessed through the project website (mitigatehazards.com/santacruzmjhmp) and allows the interactive discovery of robust risk, vulnerability, and exposure data developed especially for Santa Cruz County and the other participating jurisdictions. RAMP was built specifically for mitigation planning and is a vital tool in identifying hazard exposure and risk (Figure 2-11).

RAMP displays the total population, total parcels and property values, and a jurisdiction's facilities and buildings overlaid with natural hazards layers. Users can filter these layers by hazard and inventory type, as well as by jurisdiction. RAMP's robust data filtering and summation calculations allow the user to understand and visualize vulnerabilities at the property-level with detailed information on the number of people and structures exposed to various hazards. This brings interactivity and individual discovery to the GIS analysis performed for the vulnerability assessment, allowing for the exploration of various hazard risks posed within and around a community and, ultimately, aiding in the prioritization of mitigation resources.

RAMP enabled Santa Cruz County and the other participating jurisdictions to pinpoint their vulnerabilities and reinforce problem statements to support the mitigation strategy. The county-wide HMPT and each of the jurisdictional planning teams used RAMP in meetings and as needed to understand vulnerabilities both county-wide and to their planning areas, and especially to vulnerable populations and critical facilities and infrastructure.



Figure 2-11: RAMP User Interface

2.2.2 Vulnerability Assessment Methodology

This subsection explains the methodologies used to assess vulnerabilities across the county and in individual communities. The approach includes both qualitative and quantitative analyses to evaluate the risks associated with specific hazards. Methodologies were selected based on FEMA guidelines, state-level best practices, and local policy and expertise to ensure accuracy and relevance, and all data sources used in the analysis meet standards appropriate for hazard mitigation planning. The vulnerability assessment includes:

- **GIS-Based Mapping:** Visually representing hazard-prone areas, critical infrastructure and facilities, and vulnerable populations.
- **Data Collection and Analysis:** Utilizing historical disaster data, climate projections, and demographic information to estimate risk.
- **Scenario Modeling (Earthquake and Climate Change):** Conducting hypothetical disaster scenarios to understand potential impacts under varying conditions, including climate change.

- **Community Surveys and Stakeholder Feedback:** Incorporating local knowledge to identify vulnerabilities not captured in traditional data.

This section also describes how the vulnerability assessment accounts for climate change impacts, which are expected to increase the frequency and severity of hazards like wildfire, flood, and coastal erosion.

In order to describe vulnerability for each hazard, it is important to first understand the total population and assets at risk. This section provides an overview of the methods used in the hazard-specific vulnerability assessments of Section 3.2. For each type of hazard, the assessment begins with a general explanation of the phenomenon. Vulnerabilities to each hazard are then assessed through a two-step process. First, population, critical facilities and infrastructure, and all parcels across the county are inventoried to establish a comprehensive understanding of the area ("lay of the land"). Second, the inventories are used to calculate the exposure and potential damage (flooding and earthquake) at various levels of severity. A more detailed explanation of the explanation on risk assessment methods, see Appendix B.

2.2.2.1 Population & Asset Inventory

This subsection details the process for developing the inventory of populations and assets that are vulnerable to hazard events. It includes the following:

- **Critical Facilities:** Hospitals, fire stations, police stations, and emergency shelters.
- **Critical Infrastructure:** Roads, bridges, utilities, and communication networks.
- **Essential Services:** Water treatment facilities, power plants, and public health facilities.
- **Vulnerable Populations:** Areas with high concentrations of elderly residents, disabled individuals, low-income households, and non-English-speaking communities.

The inventory was mapped using GIS tools to clearly illustrate hazard exposure and support data-driven decision-making for developing the mitigation strategies. The population and asset inventory provides a baseline to measure the significance of or vulnerability to natural hazard events. The asset inventory can also be used to estimate damages and financial losses expected during a "worst-case scenario" event for each hazard.

Each participating jurisdiction's assets have been inventoried to use as inputs for the vulnerability assessment, including people, parcels, property values, and critical facilities and infrastructure.

Population

The primary purpose of the MJHMP is to better protect people; thus, determining the population located near each geographically defined natural hazard is critical. The demographic data for Santa Cruz County and the other participating jurisdictions discussed is derived from the U.S. Census Bureau's American Community Survey 5-Year Estimates (ACS 5-Year) from 2018 to 2023. The figures presented are intended to highlight broader regional trends relevant to hazard mitigation planning efforts rather than inform specific decision-making or administrative actions.

Each natural hazard scenario affects county residents differently depending on the location of the hazard, the population characteristics and density where the hazard event could occur, and other local factors. In the Community Profile, Section 1.4, specific characteristics of Santa Cruz County's population are discussed in detail, including highlighting which populations are most vulnerable to hazard events and impacts. The hazard-specific vulnerability assessments presented in the hazard profiles of Section 3.2 summarize the population exposure for each priority hazard, if definable.

Parcel Value Inventory

The Santa Cruz County Assessor's data was essential in identifying parcel and property value exposures to each priority hazard. The data includes 2025 fair market values of at-risk private parcels and improvements as well as jurisdictional properties and assets. The parcel value inventory for Santa Cruz County is summarized in Table 2-11 and includes market value[1], content replacement value, and total assessed value ("total value"). These elements are called out in the table because, in the event of a disaster, the value of the infrastructure or improvements to the land is usually the focus of concern, as structures can be rebuilt or contents replaced. Although there may be severe environmental impacts that result from a hazard event, the land itself is generally not a total loss.

- **Total market value** as presented in this MJHMP reflects Santa Cruz County Assessor data, including fair market value where available. If no fair market value was available for a given property, the value reflects the assessed improvement value, which is often an underestimate of actual value.
- **Total content value** was calculated based on the Assessor's use codes, translated to occupancy-based multipliers.

Each occupancy class prescribes a specific content cost multiplier used to calculate the content cost values shown in the summary and in the hazard profiles in Section 3.2. Occupancy-based content cost multipliers used in this plan reflect those found in the FEMA HAZUS-MH (Hazards U.S. Multi-Hazard) 4.2 technical manuals.

The hazard profiles in Volume 1 outline predicted impacts to Santa Cruz County's parcel value inventory for each hazard's geographic extent. The annexes in Volume 2 contain the same information for other participating jurisdictions.

[1] Market Value Includes a long-term asset which indicates the cost of the constructed improvements to land, such as buildings, driveways, walkways, lighting, and parking lots.

Table 2-11: Santa Cruz County Parcel Counts and Values

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$ 35,189,614,790	$ 19,116,504,796	$ 54,306,119,586
City of Watsonville	9,501	$ 8,496,490,409	$ 6,290,123,018	$ 14,786,613,427
City of Santa Cruz	16,939	$ 13,397,517,595	$ 8,354,246,391	$ 21,751,763,986
City of Capitola	3,957	$ 2,814,517,999	$ 1,710,821,997	$ 4,525,339,996
City of Scotts Valley	3,951	$ 4,343,987,999	$ 2,894,213,196	$ 7,238,201,195
Total Santa Cruz County	**81,978**	**$ 64,242,128,792**	**$ 38,365,909,398**	**$ 102,608,038,191**

Note: Total market value as provided by the Santa Cruz County Assessor's Office. Content value calculated using content multipliers per HAZUS occupancy classes.

Critical Facilities & Infrastructure Inventory

Critical facilities and infrastructure, such as a fire station or bridge along an evacuation route, are of particular concern when conducting hazard mitigation planning. These critical assets can be structures, infrastructure, or other improvements that, because of their function, size, service area, or uniqueness, have the potential to cause disruption of vital socioeconomic activities if destroyed, damaged, or functionally impaired. As such, the vulnerability assessment for each profiled hazard qualitatively discusses critical facilities and infrastructure with regard to each hazard's severity footprint.

The critical facilities and infrastructure inventory for this MJHMP was developed from a variety of sources, including datasets from participating jurisdictions as well as state, federal, and private industry sources. Although the inventory is not comprehensive due to data limitations, all data sources have a level of accuracy acceptable for planning purposes. For additional information on sources, see Appendix B. Based on the inventory, a spatial database developed to translate this information into georeferenced[2] points and lifelines that represent physical locations.

- **Points** include critical facilities such as government buildings, police stations, fire stations, shelters, hospitals, elder care facilities, childcare facilities, schools, and transportation and utility structures. Points also include facilities that handle hazardous materials.
- **Lifelines** include critical infrastructure related to transportation routes; delivery of water, wastewater, electrical power, liquid fuel, and natural gas; and other crucial utility infrastructure lines.

Figure 2-12provides an overview of the critical facility points and infrastructure lifelines located within the participating jurisdictions. Some critical facility information has been omitted from this document due to security concerns and requirements, and a detailed list of these assets is not provided. More detailed lists are on file with the individual jurisdictions that oversee those assets.

[2] To georeference something means to define its existence in physical space; that is, to establish its location in terms of map projections or coordinate systems. The term is used both when establishing the relation between raster or vector images and coordinates and when determining the spatial location of other geographical features.

2.2.2.2 Hazard Exposure & Damage Estimation

This subsection describes how the exposure of populations and assets to hazards was quantified. Damage estimation uses analytical tools to project financial impacts and loss estimations under various disaster scenarios and footprints. The analysis estimated potential damage based on factors such as:

- **Hazard Intensity and Frequency:** Historical data on past events, combined with climate projections.
- **Building Stock and Infrastructure Vulnerabilities:** Age, construction materials, and resilience of existing infrastructure.
- **Geographic Distribution:** Identification of floodplains, wildfire zones, landslide-prone areas, seismic fault lines, and other hazard areas with geospatial extents.
- **Socioeconomic Impacts:** Potential economic losses to businesses, critical services, and residential properties.

Alongside a study of past hazard events, geospatial data plays a critical role in these assessments by pinpointing the population and assets vulnerable to the hazards identified in this plan. This analysis is particularly effective when hazards have distinct spatial footprints that can be overlaid onto the locations of people and assets. In Santa Cruz County's planning area, such hazards as flood, wildfire, and earthquake have known geographic extents and corresponding spatial information; drought and severe weather hazards, on the other hand, impact large areas and do not have specific geospatial extents.



Figure 2-12 Critical Facilities Point Locations

Once the geographic extents of spatially-discreet hazards were established, the population and asset inventories were then used to generate specific exposure and damage estimations based on the severity of specific hazard event scenarios. The hazards in Santa Cruz County which have known geographic extends and corresponding spatial information, and thus have exposure and damage estimations, are:



Several data sources are necessary to conduct a thorough vulnerability analysis. Figure 2-13 provides an exhibit of the data inputs and outputs used to create the vulnerability analysis results presented in the hazard profiles of Section 3.2.



Figure 2-13: Data Inputs and Outputs

Population & Asset Exposure

"Exposure" of assets and population refers to the total counts of people, parcels, facilities, and other assets within the planning area in which a hazard event may occur. A natural hazards overlay was developed to reflect the combination of many known natural hazard spatial footprints. The spatial overlay method enables summarization of building values, parcel counts, population, and critical facility and infrastructure exposure within a hazard's geographic extents. Exposure numbers were generated using Santa Cruz County Assessor information, address points, and parcel data for replacement and content cost estimates. See Figure 2-14 as an hypothetical exposure to flood hazards.

Figure 2-14: Hazard Exposure Explanation Graphic

Damage Estimation (Flood Only)

For flood, specifically, detailed damage assessments were conducted through FEMA's HAZUS software. HAZUS is a nationally applicable standardized methodology that contains models for estimating potential losses from earthquakes, floods, and hurricanes. HAZUS uses GIS technology to estimate physical, economic, and social impacts of disasters. The estimated damage and losses provided by the HAZUS software is a based upon chosen severity of events and provides the ability to understand possible widescale damage to buildings and facilities. At-risk populations, critical infrastructure, improved parcels, and loss results for each hazard category are provided in Section 3.2 to evaluate the percentage of assets exposed to different types of hazards. The side-by-side comparison allows participating jurisdictions to evaluate impacts of potential hazards to prioritize hazard mitigation resources.

In the hypothetical geography shown in Figure 2-15, even though both structures are exposed to flooding, it is expected that the structure with a first-floor height below the depth-of-flooding will receive significantly more damage than the structure with a first-floor height above the expected water depth.

Figure 2-15: HAZUS Damage Estimation Example

2.3 Developing a Mitigation Strategy

This MJHMP was prepared in accordance with DMA 2000 plan update requirements, FEMA's mitigation guidance, Cal OES policies, and the California Office of Planning and Research's (OPR) recommendations. The development of this plan included identifying hazard problems across the planning area, setting goals for a mitigation strategy, assessing existing capabilities, considering the costs and benefits of alternatives, and developing new and improved mitigation actions.

Volume 1, 3.4.4, provides an explicit mitigation strategy and blueprint for reducing potential losses identified in the risk assessment based on the existing capabilities of Santa Cruz County; the same is provided in Volume 2 for each of the other participating jurisdictions.

2.3.1 Identify the Problem

As part of the mitigation action identification process, the HMPT and the jurisdictional planning teams identified areas of concern in and the potential impacts of each of the prioritized hazards, both county-wide and in their respective communities. Specific statements were developed to describe each jurisdiction's hazard problems based on the risk assessment contained in Section 3 and lengthy discussions about unmapped vulnerabilities. These "problem statements" are organized by three major areas of concern, which describe the nature of the consequences or effects of a hazard occurrence on the community and its assets as victim, impact, or threat. This categorization ensures that the identified actions in the mitigation strategy are tailored to each jurisdiction and the specific problems created by various hazard scenarios.

Each hazard problem statement that was developed is addressed by at least one mitigation action; however, most are mitigated with a combination of short- and long-range activities, through planning, regulatory, operational, physical, or other projects. Santa Cruz County's problem statements are identified at the end of

each hazard profile in Section 3.2 and those of other participating jurisdictions are identified in their individual annexes in Volume 2.

The problem statements are also available as part of the Mitigation Action Support Tool (MAST), which is summarized in Section 2.3.4.4 and will be available via the project website throughout the plan's lifecycle to assist the participating jurisdictions in monitoring and improving the mitigation strategy.

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim
Who is (most) impacted?

Example Statement
Seniors and people with mobility limitations lack adequate evacuation support during a fast-moving wildfire.

Impact
What are the direct and indirect impacts of hazard events?

Example Statement
Heavy rain events overwhelm aging and inadequate drainage infrastructure such as undersized culverts.

Threat
What local conditions create location-specific risk?

Example Statement
FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

2.3.2 Identify Mitigation Goals

Hazard mitigation plans must identify goals for reducing long-term vulnerabilities to identified hazards. (44 CFR § 201.6(c)(3)(i)) The county-wide HMPT and jurisdictional planning teams reviewed past mitigation goals from their plan, as applicable, and from the 2021 Santa Cruz County HMP, 2023 California State Hazard Mitigation Plan (SHMP), and other relevant plans to determine their present validity. The teams also reviewed the updated risk assessment (Section 3) and public survey results (Section 2.1.2) in defining the goals for this plan.

The teams ultimately decided to keep and update the 2021 county plan goals, which were found to be consistent with the current policies and goals of participating jurisdictions. The four resulting goals formed the basis for the development of the Mitigation Strategy and specific mitigation projects, which are presented in Section 4.

2.3.3 Conduct Capabilities Assessment

A capabilities assessment is a comprehensive review of participating jurisdictions' existing capabilities to implement the mitigation actions in the MJHMP and tools available to address known issues and weaknesses from identified natural hazards. The Steering Group and planning teams identified their jurisdiction's capabilities to implement the mitigation strategy. These capabilities were also reviewed for future opportunities for integration or enhancement, including the development of new policies, expansion of training programs, and increased collaboration with regional and state partners.

Santa Cruz County's assessment of its capabilities and future opportunities is found in Volume 1, Section 3.5.1; Volume 2 of this plan includes capabilities assessments all other participating jurisdiction as part of their specific annex. For more information on the regulatory environment surrounding each hazard, see the hazard profiles in Section 3.2.

2.3.4 Develop Mitigation Actions

The county-wide HMPT and jurisdictional planning teams developed mitigation actions, as both planning activities and other types of projects, to address identified hazard problems from the risk assessment in line with their capabilities. As part of this process, the teams reviewed and analyzed the status of mitigation actions from previous plans, determining which have been completed, which are no longer relevant, and which need to be updated to reflect current circumstances. Alternative actions considered and the final mitigation action plans adopted are provided as part of the Planning Process Library (Table 2-10).

After reviewing mitigation actions from past hazard plans and priorities, projects, and activities other relevant documents, the planning teams developed potential new actions through interactive exercises and discussions, as outlined in Section 2.1.3. The potential mitigation actions were then further scrutinized based on their relevance to the priority hazards, support from community members, realistic implementation parameters, and alternative measures that could be used to address various aspects of the hazard problems.

2.3.4.1 Public & Stakeholder Input

As part of the mitigation strategy development, Santa Cruz County and the other participating jurisdictions reviewed and incorporated stakeholder feedback and public comments collected throughout the planning process to tailor the goals and mitigation actions toward specific community concerns and needs. Public input was collected on an ongoing basis via an online survey and at major injection points, such as during community outreach events and during the public review period. These results are fully documented in Appendix B and summarized in Section 2.1.2. Section 4 also highlights public and stakeholder input that was specifically used in developing the mitigation strategies.

2.3.4.2 SMARTIE Principles



In developing the mitigation actions for this 2025 MJHMP, the planning teams used the principles of "SMARTIE" to ensure the mitigation strategy was realistic and actionable. These principles provided a framework for defining actions and evaluating their costs and benefits. A mitigation action that meets SMARTIE principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Acknowledges impacts to access and functional needs populations and other special considerations.

2.3.4.3 Mitigation Alternatives

Once hazard problems were defined (problem statements) and local resources and capabilities accounted for (capabilities assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. This section describes the process that was used in identifying and evaluating a range of mitigation alternatives to address the hazards prioritized in the risk assessment (Section 3). Alternatives include both structural measures (e.g., flood barriers, firebreaks, seismic retrofitting) and non-structural measures (e.g., zoning changes, public education, early warning systems) and were assessed based on:

- SMARTIE Principles
- Cost-Effectiveness
- Environmental Impact
- Community Acceptance
- Alignment with Mitigation Goals

The Consultant Team drafted many mitigation actions for each jurisdiction to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad

mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions. Categorizing mitigation actions in this way ensures a comprehensive approach to mitigation in the county, addressing various facets of vulnerability reduction and resilience enhancement across the community and its natural environment.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through planning and the implementation of building codes, land use regulations, and other preventative measures.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage by modifying or relocating existing buildings and structures to enhance resilience.
- **Public Education and Awareness (PE&A):** Efforts to engage and inform community members about hazard risks and effective mitigation strategies to foster preparedness and resilience.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural resources, systems, and functions to reduce hazard impacts.
- **Emergency Services (ES):** Measures that help minimize the impacts of hazard events on people and property by enhancing emergency preparedness and response capabilities.
- **Structural Projects (SP):** Projects to construct, install, or improve infrastructure and systems designed to reduce hazard impacts.

During Breakout Meeting Series #2 and HMPT Meeting #4, the planning teams drafted, evaluated, and refined mitigation actions that considered a wide range of implementation strategies, relevant to both county-wide needs and individual jurisdictions, using FEMA's six broad categories. Early discussions focused on reviewing previous mitigation strategies, identifying current hazard-related challenges, and developing potential actions to address priority hazard concerns. These ideas were then further reviewed and prioritized through collaborative sessions involving input from jurisdictional staff and a diverse group of stakeholders. The planning teams selected the most efficient and cost-effective actions by assessing vulnerabilities, evaluating existing capabilities, and building consensus on how best to address identified problems and meet the community's mitigation goals.

The final mitigation actions selected by each participating jurisdiction's planning team are presented in the Mitigation Action Plan. The Santa Cruz County Mitigation Action Plan is found in Volume 1, Section 4.4; action plans for all other participating jurisdictions are found in the Volume 2 annexes. In addition, the collaborative, County-Wide Mitigation Action Plan presented in Section 4.3 identifies combined efforts to address common hazard problems to increase the overall resilience of the county.

The following subsections provide examples of mitigation actions according to the six FEMA mitigation categories that were considered by the planning teams. This alternatives evaluation process is documented as part of the Planning Process Library discussed in Section 2.1.3 and provided in Table 2-10 (Alternatives Considered) to demonstrate transparency and support future funding applications.

PREVENTION (PRV)

Preventative (PRV) activities keep hazard problems from getting worse and are typically administered through government programs or regulations addressing building and land development. Preventative actions are particularly effective in reducing a community's future vulnerability in areas where development has not yet occurred or where capital improvements have not been substantial. Examples of preventative activities include:

- Planning and zoning ordinances
- Building codes
- Riverine or fault zone setbacks
- Open space preservation
- Floodplain regulations
- Stormwater management regulations
- Drainage system maintenance
- Capital improvements programming

Examples of Local PRV Alternatives

- **Update Land Use and Development Regulations:** Revise development codes and standards to better address natural hazards such as wildfire, flood, slope failure, drought, and climate change.
- **GIS and Hazard Mapping Enhancements:** Conduct detailed mapping for hazards such as flood and slope failure and expand GIS capabilities to increase utility of the data.
- **Restrict Development in High-Risk Zones:** Adopt policies to limit new development and capitol investments in coastal and high wildfire risk zones.

PROPERTY PROTECTION (PPRO)

Property protection (PPRO) measures involve the modification, relocation, or removal of existing buildings and structures to help them better withstand the forces of a hazard. Examples include:

- Building elevation
- Retrofitting (e.g., seismic design techniques, etc.)
- Safe rooms, shutters, shatter resistant glass
- Insurance
- Critical facilities protection

Examples of Local PPRO Alternatives

- **Backup Power for Critical Facilities and Services:** Secure backup power supplies for emergency shelters, water treatment plants and pumps, and other critical facilities to ensure continuity of service during outages.
- **Structure Hardening Incentives:** Create a program that incentivizes private property owners to conduct structural improvements to protect homes, such as low-interest loans for elevation above the base flood or rebates for installing flashing and vents in high-risk wildfire zones.

PUBLIC EDUCATION & AWARENESS (PE&A)

Public education and awareness (PE&A) activities advise community members and elected officials about hazards, hazardous areas, and mitigation techniques they can use to protect themselves and their property. Measures to educate and inform the public include:

- Outreach projects, including neighborhood and community outreach
- Hazard mapping
- Materials library
- Speaker series/ demonstration events
- Real estate disclosures
- School children educational programs
- Hazard expositions

Examples of Local PE&A Alternatives

- **Hazard Awareness Events:** Develop annual community outreach events and educational activities to increase awareness of local hazards and mitigation strategies.
- **Water Conservation Campaign:** Develop a public outreach campaign to promote water conservation during drought conditions.
- **Flood Insurance Information:** Make National Flood Insurance Program (NFIP) and flood risk information available at public locations, such as libraries, and via a virtual planning desk.

NATURAL RESOURCE PROTECTION (NRP)

Natural resource protection (NRP) activities reduce the impacts of hazards by preserving or restoring natural areas and their protective functions. Such areas include floodplains, wetlands, steep slopes, and sand dunes. Parks, recreation, or conservation agencies and organizations often implement these protective measures. Examples of these measures include:

- Erosion and sediment control
- Floodplain protection
- Vegetation management (e.g., fire-resistant landscaping, fuel breaks)
- Watershed management
- Wetland and habitat preservation/restoration

Examples of Local NRP Alternatives

- **Groundwater Recharge Infrastructure:** Preserve and improve natural areas and ecosystems that support groundwater recharge to enhance water availability during drought conditions and prevent saltwater intrusion.
- **Fuel Management Projects:** Implement vegetation management strategies outlined in the CWPP, including thinning, prescribed burning, and invasive species removal.
- **Slope Stabilization Projects:** Develop a priority list of areas at high risk for slope failures, then implement stabilization projects using natural and engineered techniques to prevent landslides and erosion.

EMERGENCY SERVICES (ES)

Emergency services (ES), while not traditionally categorized as mitigation, play a critical role in minimizing the impacts of natural hazard events on people and property. These services focus on preparedness, response, and recovery efforts to protect lives, reduce damages, and ensure the continuity of critical operations. The measures often include pre-disaster planning, resource staging, and infrastructure improvements to enhance emergency response capabilities. Examples include:

- Warning systems
- Sandbag staging for flood protection
- Identification / construction of evacuation routes
- Installing temporary shutters on buildings for wind protection

Examples of Local ES Alternatives

- **Expand Emergency Shelter Capacity:** Work with partner jurisdictions to expand shelter capacity and improve shelter accessibility and safety across the county.
- **Communications System Improvements:** Improve the reliability and coverage of emergency communications and alter systems to ensure consistent messaging and enhanced interagency coordination during emergencies.

STRUCTURAL PROJECTS (SP)

Structural projects (SP) are intended to lessen the impacts of a hazard by modifying the environment and natural progression of a hazard event through construction. They are usually designed by engineers and managed or maintained by public works staff. Examples include:

- Utility facility / infrastructure upgrades
- Stormwater detention / retention facilities
- Dam Retrofits

Examples of Local SP Alternatives

- **Transportation Infrastructure Improvements:** Evaluate bridges, roads, and other transportation infrastructure located in high-hazard areas and implement improvements as necessary to ensure reliability of emergency access and evacuation routes.
- **Drainage Structure Replacement Program:** Develop an inventory of culverts and other drainage structures and establish a program for replacing and improving inadequate and failure-prone stormwater infrastructure.
- **Electrical Grid Hardening:** Collaborate with utility providers to harden electrical grid infrastructure against hazards such as high wind and wildfire, including burying power lines, installing reinforced poles or protective devices, and managing nearby trees.

2.3.4.4 Cost/Benefit Review

Mitigation action plans must be prioritized according to a cost/benefit analysis of the proposed projects and programs and their associated costs. (44 CFR §2 01.6(c)(3)(iii)) The benefits of proposed actions were weighed against estimated costs as part of the project prioritization process; however, it should be noted that this review does not meet FEMA Hazard Mitigation Grant Program (HMGP) and Pre-Disaster Mitigation (PDM) grant program requirements. A less formal, less costly approach was used because some projects may not be implemented for up to 10 years, and associated costs and benefits could change dramatically in that time. Parameters were established for assigning subjective ratings (high, medium, and low) to the costs and benefits of these projects.

Cost ratings were defined as follows:

- **High:** Existing funding will not cover the cost of the project; implementation would require new revenue through an alternative source (for example, bonds, grants, and fee increases).
- **Medium:** The project could be implemented with existing funding but would require a re-apportionment of the budget or a budget amendment, or the cost of the project would have to be spread over multiple years.
- **Low:** The project could be funded under the existing budget. The project is part of or can be part of an ongoing existing program.

Benefit ratings were defined as follows:

- **High:** Project will provide an immediate reduction of risk exposure for life and property.
- **Medium:** Project will have a long-term impact on the reduction of risk exposure for life and property, or project will not provide an immediate reduction in the risk exposure for property.
- **Low:** Long-term benefits of the project are difficult to quantify in the short-term.

Using this approach, projects with positive benefit versus cost ratios (such as high over high, high over medium, medium over low, etc.) were considered cost-beneficial and prioritized accordingly. For many of the strategies identified in this action plan, the partners may seek financial assistance under the HMGP or PDM programs, both of which require detailed benefit/cost analyses. These analyses will be performed on projects at the time of application using the FEMA benefit-cost model. For projects not seeking financial assistance from grant programs that require detailed analysis, the partners reserve the right to define "benefits" according to parameters that meet the goals and objectives of this MJHMP.

2.3.4.5 Prioritization Framework

In addition to considering public and stakeholder input and the initial cost/benefit analysis, mitigation actions were prioritized according to four criteria. This prioritization framework was developed by the Steering Group to further focus the individual and county-wide mitigation strategies on those efforts that address the most concerning hazards, can achieve multiple outcomes, will have positive equity impacts,

and align with existing jurisdictional strategies. Action priority was scored on a scale of zero (low) to five (very high) using the following metrics:

- **Hazard Risk (+0-2):** Actions that address high-priority hazards based on the jurisdiction's completed Risk Matrix (medium+0, high+1, or extreme+2) (see Section 3.1.2.2).
- **Multi-Benefit Outcomes (+1):** Actions that achieve multiple beneficial ecological, social, and economic outcomes, including taking public and stakeholder perceptions into account.
- **Equity Impact (+1):** Actions that help reduce disparities in access to opportunities, improve environmental health conditions in disadvantaged neighborhoods, support vulnerable populations, or otherwise reduce socioeconomic barriers to mitigation.
- **Strategic Alignment (+1):** Actions that are in alignment with adopted local, regional, or state plans, policies, and programs.

2.3.5 MAST (Mitigation Action Support Tool)

Development of the mitigation strategy for this 2025 MJHMP was strengthened by using an online platform called MAST, the Mitigation Action Support Tool. MAST is a web-based interactive tool that enables multiple users to search, view, enter, and update mitigation actions, ideas or projects, and other information.

As the planning cycle progresses, MAST will also be used to monitor and revise the mitigation strategy. As a living document, mitigation activities will be updated through this web interface application developed specifically for this 2025 MJHMP.

State & Federal Funding Application Assistance

Using MAST, participating jurisdictions can improve their ability to apply for state and federal funding, including in the initial grant application processes through Cal OES. MAST provides participating jurisdictions and plan reviewers (Cal OES and FEMA) easy access to mitigation action details that can be leveraged to support future risk reduction efforts and specific mitigation projects within the planning area. Additionally, MAST can be used to assist jurisdictions in tracking project progress for grant and other required reporting.

Monitoring & Evaluating the Strategy

As local circumstances change and the plan evolves, mitigation actions will be updated through MAST. The online interface provides jurisdictions the ability to easily record changes and progress and to make adjustments to the strategy as needed. MAST will assist mitigation project managers across all the participating jurisdictions in making adjustments reporting on the status and effectiveness of the mitigation action and overall strategy.

As described in Section 2.4.1, a county-wide advisory team will oversee the collection and review of progress reports on jurisdiction-specific strategies and will develop a county-wide progress report to deliver to the

public and appropriate governing bodies annually. With MAST, updating the status and details of mitigation projects throughout the planning lifecycle will be greatly simplified and consolidated into one location.

2.4 Adopting & Implementing the Plan

Ensuring the MJHMP serves as a practical and accessible tool for Santa Cruz County and other participating jurisdictions is crucial for effective implementation and minimizing community hazard impacts. Section 2.4.2 describes the planning frameworks, maintaining ongoing public engagement, and establishing procedures for implementation, monitoring, evaluation, and regular updates to keep the plan current and responsive to evolving needs. These efforts aim to enhance resilience and safeguard community well-being against hazards.

The County and all participating jurisdictions adopted the plan in compliance with DMA 2000. See Adoptions Records in the Executive Summary of this plan.

2.4.1 Monitoring, Evaluating & Updating

This section describes the strategies for monitoring, evaluating, and updating the 2025 MJHMP throughout its lifecycle. Santa Cruz County and the other participating jurisdictions will monitor and adjust this plan in accordance with all FEMA and Cal OES requirements in order maintain eligibility for federal and state funding opportunities. The strategy includes designating an advisory team, monitoring progress and conducting annual reviews, continuing public and stakeholder engagement, and integrating the plan with other mechanisms to ensure its success.

2.4.1.1 Hazard Mitigation Advisory Team (HMAT)

The Steering Group oversaw the development of the 2025 MJHMP and made decisions on key elements of the plan, including the maintenance strategy; however, a Hazard Mitigation Advisory Team (HMAT) will oversee the implementation phase of the five-year planning cycle. The primary roles of the HMAT in overseeing the implementation of the MJHMP are:

- Acting as a forum for hazard mitigation issues and continuing to solicit community input
- Facilitating interjurisdictional collaboration on hazard mitigation
- Coordinating implementation efforts across jurisdictions and partner agencies
- Reviewing annual progress reports and developing a county-wide progress report
- Tracking county-wide strategy progress and making recommendations on improvements

The HMAT will strive to include representation from all participating jurisdictions, Key Stakeholders and other partner agencies, and members of the public. Keeping the HMAT intact for the duration of the planning cycle will also assist in jump-starting the next plan update.

The HMAT will exist as a subcommittee the Readiness Working Group (RWG), established during the Emergency Operations Plan (EOP) planning process from 2023 to 2024 to leverage existing partnerships relevant to whole community planning.

Duties of the HMAT

The HMAT will coordinate with the participating jurisdictions and other responsible parties for each county-wide mitigation action to assess its effectiveness and make modifications as appropriate. In addition, the HMAT will collect and review annual progress reports from participating jurisdictions and develop a county-wide report to provide input to the Santa Cruz County Board of Supervisors and, as appropriate, elected officials of other participating jurisdictions.

The progress reports will cover possible improvements to the county-wide and jurisdiction-specific strategies and changes to be considered at the next update, in addition to progress on mitigation actions. In evaluating the MJHMP's effectiveness, the following questions should be considered:

- Has the nature or magnitude of hazards affecting the planning area changed?
- Are there new hazards that have the potential to impact the planning area?
- Do the identified goals and actions address current and expected conditions?
- Have mitigation actions been implemented or completed?
- Has the implementation of identified mitigation actions resulted in expected outcomes?
- Are current resources adequate to implement the MJHMP?
- Should additional local resources be committed to address identified hazards?

Completion of the individual jurisdiction progress reports will be the responsibility of each participating jurisdiction annually. The reports will also be posted online for public review and released to the media. It will be the HMAT's role to help identify revisions and issues to be addressed by in the next update or other community plans.

The HMAT will also play a key role in preparing for the next MJHMP update by maintaining records and identifying emerging risks. Future updates to the plan will account for any new hazard vulnerabilities, special circumstances, or information or methodologies that become available. Issues that arise or updates made during the interim monitoring and evaluating period will be incorporated into the next update of the MJHMP, and the questions identified above will remain valid during its preparation.

2.4.1.2 Monitoring & Update Schedule

Monitoring the progress of mitigation actions will continue through the five-year period between adoption of this plan and the next update effort. The newly formed HMAT will meet annually, at a minimum, to monitor implementation, develop a progress and improvement report, and deliver that report to the Santa Cruz County Board of Supervisors and other jurisdictional decision-makers, as appropriate. The team's meeting schedule will be posted online, and meetings will be open to the public.

The MJHMP will be updated again after five years, as required by DMA 2000, and the update process will begin at least one year prior to the plan's expiration in 2031. However, should a significant hazard event occur within Santa Cruz County in the meantime, the HMAT will reconvene within 30 days of the disaster to review and update the plan as appropriate. As a DMA 2000 requirement, the County Board of Supervisors and decision-makers of other participating jurisdictions, as appropriate, will adopt any written updates.

Funding Assistance Monitoring

The true worth of any mitigation plan is its implementation and success under grant and other funding programs. This MJHMP was assembled to reduce the risk of natural hazards and also to meet the requirements of DMA 2000 to maintain eligibility under FEMA's Hazard Mitigation Assistance (HMA) grant programs. FEMA's HMA Program is the catalyst that drives increased understanding and supports proactive community action to reduce losses from natural hazards. As discussed further under Section 3.5.2, FEMA administers several programs that provide funding for local agencies with approved mitigation plans, including:

- **Hazard Mitigation Grant Program (HMGP):** Assists in implementing long-term hazard mitigation planning and projects following a Presidential major disaster declaration.
- **Flood Mitigation Assistance (FMA):** Provides funds for planning and projects to reduce or eliminate risk of flood damage to buildings that are insured under the National Flood Insurance Program (NFIP) on an annual basis.

Post-Disaster HMGP Process

Following a disaster, Cal OES and Santa Cruz County officials would perform Preliminary Damage Assessments (PDA) of areas that sustained damage in a joint effort with FEMA. Cal OES then submits the information collected through the FEMA Regional Office, along with a damage estimate to request a declaration from the President. A Presidential Major Disaster Declaration provides for the availability of HMGP funds at the request of the Governor in eligible communities. Figure 2-16 shows a timeline of how projects should be developed and administered by local government and FEMA under the HMGP program. HMGP grant recipients have 36 months from the close of the application period to complete projects.

Figure 2-16: HMGP Timeline

Mitigation Action Support Tool (MAST) Updates

Hazard problem statements and mitigation activities will be updated through a web-based interface application developed specifically for the county and other participating jurisdictions, which is available on the project website. This Mitigation Action Support Tool (MAST) will assist jurisdictions in making adjustments to their mitigation strategy as circumstances evolve, and will assist mitigation project managers across all the participating jurisdictions in reporting on the status and effectiveness of the mitigation action and overall strategy. Plan maintenance will be primarily performed through MAST, with most updates to the MJHMP occurring easily through this tool. MAST is further described in Section 2.3.4.4.

2.4.1.3 Continuing Public & Stakeholder Engagement

The strategy for continuing engagement will utilize the same goals and resources as the strategy for developing the 2025 update, as described in Section 2.1.2 and documented in Appendix B. During the five-year planning cycle, the HMAT and individual jurisdictions will continue to involve members of the community in the implementation phase of the process through public gatherings, meetings, and workshops. In addition, the Key Stakeholders involved in this update and other partner organizations will be invaluable resources for supporting continued public engagement, especially with underserved populations.

An electronic copy of the 2025 MJHMP document will be accessible through the Santa Cruz County website and at pre-determined physical locations. Santa Cruz County posts public notices and official information in its county administration building, which can be found at 701 Ocean Street, Santa Cruz, CA 95060.

Information on events related to hazard mitigation or the MJHMP will be announced via the same media tools discussed in Section 2.1.2.1, including jurisdictional and partner websites, social media, and the project website (mitigatehazards.com/santacruzmjhmp) and on the county's webpage.

2.4.2 Plan Integration

For the MJHMP to be successful, the recommendations and underlying principles of the plan should be incorporated into various aspects of local governance, including community planning and development (e.g., capital improvement budgeting) as well as everyday operations. Integration into a variety of departments and roles within the county and participating jurisdictions provides an opportunity to network, identify, and highlight mitigation activities and opportunities at all levels of government. It is also important to monitor resources and opportunities which can be leveraged to implement the mitigation strategy.

As the plan evolves, the following should be considerations for implementing and integrating the mitigation strategy:

1. **Use processes that already exist.** Take advantage of tools and procedures identified in the capability assessment in Section 3.5.1. Leaning on mechanisms already in use and familiar to participating jurisdictions will give the planning implementation phase a strong initial boost.
2. **Update work plans, policies, and procedures.** Incorporating hazard mitigation concepts and activities can help integrate the HMP into daily operations. These changes can include how major development projects are addressed in hazard-prone areas or can ensure that hazard mitigation concerns are considered in the approval of major capital improvement projects.
3. **Revise job descriptions.** Work with department or agency leads to revise job descriptions to include mitigation-related duties. Designating a "mitigation lead" within a department can further institutionalize hazard mitigation with little financial expenditure or programmatic overhaul.

The capabilities assessment for each participation jurisdiction identifies the past and current usage of various planning and regulatory mechanisms relevant to hazard mitigation, and opportunities for their future integration with the MJHMP directly or indirectly. This integration helps to ensure plan alignment with ongoing efforts, identify opportunities for integration, and avoid redundancy. In general, information from this MJHMP will be incorporated into:

- **General Plans:** The MJHMP will provide information that can be incorporated into the safety, land use, and other elements of general plans for the county and municipalities as they are updated, and many jurisdictions will update their safety element to incorporate the MJHMP in compliance with Assembly Bill (AB) 2140. Specific risk and vulnerability information from the MJHMP will also assist in identifying areas where development may be at risk to potential hazards for integration with land use, circulation, economic, and other elements.
- **Land Use and Development Regulations:** The MJHMP provides information that enables the county and other participating jurisdictions to make decisions on appropriate land use and development codes, such as zoning or construction standards which can increase resilience against natural disasters. Some participating jurisdictions' mitigation actions directly recommend updates to or adoption of new regulations to better address hazard risks.

- **Santa Cruz County Strategic Plan:** The Santa Cruz County Strategic Plan & Equity Framework outlines six strategic goals—including health and safety, housing, transportation, and environmental sustainability—that align closely with the objectives of the MJHMP. Both plans prioritize risk reduction, climate resilience, and equity, especially for vulnerable populations. The Strategic Plan's focus on cross-sector collaboration and data-driven outcomes directly supports MJHMP goals to integrate mitigation actions into broader county planning, ensuring a safer, more resilient Santa Cruz.
- **Hazard and Other Specific Plans:** The MJHMP will provide information that can be incorporated into community wildfire plans and other specific or areas plans, and the MJHMP likewise captured mitigation actions derived from these types of documents. The MJHMP will provide risk assessment information that can be included in updates to groundwater, stormwater, floodplain management, and other plans. In addition, the MJHMP may be integrated with capital improvement, operational, maintenance, or emergency response plans with valuable information from this plan such as geospatial hazard footprints, exposure summaries, and damage estimations.

A summary of county-related mechanisms into which hazard mitigation and this 2025 MJHMP have been or could be incorporated is provided in the Capabilities and Opportunities Assessment, Section 3.5.1. Capabilities assessments for other participating jurisdictions are provided in the Volume 2 annexes.

Section 3. Risk Assessment

The risk assessment measures the potential impacts of hazards on life, property, and critical facilities and infrastructure within Santa Cruz County. The intent of a risk assessment is to identify the qualitative and quantitative vulnerabilities of a community to the greatest extent possible given available data. These assessments increase understanding of hazard impacts and provide the foundation to develop and prioritize mitigation actions. In turn, mitigation actions reduce damage from disasters through increased preparedness and focusing resources on areas of the greatest vulnerability.

This risk assessment section evaluates potential losses from a given hazard event by assessing the vulnerabilities of people, buildings, and critical facilities and infrastructure. It identifies the characteristics and potential consequences of hazards, explores how much of the planning area could be affected by a hazard event, and assesses the impacts on county assets, specifically. Assessments for other participating jurisdictions are found in their individual annex in Volume 2, which build upon the hazard profiles in this Volume 1 section and then evaluate those particular jurisdictions.

The process used for the risk assessment is described in Section 2.2 and Appendix A; the approach consists of three main components:

- **Section 1.4, Community Profile:** Providing a geographic and demographic overview of Santa Cruz County as the basis for the assessment, highlighting the populations most vulnerable to hazards in the planning area.
- **Section 3.1, Hazard Identification & Prioritization:** Identifying hazards that pose the most significant threats and prioritizing them based on probability and potential impact in the county and other participating jurisdictions.
- **Section 3.2, Hazard Profiles:** Detailing the characteristics, history, probability, and potential impacts of each hazard, including:
    - **Exposure Analysis:** Mapping the populations, assets, and critical facilities and infrastructure exposed to each hazard.
    - **Vulnerability Analysis:** Assessing how susceptible different populations, structures, and other assets are to hazard impacts.

The Community Profile in Section 1.4 ensures that the needs of underrepresented communities are recognized in developing the mitigation strategy and used in future planning and policymaking to foster more equitable and sustainable environments. This approach not only safeguards the most vulnerable populations but also enhances the overall resilience of the entire community. Each Volume 2 annex contains a similar discussion of that jurisdiction's geographic and demographic characteristics as part of their individual risk assessment.

3.1 Hazard Screening & Prioritization

Per FEMA guidance, the first step in developing the risk assessment is to identify a list of natural hazards that pose a significant threat to Santa Cruz County. Hazard selection is a twofold process. First, the county-wide HMPT and each of the jurisdictional planning teams considered and screened a broad set of hazards profiled in local, regional, and statewide hazard planning documents. A crosswalk of documents reviewed and the results of screening the relevant hazards for the county-wide planning area are outlined in Section 3.1.1 and Table 3-1.

Second, the planning teams reviewed the history of hazard events, particularly over the last 5 years, which impacted the planning area and the potential effects of climate change on the frequency and severity of hazards to inform the prioritization process outlined in Section 3.1.2. The teams also took into account the initial results from public and stakeholder engagement on the community's top hazard concerns, which resulted in the addition of high wind and exclusion of soil hazards from this updated plan, for example (see a summary of this and other key findings from engagement in Section 2.1.2.3). This comprehensive approach ensures that the risk assessment is thorough and accounts for both established and emerging threats, providing a robust foundation for effective hazard mitigation planning.

Following completion of the screening and prioritization exercise for all individual jurisdictions, the HMPT discussed and formed consensus on which county-wide hazards would be included and profiled in the MJHMP. Based on their evaluation, the HMPT decided to profile ten priority hazards in this 2025 update.

Wildfire
SECTION 3.2.1

Flood
SECTION 3.2.2

Earthquake
SECTION 3.2.3

Severe Weather
SECTION 3.2.4

Coastal Hazards
SECTION 3.2.5

Slope Failure
SECTION 3.2.6

Dam Failure
SECTION 3.2.7

Drought
SECTION 3.2.8

Extreme Heat
SECTION 3.2.9

Climate Change
SECTION 3.2.10

3.1.1 Potential Hazards

The county-wide HMPT reviewed previously prepared hazard mitigation plans by the participating jurisdictions, as well as plans from regional and state entities, to determine the range of hazards with the potential to affect the planning area and surrounding region. Table 3-1 provides a crosswalk of hazards

identified in the 2021 Santa Cruz County HMP, 2020 Santa Cruz County General Plan Safety Element, and 2023 California State Hazard Mitigation Plan (SHMP).

The crosswalk was used to develop a preliminary hazards list, providing a framework for HMPT to evaluate which hazards were truly relevant county-wide. For example, volcanoes were considered to have no relevance to Santa Cruz County, while earthquake, flood, and wildfire were indicated in every hazard document. The preliminary hazards list was then used as the basis for prioritizing which hazards should be profiled and analyzed in detail in this 2025 MJHMP, as discussed in Section 3.1.2.

Each participating jurisdiction's planning team also completed this document review and crosswalk identifying potential hazards relevant to their individual planning area, the results of which are reported in the annexes of Volume 2.

Table 3-1: Document Review Crosswalk of Potential County-Wide Hazards

Hazard	2021 Santa Cruz County HMP	2020 Santa Cruz County General Plan Safety Element	2023 California SHMP
Agricultural Pests			■
Avalanche			■
Climate Change	■		■
Coastal	■	■	■
Dam Failure	■	■	■
Drought	■		■
Earthquake / Liquefaction	■	■	■
Extreme Cold	■		■
Extreme Heat	■		■
Extreme Weather / Storms	■	■	■
Flood	■	■	■
Geologic / Mass Movement	■	■	■
Human-Caused		■	■
Insects			■
Levee Failure	■		■
Pandemic Disease			■
Sea-Level Rise	■	■	■
Soil	■	■	■
Subsidence	■		■
Tornado			■
Tsunami / Seiche Wave	■	■	■
Volcano			■
Wildfire	■	■	■

3.1.2 Hazard Prioritization

The hazard prioritization process integrated historical data, future probability and impact potential, local knowledge, and consensus opinions to further evaluate the hazards identified through the hazard planning document crosswalk exercise described in Section 3.1.1. As part of this process, the planning team for each participating jurisdiction participated in their own prioritization exercise using a risk assessment matrix, which was used to determine whether each potential hazard is a medium, high, or extreme priority for the jurisdiction based on its unique characteristics.

The results of the hazard prioritization process for Santa Cruz County are displayed in the completed risk assessment matrix (Figure 3-1); the completed matrixes for all other participating jurisdictions are found in their respective Volume 2 annex and in the Planning Process Library (Table 2-10).

Hazards identified as county-wide priorities were profiled and thoroughly assessed, as provided in Section 3.2, and these hazards were also the focus of the mitigation strategies, with more deference given to those rated extreme and high.

3.1.2.1 Past Major Hazard Events

An important consideration in identifying and prioritizing hazards is the history of significant events, especially those which have triggered federal or state disaster declarations. The planning teams reviewed and considered past major hazard events affecting the planning area as part of the hazard screening and prioritization process, taking into account the frequency of events and severity of the impacts that were experienced. Further, hazard events occurring outside the planning area can directly or indirectly impact the community; thus, the teams also reviewed these past events. For example, dam failures or wildfires may occur outside Santa Cruz County but either hazard event could affect watersheds that drain into the planning area, resulting in flooding or longer-term watershed health impacts.

Most available information on major past hazard events comes from federal or state disaster declarations since these provide funding opportunities when the severity or magnitude of an event surpasses the abilities of the responsible governing body to respond and recover. State funding assistance can be provided when a local jurisdiction's capacity to respond to a disaster is exceeded and federal when the state's response and recovery capacities are also exceeded. Santa Cruz County had eight federally declared disasters between 2017 and 2024 alone.

The federal government may issue a disaster declaration through FEMA, the U.S. Department of Agriculture (USDA), or the Small Business Administration (SBA). FEMA also issues emergency declarations, which are more limited in scope and do not include the long-term federal recovery programs that accompany major disaster declarations. The quantity and type of damage are the determining factors. In California, an emergency proclamation authorizes the Governor's Office of Emergency Services (Cal OES) to provide assistance under the California Disaster Assistance Act, among other provisions.

A USDA disaster declaration occurs when agricultural areas, such as the Pajaro Valley, are particularly impacted by an event. This type of declaration certifies that the affected county has suffered at least a 30% loss in one or more crop or livestock areas and provides affected producers with access to low-interest loans and other programs to help mitigate the impacts. Importantly, all counties neighboring those receiving USDA disaster declarations are eligible for the same assistance.

The Santa Cruz County planning area has received 20 federal and 16 state disaster declarations since 1985, some of which were statewide disasters. Multiple hazard events triggered state declarations and were than also declared at the federal level. Table 3-2 and Table 3-3 identify all the federal and state disaster declarations in the county since 1985.

In the past decade, multiple costly hazard events have impacted various parts of, and sometimes the entire, county, and multi-million dollar disasters are hitting the area more frequently than in the past. The winter storms that occurred in late 2016 and early 2017 caused approximately $120 million in damage, and the CZU Lightning Complex Fire in 2020 was an approximately $340 million disaster, with over 86,000 acres burned and 920 homes destroyed. Destructive, climate change-driven winter storms that cause surge, wave run-up, high wind, landslides, flooding, and the occasional tornado are also increasing in frequency and severity and led to declarations in 2023 and 2024.

Table 3-2: Santa Cruz County Federal Disaster Declarations 1985 to Present

Year	Incident Description	Disaster No.
1986	Severe storms & flooding	DR-758-CA
1989	Earthquake (Loma Prieta)	DR-845-CA
1991	Severe freeze	DR-894-CA
1995	Severe storms & flooding	DR-1044-CA
1995	Severe storms & flooding	DR-1046-CA
1997	Severe storms & flooding	DR-1155-CA
1998	Severe winter storms & flooding (El Niño)	DR-1203-CA
2006	Severe storms, flooding, landslides	DR-1646-CA
2006	Severe storms & flooding	DR-1628-CA
2008	Wildfire (Summit Fire)	FM-2766-CA
2008	Wildfire (Martin/Bonny Doon Fire)	FM-2772-CA
2008	Emergency—California Wildfires	EM-3287-CA
2017	Severe winter storms, flooding & mudslides	DR-4301-CA
2017	Severe winter storms, flooding & mudslides	DR-4305-CA
2017	Severe winter storms, flooding & mudslides	DR-4308-CA
2020	COVID-19 pandemic	DR-4482-CA
2020	Wildfires (CZU Lightning Complex)	DR-4558-CA

Year	Incident Description	Disaster No.
2023	Emergency—Severe winter storms	EM-3591-CA
2023	Severe winter storms, flooding, landslides & mudslides	DR-4683-CA
2023	Severe winter storms, flooding, landslides & mudslides	DR-4699-CA
2024	Severe Winter Storms, Tornadoes, Flooding, Landslides, and Mudslides	DR-4769-CA

Source: FEMA Disaster Database

Table 3-3: Santa Cruz County State Disaster Declarations 1985 to Present

Year	Incident Description	Disaster / Executive Order No.
1986	Severe storms & flooding	86-01 (CDAA)
1989	Earthquake (Loma Prieta)	89-01 (CDAA)
1991	Severe freeze	91-01 (CDAA)
1995	Winter storms/flooding	95-01N (CDAA)
1995	Winter storms/flooding	95-03N (CDAA)
1995	Winter storms/flooding	95-04S (CDAA)
1997	Severe storms/flooding	97-01 (CDAA)
1998	El Niño storms/flooding	98-01 (CDAA)
2008	Wildfires (Summit, Martin/Bonny Doon Fire)	2008-02 (CDAA)
2006	Severe storms/flooding	2006-01 (CDAA)
2006	Severe storms/landslides	2006-03 (CDAA)
2017	Severe winter storms, flooding & mudslides	2017-01 (CDAA)
2017	Severe winter storms, flooding & mudslides	2017-02 (CDAA)
2017	Severe winter storms, flooding & mudslides	2017-03 (CDAA)
2021	Winter storms, atmospheric river event	Emergency Proclamation
2022	Extreme heat event	N-15-22, N-14-22
2022-2023	Severe winter storms, atmospheric river events	N-1-23, N-2-23, N-10-23
2023	Winter storms, atmospheric river event	N-6-23, N-7-23, N-9-23, N-10-23
2023-2024	Severe winter storms	Emergency Proclamation
2024	Severe winter storms	Emergency Proclamation
2024	Severe storms	Emergency Proclamation
2024	Major coastal winter storm	2025-03 (CDAA)

Source: Cal OES Disaster Database

3.1.2.2 Probability & Impact

After the county-wide HMPT and each of the jurisdictional planning teams determined the realm of hazards that could affect the planning areas, the teams then completed a risk ranking exercise to determine which hazards should be prioritized for assessment in this MJHMP and, consequently, which hazards should be the focus in the mitigation strategy.

The hazard prioritization process combines historical data, local knowledge, climate projects, and consensus opinions to produce a risk matrix that illustrates whether each profiled hazard is an extreme, high, medium, or low priority for the planning area. Criteria for probability verses impact were used to evaluate hazards and identify those that pose the highest risks. Hazards determined to have a minor or limited impact and unlikely or possible probability were generally categorized as low risk and excluded from the risk assessment while those determined to cause more severe impacts and have a higher probability are profiled in detail in Section 3.2.

Impact: What are the anticipated deaths, injuries, damages, or disruptions?

- **Minor:** Very few injuries, if any; only minor property damage and minimal disruption on quality of life; temporary shutdown of critical facilities.
- **Limited:** Minor injuries only; approximately 10% to 25% of property in disaster footprint damaged or destroyed, and complete shutdown of some critical facilities for more than one day.
- **Critical:** Multiple deaths and injuries possible; between 25% and 50% of property in disaster footprint is damaged or destroyed, and complete shutdown of critical facilities for more than one week.
- **Catastrophic:** High number of deaths and injuries possible; more than 50% of property in affected area damaged or destroyed, and complete shutdown of critical facilities for a month or more.

Probability: What is the likelihood of an event?

- **Unlikely:** Less than 1% annual probability, or might occur sometime in your lifetime.
- **Possible:** Between 1% and 10% annual probability, or likely to occur sometime in your lifetime.
- **Likely:** Between 10% and 100% annual probability, or will occur several times in your lifetime.
- **Highly Likely:** 100% annual probability, or likely to occur every year in your lifetime.

Secondary & Compounding Hazard Events

The MJHMP primarily examines the vulnerabilities of hazard events individually within the planning area. However, it is recognized that hazards often occur in combination, leading to compounded effects. Frequently, a secondary hazard is triggered by or occurs following the first event, such as a severe rain event following a wildfire that causes debris flows in the burn scar. Other events are compounded by outside factors, like wildfire evacuations occurring during Public Safety Power Shutoff (PSPS) events. This plan discusses these multi-hazard risks within the hazard profiles of Section 3.2 by highlighting potential secondary and compounding hazards that could result from initial events or intensify impacts.

The plan also considers the implications of pairing hazard events with the need for emergency evacuation or response, particularly in light of experiences during the COVID-19 pandemic. This includes local governments actively considering response and mitigation strategies that address the impacts of multiple hazard events, such as a pandemic occurring alongside other hazards like floods, severe weather, or wildfires.

By understanding the interplay among different hazards and preparing for compounded events, the MJHMP aims to enhance the resilience and preparedness of the planning area against a wide range of potential disaster scenarios.

Climate Change Impacts

Climate change is a global phenomenon that can impact many aspects of society including public health, natural and managed resources, critical facilities, buildings, infrastructure, and services. Projected changes to the climate are dependent on location. In California, the University of California Berkeley Geospatial Innovation Facility developed a platform called Cal-Adapt funded by the California Energy Commission (CEC). This platform provides tools and data on climate change across the state, including for Santa Cruz County, from global scale models that have been localized (downscaled) to 3.7-mile by 3.7-mile grids.

Santa Cruz County is experiencing climate change in various forms, including increasing frequency and severity of severe weather and wildfires, which offer a tangible glimpse of future conditions. Existing conditions combined with predictive modeling indicate that the impacts of climate change will continue to be significant and will increase over time impacting all aspects of the local environment, built and natural. Recent events, including the COVID-19 pandemic, reveal another clear truth: the impacts of climate change will disproportionately be experienced by the most vulnerable and marginalized populations.

Cal-Adapt data combined with information from the California Fourth Climate Change Assessment was used to model future changes in specific types of hazards in the 2022 Santa Cruz County Climate Action and Adaptation Plan (CAAP). Projections in the CAAP are outlined by two separate Representative Concentration Pathways (RCP):

- **RCP 4.5** is a medium emissions scenario where global emissions peak by the year 2040 and then decline.
- **RCP 8.5** is a high emissions scenario in which global emissions continue to rise through the end of the twenty-first century.

The 2022 CAAP outlines the potential impacts of climate change on various hazards and notes that all impacts will disproportionately affect vulnerable populations. Table 3-4 summarizes these projected climate change impacts.

Table 3-4: Climate Change Impacts on Hazards

Hazard	Description of Impacts
Extreme Heat	Annual number of extreme heat days above 90°F increase from 3 days to 19 days. Increases in average maximum temperature also contribute to worsening air quality.
Wildfire	Approximately 20% increased probability of wildfire in a 10-year period. Increases in wildfires also contribute to worsening air quality.
Slope Failure	Increased susceptibility of landslides as precipitation variability increases and wildfires increase in frequency, area, and severity.
Flood	Low-lying areas experiencing more frequent and intense flooding, with the area of flooding potentially expanding. Additionally, increased moisture transport and delivery from atmospheric river storms.
Sea-Level Rise	Up to 6.9 feet of sea level rise by 2100, also contributing to seawater intrusion in freshwater aquifers.
Drought	More frequent and severe periods of drought, challenging drinking water supplies and aquatic species habitat. Precipitation will arrive in more intense storms, increasing runoff and reducing the amount of water recharging local aquifers, further exacerbating the impacts of drought on water supply. Increases in longer periods of drought also contribute to worsening air quality.

Source: 2022 Santa Cruz County CAAP

County-Wide Priority Hazards

The results of the risk ranking exercise completed by the county-wide HMPT and then refined by the Santa Cruz County Planning Team are identified in the county's completed matrix in Figure 3-1. Table 3-5 provides additional details about why the county-wide priority hazards were chosen and why other hazards were not prioritized. However, it should be noted that many hazards not prioritized for profiling are briefly discussed as secondary or compounding hazards, and subhazards that were profiled and included in the risk assessment are listed specifically.

This prioritization exercise was also completed by all other jurisdictional planning teams, the results of which are described in the jurisdictional annexes of Volume 2 and provided in the Planning Process Library (Table 2-10).

Risk Assessment Matrix Definitions

PROBABILITY RATING

The likelihood of a hazard event occurring within a time period?

PROBABILITY

Highly Likely	**Highly likely** - 100% annual probability. Or Likely to occur every year in your lifetime.
Likely	**Likely** - between 10 & 100% annual probability. Or will occur several times in your lifetime.
Possible	**Possible** - between 1 & 10% annual probability. Or Likely to occur some time in your lifetime.
Unlikely	**Unlikely** - less than 1% annual probability. Or unlikely but possible to occur in your lifetime.

IMPACT RATING

In terms of injuries, damage, or death, would you anticipate impacts to be minor, limited, critical, or catastrophic when a significant hazard event occurs? The impact could be in terms of one hazard event (flooding from a culvert failure) or a large-scale event (multiple rivers flooding) in the same jurisdictional boundary.

IMPACT

Minor	Limited	Critical	Catastrophic

Minor - very few injuries, if any. Only minor property damage & minimal disruption on quality of life. Temporary shutdown of critical facilities.

Limited - minor injuries only. Approx. 10% or less of property in disaster footprint damaged or destroyed. Complete shutdown of critical facilities for more than one day.

Critical - multiple deaths/injuries possible. Between 25% and 50% of property in disaster footprint is damaged or destroyed. Complete shutdown of critical facilities for more than one week.

Catastrophic - high number of deaths/injuries possible. More than 50% of property in affected area damaged or destroyed. Complete shutdown of critical facilities for 30 days or more.

To concentrate resources, the jurisdictional planning team will focus on "High" and "Extreme" risk hazards. These hazards have the higher probability and greater impact as it relates to the jurisdictions planning area.

Hazard definitions are included in **Vol. 1** of this plan. Some hazards are discussed as subset hazards— e.g., "Dam Failure" within the "Flood" hazard profile. If a hazard is not present on the risk matrix or are grey in color, the jurisdictional planning team felt the hazard had a minimal footprint within their planning area and was not ranked.

Hazard Information / Legend:

CLIMATE CHANGE

Climate Change impacts will be addressed at the end of each hazard section and as a stand alone section for each jurisdiction.
For County and Municipal governments you will be required to address climate change impacts in the Safety Element of your General Plan. Climate change may change the frequency, duration and intensity of hazards listed above.

Santa Cruz County Risk Matrix



Figure 3-1: Santa Cruz County Risk Assessment Matrix

Table 3-5: County-Wide Hazards Prioritization Summary

Hazard	Priority	Explanation
Wildfire	**Extreme**	Profiled in Section 3.2.1
Coastal	**Extreme**	Profiled in Section 3.2.5, including Coastal Storm, Coastal Erosion, Wave Run-Up and Surge, and Tsunami
Earthquake / Liquefaction	**Extreme**	Profiled in Section 3.2.3, including Liquefaction
Extreme Weather / Storms	**High**	Profiled in Section 3.2.4, including High Wind, Heavy Rain, and Winter Weather
Flood	**High**	Profiled in Section 3.2.2, including Levee Failure
Geologic / Mass Movement	**High**	Profiled in Section 3.2.6 as Slope Failure
Drought	**High**	Profiled in Section 3.2.8
Extreme Cold	**High**	Profiled in Section 3.2.4 under Severe Weather
Levee Failure	**High**	Profiled in Section 3.2.2 under Flood
Sea Level Rise	**High**	Profiled in Section 3.2.10 under Climate Change
Climate Change	**High**	Profiled in Section 3.2.10, including Sea-Level Rise, and discussed as a compounding hazard in relevant profiles
Dam Failure	**Medium**	Profiled in Section 3.2.7
Extreme Heat	**Medium**	Profiled in Section 3.2.9
Tsunami / Seiche Wave	**Medium**	Profiled in Section 3.2.5 under Coastal Hazards
Agricultural Pests	-	Not a priority due to low impact potential
Avalanche	-	Not a priority due to low probability
Human-Caused	-	Not a priority due to being addressed in other plans
Insects	-	Not a priority due to low impact potential
Pandemic Disease	-	Not a priority due to being addressed in other plans
Soil	-	Not a priority due to low impact potential
Subsidence	-	Not a priority due to low impact potential
Tornado	-	Not a priority due to low probability
Volcano	-	Not a priority due to low probability

3.2 Vulnerability to Specific Hazards

This section contains the profiles for all ten medium to extreme priority hazards that affect Santa Cruz County and other participating jurisdictions and were identified by the county-wide HMPT. The hazard profiles contained in this Volume 1 provide detailed information on hazard characteristics and related local conditions, including:

- Profiled subhazards
- Secondary and compounding hazards
- Policies, plans, and regulations
- Past events and locations
- Frequency and future probability
- Severity
- Warning time
- Population and asset exposure
- Damage assessment (flood only)
- Hazard problem statements

Importantly, the profiles assess vulnerabilities specific to the unincorporated county and how the priority hazards may affect populations, property, and critical facilities and infrastructure within Santa Cruz County's jurisdiction. The same assessment is provided for other participating jurisdictions in the Volume 2 annexes. These risk assessments informed the problem statements that are provided at the end of each hazard profile and within the jurisdictional annexes.

Santa Cruz County's hazard mitigation strategy presented in 3.4.4 responds to the particular vulnerabilities outlined in this section and described in the problem statements. The mitigation strategy provides prescriptions or actions to achieve the greatest reduction of vulnerability, which will result in saved lives, reduced injuries, reduced property and critical facility damage, fewer service disruptions, and protection for the environment in the event of a natural hazard. The process and methods for calculating exposure and loss estimates are described in Section 2.2 and Appendix A.

Wildfire
SECTION 3.2.1

Flood
SECTION 3.2.2

Earthquake
SECTION 3.2.3

Severe Weather
SECTION 3.2.4

Coastal Hazards
SECTION 3.2.5

Slope Failure
SECTION 3.2.6

Dam Failure
SECTION 3.2.7

Drought
SECTION 3.2.8

Extreme Heat
SECTION 3.2.9

Climate Change
SECTION 3.2.10

Wildfire

3.2.1 Wildfire Hazard Profile

A wildfire is any uncontrolled fire occurring on undeveloped land that requires fire suppression. Wildfires can be ignited by lightning or by human activity such as smoking, campfires, equipment use, and arson. The 2018 California State Hazard Mitigation Plan defines wildfires as:

> *Any free-burning vegetative fire that initiates from an unplanned ignition, whether natural (e.g., lightning) or human-caused (e.g., powerlines, mechanical equipment, escaped prescribed fires), where the management objective is full suppression.*

Wildfires are costly, putting lives and property at risk and compromising watersheds, wildlife habitats, and recreation; agricultural, timber, and range land; historic, cultural, and scenic assets; and local economies. Wildfires can also severely damage critical facilities and infrastructure, including power lines, telecommunications networks, and water supply treatment and distribution systems. Vulnerability to flooding increases due to the destruction of forest and ground cover within watersheds. The potential for significant damage to life and property increases in areas where development is adjacent to densely vegetated areas, known as wildland-urban interface (WUI) areas. While some fires are allowed to burn naturally in order to maintain or restore the health of forest lands, out of control wildfires need to be prevented through land management planning.

Santa Cruz County is defined by a diverse topography, with dense urban development along the coastal terrace and mountainous and heavily forested terrain throughout the Santa Cruz Mountains. These conditions contribute to a heightened risk of wildfire and subsequent urban conflagration—extensive fires that damage or destroy large swaths of land and property. The rugged, steep terrain in the San Lorenzo Valley, Bonny Doon, and the North Coast not only influences wildland fire behavior but also poses significant challenges to fire suppression efforts.

In developed areas such as the City of Santa Cruz, Capitola, and the urban-wildland transition zones of Scotts Valley, the San Lorenzo Valley, Pajaro Valley, and the unincorporated communities of Aptos, Live Oak, and Soquel, ember cast is a primary driver of fire spread. These embers can ignite spot fires in ornamental landscaping, accumulated debris, or untreated wooden structures. Compounding this risk is the presence of dense vegetative fuels within and around urban cores, including greenbelts, riparian corridors, and unmanaged vacant lots. These vegetated areas can serve as ignition points for embers and facilitate rapid fire spread between structures.

As climate change intensifies wildfire season length and fuel aridity, the potential for destructive urban conflagration in Santa Cruz County is likely to increase. Targeted mitigation efforts focused on fuel management, defensible space enforcement, ignition-resistant construction, and coordinated suppression planning are critical to reducing this risk.

Fire Hazard Severity Zones (FHSZ)

To characterize wildfire risk at a landscape-scale, the California Department of Forestry and Fire Protection (CAL FIRE) has developed and maintains Fire Hazard Severity Zones (FHSZ). These zones are established using a statewide fire behavior modeling system that incorporates the following variables:

- Vegetation type and fuel load
- Topography (slope and aspect)
- Historical fire frequency and ignition density
- Weather conditions, including the number of days per year with extreme fire behavior potential
- Spot fire potential and ember cast range

According to the most recent FHSZ data, large areas of unincorporated Santa Cruz County fall within "High" or "Very High" severity zones, as discussed in Section 3.2.1.5 and identified on Figure 3-6, particularly in and around Bonny Doon, the San Lorenzo Valley, and southern areas near Corralitos and Watsonville. These zones correspond closely with regions impacted by recent major wildfires, such as the 2020 CZU Lightning Complex.

3.2.1.1 Secondary & Compounding Hazards

Wildfires can produce a wide range of secondary effects that extend beyond the immediate fire perimeter. These secondary and compounding hazards are briefly discussed in this section in relation to wildfire, and some are discussed in other profiles. In Santa Cruz County, these include slope destabilization from post-fire flooding in the Slope Failure Hazard Profile (Section 3.2.6), high wind in the Severe Weather Profile (Section 3.2.4), drought (Section 3.2.8), and climate change (Section 3.2.10).

Slope Destabilization & Sedimentation

According to the 2025 San Mateo-Santa Cruz Unit Strategic Fire Plan, high-intensity wildfires frequently lead to the loss of vegetation and soil structure, increasing vulnerability to erosion, debris flows, and landslides, particularly on the steep slopes of the Santa Cruz Mountains. Burned areas may also develop hydrophobic soils, which inhibit water infiltration and increase surface runoff. These post-fire conditions heighten the risk of localized flooding and sedimentation during subsequent rain events, sometimes persisting for multiple years after a fire. Ash and sediment from burned watersheds can contaminate streams and reservoirs, degrading water quality and impairing aquatic ecosystems.

High Wind

Wind plays a critical role in exacerbating fire spread. Santa Cruz County is subject to seasonal offshore winds, particularly in the fall, which can rapidly drive fires westward toward populated areas. In addition, local topographic wind effects within narrow canyons and ridgelines intensify fire behavior and contribute to the long-distance transport of embers.

Climate Change & Drought

Fire in western ecosystems is determined by climate variability, local topography, and human intervention. Climate change has the potential to affect multiple elements of the wildfire system: fire behavior, ignitions, fire management, and vegetation fuels. Hot, dry spells create the highest fire risk. Drought and increased temperatures intensify wildfire danger by drying out and stressing vegetation. Climate change also may increase winds that spread fires. Faster fires are harder to contain and, thus, are more likely to expand into residential neighborhoods.

Santa Cruz County is already considered to be an area that is at high-risk for wildfires. Climate change is projected to increase this current risk by anywhere from 10% to 20%, and the county will need to continue to adapt to this projected increase and the additional threats it brings to emergency services, roads, water supplies, housing access, and quality of life. For example, in October 2017 Sonoma County lost 5,300 homes, or 2.5% of its housing stock, in an already challenging housing market. (Beacon Economics, 2018)

As climate conditions shift toward longer fire seasons and drier fuels, secondary wildfire effects are expected to increase in both frequency and severity across Santa Cruz County. A changing climate is expected to subject forests to increased stress due to drought, disease, invasive species, and insect pests, such as the shothole borer. These stressors are likely to make forests more vulnerable to catastrophic fire due to increased standing dead biomass. While periodic fires are natural processes and fulfill an important ecological function, catastrophic fire events that cannot be contained or managed can cause serious threats to homes and infrastructure, especially for properties located in or adjacent to the WUI. Moreover, rain events are predicted to become more severe in our changing climate, and post-fire flooding and slope stabilization could worsen as well.

Smoke

Smoke from wildfire events contains high concentrations of fine particulate matter (PM2.5), carbon monoxide, and other harmful compounds. These pollutants can affect air quality across wide areas, even far from the fire source. According to the California Air Resources Board (2020), wildfire smoke poses serious health risks, especially for vulnerable populations such as children, seniors, pregnant individuals, and people with existing respiratory or cardiovascular conditions.

Urban Conflagration

In addition to natural wildland fire behavior, urban conflagration presents a growing hazard in Santa Cruz County. Urban conflagration refers to a large, uncontrolled fire that spreads rapidly through developed areas, often when wildfires enter densely built neighborhoods on the fringe of the WUI and typically fueled by structures and infrastructure rather than wildland vegetation. Unlike wildfires that primarily occur in the WUI and undeveloped areas, urban conflagrations pose unique risks to life and property due to the concentration of buildings, limited defensible space, and complex interdependencies among critical infrastructure systems.

According to FEMA and the National Fire Protection Association (NFPA), an urban conflagration occurs when a structural fire spreads from building to building in a continuous, uncontrollable manner, often involving multiple city blocks. This type of hazard is exacerbated by high winds, limited firefighting access, compromised water supply, and inadequate building separation or fire-resistance standards.

The 2020 CZU Lightning Complex Fire demonstrated the destructive potential of wildfires transitioning into residential zones (Figure 3-2). High winds, dry fuels, and closely spaced structures enabled rapid fire spread, resulting in the loss of nearly 1,000 homes and the displacement of tens of thousands of residents. Key factors contributing to urban conflagration include:

- Flying embers (firebrands) igniting structures and vegetative fuels far ahead of the main fire front
- Limited defensible space around structures
- Combustible building materials
- Narrow, steep, or dead-end access roads that hinder evacuation and response

The risk of urban conflagration is highest in areas with dense housing, limited infrastructure resilience, and poor access for fire suppression, such as parts of Bonny Doon, Boulder Creek, and the San Lorenzo Valley as well as along the urban services boundary adjacent to the unincorporated communities of Aptos, Corralitos, Freedom, Live Oak, and Soquel. As wildfire behavior intensifies due to climate and fuel conditions, the potential for fires to escalate into community-scale conflagrations will remain a critical concern for hazard mitigation and land use planning in Santa Cruz County.

Figure 3-2: 2020 CZU Lightning Complex Fire

Source: Santa Cruz County

3.2.1.2 Policies, Plans & Regulatory Environment

Wildfire Protection Responsibility

Local, state, tribal, and federal organizations all have legal and financial responsibility for wildfire protection. In many instances, two fire organizations have dual primary responsibility on the same parcel of land—one for wildfire protection and the other for structural fire protection. To address wildfire jurisdictional responsibilities, in 1981 the California State Legislature outlined various wildfire responsibilities, described below, in Public Resources Code § 4291.5 and Health and Safety Code § 13108.5:

- **Federal Responsibility Areas (FRAs):** FRAs are fire-prone wildland areas that are owned or managed by a federal agency such as the U.S. Forest Service, National Park Service, Bureau of Land Management, U.S. Fish and Wildlife Service, or U.S. Department of Defense. Primary financial and rule-making jurisdictional authority rests with the federal land agency. In many instances, FRAs are interspersed with private land ownership or leases. Fire protection for developed private property is usually not the responsibility of the federal land management agency but of the relevant local government agency. The only FRA in Santa Cruz County is the Cotoni-Coast Dairies National Monument near Davenport.
- **State Responsibility Areas (SRAs):** SRAs are lands in California where the California Department of Forestry and Fire Protection (CAL FIRE) has legal and financial responsibility for wildfire protection and where CAL FIRE administers fire hazard classifications and building standard regulations. SRA boundaries are those adopted by the California Board of Forestry and are reviewed and updated every five years. Where SRAs contain structures or development, the responsibility for fire protection of those improvements falls to the relevant local government agencies. SRAs are defined as lands that:
    - Are unincorporated county areas;
    - Not federally owned;
    - Have wildland vegetation cover rather than agricultural or ornamental plants; or
    - Have watershed, range, or forage values.
- **Local Responsibility Areas (LRAs):** LRAs include land in cities, cultivated agriculture lands, unincorporated non-flammable areas, and lands that do not meet the criteria for SRA or FRA. LRA fire protection is typically provided by city or county fire departments, fire protection districts, or by CAL FIRE under contract to local governments. LRAs may still include areas of flammable vegetation and WUI.

Wildfire Protection Responsibilities in Santa Cruz County

In Santa Cruz County, wildfire protection responsibility is shared by several entities, including CAL FIRE, local fire departments, and property owners. Property owners are responsible for maintaining defensible space around their homes, while CAL FIRE and local agencies focus on larger scale wildfire prevention and response within SRAs and other designated zones.

The Santa Cruz County Fire Department (SCCFD), through a contractual agreement with CAL FIRE San Mateo-Santa Cruz Unit (CZU), provides fire protection and emergency medical services to the

unincorporated areas of Santa Cruz County that are not served by a municipal fire department or fire protection district. The SCCFD has mutual aid agreements with several fire agencies, which are typically available and involved in suppressing wildland fires.

Fire Protection Agencies in Santa Cruz County	
▪ CAL FIRE San Mateo-Santa Cruz Unit	▪ Santa Cruz County Fire Department
▪ Aromas Tri-County Fire Protection District*	▪ Ben Lomond Fire Protection District
▪ Boulder Creek Fire Protection District	▪ Central Fire District
▪ Felton Fire Protection District	▪ Pajaro Valley Fire Protection District
▪ Santa Cruz Fire Department	▪ Scotts Valley Fire Protection District
▪ Watsonville Fire Department	▪ Zayante Fire Protection District

*Note: *Limited sphere of influence within county boundaries*

The SCCFD is a combination paid and volunteer department operating out of 12 fire stations, of which three are county-owned, seven are state-owned, and two are owned by volunteer companies or the local community. There are five volunteer fire companies (Companies 29, 32, 36, 37, and 41), four by contract with CAL FIRE through an Amador agreement[3] and one as a full-time career fire company. CAL FIRE and SCCFD operate as an integrated unit. CAL FIRE hires up to 140 seasonal firefighters annually to augment its career staff during the wildland fire season. The boundaries of the fire protection agencies operating in Santa Cruz County are identified on Figure 3-3.

[33] "Amador agreement" refers to a cooperative fire protection agreement, often between CAL FIRE and a county or other local agency, where the local agency funds supplemental staffing and operational costs to maintain fire protection services, particularly during the non-fire season. These agreements ensure year-round fire protection services, often in areas that might otherwise experience reduced staffing during the off-season.



Fire Protection Districts & CAL FIRE Battalions

Source: Santa Cruz County, CAL FIRE

Figure 3-3: Santa Cruz County Fire Protection Agencies Map

Federal Regulatory Environment

Healthy Forests Restoration Act

In 2003, the federal Healthy Forests Restoration Act (HFRA) appropriated specific funding to address five main sub-categories through the National Fire Plan (NFP): preparedness, suppression, reduction of hazardous fuels, burned-area rehabilitation, and state and local assistance to firefighters. Appropriations under this Act continue through the present. The spirit of the HFRA and NFP is reflected in the Santa Cruz County Community Wildfire Protection Plan (CWPP). The CWPP meets the requirements of HFRA by:

1. Identifying and prioritizing fuels reduction opportunities across the landscape;
2. Addressing structural ignitability;
3. Assessing community fire suppression capabilities; and
4. Collaborating with stakeholders.

State Regulatory Environment

California Public Resources Code § 4290

Public Resources Code § 4290 became effective in September of 1991. These regulations require the future design and construction of structures, subdivisions, and developments in SRAs to provide wildfire protection measures for basic emergency access and perimeter. These measures provide for emergency ingress and egress, signing and building numbering, private water supply reserves for emergency fire use, and vegetation modification.

California Public Resources Code § 4291

Public Resources Code § 4291 requires property owners in mountainous areas, forest-covered lands, or any land that is covered with flammable material to create, at a minimum, a 100-foot defensible space buffer around their homes and other structures. Defensible space must at least extend to the property line if a 100-foot buffer cannot be achieved.

California Building Standards Code

The California Building Standards Code, Title 24 of California Code of Regulations, incorporates the California Fire Code and is adopted every three years by order of the California Legislature with supplements published in intervening years. The code mandates specific requirements for new building construction, placing strong emphasis on proper address signage, fire apparatus access and maneuverability, water requirements, and defensible space.

Local Regulatory Environment

San Mateo-Santa Cruz Unit Strategic Fire Plan

The CAL FIRE, San Mateo-Santa Cruz Unit (CZU), is responsible for wildfire protection and forest resource management across San Mateo and Santa Cruz counties, including Battalions 3, 4, and 5 (Figure 3-3). The 2025 CZU Strategic Fire Plan, developed in alignment with the 2018 State Fire Plan framework, provides a comprehensive, locally-informed strategy to reduce wildfire risk through assessment, planning, mitigation, and collaboration.

The CZU plan identifies the region's significant wildfire challenges, including complex topography, a growing WUI, dense vegetative fuels, and increasingly volatile fire weather conditions driven by climate change. The plan emphasizes proactive management and the development of fire-adapted communities—areas where residents, landowners, and agencies work together to prepare for, withstand, and recover from wildfire events. Key components of the CZU Strategic Fire Plan include:

- **Firefighter and Public Safety:** Prioritizing safety through improved access, defensible space compliance, and community evacuation planning.
- **Hazardous Fuel Reduction:** Targeted treatment of high-risk vegetative fuels, including shaded fuel breaks, prescribed burning, and mechanical thinning, particularly in areas like the San Lorenzo Valley, Bonny Doon, and the North Coast.
- **Fire Suppression Preparedness:** Enhancing capabilities for rapid and effective response, supported by pre-attack plans, infrastructure improvements, and real-time fire intelligence systems such as drones.
- **Public Information and Education:** Expanding outreach through programs such as Firewise USA®, Ready, Set, Go!, and Community Emergency Response Teams (CERT), with a focus on homeowner responsibility and structural hardening.
- **Interagency Collaboration:** Strengthening coordination among local fire districts, county emergency services, non-profits, and land management agencies to align priorities and pool resources for mitigation and response.

The CZU Strategic Fire Plan serves not only as a guide for fire service professionals but also as a call to action for residents and community stakeholders to engage in wildfire resilience efforts. By integrating vegetation management, land use planning, and public education, the plan supports the overarching goal of reducing wildfire losses and enhancing the safety and sustainability of Santa Cruz County's communities.

Santa Cruz–San Mateo County Community Wildfire Protection Plan (CWPP)

The 2022 Santa Cruz–San Mateo County Community Wildfire Protection Plan (CWPP) identifies wildfire hazards and priority mitigation strategies for communities in Santa Cruz County, with a strong focus on WUI areas. The plan emphasizes that High and Very High Fire Hazard Severity Zones (FHSZ) are concentrated in the Santa Cruz Mountains, San Lorenzo Valley, Bonny Doon, Corralitos, and upper Soquel Creek watershed. These areas are characterized by steep slopes, narrow canyons, and dense vegetation—including chaparral, mixed hardwood, and conifer forests—that can promote rapid fire spread under

extreme weather conditions. Many WUI neighborhoods have limited access routes or dead-end roads, complicating both evacuation and fire suppression efforts.

To address these risks, the CWPP outlines a coordinated set of priority mitigation strategies. Vegetation and fuel management is central to the approach, including the expansion of shaded fuel breaks, roadside clearance along primary evacuation corridors, targeted mechanical thinning and mastication, and the use of prescribed burning where feasible. The plan also identifies numerous locally developed projects intended to reduce wildfire risk, improve emergency access, and protect life, property, and critical resources in Santa Cruz County. These projects were proposed by local fire safe councils, community groups, public agencies, and private landowners.

To better integrate the CWPP into this MJHMP, the individual proposals have been consolidated into five broad priority themes that capture the major types of wildfire mitigation activities planned or underway in the county. These themes address common needs across multiple communities and planning areas and are summarized in Table 3-6 with representative project locations and example activities based on the 2022 CWPP. Full project descriptions and sponsoring organizations are available in the CWPP's Appendix A.

Table 3-6: 2022 CWPP Priority Mitigation Projects

Project Theme	Representative Locations	Example Activities
Roadside Fuel Reduction & Shaded Fuel Breaks	Bonny Doon, Deer Creek, South Skyline (Hwy 35), Swanton, Laguna Creek, Brown Valley Rd, Geyer Rd, Kings Creek Truck Trail, Ward Rd	Roadside clearance, shaded fuel breaks, ladder fuel removal, contiguous break maintenance
Community Defensible Space & Chipping Programs	Cliffwood Estates, Redwood Drive (Aptos), Prospect Heights (Santa Cruz), Las Cumbres, Bonny Doon neighborhoods	Neighborhood defensible space projects, community chipper days, ongoing vegetation management
Critical Infrastructure Protection	San Lorenzo Valley Water District facilities, City of Santa Cruz infrastructure, UCSC Natural Reserve, Big Creek Lumber truck routes	Defensible space around tanks/pump stations, infrastructure hardening, access improvements
Evacuation Route Improvements	Trabing Fire area, Pilkington Rd–Paul Sweet Rd crossing, multiple private roads in WUI	Road widening, signage upgrades, bridge/turnout improvements
Fuel Management & Habitat Projects	UCSC chaparral, Bonny Doon Ecological Reserve, Land Trust properties	Prescribed fire alternatives, invasive species removal, habitat-compatible fuel reduction

Source: 2022 Santa Cruz–San Mateo County CWPP, Appendix A: Project Proposals, pp. 149–153

Santa Cruz County General Plan Public Safety Element

The Santa Cruz County General Plan Public Safety Element[4] includes comprehensive goals, policies, and implementation measures aimed at minimizing wildfire risks and protecting residents, property, and natural resources from fire hazards. These provisions reflect a longstanding commitment to fire-adapted community planning and resilience in the WUI, but integration of wildfire risk considerations into the element is also a state requirement, particularly in SRAs and Very High FHSZs.

Under Senate Bill (SB) 1241 from 2012 and Government Code § 65302(g)(3), the county must include policies and implementation measures that address wildfire hazards in these high-risk areas. Guidance to support these updates is provided by the Governor's Office of Land Use and Climate Innovation (LCI), which issues wildfire planning recommendations and California Environmental Quality Act (CEQA) checklist updates for local adoption. These requirements are further reinforced by AB 2140 and SB 379, which encourage integration of the local hazard mitigation plan and climate adaptation planning into the safety element. Together, these statutory requirements shape Santa Cruz County's wildfire policies within the General Plan, ensuring alignment with statewide mitigation, land use, and climate resilience goals.

The primary objective stated in the plan regarding fire hazards is to protect the public through citizen awareness, fire risk mitigation, responsible fire protection planning, and built-in systems for fire detection and suppression (Objective 6.7). Key policies and implementation programs in the element include:

- **Policy 6.7.1 Defensible Space:** In the State Responsibility Area and Very High Fire Hazard Severity Zones within the Local Responsibility Area maintain defensible space around structures in compliance with State law, County Fire Code, and local fire district ordinances. The amount of fuel modification necessary shall take into account the flammability of the structure as affected by building material, building standards, location, and type of vegetation. Fuels shall be maintained in a condition so that a wildfire burning under average weather conditions would be unlikely to ignite the structure. This does not apply to single specimens of trees or other vegetation that are well pruned and maintained so as to effectively manage fuels and not form a means of rapidly transmitting fire from other nearby vegetation to a structure or from a structure to other nearby vegetation. The intensity of fuels management may vary in the vicinity of the structure, with the most intense management being immediately around the structure. Consistent with fuels management objectives, steps should be taken to minimize erosion. For the purposes of this policy, "fuel" means any combustible material, including petroleum-based products and wildland fuels.
- **Policy 6.7.2 Defensible Space in Environmental Resource Areas:** Fuel reduction activities that remove or dispose of vegetation are required to comply with all federal, state or local environmental protection laws, including, but not limited to, laws protecting threatened and endangered species, sensitive habitats, water quality, air quality, and cultural/archeological resources, and must obtain any and all required permits.

[4] Santa Cruz County has two versions of the Safety Element: One for the Coastal Zone and the other for areas outside of the Coastal Zone. The referenced polices are from the Safety Element that applies to areas outside the Coastal Zone.

- **Policy 6.7.4 Access Standards:** Establishes detailed minimum design requirements for fire access roads, including width, grade, surface type, turnouts, and clearance. These standards are crucial for enabling fire apparatus access during emergencies and are applied to all new structures and major additions.
- **Policy 6.7.7 Land Division Fire Standards Outside the Urban Services Line:** Limits development density and requires secondary access, compliance with response time standards, vegetation modification, and water storage provisions for land subdivisions in high fire risk areas. When approving subdivisions in SRAs and Very High FHSZs, the county must also make special findings to ensure adequate emergency access and fire protection services, pursuant to Government Code § 66474.02.
- **6.7.8 Standards for New Dead-End Roads:** Prohibit newly constructed dead-end roads without secondary access serving more than one parcel in new minor land divisions or subdivisions which exceed the following distances from an adequate through road unless approved by the applicable fire protection agency, the Department of Public Works, and by the Planning Commission; in no case shall a new dead-end road exceed ½ mile in length.
- **Urban and Suburban General Plan and Local Coastal Program (LCP) Land Use Plan:** Designate 500 feet
- **Rural General Plan and LCP Land Use Plan:** Designate 1,000 feet
- **Mountain General Plan and LCP Land Use Plan:** Designate 1,500 feet
- **Subdivision Regulations:** The standard for new subdivisions of five or more lots shall not exceed 500 feet from a through road unless acceptable to and recommended by the applicable fire protection agencies and the Department of Public Works and approved by the Planning Commission.
- **Policy 6.7.10 Certification of Adequate Fire Protection:** Mandates fire agency certification for adequate protection before approval of new subdivisions, multifamily complexes, or critical infrastructure projects.
- **Policy 6.7.12 Code Consistency:** Ensures all development adheres to current fire and building codes, including the Uniform Fire Code and California Fire Code.
- **Programs D and E Firebreak Planning:** Develops and implements strategic firebreaks to buffer communities from adjacent vegetated areas.
- **Program F Emergency Access Planning:** Aims to provide at least two emergency access routes for all communities.
- **Programs G and H Infrastructure Upgrades:** Prioritizes water system enhancements and fire protection facility expansion within the Urban Services Line.
- **Program L Public Education and Outreach:** Supports educational initiatives on fire prevention and home hardening.
- **Program P Mitigation Funding Tools:** Encourages the use of assessment districts for road improvements, water infrastructure, and vegetation management.

These policies and implementation programs form a critical component of Santa Cruz County's integrated approach to wildfire risk mitigation. In conjunction with the CZU Strategic Fire Plan and CWPP, they guide land use decisions, emergency planning, and public investment in infrastructure resilience.

Building Code

All Santa Cruz County jurisdictions have adopted the 2022 Edition of the California Building Standards Code, including Chapter 7A of the California Building Code (CBC) and Section R337 of the California Residential Code (CRC). As codified in Chapter 12.10 of the county's code, local amendments to the state codes strengthen wildfire resilience in new construction and exterior remodels. These amendments are designed to protect life and property in the county's extensive SRAs and WUI zones.

Title 7A of the California Building Code establishes minimum construction standards for buildings located in designated FHSZs and WUI areas. It aims to reduce wildfire ignition risk by requiring fire-resistant materials and designs for key exterior components, such as Class A roofing, ember-resistant vents, noncombustible siding, tempered windows, enclosed eaves, and ignition-resistant decking. These requirements apply to all new construction and substantial remodels after July 1, 2008, helping prevent structure-to-structure fire spread and improving building survivability during wildfire events.

The county's refinements remove state-level exceptions and expand ignition-resistant construction requirements to a broader range of projects, reinforcing structure hardening and ember resistance. Table 3-7 exhibits how the county codes differ from the baseline state code.

Table 3-7: Santa Cruz County Amendments to California Building Code

Category	California Building Code (CBC / CRC)	Santa Cruz County Amendments (Chapter 12.10)
Applicability of WUI Regulations	CBC Chapter 7A and CRC Section R337 apply to buildings in Very High FHSZs in SRAs or LRAs.	Chapter 7A and R337 standards apply to all new structures, additions, and exterior remodels located in SRAs. *Ref: §12.10.215(C)*
Exceptions to WUI Standards	CBC 7A and CRC R337 allow exceptions (e.g., Exception 1: ≤100 sq ft roof/siding; Exception 2: broken windows; Exception 4: vents; Exception 5: minor deck repair).	Deletes exceptions 1, 2, 4, and 5, effectively removing exemptions for most minor work. Only Exception 3 (for tent structures in campgrounds) is retained. *Ref: §12.10.215(C)(3)*
Trigger Threshold for Compliance	WUI provisions apply only to new buildings or major remodels in mapped Very High FHSZs.	WUI provisions apply to any permit-triggered exterior work, including remodels, alterations, or additions in SRAs. *Ref: §12.10.215(B), §12.10.215(C)(1)*
Required Building Features	Requires ember-resistant vents, Class A roofing, ignition-resistant siding, and tempered windows in designated areas. *Ref: CBC §§705A–708A; CRC §§R337.5–R337.10*	Same standards enforced but required universally in SRAs regardless of project size or partial alterations. *Ref: §12.10.215(B), (C)(1)*
Compliance Documentation	WUI compliance documentation only required for qualifying buildings.	Mandatory submittal of WUI checklist, fire severity map confirmation, and proof of approved materials (e.g., OSFM product listings) for all covered projects. *Ref: §12.10.215(C)(2)*

Category	California Building Code (CBC / CRC)	Santa Cruz County Amendments (Chapter 12.10)
Administrative Responsibility	Discretionary enforcement varies by local Authority Having Jurisdiction..	County Planning and Building Departments are responsible for reviewing and enforcing wildfire standards across SRA permit applications. *Ref: §12.10.215(D)*

Fire Code

Santa Cruz County jurisdictions have adopted the 2022 Edition of the California Fire Code (with local amendments) to safeguard the public from the hazards of fire in new and existing buildings, structures, and premises, and to provide safety and assistance to fire fighters and emergency responders during emergency operations.

The county amendments to the California Fire Code in Chapter 7.92 introduce refinements and stricter standards in several key areas, tailoring fire safety regulations to the county's unique topography, WUI risks, and rural development patterns. Table 3-8 exhibits how the county code differs from and exceeds minimum state requirements.

Table 3-8: Santa Cruz County Amendments to California Fire Code

Topic	California Fire Code	County Amendments
Access Roads	20-ft standard, flexible	20-ft standard, strict grades and turnouts
Dead-End Roads	General guidance	Zoned length limits, secondary access mandates
Bridges	Local standards apply	25-ton load, 10-year certification, 20-ft width
Ember Ignition	Local discretion	Lantern bans, distance rules, firewatch mandates
Appeals	Allowed	Formal board, structured timelines
Signage & Gates	Generic	Specific minimums for signage, clearance, locks

Measure Q: Safe Drinking Water, Clean Beaches, Wildfire Risk Reduction & Wildlife Protection Act

The Santa Cruz County Safe Drinking Water, Clean Beaches, Wildfire Risk Reduction, and Wildlife Protection Act (also known as Measure Q) is codified in Chapter 4.65 of the county code and establishes a special parcel tax of $87 per parcel annually starting fiscal year 2025 to 2026, generating approximately $7.3 million per year. Revenues are deposited into a dedicated fund, overseen by the county's Office of Response, Recovery, and Resilience (OR3) and the County Parks and Open Space Department, with separate subaccounts to support the different types of projects that meet the intent of the act. Within the expenditure categories, wildfire risk reduction is explicitly supported through:

- Fuel treatment programs such as implementation of shaded fuel breaks, hazardous vegetation clearance, and prescribed fire.

- Forest and land stewardship projects targeting defensible space creation, forest health improvement, and wildfire resilience enhancements on public and private lands.
- Infrastructure safety, including clearing debris from emergency access routes to support firefighting and evacuation efforts.

Eligible projects include planning, acquisition, construction, restoration, and long-term maintenance phases.

3.2.1.3 Past Events & Location

Between 1985 and 2024, Santa Cruz County experienced many notable wildfires, including the CZU Lightening Complex Fire, which was the most destructive in county history to date. These incidents occurred across various parts of the county, primarily in forested and mountainous terrain. Figure 3-4 identifies the burn areas of recent wildfires that occurred since the early 2000s and each consumed over 100 acres.

Notable Wildfires in Santa Cruz County

- **1985 – Lexington Fire:** Spanning an estimated 14,500 acres (with partial impact in Santa Cruz County), this regional fire foreshadowed the scale of events now seen more frequently under extreme weather and fuel conditions.
- **1993 – Gazos Fire:** This smaller but notable fire burned 1,450 acres near the San Mateo County line. Although it did not result in significant structure loss, it reaffirmed the region's susceptibility to coastal-range wildfires.
- **2008 – Summit Fire:** The Summit Fire was ignited in May 2008 and burned 4,270 acres in southern Santa Cruz County. The fire destroyed 132 structures and required extensive aerial suppression efforts. Its proximity to residential areas underscored the threat of WUI ignition sources during wind events.
- **2008 – Trabing Fire:** Trabing was a fast-moving fire near Freedom and Aptos that burned 630 acres and destroyed several homes. It highlighted the dangers of rapid fire spread in lowland vegetated corridors adjacent to transportation infrastructure.
- **2009 – Lockheed Fire:** This fire burned 7,817 acres in the Bonny Doon area, destroying 13 structures and causing over 2,000 residents to be evacuated. Lockheed occurred in dense vegetation with limited road access, posing significant challenges for fire suppression and containment.
- **2020 – CZU Lightning Complex Fire:** The most destructive wildfire in county history was ignited by lightning on August 16, 2020. It burned 86,509 acres across Santa Cruz and San Mateo Counties, destroyed nearly 1,500 structures, and led to the evacuation of more than 77,000 residents. The fire caused over $340 million in damages and revealed vulnerabilities in communication systems, evacuation infrastructure, and fuel buildup.

These events collectively demonstrate that wildfire is not an emerging threat but a recurring hazard with escalating impacts due to climate change, fuel accumulation, and continued development in high-risk areas. Mapping of historic fire perimeters (Figure 3-4) shows consistent patterns of ignition and spread,

especially along ridgetops and steep drainages in the San Lorenzo Valley and Bonny Doon areas. Figure 3-6 identifies Moderate, High, and Very High FHSZs, which are mostly within SRAs; although, some fire hazard areas in the county are local responsibility, especially within and near urban centers. Understanding the behavior, scale, and locations of these historic fires and understanding future high fire risk areas are critical for shaping future mitigation strategies.



Figure 3-4: County-Wide Historic Large Fires Map

3.2.1.4 Frequency & Probability of Future Occurrences

Wildfires are a regular and recurring hazard in Santa Cruz County. The likelihood of future wildfire events is high, particularly in areas with dense vegetation, steep terrain, and limited access. Based on local fire history and climate conditions, the probability of wildfire occurrence in any given year is classified as "Highly Likely," indicating an annual or near-annual probability of one or more wildfire events.

To better quantify wildfire frequency, the county uses the Mean Fire Return Interval (MFRI), a metric that estimates the average number of years between fires at a given location. See Figure 3-5 for county-wide MFRI. According to the U.S. Geological Survey (USGS) LANDFIRE dataset, much of the unincorporated area of Santa Cruz County has an MFRI between six and 35 years, with some interior ridge and slope areas showing return intervals as short as zero to 12 years, especially in the Santa Cruz Mountains and San Lorenzo Valley. These areas are prone to more frequent fire activity due to fuel type, terrain, and ignition history.

Conversely, coastal and lower valley areas exhibit longer fire return intervals, typically over 50 years, reflecting lower fuel loads and more fragmented wildland vegetation. However, as climate change accelerates fuel drying, increases wind events, and lengthens the fire season, return intervals are expected to shorten in some areas, potentially increasing the number and intensity of wildfire events in the coming decades.

3.2.1.5 Severity

Wildfire severity in Santa Cruz County is driven by several interrelated factors, including vegetation type and density, topography, and fire weather frequency, which correlate with CAL FIRE's Fire Hazard Severity Zones (FHSZ) (Figure 3-6). The county's fuel profile includes coastal scrub, chaparral, oak woodland, Douglas-fir, and redwood forests, many of which support dense surface and ladder fuels. Steep slopes, particularly in the Santa Cruz Mountains, contribute to rapid fire spread and greater flame lengths, especially under dry and windy conditions.

The modeling process for mapping fire severity zones also evaluates potential fire intensity, rate of spread, and ember dispersion based on empirical data and simulations. However, FHSZ designations focus solely on **hazard**, not risk—meaning that **land use, structure hardening, and community-level mitigation efforts** are not factored into zone assignments.

Critical fire weather in Santa Cruz County—defined by a combination of high temperatures, low humidity, and sustained winds—typically occurs from late summer through early fall, with Red Flag Warnings issued several times each year. Under such conditions, fire intensity and spread rates increase significantly, particularly in vegetated canyon systems and along ridgelines.



Mean Fire Return Interval

Unincorporated County

*Data sources: USGS LANDFIRE.

average period between fires (Years)

0-5	6-10	11-15	16-20	21-25	26-30	31-35	36-40	41-45	46-50	51-60	61-70	71-80	81-90	91-100	101-125	126-150	151-200	201-300	301-500	501-1000	>1000

Figure 3-5: County-Wide Mean Fire Return Interval (MFRI) Map



Wildfire Risk Exposure
Unincorporated County
*Data sources: Cal Fire.

Figure 3-6: County-Wide Fire Hazard Severity Zones (FHSZ) Map

3.2.1.6 Warning Time

Warning time for wildfires in Santa Cruz County can be limited, depending on ignition source, weather conditions, and location. Peak wildfire concern typically coincides with dry seasons and periods of drought, when vegetation becomes more flammable. Wildfires may ignite with little or no advance notice, particularly those caused by human activity such as debris burning, equipment use, or fireworks. The Fourth of July is a period of elevated fire risk due to increased ignition sources from fireworks.

Some wildfires may be preceded by predictable weather conditions, such as dry lightning storms or high-wind events. The National Weather Service provides Red Flag Warnings and lightning forecasts typically 24 to 48 hours in advance of potential ignition events. These forecasts can be used to elevate local readiness and outreach.

Once a wildfire begins, detection and alerting are generally prompt due to expanded communication networks, including cell phones, reverse-911 systems, and emergency radio broadcasts. Wildfire intensity typically peaks in the early- to mid-afternoon, when temperatures are highest, humidity lowest, and fire spread rates are greatest. Depending on fire growth, local conditions, and proximity to the event, evacuation timeframes may range from several hours to merely minutes.

CruzAware Notification System

CruzAware is Santa Cruz County's official alert and notification system. It is administered by the County Office of Response, Recovery and Resilience (OR3) and is designed to provide residents and visitors with timely warnings and information during emergencies. Notifications are sent by text message, telephone, or email and address a range of hazards including wildfire, as well as other public safety threats and evacuation notices.

For wildfire, CruzAware serves as a primary tool for delivering warnings before hazardous conditions develop and notifications during an event. Depending on the situation, alerts may be issued hours or only minutes in advance. These notifications can include evacuation instructions, shelter locations, and road closure information. The system is capable of targeting specific neighborhoods or hazard zones so that alerts are relevant to those directly at risk.

The system works in coordination with other county resources to support comprehensive hazard communication. The county also partners with the National Weather Service (NWS) to disseminate official watches and warnings, including Red Flad Warnings. NWS alerts are automatically issued through the Wireless Emergency Alerts (WEA) system to mobile devices in affected areas, providing rapid notification without the need for prior registration. More information about CruzAware, including how to register, is available at santacruzcountyca.gov/CruzAware.

3.2.1.7 Wildfire Vulnerability Assessment

Santa Cruz County remains vulnerable to wildfire impacts, despite its efforts to reduce risk through planning, policies, and mitigation programs. This section identifies wildfire vulnerability in relation to people, property, and critical facilities and infrastructure. Estimates of population exposure, parcel values, critical facilities, and lifeline infrastructure were developed by overlaying these asset inventories with CAL FIRE's Fire Hazard Severity Zones (FHSZs). Figure 3-7 provides a summary of wildfire exposure across the county. It should be noted that this risk assessment analyzes exposure only, meaning results are based on whether a population, parcel, or facility falls inside or outside of the mapped hazard zones.

It is important to recognize that FHSZs have a regulatory basis; CAL FIRE is charged with their designation under state law, and these zones trigger specific requirements in the California Building and Fire Codes. However, these zones are primarily designed to represent hazards from wildland fuels and do not capture the full scope of wildfire risk, particularly the potential for urban conflagration within the built environment. Additionally, insurance companies rely on proprietary models, often integrating high-resolution data such as LiDAR, drone imagery, and localized site conditions, which may result in different risk designations at the parcel level. Understanding these distinctions is critical for effective planning and risk communication.



Figure 3-7: Exposure Summary – Santa Cruz County Wildfire Risk

3.2.1.7.1 Population

One way to understand Santa Cruz County's wildfire exposure is through the Fire Hazard Severity Zones (FHSZ) developed by CAL FIRE. Wildfire risk is of greatest concern to populations residing in the High and Very High FHSZs. Roughly two-thirds of the county's population lives in these zones, with the majority in "high" severity areas and a smaller but still significant share in very high zones, as shown in Figure 3-8. This concentration of population in high-risk areas means that large wildfires have the potential to impact a substantial portion of residents, causing infrastructure damage, degrading air quality, and disrupting essential services well beyond the immediate burn area.

Smoke and air pollution from wildfires can be a severe health hazard, especially for sensitive populations including children, the elderly, and those with respiratory and cardiovascular diseases. Smoke generated by wildfire contain visible and invisible emissions that contain particulate matter such as soot, tar, water vapor, and minerals; gases such as carbon monoxide, carbon dioxide, and nitrogen oxides; and toxins such as formaldehyde and benzene. Emissions from wildfires depend on the type of fuel, the moisture content of the fuel, the efficiency or temperature of combustion, and the weather. Widespread public health impacts associated with wildfire include difficulty in breathing, odor, and reduction in visibility. First responders likewise are exposed to the dangers from the initial incident and after-effects from smoke inhalation and heat stroke



Figure 3-8: Unincorporated County Population Exposed to Wildfire Risk

Table 3-9: Unincorporated County Population in SRA vs. LRA Fire Hazard Severity Zones (LHSZ)

	Total Population
Unincorporated County	131,149

Wildfire Severity Zone (FHSZ)	Population Count	% of Total
Moderate	**20,434**	**15.58%**
LRA Moderate	6,324	*4.82%*
SRA Moderate	14,110	*10.76%*
High	**46,234**	**35.25%**
LRA High	3,895	*2.97%*
SRA High	42,339	*32.28%*
Very High	**5,450**	**4.16%**
LRA Very High	146	*0.11%*
SRA Very High	5,304	*4.04%*
Total	**72,117**	**54.99%**

Agricultural & Outdoor Workers

Wildfire can significantly impact outdoor workers in Santa Cruz County, including those in agriculture, landscaping, construction, and utility services. Agricultural workers—particularly those in the county's strawberry, vegetable, orchard, and vineyard sectors—are especially vulnerable, as peak harvest and planting periods often coincide with the region's highest wildfire risk. Smoke and degraded air quality can create unsafe working conditions, while road closures, evacuation orders, and damaged transportation infrastructure can limit access to fields and worksites. Many agricultural workers live outside the county due to high housing costs and limited affordable housing, increasing their reliance on regional transportation routes that may be disrupted during wildfire events.

3.2.1.7.2 Property

Wildfire risk in Santa Cruz County is not only a matter of population exposure, it also represents a significant concentration of economic value in high-risk areas. County parcel data shows that in the unincorporated county area, the total market value of residential property located within High and Very High FHSZs exceeds $20 billion, accounting for approximately 38% of the county's total market value. This figure reflects current real estate market conditions in Santa Cruz County, where high housing demand, limited supply, and elevated construction costs have driven property values to some of the highest in California.

The financial risk is not theoretical. In the aftermath of the 2020 CZU Lightning Complex Fire, hundreds of property owners encountered existing insurance policy shortfalls, escalating construction and insurance costs in a challenging market environment, and modern building code or development standards. Even if certain development standards can be temporarily suspended by elected officials, the complexity and apparent need to dismiss adopted policies underscores the challenges of rebuilding, especially within

legacy development patterns. The initial destruction from wildfire hazards combined with the many challenges associated with rebuilding compounds the community exposure to this economic insecurity over the long term.

In Santa Cruz County, the destruction of even a small percentage of the housing stock in high or very high severity zones could translate into hundreds of millions of dollars in direct property losses, not including the broader economic and social costs of displacement, infrastructure damage, and loss of taxable property value. Table 3-10 provides a detailed breakdown of parcel counts, market values, and total exposure by FHSZ, underscoring the fiscal stakes associated with wildfire mitigation and preparedness in Santa Cruz County.

Table 3-10: Santa Cruz County Property in SRA vs. LRA Fire Hazard Severity Zones (FHSZ)

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

FHSZ	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
Moderate	**8,886**	**18.66%**	**$6,767,219,997**	**$3,638,488,998**	**$10,405,708,995**	**19%**
LRA Moderate	2,507	*5.3%*	$2,101,182,397	$1,176,609,598	$3,277,791,995	*6.0%*
SRA Moderate	6,379	*13.4%*	$4,666,037,600	$2,461,879,400	$7,127,917,000	*13.1%*
High	**16,308**	**34.24%**	**$11,895,609,999**	**$6,137,691,999**	**$18,033,301,998**	**33%**
LRA High	1,610	*3.4%*	$1,207,929,601	$638,923,400	$1,846,853,001	*3.4%*
SRA High	14,698	*30.9%*	$10,687,680,398	$5,498,768,599	$16,186,448,997	*29.8%*
Very High	**2,526**	**5.30%**	**$1,706,991,201**	**$911,415,601**	**$2,618,406,801**	**5%**
LRA Very High	46	*0.1%*	$36,790,000	$26,774,000	$63,564,000	*0.1%*
SRA Very High	2,480	*5.2%*	$1,670,201,201	$884,641,600	$2,554,842,801	*4.7%*
Total	**27,720**	**58.2%**	**$20,369,821,197**	**$10,687,596,598**	**$31,057,417,795**	**57.2%**

3.2.1.7.3 Critical Facilities & Infrastructure

Essential facilities, high-potential-loss sites, and lifeline infrastructure in Santa Cruz County face substantial wildfire risk due to their location within CAL FIRE-designated High and Very High FHSZs. Many of these facilities are constructed with combustible materials or lack adequate defensible space, making them vulnerable to ember intrusion, radiant heat, and direct flame contact.

The exposure in Santa Cruz County is widespread. Several essential facilities such as fire stations, law enforcement facilities, hospitals, and emergency operations centers are located in wildfire-prone areas, meaning that a major fire could impair emergency response when it is most needed. Schools are also notably exposed, with more than 20 school sites in high or very high-hazard zones, creating both evacuation challenges and potential long-term disruption to education and community services.

Critical community infrastructure is also at risk. Transportation and lifeline systems—such as bridges, culverts, substations, and airports—account for the largest number of exposed assets, with over 3,000 such facilities in high and very high-hazard zones, as identified in Table 3-11. Disruption to even a few of these key assets could isolate neighborhoods, delay firefighting operations, and slow recovery.

Many high potential loss facilities, including healthcare and childcare facilities, large mobile home parks, and historic buildings, are also located in wildfire hazard zones. The loss of these sites could cause both significant economic damage and long-term cultural or social impacts.

Hazardous materials facilities, (labeled as Hazardous Waste Tracking System (HWTS)) including hazardous waste treatment and cleanup sites, are present in wildfire hazard zones as well. Wildfire damage to these facilities could create cascading environmental and public health issues that extend far beyond the immediate burn area.

Table 3-11 provides a detailed inventory of these essential facilities and infrastructure assets by wildfire hazard classification, illustrating the scope of potential loss should a large wildfire occur in Santa Cruz County.

Table 3-11: Santa Cruz County Critical Facilities in SRA vs. LRA Fire Hazard Severity Zones (FHSZ)

Critical Infrastructure - Wildfire Severity Zone									
Infrastructure Type	SRA Very High	LRA Very High	Very High Total	SRA High	LRA High	High Total	SRA Moderate	LRA Moderate	Moderate Total
Essential Facilities	4	-	4	15	2	17	6	1	7
Fire Station	3	-	3	13	1	14	5	-	5
Hospital	-	-	-	-	-	-	-	1	1
Law Enforcement	1	-	1	1	1	2	1	-	1
EOC	-	-	-	-	-	-	-	-	-
American Medical Response	-	-	-	1	-	1	-	-	-
High-Potential-Loss	22	6	28	118	25	143	56	54	110
Adult Care Facility	-	1	1	6	2	8	3	2	5
Child Care Center	2	1	3	8	1	9	6	4	10
Cell Tower	8	-	8	42	2	44	11	17	28
County Real Property Asset	3	4	7	21	13	34	12	21	33
Dam	1	-	1	5	-	5	1	-	1
Healthcare Facility	-	-	-	2	-	2	1	2	3
Historic Building	1	-	1	3	1	4	2	-	2
Library	-	-	-	1	-	1	2	-	2
Mobile Home Park	2	-	2	7	2	9	8	4	12
Power Generation	-	-	-	-	1	1	-	1	1
Radio Sites	2	-	2	8	-	8	3	-	3
School	3	-	3	15	3	18	7	3	10
Transportation and Lifeline	222	12	234	2461	104	2565	368	95	463
Airport	-	1	1	1	-	1	-	-	-

Critical Infrastructure - Wildfire Severity Zone									
Infrastructure Type	SRA Very High	LRA Very High	Very High Total	SRA High	LRA High	High Total	SRA Moderate	LRA Moderate	Moderate Total
Substation	-	-	-	4	-	4	-	2	2
NG Station	-	-	-	-	-	-	-	-	-
Church	3	-	3	16	-	16	11	3	14
Stormwater Culvert	208	8	216	2348	95	2443	337	81	418
Parks	3	-	3	19	2	21	8	4	12
Bridge NBI	8	3	11	73	7	80	12	5	17
Hazmat	10	2	12	49	14	63	28	26	54
HWTS Active Facility	9	1	10	47	11	58	25	22	47
Geotracker Cleanup Site	1	1	2	2	3	5	3	4	7
Grand Total	**258**	**20**	**278**	**2643**	**145**	**2788**	**458**	**176**	**634**

*Note: *Real Property Assets are digitized insurance rolls for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.*

Wildfires in Santa Cruz County threaten not only buildings and facilities but also critical lifeline and linear infrastructure—the networks that keep communities functioning during both normal operations and emergencies. The county has more than 1,900 miles of key transportation, utility, and service lines within High and Very High FHSZs.

Road networks account for the majority of this exposure, with over 1,400 miles of local streets and state highways traversing wildfire-prone areas. These routes are essential for evacuations, emergency responder access, and delivery of goods and services; loss or obstruction of these corridors during a wildfire could severely hinder response and recovery efforts.

Utility corridors are also exposed. Transmission lines, natural gas pipelines, and sanitation pipelines run through high-risk zones, meaning a major fire could disrupt electricity, gas, water, and wastewater services for thousands of residents. Damage to these systems can compound wildfire impacts, delaying recovery and putting public health at further risk.

Given the county's steep topography and limited ingress/egress routes in many mountain neighborhoods and communities, the vulnerability of lifeline infrastructure underscores the importance of proactive vegetation management, corridor hardening, and redundancy planning to maintain critical connectivity during wildfire events. Table 3-12 provides a detailed inventory of these linear assets by wildfire hazard classification, illustrating the scope of potential loss should a large wildfire occur in Santa Cruz County.

Table 3-12: Santa Cruz County Critical Infrastructure in SRA vs. LRA Fire Hazard Severity Zones

Infrastructure Type (Linear)	Lifelines (miles) - Wildfire Severity Zone					
	Very High		High		Moderate	
	SRA Very High	LRA Very High	SRA High	LRA High	SRA Moderate	LRA Moderate
County Maintained Roads*	32.87	2.42	23.89	262.11	66.08	24.81
Levee	-	-	-	-	-	0.28
Maintained Channel	0.71	0.71	1.94	3.23	4.53	1.79
NG Pipeline	0.04	0.09	12.30	13.18	2.86	2.78
Railroad	-	-	10.64	3.08	4.45	2.51
Sanitation Pipe	1.70	0.67	5.86	11.60	14.25	16.50
All Roads	182.16	9.65	79.81	1213.44	284.70	76.57
Alley	0.43	-	-	0.12	0.07	0.00
Drive	41.13	2.09	23.85	318.39	69.29	19.28
Major Road	18.09	1.37	11.50	170.88	39.64	12.06
Ramp	0.05	1.12	2.40	1.73	1.15	2.38
Street	94.70	1.88	28.04	564.73	151.29	30.52
State Highway	20.35	3.03	11.46	51.96	9.34	6.28
Unnamed	7.42	0.15	2.56	105.63	13.92	6.06
Transmission Line	6.42	0.08	0.56	36.09	12.45	3.56
Total	**223.89**	**13.63**	**135.00**	**1542.74**	**389.32**	**128.80**
					Grand Total	**2433.38**

3.2.1.8 Development Trends

Santa Cruz County's wildfire risk profile is shaped by two parallel forces: the continued enforcement and enhancement of strong wildfire protection regulations, and the existence of older, legacy development patterns in rural and high-risk areas that predate modern codes.

Over the last three decades, the county has significantly strengthened its wildfire resilience framework through a combination of state mandates, local code amendments, interagency plans, and dedicated funding measures. Regulations such as Public Resources Codes §§ 4290 and 4291, the California Building Standards and Fire Codes, and the county's more stringent local amendments ensure that new construction and substantial remodels in FHSZs and WUI areas meet the highest available standards for ignition resistance, defensible space, and emergency access. Complementary policy frameworks—including the county's General Plan Public Safety Element, the CZU Strategic Fire Plan, and the Santa Cruz–San Mateo CWPP—provide a coordinated roadmap for vegetation management, community preparedness, and infrastructure protection.

Santa Cruz County has also introduced innovative funding tools to sustain these efforts over the long-term, most notably Measure Q (the Safe Drinking Water, Clean Beaches, Wildfire Risk Reduction, and Wildlife

Protection Act), which will provide a dedicated annual revenue stream for fuel treatment, forest health, and wildfire safety projects on public and private lands.

Collectively, these policies and programs position the county as a leader in integrating wildfire resilience into land use planning, building design, and public infrastructure investment. New and redeveloped properties are subject to some of the most stringent wildfire safety standards in California, reducing the likelihood of structure loss and improving evacuation safety for residents in the future.

However, widespread requirements for fire-resistant materials and defensible space did not emerge until after major wildfire losses in the 1990s and 2000s and a substantial portion (80 to 90%) of the built environment in unincorporated Santa Cruz was developed before these standards existed. Many neighborhoods, especially in the San Lorenzo Valley, Bonny Doon, Corralitos, and other WUI areas, contain homes, roads, and critical facilities constructed with combustible materials, limited access routes, undersized water infrastructure, and minimal defensible space. These legacy conditions present ongoing vulnerabilities, even as surrounding parcels are upgraded to modern standards.

In addition, while fuel reduction projects and defensible space programs are expanding, the county's dense vegetation, steep topography, and changing climate conditions mean wildfire will remain an ever-present hazard. New development trends, such as rural residential in-fill, remote work-driven population shifts into WUI areas, and continued demand for housing in high-amenity rural landscapes may incrementally increase exposure if not carefully managed.

As Santa Cruz County grows and adapts, the integration of planning, regulation, funding, and on-the-ground mitigation will be essential for safeguarding people, property, and infrastructure against the escalating threat of wildfire. This MJHMP plays a critical role in addressing recognized gaps. By identifying and prioritizing projects that retrofit older structures, improve evacuation infrastructure, expand fuel management into high-priority corridors, and harden critical facilities, the plan ensures that the benefits of modern codes and policies extend to the entire community, not just to new development.

3.2.1.9 Wildfire Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing wildfire-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input.

The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure, essential facilities, economic assets, natural resources, and long-term recovery. They also recognize systemic barriers to effective mitigation, such as fragmented land ownership and post-fire hazards.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with wildfire. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-13 presents the wildfire hazard problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in Table 4-1 and Table 4-2.

Table 3-13: Santa Cruz County Wildfire Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Wildfire	Victim	**ps-WF-SCC-01**	Approximately 40% of the population and parcels in unincorporated Santa Cruz County are located in a high or very high wildfire hazard area and face post-fire recovery challenges due to insurance gaps, infrastructure damage, and limited rebuilding support.
Wildfire	Victim	**ps-WF-SCC-02**	Vulnerable populations living in high wildfire hazard areas -- especially low-income households, isolated seniors, persons with disabilities, and limited / non-English speakers -- face greater barriers to accessing wildfire mitigation and recovery resources as well as emergency communications.
Wildfire	Impact	**ps-WF-SCC-03**	Wildfires can damage or destroy critical infrastructure and facilities (public and private), including water/wastewater/stormwater conveyance and treatment, hindering emergency response and causing significant service disruptions.
Wildfire	Threat	**ps-WF-SCC-04**	Fragmented land and road ownership, presence of sensitive habitat, and coordination challenges within WUI areas pose challenges to agency implementation of landscape-scale wildfire risk reduction projects and construction of new egress routes.
Wildfire	Threat	**ps-WF-SCC-05**	Post-fire erosion and debris flows in the county's mountainous terrain threaten life safety, watershed health, homes, roads, utilities, drainage courses, and other critical infrastructure.
Wildfire	Threat	**ps-WF-SCC-06**	Many rural residents rely on private roads for ingress and egress that lack code-compliant fire apparatus access, including inadequate width, insufficient turnarounds, and washout-prone crossings. Limited financing options for road improvements limit mitigation and recovery, increasing challenges for emergency response and evacuation.
Wildfire	Victim	**ps-WF-SCC-07**	In wildfire-prone areas, rebuilding after a disaster can be significantly slowed for occupants of older homes due to requirements that did not apply when the structures were originally built, including modern state fire code, septic standards, and local / state regulations for sensitive habitats. Navigating these newer requirements—often in combination with the high cost or limited availability of insurance—can extend permitting timelines, increase expenses, and delay recovery.
Wildfire	Victim	**ps-WF-SCC-08**	Unmanaged regrowth in the CZU burn scar, as well as the lack of ongoing funding for maintenance in historic fuel treatment areas, can lead to the rapid accumulation of hazardous fuels. In the current fire regime, this increases the likelihood of high-intensity wildfire, threatening nearby communities, critical infrastructure, and ecosystem recovery.
Wildfire	Victim	**ps-WF-SCC-09**	Smoke from local or regional fires can decrease air quality resulting in health problems or an inability to engage in outdoor activities, especially for sensitive individuals.
Wildfire	Threat	**ps-WF-SCC-10**	Homeless encampments along riparian corridors and in heavily vegetated and high fuels open space areas create ignition risks, coupled with permitting/sensitive habitat requirements that pose challenges to ongoing fuel reduction and maintenance.

3.2.1.10 Climate Change Impacts & Vulnerable Populations

Wildfire is one of the most significant hazards in unincorporated Santa Cruz County, where approximately 40 percent of the population and parcels are located within high or very high wildfire hazard areas. Climate change is expected to intensify wildfire risk by producing hotter, drier summers, lengthening fire seasons, and increasing vegetation stress. These trends amplify both direct wildfire impacts and secondary hazards such as post-fire erosion, debris flows, and degraded air quality. Vulnerable populations—including low-income households, isolated seniors, persons with disabilities, renters, and limited- or non-English speakers—face the greatest barriers to preparedness, evacuation, and recovery.

Direct Impacts: Wildfires threaten lives, homes, and critical infrastructure, including water, wastewater, and stormwater systems, as well as roads and power lines that support emergency response. Many rural residents depend on private roads for ingress and egress that do not meet fire apparatus access standards, making evacuation and fire suppression more difficult. Populations living in older homes may face delayed recovery due to stricter rebuilding requirements under modern fire and septic codes, habitat protection regulations, and insurance gaps, compounding inequities in recovery timelines.

Secondary Hazards: Post-fire erosion and debris flows in mountainous terrain present significant risks to downstream communities, utilities, and watershed health. In burn scar areas, unmanaged regrowth and the lack of funding for long-term fuel treatment maintenance increase the potential for high-intensity fire recurrence, threatening ecosystem recovery and nearby communities.

Public Health and Social Impacts: Smoke from local and regional fires degrades air quality, creating serious health risks for sensitive populations, including children, seniors, outdoor workers, and individuals with respiratory or cardiovascular conditions. Homeless encampments located in vegetated riparian corridors also contribute to ignition risks, while simultaneously representing populations that are highly exposed to fire and lack access to safe evacuation options.

Climate change is expected to make these challenges more frequent and severe. For unincorporated communities, reducing wildfire risk requires targeted outreach, accessible emergency communication strategies, and coordinated investment in defensible space, vegetation management, and resilient infrastructure. Prioritizing the needs of vulnerable populations will be critical to ensuring equitable wildfire preparedness and recovery across the county.

PAGE INTENTIONALLY BLANK

Flood

3.2.2 Flood Hazard Profile

Flooding is one of the three primary natural hazards in California, along with earthquakes and wildfires, and statewide it represents the second most destructive source of hazard vulnerability and risk. (CalOES, 2018) Flooding is a priority hazard for Santa Cruz County due to its exposure to both riverine and coastal flooding, steep watershed conditions that produce rapid runoff, and the presence of populated areas and critical infrastructure in floodplains.

A floodplain is the low-lying land adjacent to a river, creek, or coastal area that becomes inundated during a flood event. Floodplains may be broad, such as the Pajaro River Valley, or narrow, as seen in the steep canyons of the San Lorenzo River and Soquel Creek. These areas form complex ecological systems that provide habitat improve water quality and reduce downstream flood impacts. When rivers are separated from their floodplains by levees or other control structures these natural benefits are diminished or lost.

In Santa Cruz County, flooding occurs when creeks rivers or coastal areas receive water flows or storm surge that exceed their conveyance capacity, resulting in overflow into adjacent lands. Riverine flooding often results from intense rainfall, particularly during atmospheric river events, while coastal flooding can occur when large storm waves and high tides coincide. Flooding can also be triggered by localized drainage issues, debris blockages, or failure of flood control facilities.

The highest intensity rainfall periods generally occur between December and February, coinciding with peak seasonal river flows and elevated coastal water levels. Storm systems during this period can produce flooding along both inland waterways, such as the San Lorenzo River, Soquel Creek, and Pajaro River, and in low-lying coastal areas subject to tidal influence and wave run-up. Coastal storm flooding affects areas along the Monterey Bay, including low-lying beaches and harbor facilities.

Santa Cruz County's flood hazards are shaped by its geography and climate as well. Orographic rainfall along the Santa Cruz Mountains funnels stormwater into steep watersheds, causing rivers and creeks to rise rapidly, often with very short warning times. Historic development patterns, particularly in the mid-twentieth century, placed homes, businesses, and agricultural uses in low-lying and flood-prone areas.

Definitions & Hazard Area Designations

Flood hazards are mapped and regulated using specific terms and categories established by the Federal Emergency Management Agency (FEMA) through its Flood Insurance Rate Maps (FIRMs) and Flood Insurance Studies (FIS). Understanding these definitions is essential for interpreting flood hazard maps, administering floodplain management regulations, and guiding development in at-risk areas. The terms described in Table 3-14 apply to flood hazard mapping and floodplain management in Santa Cruz County and are consistent with FEMA standards, including inland and coastal hazard area designations.

Table 3-14: Flood Hazard Terms

Term	Description
Special Flood Hazard Area (SFHA)	An area having special flood, mudflow, or flood-related erosion hazards and shown on a Flood Insurance Rate Map (FIRM), including all A and V Zones. The SFHA is the area where the National Flood Insurance Program's (NFIP) floodplain management regulations must be enforced and where the mandatory purchase of flood insurance may apply.
Base Flood	A flood having a 1% chance of being equaled or exceeded in any given year. This is the regulatory standard also referred to as the "100-year flood." The base flood is the national standard used by the NFIP and all federal agencies for the purposes of requiring the purchase of flood insurance and regulating new development.
100-YR / 1% Annual Chance Floodplain	The boundaries of the 100-year floodplain coincide with the base flood and an annual flood risk of 1%, consisting of both the regulatory floodway and the flood fringe. These areas are identified as various A Zones on FIRMs, depending on the risk and level of study conducted.
Floodway	The channel of a river or other watercourse and the adjacent land areas, where the highest velocities and damage potential are present during a flood, that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than a designated height. Communities must regulate development in these floodways to ensure that there are no increases in upstream flood elevations.
Flood Fringe	This is the remaining portion of the 100-year floodplain, excluding the floodway. This zone can be obstructed or developed if certain criteria are met.
500-YR / 0.2% Annual Chance Floodplain	The boundaries of the 500-year floodplain encompass the 100-year floodplain and coincide with an annual risk of 0.2%. The 500-year floodplain is advisory only for NFIP purposes.
Coastal High-Hazard Area (V Zones)	V Zones are areas along open coasts subject to high-velocity wave action from storms or other triggering events. These zones require elevated construction methods and other protective measures that can withstand the additional forces of waves.
Coastal A Zone (CAZ)	Coastal A Zones are within the SFHA, landward of a V Zone or along the open coast, where wave heights are between 1.5 and 3 feet during the base flood event. Structures in CAZs are subject to design and construction standards similar to V Zones.
Limit of Moderate Wave Action (LiMWA)	The Limit of Moderate Wave Action is a line shown on FIRMs that marks the inland limit of wave heights between 1.5 and 3 feet during the base flood event. Areas seaward of the LiMWA face higher risks from wave damage and must meet applicable construction standards.
Base Flood Elevation (BFE)	The elevation of surface water resulting from the base flood that has a 1% chance of equaling or exceeding that level in any given year. BFEs are shown on Flood Insurance Rate Maps (FIRM) for various flood zones where detailed studies have been conducted (e.g., Zone AE and V Zones).
Flood Insurance Rate Map (FIRM)	The official map of a community on which FEMA has delineated the SFHAs, BFEs, and the insurance risk premium zones applicable to a particular community.
Flood Insurance Study (FIS)	A compilation and presentation of flood risk data accompanying the FIRMs for specific watercourses, lakes, and coastal flood hazard areas within a community. When a flood study is completed for the NFIP, the information and maps are assembled into an FIS report, which contains detailed flood elevation data in flood profiles and tables.
Best Available Map (BAM)	The California Department of Water Resources (DWR) provides Best Available Maps displaying 100-, 200-, and 500-year floodplains across the state as supplemental information to FIRMs.

Floodplain Ecosystems

Floodplains are critical natural systems that support diverse and highly productive ecosystems. These areas often host an abundance of plant and animal species, with densities many times greater than those found along the river channel alone. Periodic flooding replenishes soils with nutrients from decomposed organic material, triggering rapid growth in plants and microorganisms. This productivity attracts a wide range of wildlife, including migratory birds and opportunistic feeders, and sustains agricultural uses due to the fertility of the soil. Vegetation in floodplains and riparian areas is typically adapted to disturbance, with species that are fast-growing and tolerant of saturated soils and root disruption.

Undisturbed or restored floodplains provide important benefits to both human communities and natural environments. When maintained in their natural state, floodplains:

- Slow the rate at which runoff enters streams, reducing peak flows and moderating flood impacts.
- Improve water quality by trapping sediment and filtering pollutants before they reach waterways.
- Recharge groundwater aquifers by allowing water to infiltrate into the soil.
- Provide habitat for a wide variety of plant and animal species, including sensitive and threatened species.

However, like elsewhere in California, floodplains in Santa Cruz County have been heavily affected by human development. Historically, they have been attractive locations for settlement due to proximity to water, fertile farmland, accessible transportation routes, and flat terrain suitable for building. Urbanization, agricultural expansion, and infrastructure construction can disrupt natural floodplain functions, altering drainage patterns, increasing downstream velocities, and reducing the capacity of channels to safely convey floodwaters. These changes can elevate flood risk both locally and downstream.

Responsible land use planning and floodplain management can allow human activity to coexist with floodplain ecosystems. Development within these areas must incorporate design measures that preserve or restore floodplain functions to the greatest extent feasible.

In Santa Cruz County, many areas that provide natural floodplain benefits are designated as wetlands, riparian corridors, open space, or protected lands under the county's General Plan, Local Coastal Program (LCP), and other regulatory measures. These areas are typically shielded from intensive development and, when development is proposed, must comply with the county's floodplain management regulations and the National Flood Insurance Program (NFIP). Maintaining these lands in their current condition helps reduce future flood losses while supporting ecosystem health and resilience.

3.2.2.1 Secondary & Compounding Hazards

Flooding in Santa Cruz County often triggers or contributes to other hazards that can significantly increase the overall impact of an event. One of the most persistent is bank erosion, which can, in some cases, cause more lasting damage than the initial flood. Erosion of riverbanks, stream channels, and coastal bluffs can undermine infrastructure, damage private property, and alter flow patterns, increasing vulnerability to

future floods. These secondary and compounding hazards are briefly discussed in this section in relation to flood; some are further discussed in other profiles, including wildfire burn scars (Section 3.2.1), heavy rain (Section 3.2.4), coastal bluff erosions (Section 3.2.5), slope failure (Section 3.2.6), and climate change (Section 3.2.10).

Slope Failure

Flooding can lead to landslides, mudslides, debris flows, and other types of slope failure, particularly in steep mountain watersheds where saturated soils lose cohesion and fail. These secondary events can block roadways, isolate communities, and further disrupt drainage systems, sometimes creating temporary dams from accumulated debris that can release suddenly and worsen downstream flooding.

Wildfire Burn Scars

The presence of wildfire burn scars can significantly increase flood risk. Loss of vegetation and soil damage from the intense heat produced by severe wildfires reduces the land's ability to absorb rainfall, increasing both the speed and volume of runoff. The combination of rapid runoff and elevated sediment loads can cause severe erosion, degrade water quality, and increase slope failure hazards like debris flows in downstream communities.

Climate Change, Sea-Level Rise & Atmospheric Rivers

Climate change is expected to significantly alter flood hazards in Santa Cruz County by increasing the frequency and intensity of extreme precipitation events, accelerating sea-level rise, and shifting storm patterns toward more intense atmospheric river events. Developed neighborhoods, commercial areas, and critical infrastructure will face higher flood risk and should be prioritized in climate adaptation planning.

Inland, steep watershed systems—such as those draining into the San Lorenzo River, Soquel Creek, and Corralitos Creek—are projected to experience more frequent high-flow events, increasing flood severity in both mapped SFHAs and areas currently outside FEMA's designated flood hazard zones. In low-lying coastal areas like Seacliff, Rio Del Mar, Capitola Village, Beach Drive, and Via Gaviota, higher baseline sea levels will amplify wave run-up and storm surge, overtopping existing seawalls more frequently and eroding protective beaches.

Critical infrastructure, such as road and rail corridors, wastewater treatment facilities, and emergency access routes, located in flood-prone coastal and riverine areas could be increasingly impacted. The Santa Cruz Wastewater Treatment Facility, sections of Highway 1 and the coastal rail line, and low-lying bridges over the San Lorenzo River and Soquel Creek are among the assets that may face greater risk under combined high tide, storm surge, and river flooding scenarios.

These projections underscore the need for integrating climate-informed flood hazard mapping, such as the state's BAMs for 200-year floodplains, into the county's land use, capital improvement, and emergency management planning. Proactive adaptation strategies will be essential to reduce long-term vulnerability.

Hazardous Materials and Sewage Release

Hazardous materials and sewage releases are another secondary concern during a flood event. When floodwaters overtop or breach containment systems, above ground storage tanks, or other facilities storing chemicals, fuels, or other hazardous substances, contaminants or sewage can enter storm drains, streams, or the ocean. These releases create environmental hazards to people and natural ecosystems and further complicate cleanup and recovery efforts.

3.2.2.2 Subhazard: Levee Failure

Levee failure is considered a subhazard associated with both riverine and coastal flooding in Santa Cruz County. Levees are designed to protect low-lying areas from inundation during high-water events by containing river flows or storm surge within a defined channel. While levees reduce flood risk, they do not eliminate it. Failure can occur when water overtops the levee, erodes the structure, seeps through or under the levee embankment, or causes structural collapse due to prolonged saturation or foundation instability.

In Santa Cruz County, the most significant levee systems are located along the Pajaro and San Lorenzo Rivers. The older Pajaro River levee system, which provides flood protection to agricultural lands and major population centers in the City of Watsonville, unincorporated county, and community of Pajaro in neighboring Monterey County, has a documented history of failures during major storm events, including the March 2023 breach that resulted in widespread flooding and evacuations (Figure 3-9). The Pajaro River levee system does not meet current 100-year flood protection standards. This levee system also spans two counties—Santa Cruz and Monterey; hence, the Pajaro River Flood Management Agency was created to address cross-jurisdictional issues.

The San Lorenzo River levee system, completed in 2002, has significantly reduced flood risk to downtown Santa Cruz, but overtopping or structural damage remains possible during extreme events that exceed the levee's design capacity.

Levee failure can cause rapid and severe flooding, often with little warning. In many cases, the speed and depth of inundation from a levee breach can be greater than from natural overbank flooding because stored water is suddenly released. Consequences may include damage or destruction of buildings, infrastructure, and agricultural lands; disruption of transportation networks; loss of utilities; contamination of water supplies; and potential loss of life. Perhaps the most infamous levee failures to occur in U.S. history were those during Hurricane Katrina in August 2005, when over 50 levees and flood walls failed leading to over 1,000 deaths, $160 billion in damage, and the displacement of hundreds of thousands of people in the City of New Orleans and adjacent Saint Bernard Parish.

Factors that can contribute to levee failure include:

- Extreme flood events exceeding the levee's design protection level.
- Deferred maintenance leading to erosion, vegetation overgrowth, or animal burrows that weaken the structure.

- Prolonged high water that causes seepage or internal erosion (piping).
- Seismic shaking that damages embankment stability.
- Wave action and storm surge in coastal levee systems.

Mitigation strategies for levee failure focus on inspection and maintenance programs, structural upgrades to meet modern engineering standards, emergency action planning, and public education regarding residual risk in levee-protected areas. FEMA mapping of levee systems includes analysis of levee accreditation under the NFIP; areas behind non-accredited levees are typically mapped as SFHAs.

Figure 3-9: Pajaro River Levee Breach March 2023

Source: Santa Cruz County

3.2.2.3 Policies, Plans & Regulatory Environment

Federal Regulatory Environment

National Flood Insurance Program (NFIP)

The National Flood Insurance Program (NFIP) makes federally backed flood insurance available to homeowners, renters, and business owners in participating communities. In most participating communities, FEMA has prepared a detailed Flood Insurance Study (FIS). This study presents water surface elevations for floods of various magnitudes, including the 1% annual chance or base flood (also known as the 100-year flood) and the 0.2% annual chance flood (or 500-year flood).

Base Flood Elevations (BFE) and the boundaries of the 100- and 500-year floodplains are shown on Flood Insurance Rate Maps (FIRMs). These maps are the primary tools for identifying the extent and location of flood hazards. FIRMs also designate the regulatory floodway which is the channel of the river or stream and the adjacent land that must remain free from obstruction so that the base flood can be conveyed downstream. For coastal areas, FIRMs depict additional Special Flood Hazard Areas (SFHA) including high-hazard V Zones, Coastal A Zones (CAZ), and the Limit of Moderate Wave Action (LiMWA). FIRMs represent the most detailed and consistent data source available and, in many communities, they define the minimum regulatory area for floodplain management.

The most recent county-wide FIRM for Santa Cruz County became effective on September 29, 2017. This update produced a digital flood insurance rate map (DFIRM) that allows for easier integration with geographic information systems (GIS) and more precise identification of flood risk areas.

Communities that participate in the NFIP must, at a minimum, regulate development in flood hazard areas according to NFIP criteria. Before issuing a permit to build in a mapped floodplain, participating jurisdictions must ensure that:

- New buildings and substantially improved structures are elevated or otherwise protected to resist damage from the base flood.
- New floodplain development does not increase flood hazards or cause additional damage to other properties.
- Floodplain development incorporates reasonable and prudent measures to reduce impacts on natural floodplain functions and ecosystems, including threatened and endangered salmonid species.

Santa Cruz County entered the NFIP on April 15, 1986. Structures permitted or built before that date are classified as "pre-FIRM" and structures built afterward are "post FIRM." Post FIRM buildings generally qualify for reduced flood insurance rates because they were constructed under floodplain management regulations intended to reduce flood damage. Pre-FIRM buildings are often more vulnerable to flooding because they were built before modern construction standards and land use regulations were adopted.

All four incorporated cities in Santa Cruz County—Capitola, Santa Cruz, Scotts Valley, and Watsonville—participate in the NFIP, as does the unincorporated county. Each jurisdiction is currently in good standing

with NFIP requirements. (Refer to the annexes for Capitola, Scotts Valley, and Watsonville for jurisdiction-specific details). Compliance is monitored by FEMA Region 9 and by the California Department of Water Resources (DWR) under contract with FEMA. Maintaining NFIP compliance is a key element of the county's overall flood risk management strategy. All participating jurisdictions have identified ongoing initiatives to maintain their standing in the NFIP and to continue reducing flood risks.

Community Rating System (CRS)

FEMA's Community Rating System (CRS) is a voluntary program within the NFIP that encourages floodplain management activities that exceed the minimum NFIP requirements. Flood insurance premiums are discounted to reflect the reduced flood risk resulting from community actions that meet the three goals of the CRS: 1) reduce flood losses, 2) facilitate accurate insurance rating, and 3) promote awareness of flood insurance.

For participating communities, flood insurance premium rates are discounted in increments of 5% according to the community's classification on a scale from ten to one. On this scale, a Class 1 community would receive a 45% premium discount, and a Class 9 community would receive a 5% discount. Class 10 communities are those that do not participate in the CRS and they receive no discount. The CRS classes for local communities are based on 18 creditable activities related to public information, mapping and regulations, flood damage reduction, and flood preparedness.

CRS activities can help to save lives and reduce property damage. Communities participating in the CRS represent a significant portion of the nation's flood risk; over 66% of the NFIP's policy base are communities in the CRS. Communities receiving premium discounts through the CRS range from small to large and represent a broad mixture of flood risks, including coastal and riverine. Table 3-15 lists NFIP and CRS information for Santa Cruz County, which shows flood insurance claims paid since February 1, 1980.

Table 3-15: Santa Cruz County NFIP Status and Flood Insurance Statistics

Santa Cruz County NFIP Status and Flood Insurance Statistics	
NFIP Status	Participating Since 1986
Community Identification (CID)	060353
CRS Class (Entry Date)	Class 8 (October 2012)
Policies in Force (Total Coverage)	1,114 Policies ($298,140,000 in Coverage)
Policies Inside SFHA / Outside SFHA	485 Inside / 628 Outside
Policies in Coastal Zones (Total Coverage)	85 Policies ($21,484,000 in Coverage)
Total Claims (Total Paid)	1,168 Claims ($17,230,444 Paid)
Repetitive Loss (RL) / Severe Repetitive Loss (SRL) Properties	46 RL / 5 SRL (unmitigated insured)
Repetitive Loss Payments	$8,017,000 for Buildings / $677,000 for Contents

Note: The number of policies is by property and does not count policies for individual buildings. The Privacy Act of 1974 (5 USC 522a) restricts the release of certain types of data to the public. Flood insurance policy and claims data is included in the list of restricted information. FEMA can only release such data to state and local governments, and only if the data is used for floodplain management, mitigation, or research purposes. Therefore, this plan does not identify the repetitive loss properties or include claims data for any individual property.

The Planning Division within the County plays a central role in Santa Cruz County's flood hazard mitigation program. Its responsibilities include administering regulatory permitting for development in flood-prone areas, ensuring compliance with the NFIP, and managing participation in the CRS program. These functions help guide safe development, maintain eligibility for flood insurance, and provide residents with premium discounts through the CRS program. Together, these activities form a major component of the County's overall strategy to reduce long-term flood risk while supporting resilient growth.

U.S. Army Corps of Engineers (USACE)

The U.S. Army Corps of Engineers (USACE) plans, designs, constructs, and maintains water resources projects, including flood risk management infrastructure. In Santa Cruz County, USACE's role is focused on large-scale flood control, coastal storm damage reduction, and ecosystem restoration projects, often in partnership with local sponsors such as the Santa Cruz County Flood Control and Water Conservation District and the Pajaro Regional Flood Management Agency (PFRMA). Key USACE responsibilities and activities in Santa Cruz County include:

- **Pajaro River at Watsonville Project:** USACE and Pajaro River Flood Management Agency is leading the design and construction of major levee improvements along the Pajaro River and its tributaries in both Santa Cruz and Monterey Counties. This congressionally authorized project will provide a 100-year level of flood protection to urban areas and significantly reduce flood risk to surrounding agricultural lands.
- **Technical Assistance:** The Corps provides hydrologic and hydraulic modeling, sediment transport studies, and engineering design services for local flood protection and restoration projects under programs such as Floodplain Management Services (FPMS) and Planning Assistance to States (PAS). Through the Silver Jackets interagency partnership, USACE also supported the development of a Communications-Focused Emergency Action Plan (EAP) for the Pajaro levee system in 2025, aimed at improving community readiness and coordination during flood emergencies.
- **Coastal Storm Damage Reduction:** USACE conducts studies and implements measures to protect coastal communities from wave run-up, shoreline erosion, and coastal flooding. This includes collaboration on beach nourishment and bluff stabilization projects where feasible and authorized.
- **Ecosystem Restoration:** The Corps works with local partners on multi-benefit projects that restore riparian corridors, wetlands, and estuarine habitats in a way that also reduces flood risk.
- **Emergency Operations:** Under Public Law 84-99 (Flood Control and Coastal Emergencies), USACE can provide direct flood fight assistance to local agencies during major flood events and can perform post-disaster repairs to federally authorized flood control works.

USACE's activities in Santa Cruz County are typically carried out through formal project cooperation agreements with local sponsors, with federal funding often matched by state and local cost-share contributions. These efforts complement the work of FEMA, the California Department of Water Resources (DWR), and local agencies to provide an integrated approach to flood risk reduction.

State Regulatory Environment

California Department of Water Resources (DWR)

The California Department of Water Resources (DWR) is the state agency responsible for managing and protecting California's water resources, including oversight and coordination of flood management programs. While DWR does not directly operate most local flood control infrastructure in Santa Cruz County, it plays an important role in planning, technical assistance, and funding for flood risk reduction projects. In the county, DWR's responsibilities and activities include:

- **Floodplain Mapping and Data:** DWR works with FEMA and local agencies to develop and update flood hazard maps, including the Best Available Mapping (BAM) program, which identifies areas vulnerable to flooding from events, including the 200-year flood level (0.5% annual chance). While the 200-year standard primarily applies to urban levee systems in the Central Valley, DWR's mapping products are used statewide to support planning and hazard awareness. DWR also provides technical support for FEMA FIRM updates and maintains the Awareness Floodplain Mapping Program for unmapped or under-mapped areas.
- **Levee Safety and Inspection:** Through the Division of Flood Management's Levee Safety Program, DWR conducts periodic inspections of levee segments that are part of the State-Federal Flood Control System and maintains the Central Valley Flood Protection Board Levee Database for applicable facilities. In Santa Cruz County, this includes coordination with the Pajaro River at Watsonville Project for levee improvements along the southern county line.
- **Flood Operations Center (FOC):** During major storm events, DWR operates the FOC to provide real-time hydrologic data, reservoir operations information, and technical support to local emergency managers and flood control districts.
- **Grant Funding:** DWR administers grant programs that local agencies can use for planning, design, and construction of flood risk reduction projects, including the Floodplain Management, Protection, and Risk Awareness Program (FMPRA), Urban Flood Risk Reduction Program (UFRR), and Small Communities Flood Risk Reduction Program (SCFRR).
- **Climate Adaptation and Resilience:** DWR supports local adaptation planning through sea-level rise science, hydrologic modeling, and funding for multi-benefit floodplain restoration projects under the FloodSAFE California initiative.

Through these functions, DWR serves as a key partner to the Santa Cruz County Flood Control and Water Conservation District, the county's Public Works Department, and the PRFMA in advancing both structural and non-structural flood mitigation measures.

Local Regulatory Environment

Santa Cruz County Flood Control & Water Conservation District (FCWCD)

The Santa Cruz County Flood Control and Water Conservation District (FCWCD) is responsible for long-range planning and capital investment in the county's designated flood control zones. FCWCD encompasses four

active control zones, described in Table 3-16 and shown on Figure 3-10. Responsibilities include developing and maintaining storm drain master plans for each zone to identify drainage deficiencies, assess system performance, and prioritize needed capital projects. FCWCD manages funding generated through zone assessments and actively pursues state and federal grants to finance flood management improvements.

FCWCD also oversees the design and construction of major flood control infrastructure, such as levees, pump stations, culvert replacements, and channel modifications. In delivering these projects, FCWCD works in close coordination with FEMA, USACE, DWR, and the Regional Water Quality Control Board to ensure regulatory compliance and effective project delivery. Capital improvements are generally designed to provide a 10-year storm conveyance capacity, with higher levels of protection applied where conditions warrant.

Santa Cruz County Flood Control Unit

The Flood Control and Storm Water Unit, housed within the County's Department of Community Development and Infrastructure (CDI), plays a critical role in reducing flood risk and maintaining stormwater infrastructure. The unit is responsible for managing stormwater conveyance systems to reduce flooding, erosion, and water quality impacts associated with pollutants such as oils, fertilizers, and litter. In 2023, responsibilities for maintaining the Pajaro River, Salsipuedes Creek, and portions of Corralitos Creek were formally transferred from Zone 7 to the Pajaro Regional Flood Management Agency (PRFMA), though the County had previously carried out critical levee maintenance and emergency preparation along these waterways. In addition to flood control operations, the unit supports stormwater compliance efforts, emergency response, and coordination with planning staff to integrate flood hazard considerations into development review. Together, these responsibilities strengthen the County's resilience to extreme weather events and climate-driven flood hazards.

Pajaro Regional Flood Management Agency (PRFMA)

The Pajaro Regional Flood Management Agency (PRFMA) is a joint powers authority that includes the County of Santa Cruz, Santa Cruz County Flood Control District, Water Conservation Zone No. 7, the County of Monterey, the Monterey County Water Resources Agency, and the City of Watsonville. Former in 2021, the agency plans, finances, and implements projects and programs to reduce flood risk from the lower Pajaro River and its tributaries in Santa Cruz and Monterey Counties. PRFMA oversees about 24 miles of levees, 12 miles of channels, 15 pump stations, and 85 culverts. These assets protect Watsonville, Pajaro, and surrounding agricultural areas from riverine flooding, although the current system provides only limited protection, estimated at an eight-year flood event.

PRFMA leads the Pajaro River at Watsonville Project, a major upgrade effort with USACE to achieve 100-year flood protection. The agency also oversees regular operations and maintenance, emergency preparedness coordination, and environmental stewardship initiatives that integrate habitat restoration with flood control.

Until these upgrades are complete, the extensive floodplain near Watsonville remains vulnerable, as the levees in this area are not urban-standard structures and do not provide full protection against larger flood events. This exposure is reflected in the county's leveed-areas flood risk analysis, which identifies significant portions of the lower Pajaro River floodplain as remaining at risk despite existing levee protection.

Table 3-16: Santa Cruz County Flood Control Zones

Zone	Boundaries / Service Area	Waterways	Key Infrastructure
Zone 5	Soquel, Capitola, Aptos, and Rio Del Mar area; extends inland to hills above Soquel and Aptos valleys	Soquel Creek, Valencia Creek, Noble Gulch, Aptos Creek, Trout Gulch Creek	Storm drain networks, culverts, roadside ditches, Soquel Creek floodplain improvements, Valencia Creek channel improvements, tide gates and coastal outfalls at Rio Del Mar and Capitola
Zone 6	Live Oak area, east of Santa Cruz City limits, extending to the coastline	Corcoran Lagoon, Rodeo Creek	Storm drain network with direct coastal outfalls, pump stations, tide gates, and sediment control structures
Pajaro Storm Drain Maintenance District (PSDMD) (Previously Zone 7)	Pajaro Valley area in South County; unincorporated areas adjacent to Watsonville; includes Salsipuedes Creek watershed	College Lake, East Branch Salsipuedes Creek	College Lake pump station and outlet structure, agricultural drainage ditches, culverts, flood gates
Zone 8	San Lorenzo River watershed from Santa Cruz City limits upstream into San Lorenzo Valley; includes Boulder Creek, Ben Lomond, Felton	San Lorenzo River, Zayante Creek, Bear Creek, Boulder Creek	San Lorenzo River levee system (downtown Santa Cruz), storm drain systems in valley communities, culverts and bridges, bank stabilization projects

Santa Cruz County Department of Community Development & Infrastructure (CDI), Public Works Division (PWD)

The Santa Cruz County Public Works Department (PWD) provides the operational capacity and technical expertise necessary to implement FCWCD programs. PWD is responsible for the operation and maintenance of drainage facilities across the flood control zones, including storm drains, culverts, roadside ditches, tide gates, and detention basins. The department conducts regular inspections and makes repairs to ensure system integrity, with special emphasis on preparation before and during storm seasons. During high-water events, PWD leads emergency response operations to clear blockages, repair damaged infrastructure, and deploy temporary flood protection measures. Public Works also maintains GIS-based inventories and hydraulic models for the county's storm drain systems and waterways, which support both planning and emergency operations. In addition, the Department ensures regulatory compliance with the the Municipal Separate Storm Sewer System (MS4) stormwater permit under the Clean Water Act.

Together, FCWCD and PWD provide the policy direction, funding mechanisms, long-term capital planning, and day-to-day operational capability required to maintain and improve Santa Cruz County's flood control infrastructure. This integrated approach enables the county to address both immediate maintenance needs and long-term resilience goals in its flood-prone watersheds.



Flood Control Zones

Source: Santa Cruz County

Figure 3-10: Santa Cruz County Flood Control Zones

Santa Cruz County General Plan Public Safety Element

The Santa Cruz County General Plan Safety Element contains one overarching goal of protecting human life, private property, and the environment and a set of targeted policies to address flood hazards. These provisions are intended to protect residents, businesses, public facilities, and natural resources from the damaging effects of flooding while maintaining the beneficial functions of floodplains. In summary, the flood hazard objective in the element is to protect structures in order to minimize economic damages and threats to public health and safety, and to prevent adverse impacts on floodplains, maintaining their beneficial function (Objective 6.6). To meet this objective, the General Plan includes the following key policies:

- **Review Development in Special Flood Hazard Areas (Policy 6.6.2):** Evaluate projects within SFHAs and designated floodways for potential impacts on flood levels and conveyance, and require mitigation for adverse effects.
- **Restrict Development in Flood Hazard Areas (Policy 6.6.4 and Policy 6.6.7):** Prohibit or limit new construction in mapped floodplains unless adequate mitigation measures, such as elevation or floodproofing, are incorporated in accordance with FEMA and county floodplain management standards.

This framework combines preventative measures, such as land use regulation, with protective actions that sustain the structural integrity of flood control facilities. Together, these measures help reduce flood risk across both inland and coastal areas of Santa Cruz County.

Santa Cruz County Local Coastal Program (LCP)

Within the Coastal Zone, the county's certified Local Coastal Program (LCP) applies policies from the Public Safety Element specifically to hazards originating from coastal sources, including storm surge, wave run-up, and sea-level rise. These policies integrate FEMA floodplain regulations and ensure compliance with the California Coastal Act while complementing inland flood hazard management, creating a dual-layer system for managing coastal flood risk in Santa Cruz County.

The components of the county's LCP are defined in Santa Cruz County Code Chapter 18.60 and policies and procedures regulating coastal flooding and related hazards are among them. These regulations establish the procedures and standards for administering the county's LCP in compliance with the California Coastal Act. Santa Cruz County Code Chapter 13.20 sets forth permit review procedures, appeal rights, and coordination requirements with the California Coastal Commission for projects in appealable areas. Through these measures, the Public Safety Element and the Santa Cruz County Code provides the administrative framework to implement coastal flood hazard policies and ensure that new development is compatible with long-term coastal resilience. This program and its administration are discussed further under the local regulatory environment in the Coastal Hazards Profile, Section 3.2.5.

Santa Cruz County Floodplain Management Regulations

Santa Cruz County has participated in the NFIP since 1986 and has adopted the most recent FIRMs and FIS issued by FEMA (dated September 27, 2017) as well as local floodplain development regulations in compliance with the minimum NFIP standards (Chapters 16.10 and 16.13of the County Code). These minimum standards include procedures and provisions for substantial improvements and substantial damages to existing structures, the latter of which are employed by the floodplain administrator and county building inspectors following any hazard event affecting structures located in the flood hazard area in accordance with NFIP requirements. Regulations for substantial or cumulative improvements are enforced via permitting procedures. By code, implementation and enforcement of the County's floodplain regulations are assigned to the Planning Director or their designee.

The provisions of Chapter 16.10 and 16.13 are intended to promote public health, safety, and welfare, and to minimize public and private losses due to flood conditions. The regulations restrict land uses that could increase erosion, obstruct flood flows, or exacerbate flooding; require that new construction and substantial and cumulative improvements over a 5-year period be protected against flood damage at the time of initial construction; limit the alteration of natural floodplains, stream channels, and protective barriers; and avoid development practices that could unnaturally divert floodwaters or increase flood hazards in other areas. County Code Section 16.30 Riparian Corridor and Wetlands Protection provides additional protections for riparian corridors to maintain their natural flood and erosion control functions.

3.2.2.4 Past Events

Flooding has caused significant damage to agriculture, transportation networks, and developed areas in Santa Cruz County in the past. Historic records indicate repeated damaging floods, with notable events in 1955, 1982, 1995, 1997, 1998 and 2023, including the catastrophic Pajaro River levee failure in March 2023 that inundated portions of Pajaro and surrounding agricultural lands in Monterey County. Below is a summary of the historic flooding for the major rivers, creeks, and beaches in Santa Cruz County. The historical information cited below comes from studies and reports completed by the United States Army Corps of Engineers (USACE) and the FEMA Flood Insurance Studies (FIS).

Aptos, Trout & Valencia Creeks

Aptos Creek drainage basin is of small size and limited flood problems. It includes the drainage areas of Valencia Creek, Trout Creek, Bridge Creek and Mangles Gulch. Floods are known to have occurred in 1955, 1963 and 1982, however little information is available prior to 1955. 74

During the four-day period ending December 22, 1955, heavy rains fell over the basin causing Aptos and Valencia Creeks to slightly exceed bank full stages at several points in the lower basin. Agricultural damage was primarily due to scour and erosion of first shelf lowlands planted to pasture, a few orchard crops, and idle croplands. The peak flow was measured at 3,500 cfs and approximately 140 acres were inundated, of which 20 acres were cropland. Non-cropland damages were generally very minor, consisting of eroded

private roads and washed-out culverts. County roads and bridges experienced relatively heavy damages at the Valencia Road crossing. The bridge on Aptos Creek just below the confluence of Aptos and Valencia Creeks sustained a washout of cribbing endangering the bridge structure. Four homes along Moosehead Drive, downstream from the village of Aptos, experienced flooding. The Southern Pacific Railroad sustained minor damage due to undermining of the roadbed at Aptos, which resulted in a seven-day interruption of rail service. The local telephone company sustained minor damages to the undermining of facilities in the floodplain (USACE, Floodplain Information, Aptos, Trout, and Valencia Creeks, 1973).

The January 1982 flood had a peak flow of 3,950 cfs and corresponded to a 40-year recurrence interval based upon stream gauge data in Aptos Creek. Heavy damage occurred from this storm. At least seven homes along Moosehead and Spreckels Drive between Highway 1 and the Spreckels Drive Bridge suffered major damage. Further downstream damage resulted to major portions of two streets paralleling Aptos Creek.

Pajaro River, Salsipuedes Creek & Corralitos Creek

During December 21 through 24, 1955, and April 2 through 4, 1958, the Pajaro Valley experienced flooding. These floods are the two largest on record for the Pajaro River. The associated discharges for these events were 24,000 cfs and 23,500 cfs, respectively, at the Chittenden gauge (USACE, 1963). The estimated recurrence intervals for floods of these magnitudes are 27 years and 26 years, respectively. In comparison, the estimated discharge at Chittenden for a 100-year flood is 43,000 cfs. (FEMA FIS 2006).

In the December 1955 flood, the Pajaro River was maintained within the levees in the Watsonville area, but the levees were breached 2.1 miles upstream of the confluence with Salsipuedes Creek (USACE, 1963). Although no lives were lost, 972 people were evacuated, and $1.12 million damage incurred. Included in these costs were monies spent to repair levees damaged by erosion. Additional levee repairs were required because of the April 1958 flood; however, no other significant damage resulted (USACE, 1963). Significant flooding along Corralitos and Salsipuedes Creeks also occurred in December 1955 and April 1958. Peak discharges for Corralitos Creek at Green Valley Road have been estimated from high-water elevations (USACE, 1956). The estimated discharges for the 1955 and 1958 floods are 3,620 cfs and 2,680 cfs, which correspond to recurrence intervals of 12 and 7 years, respectively. The overflow of Corralitos Creek upstream of the leveed section on Salsipuedes Creek flooded 29 blocks within the City of Watsonville during the December 1955 flood (USACE, 1963).

The Pajaro Valley experienced only minor damage from the January 1982 flood. (FEMA FIS, 2006). In 1995, a major flood event breached the Pajaro River levees and the Town of Pajaro was flooded.

Most recently, in March 2023, a powerful atmospheric river event caused the Pajaro River levee to fail, resulting in widespread flooding of the Town of Pajaro in Monterey County and adjacent agricultural areas. Significant overbank flooding also occurred along Salsipuedes and Corralitos Creeks, which contributed to localized inundation in Watsonville and surrounding communities. These impacts triggered a federal disaster declaration and highlighted the persistent vulnerabilities of the lower Pajaro River watershed to

major storm events, underscoring the critical need for comprehensive levee improvements and watershed-scale flood mitigation.

San Lorenzo River

The San Lorenzo River basin is the largest drainage basin contained entirely within the county. Few records exist of flooding in the San Lorenzo Basin (outside of the City limits) prior to 1940. However damaging storms are known to have occurred in 1940, 1955, 1958, and 1982.

December 1955 was the highest historic flood along the San Lorenzo River and had a peak discharge of 30,400 cfs, which equates to approximately a 30-year recurrence interval. The most intensive rainfall fell during a four-day period from December 21-24. In the central part of the basin, known as the Ben Lomond area, the San Lorenzo River exceeded bank full stage. Local reports indicate previous maximum stages of record were exceeded along Kings, Boulder, Two Bar, and Zayante Creeks in the upper basin. Overflows occurred from the headwaters to the mouth, resulting in the maximum flood of record. The heavy rains and overflows loosened and scoured out large trees and floated them downstream where they became lodged at channel points of constriction, impounding flow, causing extremely severe local flooding. The numerous log jams and other channel obstructions diverted the high-velocity flows, causing the streams to change from the normal alignment, undercut and scour out numerous bridges, road fills, channel dams and private developments. It is estimated that at least 388 acres were flooded. Seven people (five within the Santa Cruz City limits, two outside) lost their lives as a result of the flood. It is estimated that 390 people outside the City limits were displaced by the floodwaters. Numerous houses, roads, parks, and commercial properties were damaged or destroyed in the Boulder Creek, Ben Lomond, Felton, and Paradise Park areas. (USACE, 1973)

The April 1958 flood was minor in comparison to the 1955 flood, but still saw erosion, creek bank failures and damage and loss of houses.

The magnitude of the January 1982 flood was similar to the December 1955 flood and had a peak discharge of 19,700 cfs. Damage upstream of the City of Santa Cruz was extensive. The damage was most extensive in the area between the upstream limits of Felton and in the areas of Paradise Park, Gold Gulch and Felton Grove. In the Felton Grove area, floodwaters in the overbanks reached three to seven feet and inundated 50 homes and cabins. An additional 60 to 70 homes were flooded between Felton and Ben Lomond. It is estimated that the 1982 flood had a recurrence interval along the San Lorenzo River of approximately 30 years. (FEMA FIS, 2006)

Felton Grove also saw numerous evacuations during the 2023 atmospheric river events and storm season due to overtopping of the San Lorenzo River. During these events, the biggest impacts of flooding, rain, and mudslides were on the Central Coast, with a peak discharge of 17,400 CFS.

Beach & Coastal Flooding

Flooding along the Pacific coast of Santa Cruz is typically associated with the simultaneous occurrence of high tides, large waves, and storm swells during the winter. Significant storms, with associated damage,

strike the Monterey Bay communities with regular frequency. As a result, ocean front development has not been compatible with the natural instability of the shoreline and intense winter weather conditions. (FEMA FIS, March 2, 2006).

The most severe storms on record to hit the California coast occurred in 1978 and 1983 when high water levels were accompanied by very large storm waves (FEMA FIS, 2006).

In 1978, a series of storms emanated from a more southerly direction, than normal. Consequently, some of the more protected beaches were damaged. Jetties and breakwater barriers were overtopped, and in some cases, undermined. Direct wave damage occurred to many beachfront homes and seawalls, especially in the more populated beachfront areas such as at Seacliff Beach and Rio Del Mar Beach. (FEMA FIS, 2006).

In 1983 a similar storm hit the Santa Cruz Coast. During this storm, a new 3,500-foot seawall was destroyed and in Seacliff Beach 19 of 21 homes were significantly damaged when the existing riprap protection was overtopped. (FEMA FIS, 2006).

The Pajaro Dunes area of the County that is fronted by dunes has also been subject to severe damage to structures as well as rapid beach retreat in 1968, 1969, 1978 and also in 1983. (FEMA FIS, 2006).

Powerful wave events and coastal flooding have occurred since the previous county plan was adopted, most notably during the 2023 atmospheric river events and the December 2024 storm. These events, combined with high winds, caused major damage to wharfs and coastal access points, significant debris accumulation along beaches, and flooding of homes in repetitive loss areas such as Las Olas and Beach Drive.

Significant storms and associated damage from flooding strike the Monterey Bay communities with a frequency of one large storm every three to four years. A 100-year flood has a one percent probability of occurring in any given year and while considered to be a severe flood, it still has a reasonable possibility of regular occurrence. For the purposes of the protection of property, life and safety, floods of other magnitudes and occurrence intervals should also be considered in mitigation efforts.

Floods are gauged by their cresting elevation, the area of inundation or damages and either the size of the event or the probability of occurrence. The size and depth of the floodplain area is computed using mathematical models of precipitation, slope, runoff, soil type and cross-section. Flood depths are calculated at intervals along a stream or channel corridor and then mapped and interpolated between sections. This results in the floodplain map.

Notable Recent Flood Events

More recent events underscore the county's continuing vulnerability. While Santa Cruz County has experienced numerous flood events over the last two decades, three events stand out for their scale, impacts, and role in shaping current mitigation priorities:

- **2006 Floods:** Following record rainfall in late December 2005, the San Lorenzo River and several tributaries overtopped their banks. Flooding was widespread in Felton and low-lying agricultural areas. Property damage countywide was estimated at $115 million, with crop losses exceeding $32 million.
- **2017 Winter Storms:** In February 2017, a series of atmospheric river events brought record rainfall and saturated soils, causing flooding along Soquel Creek, Corralitos Creek, and the San Lorenzo River. The storms damaged levees, bridges, culverts, and private property, while triggering numerous landslides and road closures.
- **2023 Pajaro River Levee Failure:** In March 2023, a major levee breach along the Pajaro River on the Monterey County side inundated hundreds of homes and extensive agricultural areas, displaced thousands of residents, and caused hundreds of millions of dollars in losses to homes, businesses, and crops. Multiple flood events occurred over a 3-month period including flooding from Corralitos Creek and overtopping. The flood events caused an estimated $300 million in property damage and $200 million in crop damage, marking it as one of the most damaging flood events in county history.

These events underscore the county's vulnerability to both riverine and coastal flood hazards and highlight the importance of structural and non-structural mitigation strategies, including levee rehabilitation, stormwater system upgrades, and land use controls in flood-prone areas.

3.2.2.5 Location

Flooding in Santa Cruz County occurs in both inland and coastal areas and can result from riverine overflow, coastal storm surge, tidal inundation, and localized stormwater drainage issues. FEMA mapping in Figure 3-11 shows Special Flood Hazard Areas (SFHA) in the unincorporated county, which are concentrated along the San Lorenzo River, Soquel Creek, Aptos Creek, Corralitos Creek, and the Pajaro River, as well as low-lying coastal areas exposed to wave run-up and high tides.

The county's largest riverine floodplain is associated with the Pajaro River, which forms the southern boundary with Monterey County. This area includes extensive agricultural lands and residential neighborhoods in the vicinity of Watsonville, where levee overtopping or failure can cause catastrophic flooding. In March 2023, a levee breach in this area inundated hundreds of homes and thousands of acres of farmland.

Other riverine systems can be characterized by rapid rise in river stage depending on precipitation patterns. These systems include:

- **San Lorenzo River:** The primary drainage for the Santa Cruz Mountains, flowing through Boulder Creek, Felton, and downtown Santa Cruz before discharging into Monterey Bay. Several tributaries, such as Zayante Creek and Branciforte Creek, contribute to flash flooding in urbanized reaches.
- **Soquel Creek:** Recurrent flash flooding occurs along Soquel Creek, most notably at the intersection of Main Street and Soquel Drive in Soquel Village, where consecutive years of inundation have impacted several businesses and a nearby mobile home park. Further downstream, Capitola Village and adjacent

neighborhoods are subject to flooding during intense winter storms, often worsened by tidal influences at the creek's outlet to Monterey Bay.

- **Aptos and Valencia Creeks:** Drain lowland areas of Aptos, where limited channel capacity and tidal influences can combine to cause flash flooding.
- **Corralitos and Salsipuedes Creeks:** Major Pajaro River tributaries that drain agricultural and residential areas in the southeastern portion of the county.

DWR Flood Hazard Mapping

In addition to FEMA-designated SFHAs, the California Department of Water Resources' (DWR) Best Available Mapping (BAM) program identifies Flood Awareness Zones (Figure 3-12) where flood risk is present but not captured in FEMA's detailed studies. These areas include upper watershed channels and smaller tributaries where historical flooding has been documented, and where future development or land use changes could exacerbate downstream flood hazards.

As shown in the BAM data for Santa Cruz County, Flood Awareness Zones extend along many steep, upper watershed tributaries such as Bean Creek, Carbonera Creek, Branciforte Creek, and Soquel Creek in the central portion of the county, as well as Zayante Creek, Fall Creek, and tributaries to the San Lorenzo River in the north. To the east, smaller creeks draining the Santa Cruz Mountains; such as Aptos Creek, Valencia Creek, and Trout Gulch Creek, also show mapped flood awareness extents.

While these zones are not part of FEMA's Special Flood Hazard Areas, their identification highlights potential exposure for hillside and canyon communities (e.g., Boulder Creek, Ben Lomond, Felton, Scotts Valley, Soquel, Aptos). Flooding in these tributaries can occur rapidly during intense rainfall due to steep slopes, shallow soils, and confined channels, resulting in localized flash flooding, debris flows, and downstream impacts.

The presence of these BAM-identified zones underscores the importance of monitoring watershed conditions, maintaining riparian corridors, and carefully managing development in headwater areas. Even modest land use changes in these upper basins can increase runoff volumes and velocities, compounding hazards for downstream residents and infrastructure.

Coastal Hazard Locations

Coastal flood hazards are most pronounced along low-lying beaches, lagoons, and estuaries, including areas at the mouths of the San Lorenzo River, Soquel Creek, Pajaro River, Aptos Creek, and along Beach Drive in Rio Del Mar. These locations are susceptible to flooding from a combination of high tides, wave run-up, and storm surge, which can be amplified during El Niño events or periods of elevated sea level.

All lands within mapped SFHAs and BAM awareness zones along rivers, creeks, and the coast are subject to inundation under severe storm conditions. Damage potential is exacerbated in areas where levees, floodwalls, or stormwater systems are aging or undersized for current and projected hydrologic conditions.

Mitigation measures to reduce flood risk include maintaining and upgrading levees, improving bridge and culvert capacity, restoring riparian corridors, and adopting land use practices that limit exposure of new development to flood hazards.

Levee Systems

In Santa Cruz County, there are two primary levees systems, one on the San Lorenzo River through the City of Santa Cruz and the other along the Pajaro River (Figure 3-13 and Figure 3-14). The most significant levee systems are located along the lower Pajaro River and its tributaries, maintained by PRFMA. These levees protect developed lands in unincorporated Santa Cruz County and the City of Watsonville, the unincorporated community of Pajaro in Monterey County, and extensive surrounding agricultural lands. However, unlike urban-protecting levees built to withstand major events, the Pajaro River levees currently provide only a low level of protection, estimated at about an eight-year flood event. This means the floodplain near Watsonville remains extensive, and thousands of acres of agricultural land, roadways, and other assets remain at significant risk during large storms.

This vulnerability was underscored during the March 2023 Pajaro River levee breach, which caused widespread flooding, prolonged evacuations, and substantial economic losses. Flood hazard mapping of leveed-areas in Santa Cruz County in Figure 3-11 illustrates the extent of flood risk should the levees overtop or fail. While planned upgrades through the Pajaro River at Watsonville Project aim to achieve 100-year flood protection, until those improvements are complete, the potential for damaging floods remains high.



Figure 3-11: County-Wide FEMA Flood Hazard Zones Map



Figure 3-12: County-Wide DWR Flood Awareness Zones Map



San Lorenzo River Levees (USACE)

Levees Along San Lorenzo River in Santa Cruz County

Source: USACE, FEMA

Figure 3-13: San Lorenzo River Levees



Pajaro River Levees (USACE)

Levees Along The Pajaro River in Santa Cruz County

Source: USACE, FEMA

Figure 3-14: Pajaro River Levees

3.2.2.6 Repetitive Loss (RL)

A repetitive loss (RL) property is a FEMA designation, defined as an insured property that has made two or more claims of more than $1,000 in any rolling 10-year period since 1978. The term "rolling 10-year period" means that both qualifying claims happen within 10 years of each other. For example, a property would be designated as RL if there was a claim of $1,500 in January 2006 and another claim for $2,000 in December 2015, but not if the second claim occurred after January 2016. Claims must be at least 10 days apart but within 10 years of each other.

RL properties may be classified as Severe Repetitive Loss under certain conditions. A Severe Repetitive Loss property (SRL) has had four or more claims of at least $5,000, or at least two claims that cumulatively exceed the buildings reported value. A property that sustains repetitive flooding may or may not be on Santa Cruz County's RL property list for a number of reasons:

- Owners who have completed the terms of the mortgage or who purchased their property outright may not choose to carry flood insurance and instead bear the costs of recovery on their own.
- The owner of a flooded property that does carry flood insurance may choose not to file a claim.
- Even insured properties that are flooded regularly with filed claims may not meet the $1,000 minimum threshold to be recognized as an RL property.
- The owner adopted mitigation measures that reduce the impact of flooding on the structure, removing it from the RL threat and the RL list (in accordance with FEMA's mitigation reporting requirements).

A property does not have to be currently carrying a flood insurance policy to be considered a RL or SRL property. Often homes in communities are not carrying flood insurance but are still on the community's RL list. The RL designation follows a property from owner to owner, from insurance policy to no insurance policy, and even after the property has been mitigated. Having an insurance policy and making claims that fall into the repetitive loss criteria will put a property on the RL list. Even after the policy on a property has lapsed or been terminated, the property will remain on the county's RL list.

Extensive FEMA NFIP databases are used to track claims for every participating community, including unincorporated Santa Cruz County. It is important to note that FEMA's RL inventory for Santa Cruz County includes SRL properties; therefore, RL totals presented in this section represent the combined number of RL and SRL properties.

As of July 2025, unincorporated Santa Cruz County has 103 total RL/SRL properties, including both insured and uninsured structures that have not been mitigated, under its jurisdiction (91 RL and 12 SRL). According to NFIP records, these properties have received around $8,017,000 in building claims and $677,000 in contents claims, making the total combined NFIP payout almost $8.7 million.

Since 2010, Santa Cruz County has successfully mitigated several RL/SRL properties, primarily through elevation and relocation to reduce exposure in certain repetitive loss areas (RLA). However, **51 properties remain unmitigated and insured** under the NFIP which continue to generate claims during significant flood events. Addressing these remaining properties through cost-effective mitigation measures remains a

priority in the county's flood risk reduction strategy. Loss statistics under the NFIP are presented in Table 3-15 in Section 3.2.2.3.

3.2.2.6.1 Repetitive Loss Areas Analysis (RLAA)

A Repetitive Loss Areas Analysis (RLAA) identifies clusters of RL and SRL properties located in close proximity and subject to similar flood hazard conditions. These repetitive loss areas (RLA) typically share the same flooding source—such as a river, creek, or coastal reach—and are susceptible to repetitive damage during high-water events. In unincorporated Santa Cruz County, repetitive loss properties are concentrated in two primary hazard environments: riverine corridors like the San Lorenzo River and its tributaries and costal lowlands such as Capitola Village.

The county-wide repetitive loss areas map in Figure 3-15 depicts all 12 identified RLAs in unincorporated Santa Cruz County. Each RLA represents a geographic cluster of RL and SRL properties that share similar flooding sources and conditions. The boundaries are based on FEMA NFIP claim records, spatial clustering of affected parcels, and local knowledge of flood hazard patterns. These areas capture the most concentrated repetitive flooding risks in the county, occurring in both riverine and coastal environments:

- **Riverine RLAs** are concentrated along the San Lorenzo River, Zayante Creek, Soquel Creek, Aptos Creek, Corralitos Creek, and the Pajaro River.
- **Coastal RLAs** occur in low-lying beachfront neighborhoods such as Seacliff, Beach Drive, and New Brighton, which experience flooding from wave run-up, tidal inundation, and coastal storms.

The RLA map series prepared for this plan delineates these clusters and provides aggregated data on claim history, historic losses, and current property values for each identified RLA. These RLAs represent the most concentrated geographic expression of repetitive flooding in the county and are the logical focus for targeted mitigation actions such as structure elevation, acquisition, or floodproofing. Each RLA is profiled individually in this section, contains a summary of its location, flood source, historical flooding patterns, NFIP claims history, known mitigation actions, and recommended strategies for reducing RL exposure.

Under the Privacy Act of 1974 (5 U.S.C. 552a), FEMA restricts public release of flood insurance policy and claims data. Individual property-level information can only be shared with state and local governments for floodplain management, mitigation, or research purposes. Accordingly, this plan presents only aggregated information for each RLA and does not identify specific properties or individual claim records. Other sources used to inform the RLAA and recommended mitigation measures include: 2021 Santa Cruz County HMP, 2025 Santa Cruz County Climate Adaptation and Vulnerability Assessment (CAVA), 2018 California Coastal Commission Sea-Level Rise Guidance, 2013 Zone 5 Master Plan, 2023 Zone 5 Storm Drainage Master Plan (SDMP), Zone 7 Master Plan, 2016 FEMA Flood Insurance Study (FIS), and 2013 FEMA Mitigation Ideas.



RLA	Properties w/ Repetitive Loss	Total # Losses	Total Claims Paid	Average Claims Payment	Total Parcel Count	Average Flood Depth	Maximum Flood Depth
Ben Lomond	4	8	$ 182,909	$ 22,864	67	5.1′	21.0′
Felton Grove	31	110	$ 2,170,795	$ 20,748	79	6.8′	10.9′
Beth Road	7	16	$ 445,798	$ 24,973	46	16.2′	36.4′
Paradise Park	7	22	$ 603,469	$ 24,137	115	3.7′	18.3′
Paradise Park Lower	7	26	$ 872,461	$ 38,485	89	0.4′	6.0′
Soquel	3	11	$ 85,112	$ 7,564	15	11.4′	21.8′
Pot Belly	3	7	$ 34,921	$ 5,064	17	12.7′	14.1′
Las Olas Drive	3	7	$ 46,980	$ 7,429	31	5.4′	9.8′
Beach Drive Upper	12	25	$ 248,932	$ 9,818	94	1.1′	3.9′
Beach Drive Lower	10	39	$ 1,516,214	$ 37,154	50	3.5′	8.7′
Via Gaviota	5	11	$ 290,447	$ 27,098	37	-	-
Interlaken	15	34	$ 1,325,950	$ 38,186	234	1.9′	10.0′

Note: Approximate flood depths derived from FEMA flood zones and countywide topography. Repetitive loss data derived from FEMA reporting 3/2025.

SANTA CRUZ COUNTY FLOODING

REPETITIVE LOSS AREAS (RLA)

Figure 3-15: Santa Cruz County Repetitive Loss Areas (RLAs)

Ben Lomond

The Ben Lomond RLA lies along the San Lorenzo River in the town center, where the channel's narrow floodplain and close proximity to development create persistent flood risk (Figure 3-16). Steep upstream watersheds in the Santa Cruz Mountains can generate rapid rises in river levels during intense winter storm events, particularly between December and February. Limited floodplain width, aging bridge crossings with low clearance, and high-velocity flows have historically contributed to bank overtopping and flooding during significant rain events.

Historical flood impacts have included inundation of ground floors, roadway closures, and erosion of riverbanks adjacent to residential parcels. Debris accumulation in culverts and at bridge crossings during storms can exacerbate backwater effects, raising flood elevations in the downtown area.

Past mitigation measures have included selective vegetation management along the river corridor and targeted debris removal to improve flow conveyance. Bridge and culvert upgrades are under discussion to increase hydraulic capacity, though no large-scale capital flood control projects have been completed. Individual property owners have elevated utilities and installed site-specific drainage improvements to reduce localized damage.

Mitigation options are constrained by the legacy pattern of development, where structures were built with limited setbacks from the river's edge. These siting limitations restrict opportunities for large-scale channel modifications, emphasizing the importance of property-level mitigation and ongoing monitoring of bank stability.

Future recommendations for the Ben Lomond RLA include:

- Advancing design and funding for bridge and culvert replacement to increase flow capacity and reduce backwater effects.
- Continuing vegetation and debris management to maintain conveyance during peak stormflows.
- Encouraging participation in FEMA mitigation programs for property elevation and floodproofing.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87'

0'



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
4	8	$182,909	$22,864

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
67	5.1'	21.0'

REPETITIVE LOSS AREA (RLA)

BEN LOMOND

Figure 3-16: Ben Lomond Repetitive Loss (RL) Area

Felton Grove

The Felton Grove RLA is located in Felton, centered on the historic covered bridge crossing of the San Lorenzo River (Figure 3-17). Flooding in this neighborhood occurs frequently, with much of the area situated within the three-year floodplain. FEMA SFHA mapping confirms that much of this RLA is also within the 1% annual chance floodplain, with modeled depths exceeding two feet in portions of the neighborhood. Contributing factors may include the cement sill at the Felton Diversion Dam, which prevents scour and has been raised in past litigation but was ultimately not determined to be a primary cause of flooding. In addition, the confluence with Zayante Creek can exacerbate flood conditions when high flows and sediment loads coincide with San Lorenzo River peaks. Atmospheric river events and prolonged winter rains can further elevate flood risk in this reach.

Past mitigation measures have included periodic debris removal at the bridge to maintain flow capacity, as well as structure elevation and the installation of low floodwalls by individual property owners. The 2021 county HMP identified potential long-term strategies, such as retrofitting the bridge approaches and improving channel conveyance, though the bridge's cultural and historic values present constraints to large-scale structural modifications. Future recommendations for the Felton Grove RLA include:

- Continuing and expanding debris management programs to maintain bridge conveyance capacity during major storm events.
- Evaluating feasibility of targeted channel modifications upstream to reduce backwater effects while preserving historic integrity.
- Enhancing flood warning and emergency response systems for the surrounding community.
- Encouraging FEMA-funded property-level mitigation, including structure elevation and dry floodproofing.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87'
0'



REPETITIVE LOSS STATISTICS WITHIN RLA
PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
31	110	$2,170,795	$20,748

PARCEL COUNT AND EXPECTED FLOOD DEPTHS
FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
79	6.8'	10.9'

REPETITIVE LOSS AREA (RLA)

FELTON GROVE

Figure 3-17: Felton Grove Repetitive Loss (RL) Area

Beth Road

The Beth Road RLA is located along a broad meander of the San Lorenzo River, where the floodplain widens slightly but remains tightly bordered by residential development (Figure 3-18). This geometry allows floodwaters from upstream winter storm events, particularly atmospheric rivers, to spread laterally into low-lying parcels. The steep upper watershed of the San Lorenzo delivers high-velocity, debris-laden flows that can cause rapid inundation during prolonged rainfall.

Historical flood events in this area, documented in the FEMA Flood Insurance Study (FIS) and 2021 HMP, have produced depths sufficient to inundate first floors, damage utilities, and deposit sediment across yards and roadways. The FEMA SFHA mapping shows much of the RLA subject to the 1% annual chance flood, with portions experiencing modeled depths exceeding three feet.

Past mitigation actions in the Felton RLA have included drainage ditch regrading to improve overland flow routing; localized levee berm repairs along sections of the riverbank; and private property measures such as elevation of structures, utility relocation, and floodproofing of basements or crawl spaces. The 2021 HMP recommended coordinated riparian vegetation management to maintain channel conveyance. Additional considerations include enhanced early warning systems and better integration of community evacuation planning with upstream flow monitoring. Future recommendations for the Beth Road RLA include:

- Expanding property owner education programs through the County or the Resource Conservation District (RCD).
- Encouraging FEMA-funded property-level mitigation, including structure elevation.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87'

0'

REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
7	16	$445,798	$24,973

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
46	16.2'	36.4'

REPETITIVE LOSS AREA (RLA)

BETH ROAD



Figure 3-18: Beth Road Repetitive Loss (RL) Area

Paradise Park

The Paradise Park RLA is located along a sharp bend in the San Lorenzo River near Highway 9, where the river's curvature concentrates high-velocity flows against the outer bank during winter storm events (Figure 3-19). The combination of steep upstream tributaries, narrow channel width, and confined floodplain causes rapid-onset flooding during prolonged rainfall or atmospheric river conditions.

Historical flooding has been characterized by deep, fast-moving water capable of causing bank erosion, undermining structures, and depositing debris in residential areas. The FEMA FIS identifies much of the RLA as SFHA, with modeled depths exceeding three feet in the 1% annual chance event. Past mitigation actions include:

- Bank stabilization projects using riprap and native vegetation to reduce erosion.
- Private property improvements such as structure elevation and installation of floodproofing measures for basements and ground floors.
- Targeted erosion control maintenance by the County to protect infrastructure.

Future recommendations for the Paradise Park RLA include:

- Coordinating with the Paradise Park HOA to explore feasible property-level mitigation strategies given height limitations that complicate compliance with elevation requirements.
- Continuing monitoring of channel migration and periodic inspection of stabilization structures (per 2021 HMP).
- Expanding riparian buffer zones to slow bank erosion and enhance natural floodplain function. (per 2021 HMP).
- Exploring potential funding for small-scale floodwalls or berms to protect the most vulnerable parcels. (per 2021 HMP).



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87'

0'



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
7	22	$603,469	$24,137

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
115	3.7'	18.3'

REPETITIVE LOSS AREA (RLA)

PARADISE PARK

Figure 3-19: Paradise Park Repetitive Loss (RL) Area

Paradise Park Lower

The Paradise Park Lower RLA lies in a large meander loop of the San Lorenzo River, southwest of Highway 9 (Figure 3-20). The community's location within the mapped floodway exposes it to high-flow velocities and deep inundation during major winter storms. Flooding is most frequent between December and February when atmospheric river events drive rapid river rises, with limited overbank storage to slow flows.

Historic events have caused water to overtop banks and flood multiple homes, along with Paradise Park's community facilities. FEMA SFHA mapping shows much of the RLA in the regulatory floodway, with modeled depths exceeding four feet in the 1% annual chance event. The narrow channel and tight meander bend also concentrate hydraulic forces, increasing erosion risk along outer banks. Past mitigation actions in Paradise Park include:

- Elevating key community buildings, such as the clubhouse and maintenance facilities.
- Drainage improvements to reduce ponding in interior streets.
- Ongoing coordination between the Paradise Park Masonic Club and Santa Cruz County for emergency evacuation planning.

Due to its location in the floodway, structural flood control measures are limited by regulatory and environmental constraints. The 2021 HMP and the county's Climate Adaptation and Vulnerability Assessment recommend focusing on non-structural measures, including emergency planning, early and warning system. Future recommendations for the Paradise Park Lower RLA include:

- Coordinating with the Paradise Park HOA to explore feasible property-level mitigation strategies given height limitations that complicate compliance with elevation requirements.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′
0′



REPETITIVE LOSS STATISTICS WITHIN RLA
PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
7	26	$872,461	$38,485

PARCEL COUNT AND EXPECTED FLOOD DEPTHS
FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
89	0.4′	6.0′

REPETITIVE LOSS AREA (RLA)

PARADISE PARK LOWER

Figure 3-20: Paradise Park Lower Repetitive Loss (RL) Area

Soquel

The Soquel RLA encompasses properties adjacent to Soquel Creek, a dynamic coastal stream with a history of overtopping its banks during extended winter storm events (Figure 3-21). Flooding risk in this reach is heightened when heavy rainfall coincides with high tide conditions in Monterey Bay, which can slow downstream outflow and back water into developed areas. The narrow floodplain through Soquel Village and downstream neighborhoods constrains floodwaters, while sediment deposition in the lower channel further reduces conveyance capacity.

Historically, Soquel Creek has experienced damaging flood events linked to atmospheric river storms, which deliver intense rainfall over the steep upper watershed. These storms can mobilize large quantities of sediment and debris, contributing to localized blockages at bridges and culverts. Notable flood impacts have included inundation of commercial properties in Soquel Village and residential structures along downstream reaches.

Mitigation actions in the Soquel RLA have included sediment removal and targeted bank stabilization projects undertaken through the Santa Cruz County Flood Control and Water Conservation District (FCWD), Zone 5. The Zone 5 Master Plan also identifies the need for channel capacity improvements in the lower reaches, particularly between State Route 1 and the creek's mouth, and has called for continued maintenance of tide gates and outfall structures to reduce backwater flooding. Several property owners have pursued NFIP-funded elevation projects and implemented floodproofing measures for utilities and ground floors. Future recommendations for the Soquel RLA include:

- Advancing feasibility studies for downstream channel widening or benching to improve flood conveyance while preserving habitat.
- Increasing maintenance of sediment-prone reaches upstream of key bridges.
- Continuing seasonal inspections and repairs to tide gates to maintain full functionality during storm events.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′

0′



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
3	11	$85,112	$7,564

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
15	11.4′	21.8′

REPETITIVE LOSS AREA (RLA)

SOQUEL

Figure 3-21: Soquel Repetitive Loss (RL) Area

Pot Belly

The Pot Belly RLA is situated along the Monterey Bay shoreline near New Brighton State Beach on Pot Belly Beach Road (Figure 3-22). This area is subject to coastal flooding driven by wave run-up, storm surge, and high tides, particularly during winter atmospheric river events. Long-period swells and storm-driven waves can overtop the beach berm, sending water inland toward properties and infrastructure. The area's low elevation relative to ocean water levels increases susceptibility to flooding during king tides, especially when combined with storm conditions.

Historical flood impacts here have primarily occurred during severe Pacific storms when elevated water levels and energetic surf coincide. Coastal erosion is an ongoing hazard, gradually reducing the natural protective capacity of the beach and dune system. Shoreline retreat can expose infrastructure to direct wave attack, further increasing the frequency of flood-related losses.

Mitigation actions have included rebuilding and improvement of rip rap revetments and home elevation. . Some property owners have constructed private seawalls or elevated ground-floor living areas to meet or exceed projected water elevations of the 1% annual chance flood. The 2021 HMP also notes the importance of continued monitoring of shoreline change rates to anticipate and adapt to erosion-related flood risk. Future recommendations for the Pot Belly RLA include:

- Evaluating feasibility of dune restoration or hybrid nature-based coastal defenses to supplement hard infrastructure.
- Re-stacking the recovered rip rap on the revetment;
- Monitoring and updating flood hazard mapping to incorporate sea-level rise projections.
- Technical assistance and information

FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′

0′



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
3	7	$34,921	$5,064

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
17	12.7′	14.1′

REPETITIVE LOSS AREA (RLA)

POT BELLY

Figure 3-22: Pot Belly Repetitive Loss (RL) Area

Las Olas Drive

The Las Olas Drive RLA extends along the bluff-backed shoreline near Seacliff State Beach, an area highly exposed to direct Pacific Ocean wave attack, storm surge, and coastal erosion (Figure 3-23). During major winter storms, particularly atmospheric river events coinciding with king tides, wave run-up and overtopping can rapidly flood the narrow strip of development situated directly landward of the shoreline. Flooding in this RLA is often accompanied by erosion damage to seawalls, bluff faces, and adjacent infrastructure.

Historical flood impacts have been driven by high-energy wave events during El Niño winters and strong coastal storms, which elevate water levels and reduce the protective function of the beach berm. The bluffs provide some protection from wave energy; however, where development is sited at lower elevations or adjacent to creek mouths, floodwaters can directly impact ground floors and utilities.

Mitigation measures implemented to date include construction and reinforcement of seawalls and riprap armoring along vulnerable reaches. The county and State Parks have also explored beach nourishment as a supplementary measure, though funding and permitting challenges have limited large-scale implementation. Private property owners have elevated utilities and applied wave-impact-resistant materials to ground-floor levels. Future recommendations for the Las Olas Drive RLA include:

- Coordinating with the California Coastal Commission on hybrid natural–structural coastal protection strategies.
- Evaluating long-term retreat or elevation strategies for the most at-risk parcels, incorporating projected sea level rise impacts.
- Providing technical guidance and outreach to homeowners on how to elevate existing structures in coastal and flood-prone areas, in alignment with FEMA best practices and in coordination with local permitting requirements.

FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′

0′



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
3	7	$46,980	$7,429

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
31	5.4′	9.8′

REPETITIVE LOSS AREA (RLA)

LAS OLAS DRIVE

Figure 3-23: Las Olas Drive Repetitive Loss (RL) Area

Beach Drive Upper

The Beach Drive Upper RLA is located along the narrow oceanfront in Rio Del Mar, directly exposed to Pacific Ocean wave attack, storm surge, and coastal erosion (Figure 3-24). During major winter storms—particularly atmospheric river events coinciding with king tides—wave run-up and overtopping can inundate properties situated directly behind the seawall. Flooding in this RLA is typically rapid-onset, with waves breaking against structures, leading to saltwater intrusion, erosion of foundations, and damage to utilities and lower floors.

Historical flood impacts have been driven by high-energy swell events during El Niño winters and strong coastal storms, which combine elevated water levels with reduced beach berm protection. Long-term shoreline erosion has gradually diminished the berm's buffering capacity, increasing vulnerability to overtopping and flood damage.

Mitigation measures implemented to date include seasonal placement of temporary sand berms and reinforcement of existing seawall structures prior to winter storms. Several property owners have elevated utilities, reinforced ground floors with wave-impact-resistant materials, and installed removable storm barriers. Future recommendations for the Beach Drive Upper RLA include:

- Pursuing coordinated beach nourishment and sediment management to rebuild the berm and maintain a buffer against wave energy.
- Evaluating the feasibility of increasing seawall height or incorporating hybrid natural–structural solutions.
- Providing technical guidance and outreach to homeowners on how to elevate existing structures in coastal and flood-prone areas, in alignment with FEMA best practices and in coordination with local permitting requirements.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′

0′



REPETITIVE LOSS STATISTICS WITHIN RLA
PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
12	25	$248,932	$9,818

PARCEL COUNT AND EXPECTED FLOOD DEPTHS
FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
94	1.1′	3.9′

REPETITIVE LOSS AREA (RLA)

BEACH DRIVE UPPER

Figure 3-24: Beach Drive Upper Repetitive Loss (RL) Area

Beach Drive Lower

The Beach Drive Lower RLA is located along the southern segment of Rio Del Mar's narrow beachfront, immediately landward of the Pacific Ocean and within the direct wave impact zone (Figure 3-25). The area is highly vulnerable to flooding from wave run-up, storm surge, and coastal erosion during intense winter storms, particularly when atmospheric river systems coincide with king tides. Due to its orientation and exposure, overtopping waves can rapidly inundate residences, leading to structural damage, saltwater corrosion, and erosion of the beach berm.

Historical flooding in this RLA has been linked to El Niño winters and high-energy Pacific swell events, which generate elevated water levels and powerful waves capable of breaching seasonal berms and overtopping seawalls. Long-term shoreline retreat has further reduced natural flood protection.

Mitigation measures undertaken include seasonal construction of temporary sand berms, maintenance and reinforcement of existing seawalls, and installation of removable flood barriers at property entrances. Some homeowners have elevated utilities and reinforced lower levels with wave-resistant materials. Future recommendations for the Beach Drive Lower RLA include:

- Providing technical guidance and outreach to homeowners on how to elevate existing structures in coastal and flood-prone areas, in alignment with FEMA best practices and in coordination with local permitting requirements.
- Evaluation of seawall height increases or incorporation of hybrid natural–structural coastal defenses.
- Development of a long-term adaptation strategy considering projected sea level rise and increased storm frequency.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′

0′



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
10	39	$1,516,214	$37,154

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
50	3.5′	8.7′

REPETITIVE LOSS AREA (RLA)

BEACH DRIVE LOWER

Figure 3-25: Beach Drive Lower Repetitive Loss (RL) Area

Via Gaviota

The Via Gaviota Repetitive Loss Area encompasses a narrow stretch of beachfront development in Rio Del Mar, directly fronting the Pacific Ocean and subject to high-energy wave action, storm surge, and coastal erosion (Figure 3-26). Due to the street's immediate proximity to the shoreline, wave overtopping during major winter storms, especially atmospheric river events coinciding with king tides, can result in rapid flooding of residences and public access ways.

Historic flood events in this RLA have been tied to El Niño winters and large Pacific swell episodes that elevate water levels, drive wave run-up beyond the natural berm, and cause structural damage to seawalls and private property. Erosion trends have incrementally reduced the width and height of the beach berm, increasing exposure to direct wave impact.

Mitigation measures implemented to date include seasonal sand berm construction, reinforcement of seawall segments, and installation of removable flood panels at building entrances. Several homeowners have elevated utilities and reinforced lower-level walls with impact-resistant materials. Future recommendations for the Via Gaviota RLA include:

- Providing technical guidance and outreach to homeowners on how to elevate existing structures in coastal and flood-prone areas, in alignment with FEMA best practices and in coordination with local permitting requirements.
- Exploration of hybrid coastal defense strategies, combining engineered armoring with dune or berm restoration.
- Development of a long-term adaptation framework incorporating projected sea level rise and potential relocation or elevation of the most vulnerable structures.



FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87′

0′



REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
5	11	$290,447	$27,098

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
37	-′	-′

REPETITIVE LOSS AREA (RLA)

VIA GAVIOTA

Figure 3-26: Via Gaviota Repetitive Loss Area

Interlaken

The Interlaken RLA is located near the confluence of the Salsipuedes Creek and Corralitos Creek tributaries to the Pajaro River near College Lake, Kelley Lake, and Drew Lake. Residential properties in this area are currently not protected by levees, which do not exist along Corralitos Creek or the eastern reach of Salsipuedes Creek. These areas flood from a combination of overtopping of Corralitos Creek northwards across Holohan Road as well as flooding influences from these lakes and stormwater capacity issues (Figure 3-27). The surrounding watershed drains toward the lake, and prolonged rainfall, especially during atmospheric river events, can raise lake levels enough to overtop banks or overwhelm local drainage systems. Backwater effects from saturated soils and limited outlet capacity further increase flood durations.

Historical flood impacts have included inundation of ground floors, septic system failures, and damage to multiple structures and outbuildings. The area's relatively shallow groundwater table exacerbates flooding during wet winters, as soils quickly reach saturation.

Mitigation measures implemented to date include targeted ditch regrading to improve surface runoff, localized pump installations, and elevation of select utilities above historic high-water marks. The county, in coordination with Zone 7 Flood Control and Water Conservation District (FCWD) (now PRFMA), has assessed outlet control improvements to better regulate lake levels during high inflow periods, though no major structural projects have been completed. Future recommendations for the Lake View RLA include:

- Conducting a detailed hydrologic and hydraulic study to assess lake outlet improvements and stormwater detention options.
- Expanding participation in FEMA hazard mitigation programs through outreach efforts.
- Providing technical guidance and outreach to homeowners on how to elevate or flood proof structures in in alignment with FEMA best practices and in coordination with local permitting requirements.
- Coordinating with regional partners to improve watershed-scale runoff management upstream of Pinto Lake.





FEMA FLOOD ZONES

- 100-Year
- Floodway
- 500-Year
- Cross Section
  Base Flood Elevation Labeled

FLOOD DEPTHS

87'
0'

REPETITIVE LOSS STATISTICS WITHIN RLA

PROPERTIES EXPERIENCING REPETITIVE LOSS

PROPERTIES W/ LOSSES	TOTAL LOSSES IN RLA	TOTAL CLAIMS PAYMENTS	AVERAGE CLAIM PAYMENT
15	34	$1,325,950	$38,186

PARCEL COUNT AND EXPECTED FLOOD DEPTHS

FLOODING DEPTH BASED ON FEMA FLOOD ZONES

PARCEL COUNT IN RLA	AVERAGE FLOODING DEPTH	MAXIMUM FLOODING DEPTH
234	1.9'	10.0'

REPETITIVE LOSS AREA (RLA)

INTERLAKEN

Figure 3-27: Lake View Repetitive Loss (RL) Area

3.2.2.7 Frequency & Probability of Future Occurrences

Flood frequency terms like "100-year flood" can be misleading, giving the false impression that such events happen only once a century. When we talk about the "1% annual chance" flood—often called the 100-year flood—it does not mean flooding happens only once every hundred years. Instead, it means that in any given year, there's a one in 100 (or 1%) chance that such a flood will occur. Over the course of a 30-year mortgage, that works out to roughly a 26% chance, higher than the odds of experiencing a major house fire. And just like lightning, it can strike more than once in quick succession; two or more "100-year" floods can happen in back-to-back years.

Even properties outside FEMA's mapped 1% annual chance flood zones are not immune; localized flooding can occur when intense rainfall, debris blockages, or wave-driven surge overwhelm drainage systems or overtop natural barriers. This is why understanding flood probability is important for residents, planners, and decision-makers. In Santa Cruz County, steep mountain watersheds, short and flashy river systems, and exposure to Pacific storms mean that damaging floods can occur more often than these averages suggest.

Table 3-17 below shows how flood probabilities are expressed, what they mean over a 30-year period, and how they can be understood in plain language.

Table 3-17: Flood Probability Annually and Over 30-Year Period

Annual Chance	Common Name	30-Year Chance of Occurrence	Example
0.2%	500-YR Flood	**6%**	Like rolling a 100-sided die each year for 30 years, you have about a 1-in-16 chance of getting a "flood" roll.
1%	100-YR Flood	**26%**	Each year over a 30-year period, you have about a 1-in-4 chance of a flood roll.
2%	50-YR Flood	**45%**	Nearly even odds for each yearly die roll over the span of 30 years.
10%	10-YR Flood	**96%**	Almost certain to get a flood roll at least once, if not multiple times, in 30 years.
50%	2-YR Flood	**100%**	Expected to get a flood roll many times during a 30-year period.

In Santa Cruz County, flooding can and does happen annually, especially during the winter storm season (November through March) when atmospheric rivers bring intense, sustained rain. Steep mountain watersheds, like those feeding the San Lorenzo River, Soquel Creek, and Corralitos Creek, can funnel rainfall into narrow channels, producing fast-moving, debris-laden floods. Coastal areas such as Seacliff, Beach Drive, and Via Gaviota face additional threats from wave overtopping during high tides and winter storms. Some locations, such as New Brighton, experience a mix of both river and coastal flooding, making them especially vulnerable.

While FEMA's SFHA maps outline where 1% annual chance flooding is most likely, real-world storms do not always follow these boundaries. In recent years, atmospheric rivers have caused damaging floods outside mapped floodplains, often triggered by culverts clogged with debris, eroding streambanks, or temporary storm surge effects. Combined with projected sea level rise, this means flooding in Santa Cruz County could become more frequent and more severe, even in places that have not historically flooded.

3.2.2.8 Severity

The severity of a flood event in Santa Cruz County depends on a combination of water depth, flow velocity, and the amount of debris carried by the water. While deep flooding can submerge structures and infrastructure, even relatively shallow flows can cause severe damage if the water is moving quickly. High-velocity flows have greater force and can erode foundations, undermine roads, and carry large debris such as trees or boulders, amplifying impacts.

This is particularly relevant in Santa Cruz County's steep mountain watersheds—such as the upper San Lorenzo River, Soquel Creek, and Corralitos Creek—where intense rainfall from atmospheric rivers can quickly generate swift-moving floods. In broader valley areas, slower but deeper inundation can still result in substantial property damage, crop loss, and long-term disruption to communities.

Coastal flooding adds another layer of hazard. Wave run-up and overtopping during winter storms can produce floodwaters with strong currents, especially where waves breach dunes or seawalls. In places like Beach Drive, Via Gaviota, and Seacliff, this combination of depth and velocity often causes structural damage to buildings, roadways, and utilities.

FEMA's Flood Insurance Study (FIS) for Santa Cruz County provides modeled water surface elevations and flow velocities for the 1% annual chance flood event. These models help estimate the likely severity of flooding in mapped SFHAs and are used for both regulatory purposes and mitigation planning. Table 3-18 lists the modeled peak discharges in cubic feet per second (cfs) for key Santa Cruz County streams and rivers, which represent the flow rates used in FEMA's mapping of the SFHAs. Figure 3-28 provides stream river locations identified in the table.

Table 3-18: Santa Cruz County Modeled Peak Discharges for 1% Annual Chance Flood

			Peak Discharge (CFS)			
			10% Annual Chance	**2% Annual Chance**	**1% Annual Chance**	**0.2% Annual Chance**
Source	Location	Drainage Area (Square Miles)	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
Pajaro River	*Downstream confluence with Salsipuedes Creek*	1275.0	14,250	32,500	43,600	76,200
San Lorenzo River	*At mouth*	136.0	23,700	42,300	50,600	70,100
Salsipuedes Creek	*At confluence with Pajaro Creek*	46.0	2,000	4,500	5,950	12,500
Soquel Creek	*At mouth*	42.8	8,310	14,700	17,500	24,300

			Peak Discharge (CFS)			
			10% Annual Chance	2% Annual Chance	1% Annual Chance	0.2% Annual Chance
Source	Location	Drainage Area (Square Miles)	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
Zayante Creek	*At confluence with San Lorenzo River*	26.2	6,250	10,100	11,800	15,600
Aptos Creek	*At mouth*	24.5	3,110	6,550	8,280	12,700
Corralitos Creek	*East Lake Ave junction w Salsipuedes Creek*	24.2	3,300	6,640	7,930	11,730

Source: FEMA 2016 Flood Insurance Study (FIS) for Santa Cruz County, CA (06087CV001C)



FEMA FIS Flood Discharge Locations

Source: FEMA, Santa Cruz County

Figure 3-28: Santa Cruz County Waterway Discharge Locations

3.2.2.9 Warning Time

In Santa Cruz County, the speed at which flooding develops depends on both geography and flood source. In inland mountain watersheds, such as the upper San Lorenzo River and its tributaries, steep slopes and small drainage basins mean that heavy rainfall can cause rapid rises in water levels, sometimes within just a few hours. This "flashier" response contrasts with larger watersheds, such as the Corralitos Watershed, where drainage areas are broader and flood peaks may take longer to develop. The flashier systems leave little time for protective actions, making close coordination with real-time gage data and weather alerts critical.

In contrast, coastal flooding from wave overtopping, storm surge, and king tide events generally develops over longer periods, often allowing for one or more days of warning. However, storm timing, wind direction, and wave height can change quickly, reducing available lead time for vulnerable communities like Seacliff, Beach Drive, and Via Gaviota.

The county integrates multiple data sources for flood warning, including:

- **Rainfall and Stream Gauges:** Real-time rainfall and stream gauges operated by county Public Works, USGS, and NWS, including sites on the San Lorenzo River, Scott Creek, and the Pajaro River.
- **Weather Radar:** The county now operates a high-resolution X-band radar in Live Oak, supplementing the regional NWS Doppler radar at Mount Umunhum. This system provides near real-time rainfall intensity updates, improving detection of localized heavy rain and filling gaps in low-elevation coverage.
- **Forecast Modeling:** The California–Nevada River Forecast Center (CNRFC) provides projected riverine flood stages for the county.
- **Tide and Surf Advisories:** The NWS Monterey Office issues advisories for high surf, king tides, and storm surge along the county's coastline.

This integrated network supports both rapid warnings for flashier inland floods and multi-day outlooks for coastal hazards, enabling emergency managers to better position resources and issue timely alerts.

Flood Awareness Tools & Dashboards

Santa Cruz County maintains several online platforms that provide emergency managers, residents, businesses, and visitors with timely, actionable information about flood hazards. These systems are intended to complement official alerts, offering both real-time monitoring and situational awareness before, during, and after storm events. Together, they improve the community's ability to anticipate changing conditions, prepare appropriately, and respond effectively.

OneRain System

The county operates a real-time rainfall and stream gauge platform powered by OneRain, available at santacruz.onerain.com. This system integrates data from ground sensors such as rain gauges and river-stage monitors with other weather feeds to display current and historical rainfall totals, stream levels, and modeled flood conditions. Users can view data over various time intervals, such as 15-minute, hourly, daily, or weekly trends, to better understand storm intensity and watershed response. During heavy rain or flash flood situations, the platform supports faster recognition of rising water levels and more informed decision-making on road closures, evacuations, and other protective actions.

Situational Awareness for Emergency Response (S.A.F.E.R.)

Santa Cruz County's Situational Awareness for Emergency Response (S.A.F.E.R.) platform is an ArcGIS-based online tool that consolidates hazard and response information into a single location for public and emergency management use. While S.A.F.E.R. covers multiple hazards, flood awareness is a central feature. In its flood maps section, users can view FEMA-designated flood zones, identify areas susceptible to stormwater flooding, and locate sandbag distribution sites. This section also links to tsunami hazard maps for coastal communities. By combining mapped hazard data with real-time information on weather, transportation, and other incidents, S.A.F.E.R. allows residents to quickly assess their risk and take early action. In a county where both riverine and coastal flooding can develop rapidly, this platform's accessibility is an important tool for maintaining public readiness.

CruzAware Notification System

CruzAware is Santa Cruz County's official alert and notification system. It is administered by the County Office of Response, Recovery and Resilience (OR3) and is designed to provide residents and visitors with timely warnings and information during emergencies. Notifications are sent by text message, telephone, or email and address a range of hazards including floods and coastal storms, as well as other public safety threats and evacuation notices.

For flood preparedness, CruzAware serves as a primary tool for delivering warnings before hazardous conditions develop. Depending on the situation, alerts may be issued hours or only minutes in advance. These notifications can include evacuation instructions, shelter locations, sandbag distribution sites, and road closure information. The system is capable of targeting specific neighborhoods or hazard zones so that alerts are relevant to those directly at risk.

The system works in coordination with other county resources, such as the S.A.F.E.R. dashboard and real-time weather monitoring systems, to support comprehensive hazard communication. The county also partners with the NWS to disseminate official watches and warnings, including Flood Watches, Flood Warnings, and Coastal Flood Advisories. NWS alerts are automatically issued through the Wireless Emergency Alerts (WEA) system to mobile devices in affected areas, providing rapid notification without

the need for prior registration. More information about CruzAware, including how to register, is available at santacruzcountyca.gov/CruzAware.

Annual Public Flood Risk Outreach

In addition to real-time alerts, Santa Cruz County conducts annual flood risk notification for property owners and renters in mapped SFHAs. This outreach, coordinated through the county's Floodplain Management Program and NFIP and CRS activities, typically includes:

- Letters or brochures explaining the property's location within the SFHA and the associated flood risk.
- Guidance on purchasing or maintaining flood insurance.
- Information on flood preparedness, evacuation routes, and property protection measures.
- Updates on recent flood events, ongoing mitigation projects, and changes to FEMA flood maps.

The county also leverages its website, social media channels, and community meetings to share seasonal reminders before the winter storm season, emphasizing steps residents can take to prepare.

By combining immediate warning capabilities with recurring risk communication, Santa Cruz County helps ensure that residents are aware of both their long-term vulnerability and any short-term threats from developing storms.

3.2.2.10 Flood Vulnerability Assessment

Santa Cruz County remains at risk from flood impacts despite ongoing efforts to reduce exposure through land use planning, policy measures, and targeted mitigation projects. This section assesses vulnerability by examining the relationship between flood hazards and the county's population, property, and critical facilities and infrastructure.

Population exposure, parcel values, critical facilities, and lifeline infrastructure were evaluated by overlaying the county's asset inventory, discussed in Section 2.2.2, with FEMA SFHAs and DWR BAM awareness zones for 100- to 500-year floodplains (or 1% and 0.2% annual chance flood hazard areas). Figure 3-29 and Figure 3-30 summarize flood exposure county-wide. Detailed results for each vulnerability category are provided in the subsections that follow.

In addition to assessing risk through hazard exposure, damage estimates were also generated for flood, specifically, using a Level 2 HAZUS-MH analysis. This dual approach ensured the assessment captured both mapped hazard exposure and modeled loss potential for the county. The HAZUS analysis integrates GIS-based 100-year flood depth grids from FEMA A zones with BFE. Parcel data described in Section 2.2.2 was imported into HAZUS as User Defined Facilities (UDF), forming the basis for estimating building replacement costs, contents values, and associated losses.



Figure 3-29: Exposure Summary – Santa Cruz County Flood Risk (FEMA Zones)



Figure 3-30 Exposure Summary – Santa Cruz County Flood Risk (DWR Awareness Zones)

3.2.2.10.1 Population

Population at risk from flooding in Santa Cruz County was estimated by intersecting FEMA's 100-year (1% annual chance) and 500-year (0.2% annual chance) floodplain boundaries with U.S. Census Bureau population data. Using GIS, census blocks, and tracts, populations were weighted according to the percentage of each block lying within the mapped flood hazard areas.

The results show that a substantial share of the county's population resides within areas that could experience significant flooding during a 100-year event, with additional residents located in areas subject to the less frequent but still damaging 500-year flood. Most at-risk residents are in the broader flood fringe, with smaller portions in high-velocity floodways and low-lying coastal areas vulnerable to storm surge and wave overtopping.

Using this approach, it was estimated that more than nine thousand county residents are exposed to some sort of FEMA-identified flood risk, in either 100-year or 500-year floodplains, as shown in Figure 3-31 and Table 3-19.



Figure 3-31: Santa Cruz County Population Exposed to Flood Risk

Table 3-19: Santa Cruz County Population Exposed to Flood Risk

	Total Population
Unincorporated County	131,149

Flood Hazard Zone	Population Count	% of Total
Flood Fringe	5,679	*4.33%*
Floodway	1,694	*1.29%*
Coastal	840	*0.64%*
100-YR Total*	8,213	*6.26%*
500-YR sans 100-YR	1,066	*0.81%*
500-YR Total	9,279	*7.08%*

**Special Flood Hazard Area (SFHA)*

Population exposure to flood hazards in Santa Cruz County is concentrated along the county's major waterways and low-lying coastal zones. Communities in the San Lorenzo River, Soquel Creek, and Pajaro River corridors show some of the highest concentrations of residents within FEMA-mapped floodplains, along with portions of Watsonville, Capitola, and Santa Cruz. Smaller but notable clusters occur in mountain valleys such as Boulder Creek, Ben Lomond, and Lompico, where narrow channels and steep slopes increase flood risk. Coastal neighborhoods, particularly in Capitola, Seacliff, La Selva Beach, and Pajaro Dunes, also host significant populations in flood-prone areas. These patterns reflect a mix of historical settlement along rivers and the coast, as well as the concentration of housing in valleys and floodplains where developable land has been available.

3.2.2.10.2 Property

Table 3-20 summarizes parcel exposure to flood hazards in Santa Cruz County. Within the 100-year floodplain, almost $1 billion in combined assets are at risk. Of this, more than $700 million in assets are associated with riverine flooding along inland waterways, while over $200 million is tied to coastal flooding areas exposed to waves, storm surge, and high tides. Additional parcels in the 500-year floodplain raise the total exposure to approximately $3 billion in combined structure and content value. These figures underscore the substantial economic stakes of both riverine and coastal flooding, reinforcing the need for ongoing mitigation and preparedness efforts.

The highest concentration of at-risk assets follows the county's major inland waterways, particularly along the San Lorenzo River corridor from Boulder Creek through Ben Lomond, Felton, and into the City of Santa Cruz. Clusters are also visible along Soquel Creek in Capitola, Aptos Creek in Aptos Village, and Corralitos Creek near Freedom.

On the coast, assets are concentrated in low-lying shoreline neighborhoods such as Seacliff, Rio Del Mar, La Selva Beach, and Pajaro Dunes, where ocean waves, storm surge, and high tides drive coastal flooding.

Significant asset exposure exists in the Pajaro River floodplain, which spans Watsonville and extends into neighboring Monterey County.

Overall, the distribution reflects a mix of riverine and coastal hazard zones, including river valleys with dense development and coastal areas where residential and commercial properties sit at or near sea level. These patterns reinforce the need for both inland and shoreline flood mitigation strategies in the county.

Table 3-20: Santa Cruz County Parcels Exposed to Flood Risk

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

Flood Hazard Zone	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
Flood Fringe	1,446	*3.0%*	$900,474,800	$537,620,000	$1,438,094,799	*2.6%*
Floodway	532	*1.1%*	$304,682,400	$184,615,800	$489,298,199	*0.9%*
Coastal	673	*1.4%*	$427,509,997	$213,754,999	$641,264,996	*1.2%*
100-YR Total	2,651	5.6%	$1,632,667,197	$935,990,798	$2,568,657,995	4.7%
500-YR sans 100-YR	393	*0.8%*	$237,003,600	$138,601,600	$375,605,200	*0.7%*
500-YR Total	3,044	6.4%	$1,869,670,797	$1,074,592,398	$2,944,263,195	5.4%

Note: The table above does not display loss estimation results; the table exhibits total value at risk based upon the hazard overlay and Santa Cruz County Assessor data.

Damage Estimation

Unlike the exposure analyses presented in other hazard profiles of this MJHMP—which simply identify assets located within mapped hazard areas—this section presents damage estimations for flood hazards based on modeled flood depths. Using FEMA's HAZUS software, losses to structures and their contents are calculated by combining flood depth data with structure type, occupancy, and replacement value. HAZUS applies established damage functions, developed from historical flood insurance claims, to estimate the percentage of damage for each property.

For this study, local parcel-level market value data for all non-vacant parcels was used in place of HAZUS's default national dataset, providing a more accurate reflection of potential economic losses in Santa Cruz County. Results are provided separately for riverine flooding, which affects inland waterways and floodplains, and for coastal flooding, which includes storm surge and wave impacts. These estimates offer insight into the potential scale of structural and content damage during a 100-year flood event, supporting more informed mitigation, planning, and response strategies.

Riverine Flood Damage

HAZUS modeling for the 100-year riverine flood scenario shows that losses are not evenly distributed across building types. Residential structures account for the majority of total damages, driven largely by content losses in addition to building damage. Commercial properties show a higher proportion of content loss relative to building loss, reflecting the high value of goods, equipment, and inventory stored in these structures. Industrial facilities experience a similar pattern, though their overall share of the county-wide loss is smaller. Public, religious, and government buildings contribute a comparatively minor portion of the total damages but may still represent critical community services and functions.

In total, a 100-year riverine flood is estimated to cause more than $785 million in combined building and content losses across all property types, representing about 1.4% of the total value in the 100-year floodplain. Table 3-21 and Figure 3-32 shows the 100-year flood loss estimation (based on depth-of-flooding).

Table 3-21: Santa Cruz County 100-YR Riverine Flood Damage Estimates

Building Type	Building Damage ($)	Building Damage (% of total loss)	Content Damage ($)	Content Damage (% of total loss)	Total Damage ($)	Proportion of Loss (%)
Agriculture	$1,980,000	0.3%	$5,473,000	0.7%	$7,453,000	1%
Commercial	$95,763,000	12.2%	$300,620,000	38.3%	$396,383,000	50%
Education	$5,442,000	0.7%	$21,445,000	2.7%	$26,887,000	3%
Government	$1,551,000	0.2%	$7,945,000	1.0%	$9,496,000	1%
Industrial	$12,568,000	1.6%	$30,688,000	3.9%	$43,256,000	6%
Religion	$2,696,000	0.3%	$17,633,000	2.2%	$20,329,000	3%
Residential	$174,763,000	22.3%	$106,723,000	13.6%	$281,486,000	36%
Total					**$785,290,000**	

Note: Total Inventory Values
1 - Building Replacement Costs = $19,116,504,796
2 - Content Replacement Costs = $35,189,614,790
3 - Total Value = $54,306,119,586



Figure 3-32: Santa Cruz County 100-YR Riverine Flood Damage Estimates by Building Type

Coastal Estimated Flood Damage

HAZUS modeling for the 100-year coastal flooding scenario indicates that predicted damages vary significantly by building type. Residential properties represent the largest share of total losses, with damages driven by a combination of building impacts and substantial content losses. Commercial buildings account for a smaller portion of total damages but show a higher ratio of content to building loss, reflecting the high value of goods, inventory, and equipment typically stored in these structures. Industrial facilities display a similar pattern of proportionally greater content losses but contribute only a small fraction of overall damages. Education, government, and religious facilities show minimal predicted damage in the coastal flooding scenario compared to other occupancy types.

In total, the model estimates more than $93 million in combined building and content losses for the unincorporated county in a 100-year coastal flood event. This represents a small fraction of the total value within the 100-year coastal floodplain, but it underscores that impacts can be highly concentrated in certain property types. Table 3-22 and Figure 3-33 present the detailed loss breakdown by occupancy type, based on depth-of-flooding analysis.

Table 3-22: Santa Cruz County 100-YR Coastal Flood Damage Estimates

Building Type	Building Damage ($)	Building Damage (% of total lossl)	Content Damage ($)	Content Damage (% of total loss)	Total Damage ($)	Proportion of Loss (%)
Agriculture	$59,000	0.1%	$101,000	0.1%	$160,000	1%
Commercial	$5,768,000	6.2%	$23,246,000	25.0%	$29,014,000	50%
Education	$21,000	0.0%	$103,000	0.1%	$124,000	3%
Government	$0	0.0%	$6,000	0.0%	$6,000	1%
Industrial	$355,000	0.4%	$441,000	0.5%	$796,000	6%
Religion	$55,000	0.1%	$197,000	0.2%	$252,000	3%
Residential	$38,198,000	41.0%	$24,613,000	26.4%	$62,811,000	36%
Total					**$93,163,000**	

Note: Total Inventory Values
1 - Building Replacement Costs = $19,116,504,796
2 - Content Replacement Costs = $35,189,614,790
3 - Total Value = $54,306,119,586



Figure 3-33: Santa Cruz County 100-YR Coastal Flood Damage Estimates by Building Type

3.2.2.10.3 Critical Facilities & Infrastructure

Essential facilities, high-potential-loss sites, and lifeline infrastructure in Santa Cruz County face notable flood risks due to their location within FEMA-mapped 100-year and 500-year floodplains. Unlike with parcel values, this assessment analyzes exposure only, meaning results are based on whether a facility falls inside or outside of mapped hazard zones. No first floor elevation or flood depth data was available, so these findings should be interpreted as indicators of potential risk rather than predictions of actual damage.

Flood exposure is dispersed throughout the county. Several fire stations, law enforcement facilities, hospitals, and emergency operations centers are situated within mapped flood hazard areas. Importantly, one fire station is located within a designated floodway, where flood flows are deepest and fastest, increasing the likelihood of operational disruption during an event. Schools are also represented in these zones, creating potential evacuation and continuity-of-operations challenges for education and community services.

Transportation and utility lifeline systems make up a substantial portion of the at-risk infrastructure. Roads, bridges, culverts, utility substations, and rail corridors in floodplains are vulnerable to damage or service interruption, impacts that could isolate neighborhoods, delay emergency response, and slow recovery.

High-potential-loss facilities, such as large mobile home parks, healthcare centers, and historic properties, are also present in flood-prone areas, where damage could carry significant economic, cultural, and social consequences. Hazardous materials facilities, including storage and treatment sites, are likewise at risk; flooding at these locations could cause environmental contamination and public health hazards extending well beyond the flooded area.

Table 3-23 details the critical facilities and infrastructure intersecting with the 100-year and 500-year floodplains, illustrating the scope of public assets that could be affected in a major flood event.

Table 3-23: Santa Cruz County Critical Facilities Exposed to Flood Risk

Critical Infrastructure - Flood Exposure							
Infrastructure Type	Flood Fringe	Floodway	Coastal	100-YR Total[2]	500-YR sans 100-YR	500-YR Total	BAM[3] Awareness Zone
Essential Facilities	3	1	-	4	-	4	1
Fire Station	2	1	-	3	-	3	1
Hospital	-	-	-	-	-	-	-
Law Enforcement	-	-	-	-	-	-	-
EOC	-	-	-	-	-	-	-
American Medical Response	1	-	-	1	-	1	-
High-Potential-Loss	23	11	3	37	8	45	3
Adult Care Facility	1	-	-	1	1	2	-
Child Care Center	1	2	-	3	1	4	-
Cell Tower	-	-	-	-	-	-	-

Critical Infrastructure - Flood Exposure							
Infrastructure Type	Flood Fringe	Floodway	Coastal	100-YR Total[2]	500-YR sans 100-YR	500-YR Total	BAM[3] Awareness Zone
County Real Property Asset[1]	15	5	3	23	5	28	1
Dam	1	-	-	1	-	1	-
Healthcare Facility	-	-	-	-	-	-	1
Historic Building	-	-	-	-	-	-	-
Library	-	-	-	-	-	-	1
Mobile Home Park	5	1	-	6	1	7	-
Power Generation	-	-	-	-	-	-	-
Radio Sites	-	1	-	1	-	1	-
School	-	2	-	2	-	2	-
Transportation and Lifeline	119	36	7	162	14	176	112
Airport	-	-	-	-	-	-	-
Substation	-	-	-	-	-	-	-
NG Station	-	-	-	-	-	-	-
Church	6	-	-	6	1	7	1
Stormwater Culvert	67	15	1	83	11	94	102
Parks	5	3	5	13	-	13	2
Bridge NBI	41	18	1	60	2	62	7
Hazmat	27	8	1	36	4	40	2
HWTS Active Facility	22	8	1	31	4	35	2
Geotracker CleanupSite	5	-	-	5	-	5	-
Grand Total	**172**	**56**	**11**	**239**	**26**	**265**	**118**

1Real Property Assets are digitized insurance rolls and other asset lists for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.
2Special Flood Harzard Area (SFHA)
3Best Available Mapping

Lifeline infrastructure in Santa Cruz County, including transportation corridors, utilities, and flood control systems, faces notable flood risk due to their location within FEMA-mapped 100-year and 500-year floodplains. County-maintained roads make up the largest share of exposed linear infrastructure. Many of these routes pass through low-lying river valleys, cross floodplains, or run adjacent to coastal areas. Flooding on these roadways can quickly isolate communities, block access for emergency responders, and delay recovery efforts. Even short-term closures on these primary routes can disrupt mobility across large portions of the county. Other at-risk transportation lifelines include state highways, local streets, and railroads. Flood damage or blockage to these systems can halt the movement of people and goods, with ripple effects for emergency response and the local economy.

Utility lifelines, including water and sewer pipelines, natural gas pipelines, and electric transmission lines, are also present in flood-prone areas. Damage to these systems could result in water contamination,

wastewater backups, extended outages, and safety hazards. Flood control features, such as levees and maintained channels, are themselves vulnerable; overtopping or failure could inundate the very areas they are intended to protect.

While exposure is widespread, the concentration of county-maintained roads in flood hazard zones underscores the importance of resilient design, maintenance, and emergency detour planning. Table 3-24 provides a detailed breakdown of lifeline features by flood hazard classification, illustrating the breadth of infrastructure that could be affected during a major flood event in Santa Cruz County.

Table 3-24: Santa Cruz County Critical Infrastructure Exposed to Flood Risk

Lifelines (miles) - Flood Risk Exposure						
Infrastructure Type (linear)	Flood Fringe	Floodway	Coastal	100-YR Total	500-YR sans 100-YR	Grand Total
County Maintained Roads*	17.3	6.1	0.9	24.3	3.4	27.7
Levee	14.6	4.1	-	18.7	-	18.7
Maintained Channel	14.8	13.0	-	27.8	28.6	56.4
NG Pipeline	1.7	0.1	-	1.8	0.1	1.8
Railroad	1.6	0.5	-	2.1	0.0	2.1
Sanitation Pipe	5.4	1.4	5.2	12.1	1.5	13.6
All Roads	48.1	12.7	2.9	63.7	9.1	72.8
Alley	0.4	0.3	-	0.7	0.0	0.8
Drive	9.3	2.2	0.0	11.5	1.7	13.1
Major Road	9.8	3.5	0.2	13.4	1.8	15.2
Ramp	0.1	0.0	-	0.2	0.6	0.8
Street	19.9	5.5	2.6	27.9	4.2	32.2
State Highway	5.1	0.9	0.1	6.2	0.6	6.8
Unnamed	3.6	0.2	-	3.8	0.2	4.0
Transmission Line	3.3	0.4	-	3.8	0.3	4.1
Grand Total	**106.9**	**38.3**	**9.0**	**154.2**	**15.2**	**169.4**

**Partially Overlaps "All Roads".*

3.2.2.11 Development Trends

Santa Cruz County faces ongoing challenges in balancing development pressures with the realities of flood hazards, particularly as climate change and sea level rise increase the extent and frequency of flooding. Unlike some inland counties, Santa Cruz flood risks are driven by both riverine and coastal processes. Future development in low-lying areas must account for multiple hazard pathways, including extreme rainfall, storm surge, and wave overtopping.

Large-scale flood control structures such as levees are limited in the county, with flood protection instead relying on a mix of localized channel improvements, stormwater infrastructure upgrades, and natural shoreline features. Existing levees along the Pajaro River and Salsipuedes Creek provide partial protection, but much of the inland floodplain remains susceptible to high-water events. Coastal neighborhoods, particularly in Capitola, Aptos, and Rio del Mar, have limited options for hard protection due to permitting constraints and environmental considerations, making adaptive design and elevation strategies more important over time.

Future growth in Santa Cruz County is guided by its General Plan policies and Local Coastal Programs that restrict new development in mapped flood hazard zones and require mitigation measures such as elevating structures or improving drainage capacity when redevelopment occurs. The county, as well as the other municipalities that participated in this MJHMP, have integrated flood hazard considerations into their general plan safety elements and committed to aligning land use decisions with this plan.

Looking ahead, projected sea level rise, more intense atmospheric river events, and ongoing watershed changes including post-wildfire hydrology will likely expand the extent of both coastal and riverine flood hazards. This will require continued investment in hazard mapping, early warning systems, and resilient infrastructure, as well as proactive land use planning to ensure that new development does not exacerbate existing flood risks.

3.2.2.12 Flood Hazard Problem Statements

As part of the flood mitigation planning process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing flood-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input.

The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure, essential facilities, economic assets, natural resources, and long-term recovery. They also acknowledge systemic barriers to effective flood mitigation, such as aging infrastructure, limited funding for maintenance, and incomplete data on flood depths and first-floor elevations.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with flood. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-25 presents the flood problem statements for Santa Cruz County, along with their associated area of concern and reference numbers for cross-linking to the mitigation actions in Table 4-1 and Table 4-2

Table 3-25: Santa Cruz County Flood Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Flood	Victim	**ps-FL-SCC-01**	Severe flooding in low-lying areas of unincorporated South County disproportionately affects low-income agricultural communities.
Flood	Impact	**ps-FL-SCC-02**	Moderate to severe flooding within the Pajaro Valley region damages crops, irrigation systems, and farm access roads, causing downstream economic impacts for agricultural workers, growers, and the local economy.
Flood	Threat	**ps-FL-SCC-03**	There are numerous NFIP-defined repetitive loss areas in the county where properties continue to experience preventable damages during flood events due to lack of elevation, floodproofing, or acquisition options.
Flood	Threat	**ps-FL-SCC-04**	Many flood-prone areas, including low-lying neighborhoods along the Pajaro River and its tributaries, Aptos Creek, Soquel Creek, and the San Lorenzo River, lack reliable all-weather access routes. Seasonal flooding and storm damage can wash out or inundate roadways, hindering evacuation and cutting off access to emergency services and critical resources.
Flood	Threat	**ps-FL-SCC-05**	Many areas of the County face unmapped or under-mapped flood risks, particularly in small, flashy watersheds. Localized threats—such as debris and large woody material in streams—can cause rapid flooding that is not captured in existing FEMA or local flood hazard maps, limiting the County's ability to fully characterize risk and prioritize mitigation.
Flood	Threat	**ps-FL-SCC-06**	While the County has completed an inventory of culverts, pump stations, and other storm drainage infrastructure, many assets are in poor condition or vulnerable to damage during high-flow events. Aging materials, undersized designs, and limited capacity to handle debris can contribute to roadway washouts, localized flooding, and prolonged seasonal closures.
Flood	Threat	**ps-FL-SCC-07**	Many flood-prone or low-lying areas will be subject to greater or more frequent flood risk due to more severe rainfall associated with climate change.
Flood	Impact	**ps-FL-SCC-08**	Some county sewer infrastructure is located in low-lying areas subject to flood inundation, making the infrastructure inaccessible and causing infiltration into the system, potentially overwhelming it and resulting in a sewage spill. A critical wastewater pump station near Arana Gulch is located in a low-lying area and subject to flooding, which could disrupt sanitation services and cause damage.
Flood	Victim	**ps-FL-SCC-09**	Many mobile home parks are located in flood-prone areas and rely on vulnerable underground drainage systems. Limited resources for protective measures put this important source of affordable housing at heightened risk of damage and displacement.
Levee Failure	Threat	**ps-LV-SCC-01**	A moderate to severe flood event could overtop or cause failures in the Pajaro levee system which was not designed for today's hydrologic conditions, exposing thousands of residents and agricultural lands to damage.

3.2.2.13 Climate Change Impacts & Vulnerable Populations

Flooding is one of the most persistent and costly hazards in unincorporated Santa Cruz County, with disproportionate impacts on vulnerable populations. Climate change is projected to increase the frequency and intensity of atmospheric river events, leading to heavier rainfall, rising flood stages, and compounding risks for low-lying neighborhoods, agricultural lands, and critical infrastructure. Vulnerable populations—including low-income agricultural workers, renters in mobile home parks, isolated seniors, and limited-English households—face disproportionate risks due to their geographic location, limited access to recovery resources, and higher likelihood of displacement.

Direct Impacts: Severe flooding in South County disproportionately affects agricultural communities, where workers and families often live in flood-prone areas near the Pajaro River and its tributaries. Flooding damages housing, disrupts employment, and reduces access to essential services. Mobile home parks located in low-lying areas are particularly vulnerable, with limited resources to elevate structures, retrofit drainage systems, or recover from repeated events.

Critical Infrastructure and Access: Flooding frequently damages crops, irrigation systems, sewer networks, and storm drainage infrastructure, resulting in cascading impacts for the agricultural economy and public health. County stormwater infrastructure—including culverts, pump stations, and drainage networks—is aging and undersized, leaving communities vulnerable to road washouts and prolonged closures. Seasonal flooding along Pajaro River, Aptos Creek, Soquel Creek, and the San Lorenzo River can cut off evacuation routes, hindering emergency response and stranding vulnerable populations. Wastewater infrastructure in low-lying areas, such as the Arana Gulch pump station, faces heightened risk of inundation, which could cause sanitation service interruptions or contamination.

Systemic Challenges: Numerous repetitive loss areas remain in the county, where homes continue to flood due to limited access to elevation, acquisition, or floodproofing resources. Many smaller watersheds also remain unmapped or under-mapped, leaving localized threats from debris flows and flashy storms unaccounted for in planning. This limits the County's ability to fully characterize flood risks, prioritize mitigation, and direct resources to the most vulnerable neighborhoods.

Climate Change Trends: Climate change is expected to exacerbate these risks by driving more severe rainfall events, higher river stages, and compound flooding where fluvial, tidal, and coastal processes intersect. This will further strain the Pajaro levee system, which was not designed for current or projected hydrologic conditions. A levee failure would expose thousands of residents and extensive agricultural acreage to catastrophic losses, with disproportionate impacts on farmworker communities, many of whom lack flood insurance and face barriers to recovery assistance.

By following the mitigation strategy in this plan, Santa Cruz County will reduce flood risk in unincorporated areas by investing equitably in resilient infrastructure, updating flood maps, and improving outreach to vulnerable populations. The mitigation strategy addresses targeted needs for mobile home parks, agricultural communities, and repetitive loss areas to reduce disparities and enhance community-wide flood resilience.

PAGE INTENTIONALLY BLANK



Earthquake

3.2.3 Earthquake Hazard Profile

Earthquake is the sudden shaking of the ground caused by the passage of seismic waves through Earth's rocks. Seismic waves are produced when some form of energy stored in Earth's crust is suddenly released, usually when masses of rock straining against one another suddenly fracture and "slip." Earthquakes associated with this type of energy release are called tectonic earthquakes. The energy also can be released by elastic strain, gravity, chemical reactions, or even the motion of massive bodies. Earthquakes occur most often along geologic *faults*, narrow zones where rock masses move in relation to one another. The seismic conditions in Santa Cruz County include the San Andreas Fault Zone and major companion traces including the Zayante and San Gregorio Fault Zones.

Earthquakes have different properties depending on the type of fault that causes them (Figure 3-34). The usual fault model has a "strike" (the direction from north taken by a horizontal line in the fault plane) and a "dip" (the angle from the horizontal shown by the steepest slope in the fault). The lower wall of an inclined fault is called the footwall. Lying over the footwall is the hanging-wall. When rock masses slip past each other parallel to the strike, the movement is known as strike-slip faulting. Movement parallel to the dip is called dip-slip faulting. In dip-slip faults, if the hanging-wall block moves downward relative to the footwall block, it is called "normal" faulting; the opposite motion, with the hanging-wall moving upward relative to the footwall, produces reverse or thrust faulting.

As a fault rupture progresses along or up the fault, rock masses are flung in opposite directions and thus spring back to a position where there is less strain.



Figure 3-34: Earthquake Faulting

Earthquake Classifications

Earthquakes are typically classified in one of two ways: by the amount of energy released, measured as **magnitude**; or by the impact on people and structures, measured as **intensity**. The most common method is magnitude. While the majority of scientists now use either the Moment Magnitude (Mw) Scale or Modified Mercalli Intensity (MMI) Scale to measure an earthquake, the Richter scale is the most well-known; however, the Richter scale has been largely replaced with the more accurate Mw and MMI scales.

Magnitude

The magnitude of an earthquake is related to the total area of the fault that ruptured, as well as the amount of offset (displacement) across the fault. Table 3-26 summarizes the seven earthquake magnitude classes on the Mw scale, ranging from micro to great. A magnitude class of great can cause tremendous damage to infrastructure, compared to a micro class, which results in minor damage to infrastructure.

Table 3-26: Moment Magnitude (Mw) Scale

Magnitude Class	Magnitude Range (M = Magnitude)	Description
Great	M > 8	Tremendous damage
Major	7 <= M < 7.9	Widespread heavy damage
Strong	6 <= M < 6.9	Severe damage
Moderate	5 <= M < 5.9	Considerable damage
Light	4 <= M < 4.9	Moderate damage
Minor	3 <= M < 3.9	Rarely causes damage.
Micro	M < 3	Minor damage

Intensity

The effects of an earthquake in a particular location are measured by intensity. Earthquake intensity decreases with increasing distance from the epicenter of the earthquake. The MMI value assigned to a specific site after an earthquake has a more meaningful measure of severity to the nonscientist than the magnitude because intensity refers to the effects experienced at that place.

The **lower** numbers of the intensity scale generally deal with the manner in which the earthquake is felt by people. The **higher** numbers of the scale are based on observed structural damage. Structural engineers usually contribute information for assigning intensity values of VIII or above. Table 3-27 is an abbreviated description of the levels of MMI.

Table 3-27: Modified Mercalli Intensity (MMI) Scale

Intensity	Shaking	Description/Damage
I	Not Felt	Not felt except by a very few under especially favorable conditions.
II	Weak	Felt only by a few persons at rest, especially on upper floors of buildings.
III	Weak	Felt quite noticeably by persons indoors, especially on upper floors of buildings. Many people do not recognize it as an earthquake. Standing motor cars may rock slightly. Vibrations similar to the passing of a truck. Duration estimated.
IV	Light	Felt indoors by many, outdoors by few during the day. At night, some awakened. Dishes, windows, doors disturbed; walls make cracking sound. Sensation like heavy truck striking building. Standing motor cars rocked noticeably.
V	Moderate	Felt by nearly everyone; many awakened. Some dishes, windows broken. Unstable objects overturned. Pendulum clocks may stop.
VI	Strong	Felt by all, many frightened. Some heavy furniture moved; a few instances of fallen plaster. Damage slight.
VII	Very Strong	Damage negligible in buildings of good design and construction; slight to moderate in well-built ordinary structures; considerable damage in poorly built or badly designed structures; some chimneys broken.
VIII	Severe	Damage slight in specially designed structures; considerable damage in ordinary substantial buildings with partial collapse. Damage great in poorly built structures. Fall of chimneys, factory stacks, columns, monuments, walls. Heavy furniture overturned.
IX	Violent	Damage considerable in specially designed structures; well-designed frame structures thrown out of plumb. Damage great in substantial buildings, with partial collapse. Buildings shifted off foundations.
X	Extreme	Some well-built wooden structures destroyed; most masonry and frame structures destroyed with foundations. Rails bent.

Source: USGS, Abridged from The Severity of an Earthquake, USGS General Interest Publication 1989-288-913

Ground Motion

Earthquake hazard assessment is also based on expected ground motion. This involves determining the annual probability that certain ground motion accelerations will be exceeded, then summing the annual probabilities over the time period of interest. The most commonly-mapped ground motion parameters are the horizontal and vertical peak ground accelerations (PGA) for a given soil or rock type. Instruments called accelerographs record levels of ground motion due to earthquakes at stations throughout a region. These readings are recorded by state and federal agencies that monitor and predict seismic activity.

Maps of PGA values form the basis of seismic zone maps that are included in building codes such as the International Building Code (IBC). Building codes that include seismic provisions specify the horizontal force due to lateral acceleration that a building should be able to withstand during an earthquake. PGA

values are directly related to these lateral forces that could damage "short period structures" such as single-family dwellings. Longer-period response components determine the lateral forces that damage larger structures with longer natural periods such as apartment buildings, factories, high-rises, and bridges. Table 3-28 lists damage potential and perceived shaking by PGA factors, compared to the MMI scale.

Table 3-28: Modified Mercalli Intensity (MMI) Scale and Peak Ground Acceleration (PGA)

MMI Scale	Perceived Shaking	Potential Structure Damage		Estimated PGA (%g)
		Resistant Buildings	Vulnerable Buildings	
I	Not Felt	None	None	<0.17%
II-III	Weak	None	None	0.17% - 1.4%
IV	Light	None	None	1.4% - 3.9%
V	Moderate	Very Light	Light	3.9% - 9.2%
VI	Strong	Light	Moderate	9.2% - 18%
VII	Very Strong	Moderate	Moderate/Heavy	18% - 34%
VIII	Severe	Moderate/Heavy	Heavy	34% - 65%
IX	Violent	Heavy	Very Heavy	65% - 124%
X - XII	Extreme	Very Heavy	Very Heavy	>124%

Note: PGA is measured in percent of g, where g is the acceleration of gravity.

Source: USGS, 2008; USGS, 2010

Artificial Induction

Earthquakes are sometimes caused by human activities, including the injection of fluids into deep wells, pumping of ground water, the excavation of mines, and the filling of large reservoirs. In fluid injection, the slip is thought to be induced by premature release of elastic strain, as in the case of tectonic earthquakes, after fault surfaces are lubricated by the liquid.

3.2.3.1 Secondary & Compounding Hazards

Earthquakes can trigger secondary hazards that compound impacts, including soil liquefaction, tsunamis, dam failures, fires, and slope failure. Due to Santa Cruz County's elevated exposure, liquefaction is profiled as a specific subhazard to earthquake. Other secondary hazards relevant to Santa Cruz County are discussed in their respective profiles. These include tsunami in the Coastal Hazards Profile (Section 3.2.5), dam failure (Section 3.2.7), wildfire (Section 3.2.1), and slope failure (Section 3.2.6).

Urban Fires

Gas leaks, explosions, and fires are common after an earthquake, especially in urban areas. As seen during the 1906 San Francisco Earthquake, the damage from an earthquake is not usually the end of the devastation. The fires that ensued following this event, which resulted from and were fueled by broken gas

lines and a lack of water pressure, caused additional impacts. According to the Earthquake Country Alliance, around one in four fires after an earthquake is related to a gas leak.

3.2.3.2 Subhazard: Liquefaction

Liquefaction is a process by which sediments below the water table temporarily lose strength during an earthquake and behave as a viscous liquid rather than a solid. Liquefaction is restricted to certain geologic and hydrologic environments, primarily recently deposited sand and silt in areas with high groundwater levels, where these soils tend to be saturated, low-density, and loose. The process of liquefaction involves seismic waves passing through saturated granular layers, distorting the granular structure, and causing the particles to collapse. This causes the granular layer to behave temporarily as a liquid, resulting in liquefaction.

Saturated or partially-saturated soil substantially loses strength and stiffness in response to an applied stress, such as ground shaking or other sudden changes in stress condition. Loose sand has a tendency to compress when a load is applied. Dense sands, by contrast, tend to expand in volume or 'dilate'. If the soil is saturated by water, which often occurs when soil is below the water table or sea level, then water fills the pore spaces between soil grains.

Liquefaction can cause the soil beneath a structure to lose strength, spread laterally, or lurch in the direction of an opening. Lateral spreading is lateral ground movement, with some vertical component, caused by liquefaction. In effect, the soil rides on top of the liquefied layer. Lateral spreading can occur on relatively flat sites with slopes less than 2%, under certain circumstances, and can cause ground cracking and settlement. Lurching is the movement of the ground surface toward an open face when the soil liquefies. An open face could be a graded slope, stream bank, canal face, gully, or other similar feature.

Severe property damage can be caused by soil liquefaction, including damaging pipes, compromising building foundations, and bucking roads and airport runways. For buildings, liquefaction may result in the loss of foundation-bearing capacity. This loss of strength commonly causes the structure to settle or tip. Loss of bearing strength can also cause light buildings with basements, buried tanks, and foundation piles to rise buoyantly through the liquefied soil. Soil liquefaction and related phenomena have been responsible for tremendous amounts of damage in historical earthquakes around the world.

3.2.3.3 Policies, Plans & Regulatory Environment

Federal Regulatory Environment

National Earthquake Hazards Reduction Program (NEHRP)

The National Earthquake Hazards Reduction Program (NEHRP) was established by the U.S. Congress when it passed the Earthquake Hazards Reduction Act of 1977, Public Law 95–124. In establishing the NEHRP, Congress recognized that earthquake-related losses could be reduced through improved design and

construction methods and practices; land use controls and redevelopment; prediction techniques and early warning systems; coordinated emergency preparedness plans; and public education and involvement programs. The four basic goals of NEHRP remain unchanged:

1. Develop effective practices and policies for earthquake loss reduction and accelerate their implementation.
2. Improve techniques for reducing earthquake vulnerabilities of facilities and systems.
3. Improve earthquake hazards identification and risk assessment methods and their use.
4. Improve the understanding of earthquakes and their effects.

State Regulatory Environment

California Alquist-Priolo Earthquake Fault Zoning Act & Seismic Hazards Mapping Act

The Alquist-Priolo Earthquake Fault Zoning Act (Public Resources Code [PRC] Sections 2621 to 2630) was passed in 1972 to provide a statewide mechanism for reducing the hazard of surface fault rupture to structures used for human occupancy. The main purpose of the Act is to prevent the siting of buildings used for human occupancy across the traces of active faults. It should be noted that the Act addresses the potential hazard of surface fault rupture and is not directed toward other earthquake hazards, such as seismically induced ground shaking or landslides.

The law requires the State Geologist to identify regulatory zones (known as Earthquake Fault Zones or Alquist-Priolo Zones) around the surface traces of active faults and to depict these zones on topographic base maps, typically at a scale of one inch to 2,000 feet. Earthquake fault zones vary in width, although they are often 0.75-mile wide. Once published, the maps are distributed to the affected cities, counties, and state agencies for their use in planning and controlling new or renewed construction. With the exception of single-family wood-frame and steel-frame dwellings that are not part of a larger development (i.e., four units or more), local agencies are required to regulate development within the mapped zones. In general, construction of new buildings within 50 feet of an active fault zone is prohibited.

California Building Standards Code

The California Building Code (CBC), adopted by Santa Cruz County, is another name for the body of regulations known as the California Code of Regulations, Title 24, Part 2, which is a portion of the California Building Standards Code. The CBC incorporates by reference the International Building Code (IBC) requirements with necessary California amendments. Title 24 is assigned to the California Building Standards Commission, which, by law, is responsible for coordinating all building standards.

Compliance with the CBC requires (with very limited exceptions) that structures for human occupancy be designed and constructed to resist the effects of earthquake motions. The Seismic Design Category for a structure is determined in accordance with either CBC Section 1613, Earthquake Loads, or the American Society of Civil Engineers Standard No. 7-05, Minimum Design Loads for Buildings and Other Structures. In brief, based on the engineering properties and soil types of a proposed site, plus location-specific ground

acceleration information, a Seismic Design Category is assigned ranging from A to F, of which D, E, and F represents the most severe conditions.

The Code also requires that a geotechnical investigation be prepared for projects on sites categorized C or greater, all new buildings that are 4,000 square feet or larger, and new smaller buildings if they meet certain criteria. A California registered Geotechnical Engineer must determine design categories and prepare geotechnical investigations, as well as determine requirements for geotechnical designs necessary to meet standards for reducing exposure to geological hazards.

Benchmark Years

Revisions to the Uniform Building Code (UBC) and California Building Code (CBC) mark important milestones in the evolution of seismic design standards. These benchmarks are critical for understanding the vulnerability of Santa Cruz County's building stock, much of which was constructed before modern seismic requirements.

Table 3-29 summarizes the major revisions to the Uniform Building Code (UBC), California Building Code (CBC), and International Building Code (IBC) that shaped modern seismic design standards. These benchmarks highlight the evolution from the first voluntary seismic regulations in 1927 to the adoption of comprehensive, strength-based seismic design provisions in the late 20th century, and ongoing refinements through updated seismic hazard maps.

This context is critical for Santa Cruz County because much of the existing housing stock was constructed prior to these milestones, leaving many buildings without essential seismic safety features. Structures built before 1978 (prior to Title 24) and especially those constructed before 1997 (prior to the modern overhaul of seismic design provisions) are considered more vulnerable to earthquake damage. Buildings constructed after adoption of the CBC/IBC framework benefit from more rigorous seismic standards; however, ongoing updates underscore the continued need for seismic retrofits and strict code compliance to reduce risk in older structures.

Table 3-29: Seismic Benchmark Years

Year(s)	Code / Reference	Key Seismic Change
1927	**UBC**	First voluntary seismic regulations introduced following the 1925 Santa Barbara earthquake.
1933	**UBC / State Law**	Field Act (schools) and Riley Act (all buildings) mandated seismic design statewide after the Long Beach earthquake.
1967 & 1976	**UBC**	Requirements added to limit building drift and reduce damage to non-structural components.
1978	**CBC**	Enactment of Title 24, unifying California's building standards and incorporating seismic provisions.
1988	**UBC**	Establishment of benchmark base shear values, used as reference in later seismic codes.

Year(s)	Code / Reference	Key Seismic Change
1997	UBC	Final UBC edition; major overhaul with near-source effects, soil amplification factors, redundancy/reliability factors, and strength-based seismic design.
2000	IBC / NEHRP	International Building Code (IBC) introduced, incorporating NEHRP provisions; CBC amended from the IBC.
2007 & 2017	IBC / CBC	Major updates to seismic hazard maps based on new research, refining design requirements.

Local Regulatory Environment

Santa Cruz County General Plan Public Safety Element

The Public Safety Element of the Santa Cruz County General Plan sets forth several policies relevant to earthquakes under the seismic hazard objective to reduce the potential for loss of life, injury, and property damage resulting from earthquakes by regulating the siting and design of development in seismic hazard areas; encouraging open space, agricultural or low-density land use in the fault zones; and increasing public information and awareness of seismic hazards (Objective 6.1). Seismic hazard policies include the following:

- **Policy 6.1.1 Geologic Review for Development in Designated Fault Zones:** Require a review of geologic hazards for all discretionary development projects, including the creation of new lots, in designated fault zones. Fault zones designated for review include the Butano, Sargent. Zayante, and Corralitos complexes, as well as the State-designated Seismic Review Zones.
- **Policy 6.1.2 Geologic Reports for Development in Alquist-Priolo Zones:** Require a preliminary geologic report or full engineering geology report for development on parcels within Alquist-Priolo State-designated seismic review zones.
- **Policy 6.1.4 Site Investigation Regarding Liquefaction Hazard:** Require site-specific investigation by a certified engineering geologist and/or civil engineer of all development proposals of more than four residential units in areas designated as having a high or very high liquefaction potential, and all other projects shall be reviewed for liquefaction hazard through environmental review and/or geologic hazards assessment.
- **Policy 6.1.11 Setbacks from Faults:** Exclude from density calculations for land divisions, land within 50 feet of the edge of an active or potentially active fault trace. In addition, all new habitable structures shall be set back a minimum of 50 feet from the edge of an active or potentially active fault trace (may be reduced to 25 feet based upon paleo-seismic studies). Critical structures and facilities shall be set back a minimum of 100 feet from the edge of an active or potentially active fault trace.

Santa Cruz County Geologic Hazards Ordinance

Santa Cruz County Code Chapter 16.10 contains the Geologic Hazards Ordinance. The ordinance: 1) implements the policies of the State of California Alquist-Priolo Earthquake Fault Zoning Act, the Santa Cruz

County General Plan, and the Land Use Plan of the LCP; 2) seeks to minimize injury, loss of life, and damage to public and private property caused by the natural physical hazards of earthquakes, floods, landslides, and coastal processes; 3) sets forth standards for development and building activities that will reduce public costs by preventing inappropriate land uses and development in areas where natural dynamic processes present a potential threat to the public health, safety, welfare, and property; and 4) ensures that potential buyers are notified of property located in an area of geologic and coastal hazard, and to ensure that those who occupy areas of geologic and coastal hazard assume responsibility for their actions.

3.2.3.4 Past Events

This section describes previous earthquake events, including dates, severity, level of damage, duration, sources of information used, and maps (where available). While Santa Cruz County has sustained numerous earthquakes throughout its history, the two most destructive ones were the 1906 San Francisco earthquake and the 1989 Loma Prieta earthquake.

Moderate-Sized Earthquakes Before 1906

Four moderate-sized earthquakes estimated at magnitude (M) 6 to 6.5 were recorded in Santa Cruz County between 1864 and 1890 on the historical Richter scale. Three of these earthquakes were centered in the Santa Cruz Mountains, including a M6 earthquake on February 26, 1864; M6.5 earthquake on October 8, 1865; and M6 earthquake on March 26, 1884. In addition, a M6.25 earthquake was recorded in the Pajaro Gap on April 24, 1890. All of these, together, indicate that a pattern of earthquakes nearly the same size of the Loma Prieta earthquake have occurred in the recent past. Each of these earthquakes caused some damage and would cause damage to homes today (all magnitudes cited are estimates based on descriptions of the damage which occurred).

1906 San Francisco Earthquake

The devastating April 18, 1906, earthquake that hit San Francisco was recorded at M8.3 on the Richter scale and is estimated to have been a VIII on the MMI scale with severe shaking. Impacts extended along the California coast, into the Santa Cruz Mountains. Although there were no recorded deaths in Santa Cruz County, the old courthouse partially collapsed and about one-third of the chimneys within the City of Santa Cruz were destroyed or damaged. Landsliding was observed throughout the Santa Cruz Mountains, and fault rupture was nearly continuous along the San Andreas fault zone for nearly 300 miles. Infrastructure in the county, including bridges, were destroyed, and broken mains and pipes shut off the water supply.

October 1926 Earthquakes

Two large earthquakes occurred in 1926, recorded as M6.1 on the Richter scale. Three of the aftershocks cracked plaster in Santa Cruz, almost bringing down the chimneys of numerous buildings. The shaking broke plate glass windows along Pacific Avenue, the city water main broke at Laguna Creek, and articles fell from shelves at stores.

1989 Loma Prieta Earthquake

At 5:04 p.m. on October 17, 1989, the M7.1 Loma Prieta Earthquake rocked the Monterey and San Francisco Bay regions. The initial quake lasted only 22 seconds; although, in the following two weeks, more than 4,000 aftershocks were recorded, 20 of which were greater than M5. The epicenter of the earthquake was about 10 miles east-northeast of the City of Santa Cruz in the Forest of Nisene Marks State Park on top of the San Andreas Fault. In Santa Cruz County, 674 dwellings, 32 mobile homes, and 310 businesses were destroyed. The Loma Prieta Earthquake was the largest to strike California since 1906, causing 62 deaths and 3,757 injuries. More than 12,000 people were left homeless, and transportation, utilities, and communications were disrupted. There was more than $6 billion in property damage.

3.2.3.5 Location

There are at least six major faults and fault systems within or near Santa Cruz County, placing it in an area of high seismic risk, and past experience has shown that the entire county is vulnerable to earthquake hazards. Fault zones designated for review under county regulations include the Butano, Sargent, Zayante, and Corralitos complexes. State-designated seismic review zones include the San Andreas, San Gregorio, and portions of the Zayante and Butano complexes. No new active or potentially active faults were identified in the county for this plan update.

Because earthquakes can cause severe damage over a long distance, the Santa Cruz area remains at risk from continued seismic activity along the many faults in the greater San Francisco Bay region. The reduction of seismic stresses that occurred in the Loma Prieta earthquake did nothing to relieve, and possibly increased, stresses within other faults, including other sections of the San Andreas Fault.

According to the U.S. Geological Survey (USGS), the primary faults most likely to generate strong ground shaking in Santa Cruz County include the San Andreas Fault, which runs along the county's northeastern boundary, and the Zayante-Vergeles, Sargent, and Butano faults, which trend through the central and southern portions of the county. Additional nearby faults such as the San Gregorio Fault offshore to the west also contribute to regional seismic risk. Figure 3-35 identifies Quaternary faults located within or directly adjacent to the county, as well as designated Earthquake Fault Zones of Required Investigation established under the Alquist-Priolo Earthquake Fault Zoning Act and county regulations.

Liquefaction

Liquefaction in Santa Cruz County is most likely to occur in areas with high groundwater levels and loose, unconsolidated soils (i.e., sandy). Hence, coastal areas and areas along rivers and creeks are most susceptible to liquefaction and liquefaction-related phenomena, as shown in Figure 3-36.

Liquefaction potential varies significantly, and site-specific analysis is needed to accurately determine liquefaction potential in earthquake prone areas. Most of the valley bottoms in the southern regions of the county are underlain by alluvium and are considered at very high, high, or moderate risk for liquefaction potential. Coastline regions also have low to very high liquefaction potential.



Figure 3-35: Santa Cruz County Fault Zone Areas of Required Investigation



Figure 3-36: Santa Cruz County Areas with Potential for Liquefaction

3.2.3.6 Frequency & Probability of Future Occurrences

According the California State Hazard Mitigation Plan, earthquakes large enough to cause moderate damage to structures—those of M5.5 or larger—occur three to four times a year statewide. Strong earthquakes of M6 to 6.9 strike on an average of once every two to three years, and major earthquakes of M7 to 7.9 occur in California about once every decade. The probability of an earthquake occurring in Santa Cruz County is likely (between 10 and 100% annual probability).

30-Year Earthquake Probability (UCERF3)

To clarify the extent of future earthquake risk, a partnership of the USGS, the California Geologic Survey (CGS), and the Southern California Earthquake Center, known as the Working Group on California Earthquake Probabilities, evaluated, and systemized currently available historic and paleo-seismic information to produce a probabilistic seismic hazards analysis to indicate the type of future earthquakes. The resulting model, the Uniform California Earthquake Rupture Forecast Version 3 (UCERF3),[5] is a comprehensive model of earthquake occurrence for California and represents the best available science for estimates of the magnitude, location, and likelihood of potentially damaging earthquakes (M6.7 or greater). This rupture forecast model tells us where and when the Earth might slip along the state's many faults.

The results of the UCERF3 for the San Francisco region are shown in Table 3-30. The table indicates the average time between earthquakes and the likelihood of having one or more such earthquakes in the next 30 years (starting from 2014). It is important to note that the repeat times are averages and actual repeat times will certainly vary significantly. The fault systems producing these earthquakes are located throughout the San Francisco region and near Santa Cruz County.

According to UCERF3, the North San Andreas fault, which traverses the Santa Cruz Mountains, has a 33% probability of producing an M6.7 or greater earthquake in a given 30-Year period.

Table 3-30: 30-Year Probability of Earthquakes in the San Francisco Region

Magnitude	30-Year Probability	Average Repeat Time
5	**100%**	1.3 Years
6	**98%**	8.9 Years
6.7	**72%**	29 Years
7	**51%**	48 Years
7.5	**20%**	124 Years
8	**4%**	825 Years

Source: UCERF3

[5] Quaternary faults are those active faults that have been recognized at the surface and which have evidence of movement in the past 1.6 million years (the duration of the Quaternary Period).

3.2.3.7 Severity

Damage from earthquakes varies with the local geologic conditions, the quality of construction, the energy released by the earthquake, the distance from the earthquake's focus, and the type of faulting that generates the earthquake. Ground motion is the primary cause of damage and injury during earthquakes and can result in surface rupture, liquefaction, landslides, lateral spreading, differential settlement, tsunamis, building failure and broken utility lines, leading to fire and other collateral damage. Typically, areas underlain by thick, water-saturated, unconsolidated material will experience greater shaking motion than areas underlain by firm bedrock, but in some cases, relief may intensify shaking along ridge tops.

Movement along local faults can cause fault-related surface deformation (e.g., surface fault rupture) where the fault reaches the surface of the ground. Within the mapped fault zones in the county, it is likely that movement along these faults will damage structures, roads, utilities, and other fixed facilities. The mapping of these zones has not changed for this plan update.

In addition to these zones, other ground cracking was observed during the 1989 Loma Prieta earthquake and the 1906 San Francisco earthquake. Many of these ground cracks can be attributed to movement or consolidation of large and moderate-sized landslides while other ground cracks were most likely related to ridge spreading. Although much of the ground cracking was found near the fault zones and in the summit area of the county, other ground cracking was found on ridge tops throughout Santa Cruz County.

As demonstrated during past events, even a "moderate" earthquake occurring in or near the Santa Cruz County region could result in deaths, casualties, property and environmental damage, and disruption of normal services and activities. The severity of the event could be aggravated by collateral emergencies such as fires, hazardous material spills, utility disruptions, landslides, and transportation emergencies.

3.2.3.8 Warning Time

There is currently no reliable way to predict the day or month that an earthquake will occur at any given location, but research is being done with warning systems that use the low energy waves that precede major earthquakes. Currently, these systems are able to provide seconds and sometimes minutes of advance warning, which can allow people and systems to take actions to protect life and property from destructive shaking. Even a few seconds of warning can enable protective actions such as:

- **Public:** Individuals, including schoolchildren, drop, cover, and hold on; turn off stoves; and safely stop vehicles.
- **Businesses:** Personnel move to safe locations; automated systems ensure elevator doors open; production lines are shut down; and sensitive equipment is placed in a safe mode.
- **Medical Services:** Surgeons, dentists, and others stop delicate procedures.
- **Emergency Responders:** Open firehouse doors; personnel prepare and prioritize response decisions.
- **Power Infrastructure:** Protect power stations and grid facilities from strong shaking.

CruzAware Notification System

CruzAware is Santa Cruz County's official alert and notification system. It is administered by the County Office of Response, Recovery and Resilience (OR3) and is designed to provide residents and visitors with timely warnings and information during emergencies. Notifications are sent by text message, telephone, or email and address a range of hazards, including early warnings for earthquakes, as well as other public safety threats and evacuation notices.

The system works in coordination with other county resources to support comprehensive hazard communication. More information about CruzAware, including how to register, is available at santacruzcountyca.gov/CruzAware.

3.2.3.9 Earthquake Vulnerability Assessment

The vulnerability of a community to earthquake is based on a variety of factors, including proximity to active and inactive faults; the age and construction materials of structures; the density of the population and development; and the location of critical facilities. Recent history indicates that Santa Cruz County has a very high vulnerability to earthquakes due to proximity to faults, density of population, and development within the floodplains of many creeks and rivers, which are subject to liquefaction.

One or more moderate to large sized earthquakes (M6.5 to 7.5) will likely shake the entire County of Santa Cruz during the life span of most residents. Many older homes that were damaged but not destroyed in 1989 were improved seismically but are still at a higher risk than newer construction using the latest building code standards. Modern homes will normally fare better in earthquakes but 1989 showed that this is not necessarily the case. Some older homes fared better than newer ones due to location and design.

A major earthquake on the San Andreas Fault or other major fault in the regional will:

- Damage roads, bridges, and critical structures, and could severely damage most homes in the county.
- Trigger liquefaction along alluvial areas such as Pajaro Valley, parts of Capitola and Santa Cruz, and along streams throughout the county, such as Corralitos Creek and the San Lorenzo River.
- Potentially cause ruptures and ground cracking around the major faults and through nerby hillslopes.
- Potentially activate landslides and cause coastal bluff failure.

The following subsections summarize the population, property, and critical infrastructure and facilities exposed to earthquake hazards. Figure 3-37 summarizes the potential exposure of the population and these assets to a hypothetical M7.1 earthquake on the San Andreas Fault, and Figure 3-38 and Figure 3-39 summarize exposure to fault zones of required investigation and liquefaction, respectively.



Figure 3-37: Exposure Summary - Santa Cruz County San Andreas Earthquake Scenario M7.1



Figure 3-38: Exposure Summary - Santa Cruz County Fault Zone Areas of Required Investigation



Figure 3-39: Exposure Summary - Santa Cruz County Areas with Potential for Liquefaction

3.2.3.9.1 Population

The entire population in Santa Cruz County would be exposed to shaking during a damaging earthquake. Over 16% of the county population would be exposed to severe shaking during a M7.1 earthquake on the San Andreas fault, with the remaining 84% exposed to strong or very strong shaking. More than 50% of the county population would also be exposed to liquefaction, including about 10% in high and very high susceptibility areas. Over 7% of the population would be exposed to potential ruptures in state or county fault zones of required investigation.

Table 3-31 summarizes the population susceptible to shaking during the M7.1 San Andreas Earthquake scenario, and Table 3-32 summarizes the population susceptible to fault zones and liquefaction.

Table 3-31: Santa Cruz County Population Susceptible to Earthquake Scenario Shaking

	Total Population
Unincorporated County	131,149

Shake Severity Zone	Population Count	% of Total
VIII - Severe	21,333	16.27%
VII - Very Strong	82,706	63.06%
VI - Strong	27,110	20.67%
Total	**131,149**	**100.00%**

Table 3-32: Santa Cruz County Population Susceptible to Faults and Liquefaction

	Total Population
Unincorporated County	131,149

Fault Zone of Required Investigation	Population Count	% of Total
County Delineated Fault	7,688	*5.86%*
State Regulatory Fault	2,104	*1.60%*
Liquefaction Susceptibility		
Low	51,004	*38.89%*
Moderate	5,815	*4.43%*
High	6,667	*5.08%*
Very High	6,429	*4.90%*
Total	**69,915**	**53.31%**

3.2.3.9.2 Property

All parcels within Santa Cruz County would be exposed to shaking during a damaging earthquake, which equates to approximately $54.3 billion in assessed assets. In areas projected to receive severe shaking during such an event, there is almost $7.5 billion in total exposure to a M7.1 earthquake on the San Andreas fault. A total of approximately 3,500 parcels and $4 billion in improvements are also exposed to fault rupturing in state or county zones of required investigation, and almost 60% of all properties in the county—accounting for $3.2 billion in assets—would be exposed to liquefaction during a major earthquake event.

Table 3-33 summarizes the parcels susceptible to shaking during the M7.1 San Andreas Earthquake scenario, and Table 3-34 summarizes the parcels susceptible to fault zones and liquefaction.

Table 3-33: Santa Cruz County Parcels Susceptible to Earthquake Scenario Shaking

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

Shake Severity Zone	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
VI - Strong	8,533	17.9%	$5,828,494,398	$3,121,481,403	$8,949,975,801	16.5%
VII - Very Strong	33,014	69.3%	$24,575,046,395	$13,339,121,797	$37,914,168,192	69.8%
VIII - Severe	6,083	12.8%	$4,786,073,996	$2,655,901,597	$7,441,975,593	13.7%
Total	**47,630**	**100.0%**	**$35,189,614,790**	**$19,116,504,796**	**$54,306,119,586**	**100.0%**

Table 3-34: Santa Cruz County Parcels Susceptible to Faults and Liquefaction

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
Zone of Investigation						
County Delineated	2,795	*5.9%*	$2,044,589,599	$1,122,743,400	$3,167,333,000	*5.8%*
State Delineated	734	*1.5%*	$558,127,200	$288,279,400	$846,406,600	*1.6%*
Liquefaction Susceptibility						
Low	20,315	*42.7%*	$15,534,149,599	$8,695,116,200	$24,229,265,798	*44.6%*
Medium	3,221	*6.8%*	$2,194,385,999	$1,251,251,400	$3,445,637,398	*6.3%*
High	2,397	*5.0%*	$1,728,138,396	$986,421,197	$2,714,559,593	*5.0%*
Very High	1,903	*4.0%*	$1,345,705,600	$820,202,000	$2,165,907,600	*4.0%*
Total	**27,836**	**58.4%**	**$20,802,379,593**	**$11,752,990,797**	**$32,555,370,390**	**59.9%**

Benchmark Years

According to the Santa Cruz County Assessor's Office, large portions of the county's housing stock were constructed in the 1960s through 1980s, before the 1997 UBC overhaul (Table 3-35). This means that a significant share of local housing was built before 1997, when modern seismic design became codified, and many homes predate even the 1978 establishment of Title 24. As a result, older housing stock in Santa Cruz County is particularly vulnerable to earthquake damage unless it has been retrofitted.

Table 3-35: Building Stock and Benchmark Years

Construction Era	Seismic Code Context	Approx. Share of Housing Stock	Vulnerability Notes
Pre-1978	Built before Title 24 unified California's building standards; many predate seismic codes entirely	~40%	High vulnerability — limited lateral force resistance; retrofits are a priority
1978–1997	Title 24 adopted, but before the 1997 UBC overhaul; incremental seismic improvements	~35%	Moderate vulnerability — stronger than pre-1978 but lacks modern soil/near-source design
Post-1997	Built under modern UBC (1997) and later IBC/CBC seismic provisions	~25%	Lower vulnerability — incorporates strength design, drift limits, redundancy, updated hazard maps

Source: Santa Cruz County Assessor's Roll; Seismic Code Benchmarks from UBC/CBC/IBC history

Newer construction under CBC/IBC standards provides stronger protection against seismic forces. For the large share of older structures that predate modern code requirements, the County's role will focus on public education, outreach, and incentives to encourage homeowners to pursue voluntary retrofits. By providing information on available programs, technical guidance, and potential funding opportunities, the County can help reduce seismic vulnerability in existing housing stock while ensuring new development continues to meet updated code standards.

3.2.3.9.3 Critical Facilities & Infrastructure

All of the critical facilities and infrastructure in the county would be exposed to strong, very strong, or severe shaking during a major earthquake, such as the M7.1 San Andreas Earthquake scenario. Notably, a significant portion of essential, high-potential-loss, and hazardous materials facilities would be subject to severe shaking during such an event, including five fire stations and two dams, potentially driving up casualties and damage due to disruptions to emergency services and the triggering of secondary hazards like dam failures or hazardous material releases. In addition, over 3,000 miles of critical infrastructure is exposed to shaking, including roadways, transmission lines, sewer lines, and natural gas pipelines. Damage to these systems would not only disrupt mobility and emergency response during and after the event but could also contribute to additional hazards such as downed power lines, urban fires, and environmental contamination.

During a major earthquake event, many facilities and miles of infrastructure would also be exposed to fault rupturing and liquefaction, adding significant ground-failure risk under the assets needed for response and

recovery. About 900 miles of lifelines and almost 1,000 critical facilities lie in moderate to very high liquefaction areas, including roads, bridges, and sewer lines and nine fire stations. Within fault zones of required investigation, almost 300 miles of lifelines and about 450 facilities fall in county delineated areas, and over 100 miles of lifelines and a little under 400 facilities in state regulatory areas.

By virtue of Santa Cruz County's unique geographic attributes, there is the possibility of the county becoming an "island" after a major seismic event. For example, if State Routes 1, 9, 17, 129, and 152 were to be shut down due to earthquake damage (e.g., landslides), the county would affectively be isolated. This would be further exacerbated if the main water treatment facilities in Santa Cruz and Watsonville sustained significant damage and went offline, as Santa Cruz County is entirely reliant on local water supplies.

The exposure of levees to earthquake is notably intense, with 19 miles exposed to very strong or severe shaking during the M7.1 San Andreas earthquake scenario as well as high or very high liquefaction, and 3.6 miles in county fault zones where ground rupture may occur.

These exposures indicate a large portfolio where geotechnical investigation, seismic detailing (e.g., flexible joints, ground improvement), and retrofit prioritization will be required to maintain lifeline function and prevent secondary hazards such as dam or levee failure after a major event. Table 3-36 and Table 3-37 summarize the critical infrastructure and facilities susceptible to shaking during the M7.1 San Andreas Earthquake scenario. Table 3-38 and

Table 3-39 summarize the exposure of county assets susceptible to fault zones and liquefaction.

Table 3-36: Santa Cruz County Critical Infrastructure Susceptible to Earthquake Scenario Shaking

Lifelines (miles) - M7.1 N. San Andreas Santa Cruz Mtn			
Infrastructure Type (Linear)	VI-Strong	VII-Very Strong	VIII-Severe
County Maintained Roads*	106.4	336.3	145.1
Levee	-	8.8	10.0
Maintained Channel	2.5	33.9	15.3
NG Pipeline	11.5	26.8	2.7
Railroad	15.9	15.2	-
Sanitation Pipe	50.0	155.3	10.9
All Roads	476.5	1,291.6	517.3
Alley	1.0	1.5	-
Drive	135.4	329.4	124.4
Major Road	70.0	173.9	96.1
Ramp	0.3	14.5	0.1
Street	187.5	641.1	225.8
State Highway	31.9	60.7	28.9
Unnamed	50.5	70.5	41.9
Transmission Line	20.0	46.5	25.4

Grand Total	**682.7**	**1,914.5**	**726.7**

Table 3-37: Santa Cruz County Critical Facilities Susceptible to Earthquake Scenario Shaking

Critical Facilities - N. San Andreas Santa Cruz Mtn			
Facility Type	VIII - Severe	VII - Very Strong	VI - Strong
Essential Facilities	6	23	10
Fire Station	5	15	9
Hospital	-	2	-
Law Enforcement	1	4	1
EOC	-	1	-
American Medical Response	-	1	-
High-Potential-Loss	58	366	125
Adult Care Facility	8	22	7
Child Care Center	3	39	8
Cell Tower	16	61	24
County Real Property Asset	14	118	47
Dam	2	1	4
Healthcare Facility	-	14	1
Historic Building	-	6	1
Library	-	4	1
Mobile Home Park	2	41	20
Power Generation	-	1	1
Radio Sites	3	11	4
School	10	48	7
Transportation and Lifeline	1276	2013	477
Airport	-	1	2
Substation	1	8	6
NG Station	-	-	2
Church	4	46	7
Stormwater Culvert	1242	1819	414
Parks	7	42	26
Bridge NBI	22	97	20
Hazmat	42	271	58
HWTS Active Facility	38	250	50
Geotracker Cleanup Site	4	21	8
Grand Total	**1382**	**2673**	**670**

*Notes: *Real Property Assets are digitized insurance rolls for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.*

Table 3-38: Santa Cruz County Critical Infrastructure Susceptible to Faults and Liquefaction

	Liquefaction Susceptibility				Zone of Investigation County Delineated	Zone of Investigation State Regulatory
Infrastructure Type (Linear)	Very High	High	Moderate	Low		
County Maintained Roads*	30.2	45.0	41.7	170.9	49.4	32.6
Levee	17.7	0.7	-	0.3	3.6	-
Maintained Channel	22.9	10.2	2.9	7.4	8.3	0.4
NG Pipeline	2.1	2.7	3.1	25.9	0.9	-
Railroad	2.6	0.7	1.7	17.0	-	-
Sanitation Pipe	10.1	15.5	3.9	149.5	4.6	1.5
All Roads	79.7	116.9	116.8	497.9	195.4	83.8
Alley	0.8	0.1	0.5	0.9	-	-
Drive	15.0	33.0	27.4	132.5	46.7	18.4
Major Road	21.5	37.3	17.7	72.8	35.7	22.6
Ramp	3.4	2.0	-	6.9	-	0.0
Street	23.2	30.8	54.8	226.3	83.9	31.8
State Highway	10.0	7.5	9.2	25.2	13.0	3.9
Unnamed	5.8	6.2	7.2	33.3	16.0	7.1
Transmission Line	4.3	6.1	3.3	25.3	10.1	3.4
Grand Total	**169.5**	**197.8**	**173.4**	**894.3**	**272.1**	**121.7**

Table 3-39: Santa Cruz County Critical Facilities Susceptible to Faults and Liquefaction

	Liquefaction Susceptibility				Zone of Investigation County Delineated	Zone of Investigation State Regulatory
Facility Type	Very High	High	Moderate	Low		
Essential Facilities	2	4	6	11	3	2
Fire Station	2	3	4	5	3	2
Hospital	-	-	-	2	-	-
Law Enforcement	-	1	2	3	-	-
EOC	-	-	-	1	-	-
American Medical Response	-	-	-	-	-	-
High-Potential-Loss	28	62	54	246	23	14
Adult Care Facility	2	3	1	25	3	2
Child Care Center	4	3	7	25	-	-
Cell Tower	1	5	3	38	6	6
County Real Property Asset	16	35	16	76	9	1
Dam	-	2	-	-	-	2
Healthcare Facility	-	1	1	10	-	-

Historic Building	-	1	2	2	-	-
Library	-	-	1	1	-	-
Mobile Home Park	2	3	13	30	1	-
Power Generation	-	-	-	1	-	-
Radio Sites	1	1	1	5	1	1
School	2	8	9	33	3	2
Transportation and Lifeline	177	322	233	526	413	353
Airport	-	-	-	2	-	-
Substation	-	1	-	10	1	-
NG Station	-	-	-	-	-	-
Church	6	5	16	17	3	1
Stormwater Culvert	133	302	193	457	389	349
Parks	10	2	6	32	6	1
Bridge NBI	28	12	18	8	14	2
Hazmat	36	25	39	201	15	3
HWTS Active Facility	31	24	38	181	14	3
Geotracker Cleanup Site	5	1	1	20	1	-
Grand Total	**243**	**413**	**332**	**984**	**454**	**372**

**Real Property Assets are digitized asset lists for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.*

3.2.3.10 Development Trends

Santa Cruz County has a number of compact urban communities as well as extensive areas of agricultural land and forested hillsides and many rural villages and towns. As dictated by the 1978 Growth Management Ordinance, Measure J, most new development has occurred within or adjacent to the urban services line (i.e., the boundary point for such infrastructure as water and sewage service). As with most communities, increased housing costs has resulted in the need to provide higher density housing. In Santa Cruz County, all development of this type occurs where urban services are available; other development is mostly in-fill or reuse development, and development of existing rural residential properties.

Growth management policies including the Geologic Hazards Ordinance limit development from occurring where hazards are present and, in most cases, require substantial setbacks from these hazards. Seismic safety standards are a requirement for all building permits, and as infrastructure is repaired or replaced, updated seismic safety standards are incorporated. Development on existing lots of record is required to avoid hazards and incorporate appropriate setbacks and other requirements to mitigate potential impacts from earthquake and liquefaction hazards. The Environmental Planning Section of the Planning Department, staffed by resource planners, specializes in reviewing each application for new residential and commercial structures to ensure that new development does not occur in earthquake and liquefaction hazards and that development on existing lots of record avoid, minimize, and mitigate potential impacts from identified earthquake and liquefaction hazards.

No changes in these development regulations or patterns occurred that would affect the county's overall vulnerability since the previous plan was adopted. As noted above, most new development of residential structures and virtually all new development of commercial structures occurs within the urban services line, and always outside of the highest risk earthquake hazard areas.

3.2.3.11 Earthquake Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing earthquake-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with earthquake. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-40 presents the earthquake hazard problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in in Table 4-1 and Table 4-2

Table 3-40: Santa Cruz County Earthquake Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Earthquake	Victim	**ps-EQ-SCC-01**	With no major earthquake since 1989, many residents lack urgency or awareness about seismic risks and are unprepared with basic safety knowledge, emergency supplies, or gas shutoff procedures.
Earthquake	Victim	**ps-EQ-SCC-02**	Residents of mobile homes face outsized seismic vulnerability. Units are often unsecured, lack seismic bracing, and house low-income or elderly residents with limited preparedness resources.
Earthquake	Impact	**ps-EQ-SCC-03**	A major seismic event could damage bridges and hillside roads, particularly in slope failure–prone areas, cutting off access, isolating entire neighborhoods, and impeding emergency response. Coastal and hillside zones with soft soils or steep terrain are also at risk for liquefaction and slope failure during seismic shaking.
Earthquake	Impact	**ps-EQ-SCC-04**	A major earthquake could damage essential County-owned and operated facilities, many of which are in need of seismic retrofit including emergency shelters, fire stations, jails, and communications infrastructure, disrupting critical services delivery.
Earthquake	Threat	**ps-EQ-SCC-05**	Many older residential and commercial buildings throughout the county have not been seismically upgraded, posing threats to occupants and adjacent properties during strong earthquakes.
Earthquake	Threat	**ps-EQ-SCC-06**	A major seismic event could disrupt aging water, sanitation, and stormwater infrastructure, including above- and below-ground lines, storage tanks, pump stations, treatment facilities, and septic systems.

Hazard	Area of Concern	Problem ID	Description
Earthquake	Threat	**ps-EQ-SCC-07**	The county's water systems are vulnerable to disruption during a major earthquake, with no connection to the State Water Project and only two large capacity treatment facilities, each with limited intertie capacity (Watsonville and Graham Hill). These constraints highlight the need for stronger planning and coordination, as existing interties and treatment capacity are insufficient to ensure service continuity in a widespread seismic event.
Liquefaction	Impact	**ps-LQ-SCC-01**	Large portions of the urbanized coastal areas of Santa Cruz County (including the cities of Santa Cruz and Watsonville) have a high or very high risk of liquefaction, which could result in major damage to private and public facilities during an earthquake and/or disrupt critical services.

3.2.3.12 Climate Change Impacts & Vulnerable Populations

Unlike hazards such as flooding, wildfire, and drought, earthquakes are not directly influenced by climate change. However, climate change can compound earthquake impacts by stressing the same populations and systems that are most vulnerable to seismic risk. Residents living in older, unretrofitted housing, mobile homes, or low-income communities already face disproportionate earthquake risks, and these same groups are often more exposed to climate-driven hazards like extreme heat, wildfire smoke, or flooding. Repeated climate stressors can erode financial stability, limit access to insurance or retrofitting resources, and reduce community capacity to prepare for and recover from seismic events. In this way, climate change intensifies underlying social vulnerabilities, making recovery from earthquakes more difficult for disadvantaged and dependent populations.

Severe Weather

3.2.4 Severe Weather Hazard Profile

Severe weather refers to any hazardous atmospheric event with the potential to cause physical damage, social disruption, or loss of life. This includes thunderstorms, downbursts, heavy rain, snowstorms, ice storms, strong winds, and other extreme weather conditions. Winter weather, such as freezing temperatures, snow accumulation, and black ice, is a key component of severe weather in Santa Cruz County, particularly in higher elevation areas.

Severe weather events can be categorized into two types. Those that affect broad geographic regions, such as Pacific Northwest windstorms or large-scale winter storms, are classified as general severe weather. Events with a more confined area of impact, such as isolated thunderstorms or localized snow squalls, are considered localized severe weather.

The most significant secondary hazards associated with severe weather in the planning area include flooding, downed trees, landslides, power outages, and, in some cases, increased wildfire risk following wind-driven damage or infrastructure failure.

3.2.4.1 Subhazards

For Santa Cruz County, there are specific subhazards of severe weather that are more relevant to the planning area than others. This includes high wind, heavy rain and winter weather, which are profiled as part of this section, but it also includes mention of thunderstorms, hail and tornadoes.

High Wind

Damaging winds are classified as those exceeding 60 mph. Damage from such winds accounts for half of all severe weather reports in the lower 48 states and is more common than damage from tornadoes. Wind speeds can exceed 100 miles per hour (mph) and can produce a damage path extending for hundreds of miles. There are seven types of damaging winds:

- **Straight-Line Wind:** Any thunderstorm wind that is not associated with rotation; this term is used primarily to differentiate from tornado winds. Most thunderstorms produce some straight-line winds as a result of outflow generated by the thunderstorm downdraft.
- **Downdraft:** A small-scale column of air that rapidly sinks toward the ground.
- **Downburst:** A strong downdraft with horizontal dimensions larger than 2.5 miles resulting in an outward burst or damaging winds on or near the ground. Downburst winds may begin as a microburst and spread out over a wider area, sometimes producing damage similar to a strong tornado. Although usually associated with thunderstorms, downbursts can occur with showers too weak to produce thunder.
- **Microburst:** A small concentrated downburst that produces an outward burst of damaging winds at the surface. Microbursts are generally less than 2.5 miles across and short-lived, lasting only 5 to 10 minutes, with maximum wind speeds up to 168 mph. There are both wet and dry microbursts:. A wet microburst is

accompanied by heavy precipitation. Dry microbursts, common in places like the high plains and the intermountain west, occur with little or no precipitation reaching the ground.

- **Gust Front:** A gust front is the leading edge of rain-cooled air that clashes with warmer thunderstorm inflow. Gust fronts are characterized by a wind shift, temperature drop, and gusty winds out ahead of a thunderstorm. Sometimes the winds push up air above them, forming a shelf cloud or detached roll cloud.
- **Derecho:** A derecho is a widespread thunderstorm wind caused when new thunderstorms form along the leading edge of the boundary formed by horizontal spreading of thunderstorm-cooled air. The word "derecho" is of Spanish origin and means "straight ahead." Thunderstorms feed on the boundary and continue to reproduce. Derechos typically occur in summer when complexes of thunderstorms form over plains, producing heavy rain and severe wind. The damaging winds can last a long time and cover a large area.
- **Bow Echo:** A bow echo is a linear wind front bent outward in a bow shape. Damaging straight-line winds often occur near the center of a bow echo. Bow echoes can be 200 miles long, last for several hours, and produce extensive wind damage at the ground.

Wind is classified by the National Renewable Energy Laboratory (NREL) based on average speeds across the ground at different elevations in meters per second (m/s) and the amount of power it is capable of producing (wind power density), as provided in Table 3-41. The same wind event exhibits various speeds depending on elevation because of differences in the amount of friction encountered in proximity to the Earth's surface; this is most often measured at 10 and 50 meters above grade, or 33 and 164 feet, respectively. According to the Rayleigh wind speed distribution principle, speed increases 3% per 1,000 meters in elevation (or 5% per 5,000 feet). Power density is measured in the amount of watts (W) that can be produced per square meter (m^2) of surface area on the blades of a wind turbine.

Table 3-41: Classes of Wind Power

Wind Power Class	10 m (33 ft)		50 m (164 feet)[1]	
	Wind Power Density W/m^2	Mean Speed[2] m/s (mph)	Wind Power Density W/m^2	Mean Speed[2] m/s (mph)
1	≤ 100	4.4 (9.8)	≤ 200	5.6 (12.5)
2	100-150	5.1 (11.5)	200-300	6.4 (14.3)
3	150-200	5.6 (12.5)	300-400	7.0 (15.7)
4	200-250	6.0 (13.4)	400-500	7.5 (16.8)
5	250-300	6.4 (14.3)	500-600	8.0 (17.9)
6	300-400	7.0 (15.7)	600-800	8.8 (19.7)
7	>400	9.4 (21.1)	>800	11.9 (26.6)

Notes: [1]Vertical extrapolation of wind speed based on the 1/7 power law. [2]Mean wind speed is based on Rayleigh speed distribution of equivalent mean wind power density and is for standard sea level conditions.

Source: NREL, 2007

Heavy Rain

As storms arrive onto land from the Pacific and rise over the mountains and ridges that border the eastern boundaries of the county, the air associated with those storms cools and that cooling results in large amounts of precipitation, also known as orographic lift. The topography of the Santa Cruz Mountains provides fairly steep and well-defined watershed areas to funnel the falling rain into runoff tributaries and potentially trigger flood hazards.

Heavy rain can overwhelm both natural and man-made drainage systems, causing overflow and property destruction, and landslides can occur when the soil on slopes becomes oversaturated and fails. In Santa Cruz County, heavy rain events are common from November to April. These heavy rainstorms, often associated with an “atmospheric river” event, can deliver over one inch of rain per hour for extended time frames.

Atmospheric rivers are relatively long, narrow regions in the atmosphere (i.e., rivers in the sky) that transport water vapor, mostly from the tropics. While these rivers can vary greatly in size and strength, the average atmospheric river carries an amount of water vapor roughly equivalent to the average flow of the Mississippi River, but exceptionally strong rivers can transport up to 15 times that amount. When the atmospheric rivers make landfall, it typically releases this water vapor in the form of rain or snow. These events can disrupt travel, induce slope failures, and cause damage to life and property. A well-known referential terms for this phenomenon is the "Pineapple Express," which is a strong atmospheric river that brings moisture from the tropics near Hawaii to the West Coast. A singular or series of atmospheric rivers can cause significant damage and flooding. In 2023, more than two dozen atmospheric rivers caused two federally declared disasters. In 2024 it was one major atmospheric river that caused a federally declared disaster

Flash floods are the leading cause of heavy rain-related fatalities. Further, the presence of burn scars from

Figure 3-40: Flooding from February 2024 Severe Weather Event
Source: Santa Cruz County

previous wildfires, such as those left by the 2020 CZU Lightening Complex Fires, increases runoff and flood risks in vulnerable areas. Heavy rain and flash flooding can affect vulnerable populations such as residents living near burn scars or in low-lying areas and tourists and hikers unaware of flash flood risks in remote, mountainous areas. Impacts on property and critical infrastructure include temporary road closures as well as damage to roads, bridges, and structures. Water treatment plants and electrical substations located near waterways are particularly vulnerable.

For more information on the secondary impacts caused by heavy rain, such as flooding, refer to the Flood and Slope Failure Hazard Profiles in Sections 3.2.2 and 3.2.6, respectively.

Winter Weather

Although infrequent, winter weather events do occur in Santa Cruz County and can pose significant hazards, particularly in the higher elevations of the Santa Cruz Mountains. These events are typically associated with the passage of cold frontal systems or incursions of Arctic air masses that result in overnight temperatures dropping below freezing. Impacts may include frost, black ice, freezing rain, and, in rare cases, light snowfall.

Despite their rarity, freezing conditions have historically caused hazardous travel conditions, infrastructure stress, and public health risks. Black ice has led to roadway closures on major routes such as Highway 17, and extreme cold has contributed to life-threatening situations, especially among vulnerable populations lacking adequate heating. These low-probability but high-impact events highlight the need to include winter weather in the county's hazard mitigation strategy.

Other Subhazards

Severe Thunderstorms

Severe thunderstorms can cause both high wind and heavy rain, as well as hail and tornadoes; however, they are not highlighted as a severe weather subhazard in this profile since the primary impact of thunderstorms in Santa Cruz County is the potential spread of wildfire, which is described in more detail in Section 3.2.1.

Hail

Hail is a form of precipitation consisting of solid ice that is formed inside the updraft of a thunderstorm. Small ice particles and supercooled water droplets that are lifted into a thunderstorm by its updraft can combine before falling into the storm's downdraft. Then, if the updraft is strong enough, these hail stone "seeds" can be recycled back up above the freezing level in the storm to accumulate additional ice and water. It is the repeating of this process numerous times that produces larger and larger hail stones. Once a stone is too big for the updraft to hold it up in the storm, it will fall to the ground. To be categorized as severe, hail must reach a size of one inch in diameter or larger.

Figure 3-41: December 2024 Scotts Valley Tornado Damage along Mt. Herman Road

Source: National Weather Service

Hail is a dangerous product of thunderstorms, with stones as large as grapefruit in supercell thunderstorms. Large hail can damage aircraft, homes and cars, and can be deadly to livestock and people. Hail is categorized between a quarter-inch diameter or "pea" size, up to grapefruit at four-and-a-half inches. Hail is extremely rare in Santa Cruz County but has occurred in the past, such as an event in 2017 that caused $5 million in property damage.

Tornado

A tornado is a narrow, violently rotating column of air that extends from the base of a thunderstorm to the ground and is visible only if it forms a condensation funnel made up of water droplets, dust, and debris. The Enhanced Fujita (EF) Scale is used to classify tornado intensity based on the damage they cause. It ranges from EF0 (no damage) to EF5 (extensive damage), with each category defined by specific wind speed ranges and the corresponding damage expected at those wind speeds to particular types of construction. However, this classification system fails to capture the strength of tornadoes that do little to no structure damage, even when they might otherwise be categorized high on the scale.

Although tornadoes are a rare event in Santa Cruz County, they do occur. On December 14, 2024, an EF1 tornado with peak winds estimated at 90 mph struck in the Scotts Valley area, causing significant damage and several injuries (Figure 3-41).

3.2.4.2 Policies, Plans & Regulatory Environment

There are very few formal regulations that pertain directly to severe weather events. The California Building Standards Code, adopted by the county and other participating jurisdictions, is generally adequate to properly address development impacts from severe weather events.

California Building Standards Code

The California Building Code (CBC), adopted by Santa Cruz County, is another name for the body of regulations known as the California Code of Regulations, Title 24, Part 2, which is a portion of the California Building Standards Code. The CBC incorporates by reference the International Building Code (IBC) requirements with necessary California amendments.

3.2.4.3 Past Events

Severe weather events between 2000 and 2025 are summarized in Figure 3-42, as recorded by the National Oceanic and Atmospheric Administration (NOAA) through news reports, law enforcement officials and trained weather spotters. The most common severe weather event in Santa Cruz County is high or strong wind, followed by hail and dense fog. However, impacts from heavy rain in the county are more accurately captured as flooding, including localized urban flooding due to inadequate drainage systems as well as riverine and coastal. See the Flood Hazard Profile in Section 3.2.2 for records of past flood events.



Figure 3-42: Severe Weather Events Recorded by NOAA

Source: NOAA Storm Events Database

High Wind & Tornado Events

- 2016–2018 – Tornadoes and funnel clouds reported near Santa Cruz; scattered severe thunderstorms produced hail, strong winds, and minor flooding.
- 2017–2019 – Offshore wind events produced gusts >100 mph (Mt. St. Helena, Santa Cruz Mountains). The Kincade Fire (2019) driven by 102 mph gusts forced massive evacuations.
- 2020 – Rare August lightning storms triggered hundreds of wildfires, producing the worst air quality in the world at one point.
- 2021 – Unusual January offshore wind event produced gusts up to 90 mph in the Santa Cruz Mountains, sparking winter wildfires.
- 2022 – September heat dome brought record-breaking temps (110°F+) and widespread outages; cooling centers opened across Santa Cruz County.
- 2023–2024 – Multiple high wind warnings associated with cyclones and atmospheric rivers (ARs), causing widespread tree damage and outages.
- 2024 – Confirmed EF1 tornado in Scotts Valley (Dec 14), the first in decades; coincided with bomb cyclone impacts.

Heavy Rain & Atmospheric Rivers

- 2017 – Series of three atmospheric rivers (Jan 2–23): widespread flooding, debris flows, wind, hail, lightning, snow >2500 ft, reservoir overtopping.
- 2019 – Multiple atmospheric rivers with heavy rain, 10"+ in Santa Cruz Mountains; fatalities from downed trees (Highway 17) and car accidents.
- 2021 – atmospheric rivers (Jan 26–29): 15–20" rainfall, Highway 1 collapse at Rat Creek, widespread flooding, power outages, millions in damages in Santa Cruz County.
- 2022–2023 – atmospheric rivers (Dec 26–31 (2022) and Jan–Mar (2023)) led to repeated flooding, debris flows, landslides, widespread power outages (180,000+ customers).
- 2024–2025 – Successive atmospheric rivers and bomb cyclones caused record rainfall and flooding, school closures, evacuations, and large-scale power outages.

Winter Weather Events

- 2009 – Freezing conditions from a winter storm caused black ice and hazardous road conditions in the Santa Cruz Mountains. The southbound lane of Highway 17 near Bear Creek Road was closed due to black ice. A cold air mass led to freezing overnight temperatures, tying or setting record lows at Santa Cruz, Salinas, San Rafael, and Moffett Field.
- 2013 – A prolonged stretch of cold weather brought consecutive days of sub-freezing temperatures across the region. One fatality occurred due to carbon monoxide poisoning from improper indoor heating during the cold snap.
- 2019 – A strong winter storm brought low snow levels and rare snowfall to lower elevation peaks in the Santa Cruz Mountains. Road closures were reported at Empire Grade and Ice Cream Grade due to accumulating snow. Rain and snow mix triggered localized roadway flooding and debris flows.

- 2023 – A strong occluded front caused widespread precipitation and unusually low snow levels, with snow accumulating as low as 1,000 feet. Highway 17 was closed for over 12 hours due to heavy snow, fallen trees, and a jackknifed truck. Snow accumulations reached 10–12 inches in higher elevations.
- 2024 – Winter storms associated with cold fronts brought snow, graupel, and icy road conditions to elevations below 2,500 feet. Multiple transportation disruptions occurred, including delayed school openings and traffic collisions due to slick roads.

3.2.4.4 Location

Severe weather events have the potential to happen anywhere in the planning area and have historically occurred in all parts of the county; although, the types of events and their impacts are not evenly distributed. Local topography and microclimates, especially within the Santa Cruz Mountains, can cause the same storm system to produce different hazardous conditions as it moves across an area and encounters more or less moisture, various temperatures, and orographic lift, which can all influence its behavior. High wind events are most damaging to areas that are heavily wooded, while heavy rain impacts are typically seen over steep terrain and in low-lying urban areas. Additionally, the trajectory of storm systems plays a significant factor. Storms coming in directly off the Pacific Ocean tend to bring more moisture, while storms coming in from the south over the Santa Lucia Range in Monterey County tend to bring less moisture.

Figure 3-44 shows the distribution of average annual rainfall in Santa Cruz County, and Figure 3-45 depicts average annual wind speed by power class (refer to Table 3-41).

Winter weather impacts in Santa Cruz County are most prevalent in the higher elevation areas of the Santa Cruz Mountains, including communities such as Ben Lomond, Boulder Creek, and Lompico. These regions regularly experience overnight temperatures at or below freezing during winter months, occasionally resulting in snow, frost, or black ice. Lower elevation areas, including Watsonville and coastal zones, experience freezing temperatures far less frequently but are still vulnerable during cold snaps.

Analysis of local weather station data from 2000 to 2023 shows that Ben Lomond consistently records more days with minimum temperatures below 34°F than Watsonville, confirming the higher susceptibility of inland mountain communities to extreme cold (See Figure 3-43). In some years (e.g., 2007–2008), Ben Lomond recorded more than 35 freezing days, while Watsonville had significantly fewer. The annual minimum temperatures at both stations also reflect this trend, with colder extremes observed consistently in Ben Lomond.

The County uses 34°F as the threshold for activating warming centers, prioritizing the safety of unsheltered and vulnerable populations. This threshold is routinely met or exceeded in mountain communities during the winter season, reinforcing the importance of localized cold-weather preparedness efforts in these areas.



Figure 3-43: Minimum Annual Temperatures

3.2.4.5 Frequency & Probability of Future Events

Severe weather events for Santa Cruz County are most often related to high winds, heavy rain, and hail, as shown Figure 3-42. These events occur regularly throughout a typical year and will continue to occur in the county. However, as demonstrated over the past decade, climate change is driving an increased frequency in more extreme weather events. This is especially true in Santa Cruz due to its location on the coast and influences from a warming Pacific Ocean, as discussed in more detail in the Climate Change Hazard Profile (Section 3.2.10).

3.2.4.6 Severity

Severe weather poses significant hazards in Santa Cruz County, particularly during the winter months. While tornadoes are extremely rare, the region is regularly affected by damaging winds, heavy rain, hail, and winter weather, including extreme cold, black ice, and occasional snowfall at higher elevations. These hazards can lead to property damage, widespread power outages, and significant transportation disruptions. The most common impacts include loss of utilities and restricted mobility. Roads may become impassable due to flooding, downed trees, snow accumulation, or slope failures triggered by intense rainfall or high winds. Although fatalities are uncommon, they can occur, especially during extreme cold events or hazardous driving conditions.

High Wind

The most common impact of high wind is power outages due to downed or damaged power lines, causing interruptions to critical services, such as emergency response, or to utilities lacking backup power, such as water or communications. These impacts can be localized or widespread, depending on the type of event.

High-wind events occur multiple times per year, particularly along the coast, in exposed valleys, and in constricted canyons and mountain passes. Windstorms in the county are rarely life-threatening but do disrupt daily activities. Strong winds can cause significant damage, uprooting trees and causing power outages and structural damage to buildings. Wind-driven wildfires are also a major concern, as high winds can rapidly spread flames. Other impacts of high winds can be erosion, crop damage, and building damage, primarily to roofs. It is important to note that the predicted wind speed given in wind warnings issued by the NWS is for a one-minute average; gusts may be 25 to 30% higher.

The highest wind gusts to occur in Santa Cruz County were during a major windstorm in March 2023, recorded at a maximum of 97 mph at a weather station on top of Loma Prieta, the highest peak in the Santa Cruz Mountains.

Heavy Rain

Heavy rain alone is rarely life-threatening, but it often triggers other hazard events that can cause serious injury or death and extensive property damage, such as slope failures and localized flash flooding, particularly in burn scar areas from previous wildfires. Of particular concern in Santa Cruz County is heavy rain's impacts on urbanized areas with inadequate drainage infrastructure, mountainous terrain susceptible to slope failure, and erosion and sedimentation within vulnerable watersheds.

One of the heaviest rain events recorded in recent years in Santa Cruz County was during an atmospheric river event in October of 2021, which dumped 9.6 inches of precipitation over a 48-hour period in the Ben Lomond area of the mountains in the northern part of the county. A parade of atmospheric rivers between December 2022 and January 2023 deposited about half of the county's typical annual precipitation in the span of just a few weeks, with total accumulation ranging from 13.8 inches in the southern portion of the county to 36.2 inches in the Boulder Creek watershed. (NWS, 2023) Both of these heavy rain events triggered secondary hazards, including debris flows, erosion, and other slope failures, within the 2020 CZU Lighting Complex Fire's 85,000-acre burn scar underlying the areas that received the most rainfall.

Winter Weather

Winter weather in Santa Cruz County is typically moderate in severity but can lead to high localized impacts, particularly in the Santa Cruz Mountains. Events involving snow, black ice, and freezing temperatures have caused road closures, power outages, and hazardous driving conditions. While widespread damage is uncommon, impacts to transportation and utilities are routine during major storms. Extreme cold can also pose health risks, especially to unsheltered or vulnerable populations. Overall, winter weather is rated as moderate in severity, with periodic high-consequence events in elevated areas.



Figure 3-44: Santa Cruz County Average Annual Precipitation, 1991-2020



Figure 3-45: Santa Cruz County Annual Average Wind Speed

3.2.4.7 Warning Time

Meteorologists can often predict the likelihood of a severe storm up to 10 days in advance. This can give several days of warning time. However, weather systems can stall or shift trajectory, thus making it difficult to predict total precipitation at specific locations. Further, some storms may come on more quickly and have only a few hours of warning time. High wind and heavy rain events can typically be predicted a few hours to a few days in advance, depending on the characteristics of the underlying severe weather system.

The ability to provide early warning for severe weather hazards in Santa Cruz County depends on monitoring systems, weather radar, and alert services. The region benefits from forecasting tools provided by the NWS, NOAA, and local emergency management agencies, which use weather stations, stream gauges, weather radar, and satellite data to issue timely warnings for hazards.

Santa Cruz County is served by the NWS San Francisco Bay Area/Monterey forecasting office located next to the Monterey Regional Airport and Naval Research Laboratory in Monterey County (Figure 3-46). The office serves a total of 11 counties throughout the San Francisco and Monterey Bay regions with a population of more than eight million residents. Radar coverage in Santa Cruz County is primarily provided by an NWS-operated, next generation WSR-88D radar (KMUX) located on Mount Umunhum northeast of the county just south of the San Jose Metro Area. In addition, the county operates a high-resolution X-band radar in Live Oak, filling gaps in low-elevation coverage and improving detection of localized heavy rain by providing near real-time rainfall intensity updates.

Even with the proximity of the two radars, weather prediction and real-time observation in the county face challenges due to its mountainous terrain. To further close gaps in severe weather prediction, the county

Figure 3-46: NWS San Francisco Bay Area/Monterey Forecasting Office

integrates several other data sources for warnings, especially heavy rain, including real-time rainfall and stream gauges operated by county Public Works Department, USGS, and NWS on the San Lorenzo River, Scott Creek, and Pajaro River. The California–Nevada River Forecast Center (CNRFC) also provides projected riverine flood stages, and the NWS Monterey office issues alerts for high surf, king tides, and storm surge.

CruzAware Notification System

CruzAware is Santa Cruz County's official alert and notification system. It is administered by the County Office of Response, Recovery and Resilience (OR3) and is designed to provide residents and visitors with timely warnings and information during emergencies. Notifications are sent by text message, telephone, or email and address a range of hazards including high wind or flooding from heavy rain, as well as other public safety threats and evacuation notices.

For severe weather, CruzAware serves as a primary tool for delivering warnings before hazardous conditions develop. Depending on the situation, alerts may be issued hours or only minutes in advance. These notifications can include evacuation instructions, shelter locations, sandbag distribution sites, and road closure information. The system is capable of targeting specific neighborhoods or hazard zones so that alerts are relevant to those directly at risk.

The system works in coordination with other county resources, such as the S.A.F.E.R. dashboard and real-time weather monitoring systems, to support comprehensive hazard communication. The county also partners with the NWS to disseminate official watches and warnings. NWS alerts are automatically issued through the Wireless Emergency Alerts (WEA) system to mobile devices in affected areas, providing rapid notification without the need for prior registration. More information about CruzAware, including how to register, is available at santacruzcountyca.gov/CruzAware.

One Rain System

The county operates a real-time rainfall and stream gauge platform powered by OneRain, available at santacruz.onerain.com. This system integrates data from ground sensors such as rain gauges and river-stage monitors with other weather feeds to display current and historical rainfall totals, stream levels, and modeled flood conditions. Users can view data over various time intervals, such as 15-minute, hourly, daily, or weekly trends, to better understand storm intensity and watershed response. During heavy rain or flash flood situations, the platform supports faster recognition of rising water levels and more informed decision-making on road closures, evacuations, and other protective actions.

3.2.4.8 Severe Weather Vulnerability Assessment

Recent history indicates that Santa Cruz County has a high vulnerability to severe weather events due to its proximity to the Pacific Ocean and mountainous topography. Severe weather will continue to impact the people, properties, and critical facilities and infrastructure all across the county to varying degrees, causing damage and potentially threatening lives.

3.2.4.8.1 Population

It can be assumed that the entire planning area is exposed to some degree of severe weather events. Certain locations face greater risk due to their geographic setting and local climate conditions. Populations living at higher elevations, such as those in the mountainous regions, are more susceptible to winter weather, including freezing temperatures, snowfall, and icy road conditions, as well as wind damage and power outages during storms. Populations in low-lying areas remain vulnerable to flooding caused by heavy rainfall and saturated soils.

Vulnerable population groups such as older adults, people with limited income, individuals who speak limited English, those with serious health conditions, and residents in areas with restricted access are at the highest risk of severe weather impacts. Extended power outages can pose life-threatening risks for individuals who rely on electricity for medical support, and cold temperatures can endanger those without reliable shelter or heating. Isolation of these populations during winter storms is a significant concern, as it may hinder access to warming centers, emergency services, and life-sustaining resources.

3.2.4.8.2 Property

All property is vulnerable during a severe weather event, but structures in poor condition or located in particularly exposed areas face a greater risk of damage. Buildings situated at higher elevations, along ridgelines, or within narrow canyons where wind is funneled are more likely to experience damage from strong winds or falling trees. Winter weather can intensify these risks, as freezing temperatures and snow accumulation may weaken structures, increase ice buildup on power lines, and contribute to hazardous conditions.

Heavy rain can saturate soils, increasing the likelihood of trees being uprooted and falling onto buildings or infrastructure. Localized flooding and slope failures can damage foundations, roads, and access points. Agricultural property is also at risk, as strong winds and heavy rainfall can damage crops, erode topsoil, and disrupt growing cycles. Winter storms that combine cold temperatures with precipitation further elevate risks for both built and natural environments.

3.2.4.8.3 Critical Facilities & Infrastructure

All critical facilities are exposed to severe weather events. Facilities located on elevated terrain or within forested areas are more susceptible to wind damage, either directly or from falling trees. However, the most significant concern during severe weather is not the structural vulnerability of facilities themselves, but rather the potential for damage to roads, utilities, communications systems, and other essential infrastructure that support facility operations.

The most frequent issues during severe weather events include power outages and the resulting cascading impacts on utility systems. Downed power lines can lead to widespread blackouts, leaving entire communities without electricity. Loss of power can also disrupt phone service, water supply, and wastewater systems. Roads may become blocked or impassable due to flooding, fallen trees, or landslides

triggered by heavy rainfall. High winds can bring down trees and power lines, obstructing transportation routes, delaying emergency response, and isolating communities.

Roadways that serve isolated areas and vulnerable populations are of particular concern, as access may be compromised during or after a storm. In addition, power and communication outages can have a disproportionate effect on seniors, individuals with medical conditions, and others who may be unable to seek help without functioning phone or transportation services. Prolonged closures of major routes can interrupt the flow of goods and services, disrupting the regional economy and delaying recovery efforts. Large, long-lasting storms can result in significant economic losses and strain on public resources.

3.2.4.9 Development Trends

All current and future development will be affected by severe weather. The ability to withstand impacts lies in the consistent application and enforcement of codes and regulations for new construction. The county and other participating jurisdictions have adopted and comply with the mandated California Building Code, which is equipped to deal with the threats of severe weather events. Land use policies identified in general plans within the planning area also address many of the secondary impacts triggered by high wind or heavy rain, such as flood and landslide. However, not unlike wildfire, the proximity of residents to forested and steep slope areas places them at elevated risk of landslides and tree fall during severe weather. These localized risks, which persist despite code requirements, underscore that regulatory tools alone do not make the community fully equipped to manage all consequences of future growth and severe weather events.

3.2.4.10 Severe Weather Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing severe weather-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with severe weather. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-42 presents the severe weather hazard problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in Table 4-1 and Table 4-2

Table 3-42: Santa Cruz County Severe Weather Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Heavy Rain	Threat	**ps-HR-SCC-01**	Heavy rainfall events driven by atmospheric rivers are becoming more intense and prolonged due to climate change, overwhelming aging culverts and stormwater conveyance systems leading to road washouts, localized flooding, and infrastructure wear.
High Wind	Impact	**ps-HW-SCC-01**	High winds frequently down trees that block critical access routes and damage power and communications infrastructure, causing extended outages and disrupting emergency and other services, while also damaging private property and creating future fire risk from downed vegetation.
Severe Weather	Victim	**ps-SW-SCC-01**	Long-duration power outages from severe weather events disproportionately affect low-income, disabled, and elderly residents who lack back-up power or access to transportation.
Severe Weather	Impact	**ps-SW-SCC-02**	Key critical lifeline facilities such as fire stations, emergency shelters, and wastewater pump stations are not consistently hardened against high wind or heavy rain events or lack reliable backup power generation, which has resulted in structural damage, service disruption, and temporary closures.
Severe Weather	Threat	**ps-SW-SCC-03**	Localized microclimates and the interaction of weather systems with coastal mountains complicate notifications and limit advance coordination during fast-moving severe weather events, reducing situational awareness and hindering damage assessment.
Winter Weather	Victim	**ps-WW-SCC-01**	Seniors, those with underlying health conditions, and people experiencing homelessness face heightened, and sometimes life-threatening, risks during cold winter weather events, particularly when compounded by underlying health conditions or limited access to medical care.
Winter Weather	Impact	**ps-WW-SCC-02**	Winter weather events can cause hazardous travel conditions and stress on infrastructure from freezing rain, black ice, and sometimes snow.

3.2.4.11 Climate Change Impacts & Vulnerable Populations

Severe weather in unincorporated Santa Cruz County, including atmospheric river storms, prolonged heavy rainfall, and high wind events, is intensifying due to climate change. Warmer ocean conditions and shifting precipitation patterns increase both the frequency and severity of winter storms, while strong winds compound damage and prolonged outages. These climate-driven changes amplify risks to infrastructure, essential services, and vulnerable populations who already face barriers to preparation and recovery.

Direct Impacts: Severe weather damages lifeline infrastructure such as culverts, stormwater systems, and overhead utilities. Heavy rainfall overwhelms drainage systems, causing localized flooding and road washouts that isolate communities. Strong winds topple trees and power lines, blocking critical access routes and disrupting communications and electricity. Critical facilities such as fire stations, emergency shelters, and wastewater pump stations are not consistently hardened against these events and often lack reliable backup power, increasing the likelihood of service disruption.

Secondary Hazards: Severe weather can also trigger cascading impacts. Atmospheric river storms increase slope instability and debris flows in steep terrain, isolating neighborhoods and damaging water and wastewater infrastructure. Fallen trees and debris left by storms add to fuel loads for future wildfire events.

Extended outages further undermine the continuity of emergency operations, creating compounding risks across multiple hazard types.

Public Health and Social Impacts: Severe weather disproportionately affects vulnerable populations. Low-income households often lack resources to invest in backup power, flood protection, or temporary relocation. Elderly residents, people with disabilities, and those reliant on electricity for medical equipment face heightened health risks during long outages. Limited-English households may not receive or understand emergency alerts, while rural residents can become stranded by road closures or prolonged service disruptions. These disparities magnify the health, safety, and financial consequences of storm events.

The mitigation strategy addresses these challenges by investing in stronger stormwater infrastructure, expanding backup power capacity at critical facilities, and improving outreach and emergency communication for vulnerable populations. Linking climate change projections to the needs of at risk groups is essential for reducing inequities and building community-wide resilience against increasingly severe storms.

PAGE INTENTIONALLY BLANK



Coastal

3.2.5 Coastal Hazards Profile

Due to Santa Cruz County's location on the Pacific Coast, it is exposed to many coastal hazards, including coastal storms, erosion, wave run-up and surge, and tsunami. Coastal hazards present very similar risks to flood hazards, which are discussed in Section 3.2.2, with secondary and compounding impacts from inundation and erosion. Coastal storms can cause increases in tidal elevations (called storm surge), wind speed, wave attack, coastal erosion, and debris flows, as well as flooding. During a coastal storm, excess water from rainfall can combine with coastal storm surge to overwhelm and overtop the channels of creeks and rivers onto the banks and adjacent floodplains and inundates beaches.

3.2.5.1 Compounding Hazards

Coastal hazards are heavily influenced by ocean conditions, including changing sea levels. While sea level rise will remain an important long-term driver of risk, within the timescale of this report the more immediate compounding hazard is the increased intensity of climate change-driven coastal storms. These storms can accelerate coastal erosion, expand coastal inundation, and magnify wave impacts, particularly during El Niño and atmospheric river events. When such storms coincide with extreme king tide conditions—where high tides, large waves, and storm surge occur simultaneously; the resulting flooding and erosion can be especially damaging to coastal infrastructure, transportation assets, and adjacent development (Santa Cruz County Regional Transportation Commission, 2, 2025).

From the State of California Sea Level Rise Guidance: 2024 Science and Policy Update, the Monterey tide gauge is at a high risk of sea level rise of approximately one foot by the year 2050, with a moderate risk rating of rising two feet and an extremely low risk of risk up to 2.7 feet over the same time period. By the year 2100, the report projects a low risk of between 2.3 and 3.3 feet of sea level rise, a moderate risk of between 5.5 and 6.9 feet, and an extremely low risk of up to 10 feet of sea level rise. However, any amount of sea level rise will significantly compound coastal hazards. Sea level rise is profiled as a subhazard of climate change and discussed further in Section 3.2.10.

3.2.5.2 Subhazards

For Santa Cruz County, there are specific types of coastal hazards that are more relevant to the planning area than others. This includes coastal storm, coastal erosion, wave run-up and surge, and tsunami, which are profiled as part of this section.

Coastal Storm

As storms arrive onto land from the Pacific and rise over the mountains and ridges that border the eastern boundaries of the county, the air associated with those storms cools and that cooling results in large

amounts of precipitation, also known as orographic lift. The topography of the Santa Cruz Mountain provides fairly steep and well-defined watershed areas to funnel the falling rain into runoff tributaries and potentially trigger flood and other hazards.

Coastal storms often cause flooding along the heavily developed Monterey Bay coastline of Santa Cruz County and may simultaneously bring large waves and storm swells, especially during the winter months (Figure 3-47). Storm centers from the southwest direction produce the type of storm pattern most commonly responsible for the majority of severe coastline flooding. The strong winds combined with high tides that create storm surges are usually accompanied by heavy rains. When storms occur simultaneously with high tides, flood conditions, particularly flooding at the mouth of the Pajaro River and Aptos Creek, are exacerbated.

Figure 3-47: Damage in the Santa Cruz Harbor during December 23, 2024, Storm Surge Event

Source: Santa Cruz Port District

Wave Run-Up & Surge

Wave run-up determines the extent over which waves act. Wave run-up is specifically defined as the landward extent of wave uprush measured vertically from the still water level and consists of two parts: wave setup which is a mean (averaged over time) water surface elevation and swash.

Wave run-up an important parameter to determine inundation from coastal storms. Cross-shore and long-shore sediment transport are a function of the hydrodynamics on the beach and are therefore related to wave run-up. Wave run-up is required to determine the crest height of coastal structures that will prevent overtopping. In 2024 a long-period high-energy winter storm caused significant damage to the Santa Cruz Wharf and Port District.

Coastal Erosion

Coastal erosion is the wearing away of coastal land from forces such as wave action, wind, and rain. It is commonly used to describe the horizontal retreat of the shoreline along the ocean. Erosion can be measured as a rate, with respect to either a linear retreat (feet of shoreline recession per year) or volumetric loss (cubic yards of eroded sediment per linear foot of shoreline frontage per year).

Erosion rates are not uniform and vary over time at any single location. Annual variations are the result of seasonal changes in wave action and water levels. Erosion is caused by coastal storms and flood events, changes in the geometry of tidal inlets and bays, and human activities such as development and dredging. Further, activities aiming to protect the shoreline and improvements thereupon often actually lead to additional erosion.

Coastal erosion includes cliff, bluff, and beach erosion and is a result of both normal, constant wave action and intense wintertime wave attack associated with coastal storms. Beaches change seasonally in response to changes in wave conditions. Winter storm waves are larger, steeper, and contain more energy, and typically move significant amounts of sand from the beaches to offshore bars, creating steep, narrow beaches. In the summer, lower, less energetic waves return the sand, widening beaches and creating gentle slopes. During the winter months when beaches are narrow, or absent altogether, the storm waves attack the cliffs and bluffs more frequently.

Bluff failure takes place through processes related to the sea (mainly those that affect wave action) and to the land (rainfall and runoff, weathering, earthquakes), although the terrestrial processes are less often appreciated than the marine processes. Wave attack during periods of high tides or otherwise elevated sea level (e.g. El Niño or storm surge) is one of the most common mechanisms of episodic cliff failure. El Niño increases storm frequency, elevated sea levels, wave height and rainfall.

There are many factors involved in coastal erosion, including human activity, climate change and sea level rise, and seasonal fluctuations; consequently, sand movement is not consistent year after year in the same location. Wind, waves, and the long-shore currents are some of the driving forces behind coastal erosion. The removal and deposition of sand creates long-term changes to beach shape and structure. Sand may be transported to landside dunes, deep ocean trenches, other beaches, and deep ocean bottoms.

Tsunami

A tsunami is a series of waves generated by an impulsive disturbance in a large body of water like the Pacific Ocean. Tsunamis are produced when movement occurs on faults in the ocean floor, usually during very large earthquakes. Sudden vertical movement of the ocean floor by a fault, landslide, or similar mass movement displaces the overlying water, creating a wave that travels outward from the source. The waves can travel across oceans and maintain enough energy to damage distant shorelines.

The hazard posed by tsunamis came to the attention of the world during the 2004 Indian Ocean tsunami that killed as many as 300,000 people who lived more than a thousand miles from the source of the earthquake. An earthquake anywhere in the Pacific Ocean can cause tsunamis around the entire Pacific basin, including the coastline of Santa Cruz County.

3.2.5.3 Policies, Plans & Regulatory Environment

Federal Regulatory Environment

Coastal Zone Management Act (CZMA) & Programs

In 1972, the U.S. Congress recognized the importance of addressing challenges presented by continued growth along the nation's coastlines by passing the Coastal Zone Management Act (CZMA). This act, administered by the National Oceanic and Atmospheric Administration (NOAA), provides for the management of the nation's coastal resources. The goal is to "preserve, protect, develop, and where possible, to restore or enhance the resources of the nation's coastal zone."

The CZMA outlines three national programs, the National Coastal Zone Management Program, the National Estuarine Research Reserve System, and the Coastal and Estuarine Land Conservation Program (CELCP). The National Coastal Zone Management Program aims to balance competing land and water issues through state and territorial coastal management programs, the reserves serve as field laboratories that provide a greater understanding of estuaries and how humans impact them, and CELCP provides matching funds to state and local governments to purchase threatened coastal and estuarine lands or obtain conservation easements.

One of the most significant provisions of the CZMA gives state coastal management agencies regulatory control (federal consistency review authority) over all federal activities and federally licensed, permitted or assisted activities, wherever they may occur if the activity affects coastal resources. Examples of such federal activities include: outer continental shelf oil and gas leasing, exploration, and development; military projects at coastal locations; U.S. Army Corps of Engineers fill permits; and commercial space launch projects on federal lands. Federal consistency is an important coastal management tool because it is often the only review authority over federal activities affecting coastal resources given to any state agency.

National Flood Insurance Program (NFIP)

As detailed in the Flood Hazard Profile, Section 3.2.2, the National Flood Insurance Program (NFIP) makes federally backed flood insurance available to homeowners, renters, and business owners in participating communities according to localized flood hazard maps and studies. Flood Insurance Rate Maps (FIRM) are the primary tools for identifying the extent and location of flood hazards, including along the coast. FIRMs designate Special Flood Hazard Areas (SFHA) and specific flood zones based on type and level of risk. For coastal areas, FIRMs depict high-hazard V Zones, Coastal A Zones (CAZ), and the Limit of Moderate Wave Action (LiMWA) within the SFHA. The most recent county-wide FIRM for Santa Cruz County became effective on August 3, 2016, and is used to apply regulatory requirements to all SFHAs, including coastal flood hazard zones.

U.S. Army Corps of Engineers (USACE)

The U.S. Army Corps of Engineers (USACE) plans, designs, constructs, and maintains water resources projects, including coastal storm damage reduction measures and infrastructure. In Santa Cruz County, USACE conducts studies and implements measures to protect coastal communities from wave run-up, shoreline erosion, and coastal flooding. This includes collaboration with the Coastal Commission on beach nourishment and bluff stabilization projects where feasible and authorized.

State Regulatory Environment

California Coastal Act

The California Coastal Act of 1976 is a landmark state law that guides coastal development and resource management in California's designated Coastal Zone with the primary goals of balancing economic development with conservation, protecting and preserving natural coastal resources, and maximizing public access. The Act established the California Coastal Commission, which oversees Local Coastal Programs (LCPs) developed by local governments to regulate development through a permit process, ensuring that projects are consistent with the Act's goals. The Coastal Act includes specific policies that address issues such as public shoreline access and recreation; lower cost visitor accommodations; terrestrial and marine habitat and scenic protections; agricultural, commercial, and industrial uses including fisheries; and ports and transportation.

California Coastal Commission

The California Coastal Commission was established by voter initiative in 1972 (Proposition 20)—later made permanent by the State Legislature through adoption of the California Coastal Act—and is one of California's three designated coastal management agencies for purposes of administering the federal Coastal Zone Management Act (CZMA). The Commission is an independent, quasi-judicial state agency composed of 12 voting members, appointed equally (four each) by the Governor, the Senate Rules Committee, and the Speaker of the Assembly. Six of the voting commissioners are locally elected officials and six are appointed from the public at large. Three ex officio (non-voting) members represent the Resources Agency, the California State Transportation Agency, and the State Lands Commission.

In partnership with coastal cities and counties, the Commission plans and regulates the use of land and water in the established Coastal Zone. The Coastal Zone, which was specifically mapped by the Legislature under the Coastal Act, covers an area larger than the State of Rhode Island along the California coastline, excluding the San Francisco Bay which is regulated separately. Offshore the zone includes a three-mile-wide band of ocean, and on land the Coastal Zone varies in width from several hundred feet in highly urbanized areas up to five miles in certain rural areas.

Development activities within the Coastal Zone generally require a permit from either the Coastal Commission or the local government. These activities are broadly defined by the Coastal Act to include

construction of buildings, divisions of land, and activities that change the intensity of use of land or public access to coastal waters, among others.

California Coastal Conservancy

The California Coastal Conservancy is a non-regulatory state agency designated for purposes of administering the federal Coastal Zone Management Act alongside the Coastal Commission to protect and restore coastal resources, help people get to and enjoy the coast, and enhance climate resilience. The Conservancy works along the entire length of California's coast and within the watersheds of rivers and streams that extend inland from the coast implementing statewide and regional resource plans through various projects.

In addition, the Conservancy provides technical assistance and grant funding to local communities, non-profit organizations, tribes, and public agencies to implement multi-benefit projects that help accomplish its main goals of protecting the natural and scenic beauty of the coast; enhancing wildlife habitat and water quality; employing nature-based solutions; facilitating public access and enjoyment of coastal resources; revitalizing working waterfronts; and preparing communities for the impacts of climate change.

Local Regulatory Environment

Sana Cruz County General Plan/Local Coastal Program (LCP) Public Safety Element

The Santa Cruz County General Plan Public Safety Element sets forth objectives and policies relevant to coastal hazards, including to reduce hazards and property damage caused by coastal erosion and bluff retreat (Objective 6.2) and to minimize damages and threats to public health and safety and prevent adverse impacts to floodplain functions and ecologies (Objective 6.4). To meet these objectives, the General Plan includes the following key policies:

- **Policy 6.2.12 Setbacks from Coastal Bluffs:** All development activities, including those which are cantilevered, and non-habitable structures for which a building permit is required, must be set back from the edge of a bluff sufficiently to provide a stable building site over a 100-year lifetime of the structure, or a minimum of 25 feet, as determined through geologic and/or soil engineering reports.
- **Policy 6.2.17 Prohibit New Building Sites in Coastal Hazard Areas:** Does not allow the creation of new building sites, lots, or parcels in areas subject to coastal hazards, or where development would require the construction of public facilities or infrastructure within coastal hazard areas, or in the area necessary to ensure a stable building site for the minimum 100-year lifetime.
- **Policy 6.2.20 Reconstruction of Damaged Structures on Coastal Bluffs:** Limits the reconstruction of structures on or at the top of a coastal bluff which have been substantially damaged (beyond 50% of the market value) and encourages relocation landward of the previous site.
- **Policy 6.4.3 Development on or Adjacent to Coastal Bluffs and Beaches:** Allows development in areas immediately adjacent to coastal bluffs and beaches only if a geologist determines that wave action, storm

swell, and tsunami inundation are not a hazard to the proposed development or that such hazard can be adequately mitigated.

Local Coastal Program (LCP) Administration

The Santa Cruz County Code addresses coastal flooding and related hazards through the Local Coastal Program (LCP) Administration provisions in Chapter 18.60. These regulations establish the procedures and standards for administering the county's certified LCP in compliance with the California Coastal Act. The Public Safety Element and the Santa Cruz County Code govern the review and permitting of development within the Coastal Zone, ensuring that projects are consistent with certified LCP policies, including those related to coastal flooding, wave run-up, bluff erosion, and sea level rise. Santa Cruz County Code Chapter 16.10 requires that development in areas subject to coastal hazards be sited, designed, and constructed to minimize risks to life and property, avoid the use of protective structures where feasible, and preserve public access and natural shoreline processes. Santa Cruz County Code Chapter 13.20 also sets forth permit review procedures, appeal rights, and coordination requirements with the California Coastal Commission for projects in appealable areas. Through these policies and procedures, the LCP provides the administrative framework to implement coastal flood hazard policies and ensure that new development is compatible with long-term coastal resilience.

3.2.5.4 Past Events

Over the past several decades it has been discovered that coastal wave climate and storm frequency are related to larger scale climatic oscillations that affect the entire Pacific Ocean. During the time period from about 1945 to 1978, the California coast was characterized by a fairly calm climate, few large storms, less rainfall and less coastal erosion and storm damage. Beginning in 1978 and continuing until 1998, California experienced a period of more frequent and severe El Niño events with associated elevated sea levels, large waves, heavier rainfall, and more extensive coastal storm damage and erosion.

Coastal hazard events continue to impact Santa Cruz County, sometimes causing deaths, injuries, and property damage. Figure 3-48 summarizes past coastal hazard events since 2000. The most significant singular coastal evnet was the March 11, 2011, tsunami that caused more than $26 million in damage.



Figure 3-48: Santa Cruz County Coastal Hazard Events, 2000 -Present

Source: NOAA Storm Events Database

Coastal Storm, Wave Run-Up & Surge

Significant coastal storms, with associated damage, strike Santa Cruz County and other Monterey Bay communities with regular frequency. As a result, ocean front development has not been compatible with the natural instability of the shoreline and intense winter weather conditions.

The most severe storms on record to hit the California coast occurred in 1978 and 1983 when high water levels were accompanied by very large storm waves. (FEMA FIS, 2006) In 1978, a series of storms emanated from a more southerly direction than normal, which can act as an exacerbating factor. Consequently, some of the usually more protected beaches were damaged. Jetties and breakwater barriers were overtopped, and in some cases, undermined. Direct wave damage occurred to many beachfront homes and seawalls, especially in the more populated beachfront areas such as at Seacliff Beach and Rio Del Mar Beach.

In 1983 a similar storm hit the Santa Cruz coastline. During this storm, a new 3,500-foot seawall was destroyed and 19 of 21 homes in Seacliff Beach were significantly damaged when the existing riprap protection was overtopped. (*Id.*) The Pajaro Dunes area of the county that is fronted by dunes has also been subject to severe damage to structures as well as rapid beach retreat in 1968, 1969, 1978, and 1983. (*Id.*)

Between December 2022 and March 2023, Santa Cruz County experienced a series of destructive coastal storms fueled by successive atmospheric river events and strong low-pressure systems. On December 27, 2022, intense rainfall caused Aptos Creek to overflow, flooding streets in Rio Del Mar and trapping residents in their homes. Just days later, on December 31, another atmospheric river stalled over the region, producing record rainfall, widespread flooding, mudslides, and wind damage. In Soquel, floodwaters inundated the Old Mill Mobile Home Park, forcing evacuations. On January 4–5, 2023, a powerful atmospheric river combined with a bomb cyclone, generating damaging surf that broke the Capitola Wharf in half and battered coastal infrastructure. The storm cycle continued into February and March with multiple high wind events: on February 21, a strong upper-level low produced gusts exceeding 60 mph and toppled trees, injuring residents in Boulder Creek. In early March, subtropical moisture plumes delivered torrential rainfall, widespread flooding, and landslides, including the washout of North Main Street in Soquel on March 10. Later in March, rapidly intensifying cyclones brought hurricane-force wind gusts above 80 mph, cutting off communities like Ben Lomond and Boulder Creek, injuring residents, and leaving over 100,000 customers without power. These events highlighted the county's vulnerability to compounding coastal storm hazards, where extreme rainfall, high surf, flooding, and damaging winds intersected to cause widespread impacts to communities, infrastructure, and natural systems.

UC Santa Cruz Earth & Planetary Professors Gary Griggs and Lida Davar authored a research paper that was published in the Journal of Coastal Research that estimated coastal storms resulted in $4.7 billion in economic losses in California between December 2022 and March 2023.

More recently, the Santa Cruz Harbor was impacted by wave run-up and surge event on December 23, 2024. The surge event caused approximately $11 million in damage to boats and harbor facilities and also caused a portion of the Santa Cruz Wharf to fall into the Pacific Ocean (Figure 3-49).

Coastal Erosion

Nearly the entire California coast is actively eroding due to complex oceanographic and geologic conditions, and human activities that affect the delivery and movement of sand along the coast. Studies have been performed on El Niño, storm frequency, and coastal erosion history for the central California coast from 1910 to 1995. This research indicated that the majority of documented coastal erosion occurred during El Niño storms that originated from the southwest.

During the severe El Niño winters of 1983 and 1997 to 1998, sea levels were further elevated and storm damage along the coastal area was extensive.

Figure 3-49: Part of the Santa Cruz Warf Following its Collapse During a Storm Surge Event on December 23, 2024 Source: City of Santa Cruz

Tsunami

California is at risk from both local and distant-source tsunamis. Over 80 possible or confirmed tsunamis have been observed or recorded in California during historic times. Most of these events were small and only detected by tide gauges, but 11 were large enough to cause damage and four events resulted in deaths. Some of the most notable tsunamis to hit the county occurred in 1896, 1946, 1964, and 2011.

- **1896 Japan Tsunami:** The first recorded tsunami was a far-field tsunami that initiated from an earthquake near Japan on June 15, 1896. In Japan, the death toll was approximately 20,000 people, but in Santa Cruz the tsunami was only a meter and a half high and there is little record of damage.
- **1946 Aleutian Trench Tsunami:** A more significant tsunami occurred on April 1, 1946, when a M8.1 earthquake in the Aleutian Trench produced a 130-foot wave that struck Unimak Island, Alaska, in the Aleutian Islands 90 miles to the north, destroying the Scotch Cap lighthouse and killing five Coast

Guardsmen. (UAF, 2015) The wave was observed all along the west coast and in Hawaii, where it was 56 feet high and killed 173 people. In Santa Cruz County, a man drowned, and minor damage was done by 10-foot waves; however, it should be noted that scientific observations place the 1946 tsunami run-up at 1.5 meters.

- **1964 Good Friday Tsunami:** On March 27, 1964, Santa Cruz County was hit by a similar sized tsunami to the one in 1946, generated by the Good Friday Earthquake. Reports vary, indicating heights between 1.5 and 3.3 meters.
- **2011 Japan Tsunami:** The 2011 Japan Tsunami occurred as a result of a M9.0 earthquake in Japan on March 11, 2011. In Japan, nearly 16,000 deaths occurred as a result of the earthquake and tsunami, which generated a wave of water up to 113 feet in height traveling inland up to six miles. This tsunami hit the Santa Cruz Harbor with waves estimated to be several feet combined with swift and chaotic currents causing more than $26 million in damage.
- **2022 Tonga Tsunami:** The 2022 Tonga Tsunami occurred as a result of an undersea volcanic eruption in the South Pacific Ocean on January 15, 2022. Tsunami waves also struck shores around the Pacific, including Santa Cruz County where $9.5 million in property damage was reported.

3.2.5.5 Location

Santa Cruz County is bounded on one side by the Pacific Ocean and, by definition, coastal hazards happen along the coast. Hence, coastal areas in Santa Cruz County from Swanton in the north to Pajaro Dunes in the south are susceptible to these hazards. All areas along the county's coastline have experienced impacts at some point in the past from coastal storms, wave run-up and surge, erosion, and tsunami.

Coastal Erosion, Wave Run-Up & Surge

The entire coastal edge of the county is or can be affected by coastal erosion, wave run-up, and storm surge. On the north coast, where there are few structures near the coastline, the risk to risks to development are relatively limited compared to the central and southern coastlines, where homes, businesses, and transportation infrastructure are concentrated near the water's edge. Vulnerabilities differ by setting: cliff backed segments of the coast, such as those between the Santa Cruz Harbor and Pleasure Point, Opal Cliffs, and portions of East Cliff Drive, are most exposed to chronic erosion and episodic bluff failures. In contrast, low-lying areas near river mouths, lagoons, and beaches including Pajaro Dunes, Capitola, Rio Del Mar, downtown Santa Cruz, East Cliff at Moran Lake, and the Corcoran Lagoon area are particularly susceptible to storm surge, wave overtopping, and coastal inundation during extreme events.

Most of the significant cliff, bluff, dune, and beach erosion occurs in the area of the county from Live Oak to the Monterey County line during major coastal storms and especially during very high tides. The bluffs in the Live Oak area and eastward to Rio Del Mar are underlain by the younger Purisima formation capped by terrace deposits that are also sensitive to coastal erosion and which have been estimated to be retreating at a rate of six inches to one to two feet per year.

The north coast area of the county also experiences coastal erosion, but to a lesser degree. The north coast area of the county, from the City of Santa Cruz to the San Mateo County line, is underlain by the geologically older Santa Cruz Mudstone formation, which is less susceptible to coastal erosion than areas to the south.

Figure 3-11 in the Flood Hazard Profile (Section 3.2.2) depicts coastal flood zones as mapped by FEMA, in addition to other flood hazard areas in the county. Coastal flood zones are used to evaluate the extent of wave run-up, storm surge, and coastal erosion hazards. Coastal V Zones in the Special Flood Hazard Area indicate the potential for damaging wave attack, which triggers accelerated erosion along the affected coastline.

Tsunami

There are two primary types of tsunami vulnerability in Santa Cruz County: local-source, originating from nearby seismic activity, and tele-tsunami (distant-source) from elsewhere in the Pacific Ocean. Santa Cruz County is located on Monterey Bay, and several active and potentially active earthquake faults are located within or near the county. An earthquake occurring in or near any of the nearby faults could result in local-source tsunamis from submarine landsliding in the Monterey Submarine Canyon.

Additionally, distinct-source tsunamis from the Cascadia Subduction Zone to the north, or tele-tsunamis from elsewhere in the Pacific Ocean, are also capable of causing significant destruction. The Pacific Rim is highly seismically active, and tsunamis are not uncommon but historically have been only a few meters in height. Dangerous tsunamis would most likely originate in the Aleutian and Chilean trenches, the eastern coast of Japan, or the Pacific Islands.

Figure 3-50 is a map of potential tsunami inundation areas in Santa Cruz County.



Tsunami Runup Area Exposure

Unincorporated County

*Data sources: County.

Tsunami Run-up

Figure 3-50: Santa Cruz County Tsunami Run-Up Areas

3.2.5.6 Frequency & Probability of Future Occurrences

Santa Cruz County will continue to be impacted by coastal hazards each year, especially during the winter months when ocean conditions tend to produce coastal storms with wave run-up and storm surge contributing to coastal erosion. However, predicting the frequency and probability of future tsunamis is more similar to predicting earthquakes, as discussed in the earthquake hazard profile.

Coastal Storms, Erosion, Wave Run-Up & Surge

Significant storms and associated damage from surge, wave action, flooding, and erosion strike the Monterey Bay communities with a frequency of one large storm every three to four years. (Ott Water Engineers, Inc., 1984) This equates to a 25% to 33% chance of a large coastal storm occurring in Santa Cruz County in a given year. However, significant coastal storms have occurred in Santa Cruz County three years in a row between 2022 and 2024

Based on its coastal location, bluff and shoreline erosion will continue to occur in Santa Cruz County in the future. The amount of erosion will be dependent on the intensity of future storms and whether or not corrective actions are taken to protect shoreline areas by reducing erosion rates. With regard to beach erosion and bluff failure, it is less a matter of whether or not the hazard will occur and more a matter of the rate in which the hazard will cause additional damage (i.e. structural failure).

Wave attack combined with a global rise in sea level over the past 18,000 years has led to the continued migration of the shoreline. At the end of the last Ice Age, about 18,000 years ago, the coastline at Santa Cruz was about 10 miles offshore. As the ice sheets and glaciers melted, sea level gradually rose and continues to rise today a process that is accelerating due to climate change. Sea levels are rising globally at an accelerating rate. However, the rate of local sea level rise varies depending upon the regional geologic setting and whether the coastline is stable, rising, or sinking.

In 2017, the Central Coast Wetlands Group conducted a study of future sea level rise impacts along the Santa Cruz County coast. The study evaluated how various sea level rise scenarios would impact coastal hazards and especially coastal erosion, and the results identified areas, facilities, infrastructure, and properties vulnerable to inundation and erosion in the future with sea levels from 10 to 159 centimeters by the year 2100. This study is further discussed under sea level rise in the Climate Change Hazard Profile (Section 3.2.10).

Tsunami

Tsunamis are caused by large offshore earthquakes and ocean landslides and, since scientists cannot predict precisely when earthquakes will occur, they cannot determine exactly when a tsunami will be generated. Anticipating the extent of future tsunami hazard is difficult because the historic record is limited, as is our understanding of the source mechanisms and influence of offshore geometry on the impact of tsunami in Santa Cruz County.

Studies have recently been undertaken through the Governor's Office of Emergency Services (Cal OES) and the Department of Civil Engineering at the University of Southern California, Los Angeles. The studies resulted in tsunami inundation maps for the entire state coastline based on worst-case scenario events, which are only to be used for emergency preparedness and evacuation planning.

Pre-1994 inundation computations underestimated tsunami inundation height, but newer inundation models are capable of modeling extreme events more accurately. These new models (known as Method of Splitting Tsunami (MOST)) permit quantitative evaluation of inundation from nearfield tsunamis, provided accurate regional tectonic models and high-resolution bathymetry exist. Even using state-of-the-art inundation prediction tools, California presents unique challenges in assessing tsunami hazards because:

- There is an extremely limited historic record of tsunamis in the state, with no known records before the 19th century. Some paleo-seismic investigations have revealed evidence of pre-historic tsunamis, but not in Santa Cruz County.
- Most of the geologic work in the state has concentrated on identifying the risks associated with onshore faults and there is scant available information on offshore faults or landslide and slump scars suggestive of past submarine mass movements.
- Earlier estimates of tsunami hazards created the impression among planners and the public that the tsunami hazard was remote. However, tsunami events from the past 15 years (e.g., Japan and Tonga) have demonstrated that the hazard has a very real likelihood of occurring.
- Nearshore seismic events may trigger tsunamis arriving within less than 20 minutes from peroration, allowing little time for evacuation.
- Shorelines and shoreline platforms vary significantly throughout the state, which modify tsunami run-up and the corresponding potential damage.

3.2.5.7 Severity

As demonstrated by past events, coastal hazards regularly impact Santa Cruz County, often causing deaths, injuries, and extensive property damage. Coastal storms frequently cause flooding along the heavily developed Monterey Bay coastline of the county and may simultaneously bring storm surges and damaging waves. When storms occur simultaneously with high tides, flood conditions and erosion are exacerbated. In addition, although tsunamis have not historically caused catastrophic impacts to the Santa Cruz County coast,

Coastal Storm, Erosion, Wave Run-Up & Surge

Coastal storms can cause extensive damage along coastlines, as seen during past events when storm surge and wave attack, combined with high tide conditions, overtopped and undermined shoreline protections like seawalls, jetties, riprap, and breakwater barriers; damaged beachfront homes; and led to rapid erosion and beach retreat. In 2023 Coastal storms pushed a home off its foundation and floated it back onto the street behind the home. In December of 2024, the Santa Cruz Harbor was impacted by a wave run-up and surge event associated with a coastal storm, which caused approximately $11 million in damage to boats

and harbor facilities and also caused a portion of the Santa Cruz Wharf to fall into the Pacific Ocean (Figure 3-49).

Seasonal erosion cycles along the county's coast also cause damage to property and infrastructure, including roads, utilities, and beach facilities. Without appropriate intervention, these annual processes will be exacerbated by climate change-driven sea level rise, as discussed in Section 3.2.10. Roads at the top edge of coastal bluffs are most vulnerable to damage because the rate of retreat of unprotected coastal bluffs is expected to increase in response to increased exposure to storm waves and intense rain events. Roads at low elevations at the back beach and the subsurface infrastructure within the roads are also particularly vulnerable to coastal erosion.

Tsunami

Tsunamis create many risks similar to riverine and coastal flooding and the tsunami and coastal flood inundation areas are similar. However, tsunamis also produce a wave run-up that can be much more extensive than the run-up that occurs with typical coastal storms and flooding. Tsunamis are not like typical ocean waves produced by wind; they do not have a face, do not curl and break, and are full of hazardous debris.

A tsunami can be very dangerous to coastal life and property. These events can produce unusually strong currents, rapidly flood land, and cause great devastation. The flow and force of the water and the debris it carries can cause injuries and deaths; destroy ports and harbors, boats and vehicles, and buildings and other structures; and damage critical infrastructure and disrupt essential services. It only takes six inches of fast-moving water to knock over an adult and two feet of fast-moving water to carry away most vehicles. The water from a tsunami can be just as threatening—if not more so—as it returns to the sea, taking debris and people with it. Flooding and dangerous currents triggered by a tsunami can last for days, and even small tsunamis can pose a risk. Strong currents can injure and drown swimmers and damage and destroy boats in harbors.

The most damaging tsunami on record to hit Santa Cruz County was on March 11, 2011, and cost more than $26 million in damage. The second most damaging tsunami to hit Santa Cruz County occurred on January 15, 2022 and caused more than $15 million in damage. In determining the extent of tsunami damage, an estimate must be made of the extent of the inundation. Current mapping of tsunami run-up areas, as shown in Figure 3-50, is not meant to be measured against parcel level information and therefore is a rough estimate of damage and loss in a worst-case scenario.

3.2.5.8 Warning Time

Many coastal hazards, including storms, acute erosion, and wave run-up and surge, have advance warning of days to over a week. However, tsunamis may only have hours or minutes of warning time, depending on their source.

Coastal Storm, Wave Run-Up & Surge

Similar to severe weather hazards, coastal storms and associated wave run-up, surge, and acute erosion can be predicted by the National Weather Service (NWS) and the National Oceanic and Atmospheric Administration (NOAA) up to 10 days in advance. This can give several days of warning time; however, meteorologists cannot predict the exact time of onset or severity of coastal storms.

The ability to provide early warning for coastal storms in Santa Cruz County depends on monitoring systems, weather radar, and alert services. The region benefits from forecasting tools provided by the NWS, NOAA, and local emergency management agencies, which use a variety of tools to issue timely warnings. These forecasting and warning systems are discussed in more detail in the Severe Weather Hazard Profile (Section 3.2.4).

Santa Cruz County is served by the NWS San Francisco Bay Area/Monterey forecasting office located in Monterey County Radar coverage in Santa Cruz County is primarily provided by an NWS-operated, next generation WSR-88D radar (KMUX) located on Mount Umunhum. In addition, the county operates a high-resolution X-band radar in Live Oak, filling gaps in low-elevation coverage and improving detection of localized heavy rain by providing near real-time rainfall intensity updates. To further close gaps in severe weather prediction, the county integrates several other data sources for warnings, including real-time rainfall and stream gauges. The NWS Monterey office issues alerts for high surf, king tides, and storm surge.

Additionally, there is a buoy network and tidal gauges that can provide warning of wave events. However, nearshore impacts can be hard to predict because of interactions with wave height and period, and nearshore bathymetry and sand movement.

Coastal Erosion

Beyond the coastal erosion that occurs during acute storm and wave events, there are cyclical erosive forces that occur, though imprecise as to location, extent, and severity. There are many factors involved in coastal erosion, including seasonal fluctuations as well as human activity, climate change, and sea level rise; consequently, sand movement is not consistent year after year in the same location.

Beaches change seasonally in response to changes in wave conditions. Wintertime waves typically move significant amounts of sand from the beaches to offshore bars, while summertime wave action return sand. During the winter months when beaches are narrow, or absent altogether, the waves attack the cliffs and bluffs more frequently. However, coastal erosion is worsening as sea levels rise, increasing the extent and severity of wave action on the coastline. As discussed in the Climate Change Hazard Profile (Section 3.2.10), the State of California Sea Level Rise Guidance: 2024 Science and Policy Update provides sea level rise projections. For the Monterey tide gauge there is a high risk of sea level rise of approximately one foot by the year 2050. By the year 2100, the report projects a moderate risk of between 5.5 and 6.9 feet of sea level rise.

Tsunami

Tsunami hazards are highly dependent on the location of the triggering event (i.e., an earthquake). Depending on where the earthquake is epicentered, the National Tsunami Warning Center can issue tsunami watches and announcements minutes to hours in advance of inundation.

There are two primary types of tsunami vulnerability in Santa Cruz County: local-source originating from nearby seismic activity and tele-tsunami (distant-source) from elsewhere in the Pacific Ocean. Both types of tsunami are capable of causing significant destruction in Santa Cruz County, but a tele-tsunami would usually allow time for the Tsunami Warning System for the Pacific Ocean to warn threatened coastal areas in time for evacuation, such as the 2011 Santa Cruz Harbor tsunami that originated from an earthquake in Japan.

The more vulnerable risk to Santa Cruz County is a tsunami generated as the result of an earthquake along one of the many earthquake faults in the region. Even a moderate earthquake could cause a local-source tsunami from submarine landsliding in Monterey Bay, which would arrive just minutes after the initial shock. The lack of warning time from such a nearby event would result in higher causalities than if it were a tele-tsunami. Past experience has not resulted in extensive damage from nearby tsunamis, but proximity to faults does create the possibility as a result of future earthquakes.

CruzAware Notification System

CruzAware is Santa Cruz County's official alert and notification system. It is administered by the County Office of Response, Recovery and Resilience (OR3) and is designed to provide residents and visitors with timely warnings and information during emergencies. Notifications are sent by text message, telephone, or email and address a range of hazards including coastal storms and tsunamis, as well as other public safety threats and evacuation notices.

For coastal hazards, CruzAware serves as a primary tool for delivering warnings before hazardous conditions develop. Depending on the situation, alerts may be issued hours or only minutes in advance. These notifications can include evacuation instructions, shelter locations, sandbag distribution sites, and road closure information. The system is capable of targeting specific neighborhoods or hazard zones so that alerts are relevant to those directly at risk.

For coastal events in particular, the County must balance the urgency of public messaging with the risk of unintentionally attracting visitors to the shoreline during dangerous conditions such as storm surge or large wave events. Messaging strategies therefore also consider seasonal visitor populations, with coordination efforts directed toward hotels, vacation rentals, and other visitor-serving accommodations to ensure non-local populations receive timely and accurate warnings. In addition, WEAs may be used to reach both residents and visitors in affected areas.

The system works in coordination with other county resources, such as the S.A.F.E.R. dashboard and real-time weather monitoring systems, to support comprehensive hazard communication. The county also

partners with the NWS to disseminate official watches and warnings, including coastal flood and marine advisories. More information about CruzAware, including how to register, is available at santacruzcountyca.gov/CruzAware.

3.2.5.9 Coastal Hazards Vulnerability Assessment

The entire Santa Cruz County coastline, from Swanton in the north to Pajaro Dunes in the south, remains at risk from coast hazards despite ongoing efforts to reduce exposure through land use planning, policy measures, and targeted mitigation projects. This section assesses vulnerability by examining the relationship between coastal hazards and the county's population, property, and critical facilities and infrastructure.

Tsunami is the only coastal hazard for which there is a pre-defined geographic extent. Population exposure, parcel values, critical facilities, and lifeline infrastructure were evaluated by overlaying the county's asset inventory, discussed in Section 2.2.2, with tsunami run-up areas. Figure 3-51 summarizes tsunami exposure county-wide. Detailed results for each vulnerability category are provided in the subsections that follow.



Figure 3-51: Exposure Summary - Santa Cruz County Tsunami Run-Up Areas

3.2.5.9.1 Population

The populations at risk from coastal hazards in Santa Cruz County are assumed to be those living, working, and playing along the county's coastline. The exposure to coastal storms, erosion, wave run-up and surge is similar to the exposure to flood hazards discussed in Section 3.2.2, except concentrated along the shore. The total population located within FEMA-designated coastal flood hazard zones is 840, less than 1% of the county's total population (Table 3-19). However, this may not reflect the full extent of vulnerability to storm surge, wave attack, or erosion hazards, in particular, since these coastal hazards do not always align with mapped flood hazard areas and are highly dependent on individual events. Even so, the population exposed to coastal flooding provides a vulnerability baseline.

A larger portion of the county population—over 5% at almost 7,000 people—is exposed to tsunami inundation, demonstrating the potential challenges in evacuating these areas if a local-source event should occur with little or no warning time. Table 3-43 summarizes the population exposed to tsunami risk. Note that these population numbers reflect permanent residents; daytime visitors during peak season would be additive to these population numbers.

Table 3-43: Santa Cruz County Population Exposed to Tsunami Risk

	Total Population
Unincorporated County	131,149

Tsunami Run-up Area	Population Count	% of Total
Within Risk Zone	6,903	*5.26%*

3.2.5.9.2 Property

The parcels at risk from coastal hazards in Santa Cruz County are assumed to be those located along the county's coastline. The exposure to coastal storms, erosion, wave run-up and surge is similar to the exposure to flood hazards discussed in Section 3.2.2, except concentrated along the shore. The number of parcels located within FEMA-designated coastal flood hazard zones is a little less than 700 with a total exposure value of over $641 million (Table 3-20).

From the HAZUS modeling conducted as part of the flood hazard risk assessment, the 100-year coastal flooding scenario indicates that predicted damages vary significantly by building type (Table 3-22 and Figure 3-33). Residential properties represent the largest share of total losses, while commercial, industrial, and institutional buildings account for much smaller portions of overall damages. In total, the model estimates more than $93 million in combined building and content losses for the unincorporated county in a 100-year coastal flood event, underscoring that coastal hazard impacts can be highly concentrated in certain property types.

The actual number of structures subject to coastal erosion would also include structures on coastal cliffs and bluffs outside of the flood hazard zone, but still subject to erosive forces.

About 7% of all county parcels are exposed to tsunami inundation, accounting for almost $3.4 billion in total exposure value. While many properties in the northern areas of the county are exposed to tsunami risk, few are developed. In contrast, there is a significant amount of improved parcels located in the southern half of the county, from the City of Santa Cruz to the Monterey County line, that are at risk of tsunami run-up and damage. Areas of concentrated development along the coast would experience the largest losses, including Pajaro Dunes, Rio del Mar, New Brighton, and Live Oak, as well as the cities of Capitola and Santa Cruz. Table 3-44 summarizes parcels in the unincorporated county that are susceptible to tsunamis.

Table 3-44: Santa Cruz County Parcels Exposed to Tsunami Risk

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

Tsunami Run-up Area	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
Within Risk Zone	3,386	*7.1%*	$2,213,707,596	$1,144,771,398	$3,358,478,994	*6.2%*

3.2.5.9.3 Critical Facilities & Infrastructure

The critical facilities and infrastructure at risk from coastal hazards in Santa Cruz County are assumed to be those located along the county's coastline. The exposure to coastal storms, erosion, wave run-up and surge is similar to the exposure to flood hazards discussed in Section 3.2.2, except concentrated along the shore. The critical facilities and infrastructure located within FEMA-designated coastal flood hazard zones mostly includes parks, roads, and sanitary sewer lines (Table 3-23 and Table 3-24).

As presented in Table 3-23 in the flood hazard vulnerability assessment, there are few critical facilities located in coastal flood hazard zones. A hazardous materials facility and five county-owned parks make up the bulk of the assets exposed to coastal flooding. However, transportation and utility lifeline systems make up a substantial portion of the at-risk county infrastructure along the coastline, with about three miles of roadway, one bridge, and over five miles of sanitation pipe vulnerable to damage or service interruption (Table 3-24). However, the footprint of impacts on these critical facilities and lifelines from coastal storms, erosion, and wave run-up and surge could extend far beyond the boundaries of coastal flood zones, resulting in isolated neighborhoods, delayed emergency response, environmental contamination, and slow recovery.

The exposure of county assets to tsunami run-up is substantial. As presented in Table 3-45, almost 40 miles of roads are exposed to inundation during a major event, complicating evacuation and potentially cutting off heavily impacted areas from emergency services. The potential for wastewater backups, leakages, or other system failures is also high due to over 30 miles of sanitary pipe being within the tsunami risk area. Further, over four miles of levees are exposed to damage from a significant tsunami event, which could trigger additional flooding.

Table 3-46 summarize the critical facilities susceptible to tsunamis, including one fire station, three schools, and three childcare centers. There are also eight large mobile home parks within the tsunami inundation

area. Together, these facilities demonstrate the potential for mass casualties if a major tsunami hit the county from a local or regional source with little or no warning time and underscore the need for a highly coordinated, rapid evacuation plan. Additionally, there are 18 hazardous materials facilities within the risk area that, if damaged, could cause significant environmental harm, hinder emergency response, and complicate recovery.

Table 3-45: Santa Cruz County Critical Infrastructure Exposed to Tsunami Risk

Lifelines (miles) - Tsunami Run-up Area	
Infrastructure Type (Linear)	Within Run-Up Zone
County Maintained Roads*	19.8
Levee	4.3
Maintained Channel	6.1
NG Pipeline	0.7
Railroad	0.4
Sanitation Pipe	31.2
All Roads	38.5
Alley	1.6
Drive	3.0
Major Road	7.7
Ramp	-
Street	21.7
State Highway	1.3
Unnamed	3.3
Transmission Line	0.1
Grand Total	**100.9**

Table 3-46: Santa Cruz County Critical Facilities Exposed to Tsunami Risk

Critical Facility - Tsunami Run-up Area	
Facility Type	Within Risk Zone
Essential Facilities	1
Fire Station	1
Hospital	-
Law Enforcement	-
EOC	-
American Medical Response	-
High-Potential-Loss	44
Adult Care Facility	-
Child Care Center	3
Cell Tower	3

County Real Property Asset	26
Dam	-
Healthcare Facility	-
Historic Building	-
Library	1
Mobile Home Park	8
Power Generation	-
Radio Sites	-
School	3
Transportation and Lifeline	50
Airport	-
Substation	-
NG Station	-
Church	1
Stormwater Culvert	26
Parks	14
Bridge NBI	9
Hazmat	18
HWTS Active Facility	18
Geotracker CleanupSite	-
Grand Total	**113**

**Real Property Assets are digitized insurance rolls for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.*

3.2.5.10 Development Trends

Every coastal community in California is dealing with the issues of coastal hazards compounded by sea level rise, and how this affects and is affected by development and redevelopment along the coast becoming increasingly controversial and contentious. Since seawalls now protect so much of the developed portion of Santa Cruz County coastline, the controversy centers on improving these walls and on their impacts. These issues will be addressed in the updated LCP.

Santa Cruz County's shoreline is located on Monterey Bay, which will also influence development trends along the Santa Cruz coast. The majority of undeveloped areas along the coastline are farmland or other areas currently protected from development and, along the north coast of Santa Cruz County, regulations have limited development and structures have been constructed in very limited locations. Further, the county's growth management policies prevent development from occurring where hazards are present and, in most cases, require substantial setbacks from these hazards. This is especially true under the constraints imposed by local and state coastal development regulations. Development on existing lots of record is required to avoid hazards and incorporate appropriate setbacks, structural elevation, floodproofing, erosion control, and other requirements to mitigate potential impacts from coastal hazards.

New development within coastal flood hazard areas, which somewhat overlap with the impact areas of coastal hazards, is subject to strict regulations. No new development is allowed within the 100-year floodway, and all new or substantially improved structures within Special Flood Hazard Areas (SFHA) must be elevated or floodproofed, as dictated by FEMA guidelines and regulations. Although FEMA floodplain development regulations may protect against coastal flooding from storms, wave run-up and surge, these standards are inadequate for protection against tsunamis since these phenomena have a different direction of force and energy and can inundate areas that are not affected by riverine or coastal flooding.

The current trend in development along the coastline in Santa Cruz County is in-fill within already developed areas and reconstruction of existing structures and infrastructure. No changes in these development regulations or patterns occurred that would affect the county's overall vulnerability since the 2021 HMP.

Coastal Erosion

Coastal erosion poses many problems to coastal communities in that valuable property is frequently lost to this dynamic beach-ocean system. Additionally, human activity may modify the process of coastal erosion with uncertain results.

Much of the Santa Cruz County coastline, particularly in the developed areas, has some level of coastal armoring, such as seawalls, jetties, and riprap. The majority of the protection structures were installed within the last 40 years and have varying levels of adequacy and performance. While these protection structures help protect buildings and infrastructure during coastal storms and wave attack, they are still vulnerable to failure during larger storm events and may not provide full protection. Riprap structures along the coastline are particularly vulnerable to failure and require more maintenance and upgrading over time than concrete seawalls.

The area from the Santa Cruz Harbor to Pleasure Point contains numerous homes on the coastal bluff as well as roads and other infrastructure, particularly near the coastal lagoons, that are vulnerable to coastal erosion. There are also several sea caves that may affect the integrity of homes and infrastructure in this area as well. The primary type of coastal armoring here is riprap. It is not uncommon for East Cliff Drive to be closed or damaged where it crosses Schwann Lake, Corcoran Lagoon, and Moran Lake during winter, coastal storms.

The area from Pleasure Point to Opal Cliffs also contains numerous homes on the costal bluff as well as roads and other infrastructure that are vulnerable to coastal erosion. The coastal armoring in this area is a combination of riprap and concrete seawalls. A seawall was constructed in 2009 in the Pleasure Point area along East Cliff Drive that should greatly reduce potential damage from coastal erosion to the roadway as well as the homes on the landward side.

The area south of New Brighton Beach to the southern Santa Cruz County line contains numerous homes on the bluffs, at the base of the bluffs, on the beach. There is also critical infrastructure on the beach and

bluffs that may be affected by coastal erosion, including county roads. Many of the homes along and above both Las Olas Drive and Beach Drive will experience the continuing effects of coastal erosion. There are also several other communities, including Seascape, La Selva Beach, Sunset Beach and Pajaro Dunes, that are vulnerable to coastal erosion.

Many of the homes that exist along the coast in these areas, although somewhat protected, may be subject to further coastal erosion as sea levels rise, earthquakes occur, and waves and rainfall impact the shoreline. The county's Geologic Hazards Ordinance requires development on coastal bluffs and beaches to be reviewed by the County Geologist. The ordinance also requires development to be setback at least 25 feet from the top of a coastal bluff, or the distance required to provide 100-year stability, whichever is greater. Shoreline protection structures are subject to the ordinance and review by the County Geologist. Most current seawall permits are for maintenance and improvement of existing walls, which allows the county to require modifications that reduce the walls' impacts.

Although seawalls reduce or delay coastal erosion processes as long as they remain functioning, ultimately coastal erosion continues, and the best seawalls need maintenance. While seawalls remain in place, they modify coastal erosion through the reduction of wave erosion energy, or reflection or refraction of wave energy. Focused erosion can occur at the ends of the seawalls. While seawalls are helpful in protecting against coastal erosion, proper setbacks from the brow of bluffs, drainage control, and special construction are all necessary to protect structures, roadways, and utilities from damage.

Modern seawall construction, such as the structures constructed in 2009 in the Pleasure Point area, can also be designed to improve coastal access by incorporating stairways and viewing platforms, and removal of debris from previous attempts at coastal protection that block lateral access along the shoreline.

3.2.5.11 Coastal Hazards Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing coastal hazard-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with coastal hazards. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-47 presents the coastal hazards problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in Table 4-1 and Table 4-2

Table 3-47: Santa Cruz County Coastal Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Coastal Erosion	Threat	**ps-CE-SCC-01**	Accelerated coastal bluff retreat is threatening the long-term stability of transportation routes, low-lying / underground storm drainage and wastewater infrastructure, and public coastal access points.
Coastal Hazards	Victim	**ps-CH-SCC-01**	Coastal hazards disproportionately impact lower-income residents, including reducing access to low-cost recreational opportunities along the coastline as a result of sea level rise combined with coastal erosion and armoring removing beaches.
Coastal Hazards	Threat	**ps-CH-SCC-02**	Residential and commercial properties along the County's urban coastline face increasing coastal flooding and erosion risks from seasonal storms and high tides, especially older structures with no elevation, floodproofing, or relocation strategy.
Coastal Storm	Impact	**ps-CS-SCC-01**	Severe coastal storms can produce hazardous surf, flooding, and debris flows onto roadways and public spaces, posing direct risks to public safety, including unsuspecting year-round visitors engaged in coastal recreation, and limiting emergency access.
Coastal Storm	Impact	**ps-CS-SCC-02**	Increasingly intense coastal storms are causing more frequent flooding and wave damage to public infrastructure, private property, and coastal businesses, leading to higher repair costs and lost economic activity during peak visitor seasons.
Tsunami	Impact	**ps-TS-SCC-01**	A major tsunami could damage or destroy coastal infrastructure, including ports, roads, utilities, and public facilities, causing long-term disruption to transportation, commerce, and essential services.
Tsunami	Threat	**ps-TS-SCC-02**	A tsunami could require rapid, large-scale evacuation of residents and visitors from low-lying coastal areas, where limited routes and high seasonal population density may hinder timely clearance.

3.2.5.12 Climate Change Impacts & Vulnerable Populations

Santa Cruz County's coastline faces increasing risks from coastal erosion, sea level rise, coastal storms, and tsunamis. Climate change is accelerating bluff retreat, increasing storm surge intensity, and raising baseline sea levels, all of which compound risks to people, property, infrastructure, and ecosystems. These hazards threaten both immediate safety and long-term resilience, with disproportionate impacts on vulnerable populations who rely on coastal resources for housing, recreation, and livelihood.

Direct Impacts: Accelerated bluff erosion undermines transportation routes, storm drainage systems, and wastewater infrastructure, while also threatening public coastal access points. Severe coastal storms bring flooding, hazardous surf, and debris flows onto roadways, disrupting emergency access and creating safety risks for both residents and visitors. Residential and commercial properties along the urbanized coastline, particularly older buildings lacking floodproofing or elevation, are at increasing risk from seasonal storms, high tides, and erosion. Tsunami events, though infrequent, could cause catastrophic damage to ports, utilities, and transportation networks, disrupting commerce and essential services for months or years.

Secondary Hazards: Coastal armoring intended to protect infrastructure often accelerates beach loss, leading to coastal squeeze where natural shorelines are reduced or eliminated. Rising seas increase the

likelihood of compound flooding when high tides coincide with riverine flooding or storm surge, magnifying inundation depths and damages. Erosion of dunes, bluffs, and wetlands also reduces natural buffering capacity, further exposing inland areas to future hazard events.

Public Health and Social Impacts: Coastal hazards disproportionately impact lower-income residents and vulnerable populations. Loss of beaches and coastal access points reduces affordable recreational opportunities, particularly for households without means to travel outside the region. Coastal flooding places renters and residents of older housing stock at elevated risk of displacement, as many lack flood insurance or resources to rebuild. Tourists and seasonal visitors, who may be unfamiliar with evacuation routes, face increased danger during coastal storms and tsunami events. For seniors, people with disabilities, and limited-English residents in low-lying areas, evacuation during fast-moving events remains a significant challenge.

The mitigation strategy addresses these issues by advancing coordinated shoreline management, strengthening natural and built coastal defenses, and enhancing evacuation planning for vulnerable coastal populations. Integrating climate projections with equity focused outreach and infrastructure investment is essential to sustaining community resilience along the Santa Cruz County coastline.

PAGE INTENTIONALLY BLANK

Slope Failure

3.2.6 Slope Failure Hazard Profile

Slope failure is a general term that describes a wide variety of mass downslope movements of soil and rock in response to gravity, including many types of landslide. Slope failures occur in a variety of ways, as falls, topples, slides, spreads, flows, and a combination of these categories, and may change from one form of failure to another during their movement. Factors that contribute to slope failures include the soil and rock strengths, orientation and steepness of elements on the slope, weathering and erosion, moisture content, recent fire activity, and human activities such as the removal of vegetation and inappropriate grading. Slope failures are a worldwide hazard, but Santa Cruz County's unique geologic conditions make large portions of the planning area particularly susceptible to many forms of slope failure. Factors that contribute to the county's slope failure susceptibility include:

- Local climatology and weather patterns that include wet winters and coastal storms;
- Terrain, geology, and weather patterns that cause significant erosion;
- High seismicity in the region;
- Wildfire susceptibility in the mountainous areas and burn scars on steep terrain; and
- Human activities such as vegetation removal and grading in areas of slope instability.

Slope failures can also be caused by land or aging stormwater infrastructure, particularly in the county's mountain, canyon, and coastal regions. In areas burned by forest and brush fires, a lower threshold of precipitation will initiate failures. The deterioration of old timber harvest roads may also result in concentration of drainage that induces slope failure.

Although they can sometimes present a threat to human life, slope failures often result in a disruption of everyday services, including emergency response capabilities, blocking transportation routes, and impacting water supplies. When slope failure hazards affect transportation routes, which is one of the most common impacts, they are frequently expensive to clean up and can have significant economic consequences to the county. In 2023 a slope failure incident, closed State Route 9 for months requiring diverting traffic onto local road network, significantly impacting residents, commerce, and emergency services response times.

3.2.6.1 Compounding Hazards

There are some hazards that can trigger or exacerbate slope failure; namely, wildfire and flooding. These compounding hazards are briefly discussed in this section in relation to slope failure and detailed in their respective profiles, in Sections 3.2.1 and 3.2.2. Further, both wildfire and flood hazards are exacerbated by climate change (Section 3.2.10); consequently, slope failure is also compounded by climate change to this extent.

Heavy Rain & Flooding

Heavy rain and associated flood events can lead to landslides, mudslides, debris flows, and other types of slope failure, particularly in steep mountain watersheds where saturated soils lose cohesion and fail, as well as stormwater infrastructure exceeding capacity or culverts failing. Flood events can undercut the toe of a slope which can remove the support for the slope and cause a landslide or rockfall. Heavy rain events are common from November to April in Santa Cruz County. These heavy rainstorms, often associated with an "atmospheric river" event, can deliver over one inch of rain per hour for extended time frames and trigger flash floods in the county's steep, mountainous terrain. Atmospheric rivers are discussed in detail in the Severe Weather Profile (Section 3.2.4).

Wildfires

Wildfires can create short-term and long-term impacts on landscapes by altering the soil structure, impeding its ability to absorb moisture, and destroying vegetation that binds the soil with roots and absorbs rainfall and runoff. Post-wildfire, even small rain events can create devastating mudflows, debris flows, and landslides. Areas that are currently mapped as low to moderate risk of slope failure may have elevated risk following a wildfire.

Coastal Hazards & Erosion

Coastal hazards, including coastal storms and wave run-up and surge, along with the cyclical forces of wind and water lead to erosion and slope failures. Erosion is the wearing away of coastal land from forces such as wave action, wind, and rain, causing the horizontal retreat of the shoreline along the ocean. In Santa Cruz County, these coastal hazards contribute to the failure of the coastline's steep sea bluffs and cliffs.

Erosion rates are not uniform and vary over time at any single location. Annual variations are the result of seasonal changes in wave action and water levels. Erosion is caused by coastal storms and flood events, changes in the geometry of tidal inlets and bays, and human activities such as development and dredging. Coastal erosion includes cliff, bluff, and beach erosion and is a result of both normal, constant wave action and intense wintertime wave attack associated with coastal storms.

Beaches change seasonally in response to changes in wave conditions. Winter storm waves are larger and contain more energy, capable of moving significant amounts of sand from beaches to offshore bars. Although lower, less energetic waves return sand during the summer, the beaches are narrow and sometimes absent altogether during the winter months when storm waves attack the cliffs and bluffs more frequently, leading to slope failure. Wave attack during periods of high tides or otherwise elevated sea level (e.g. El Niño or storm surge) is one of the most common mechanisms of episodic bluff and cliff failure.

3.2.6.2 Types of Slope Failure

FEMA NRI ranked Santa Cruz County as the most landslide-prone county in the state in terms of hazard exposure. Local geology (i.e., geologically young coastal mountains with high annual precipitation) as well

as significant development within areas with slopes (e.g., the Santa Cruz Mountains) are the two primary factors for why Santa Cruz County is highly susceptible to slope failure.

In Santa Cruz County, there are three primary types of slope failure that pose significant threats to people, property, and critical facilities and infrastructure. Landslide and debris flow were identified as the main slope failure concerns in Santa Cruz County and are briefly described in this section.

It is important to note that bluff failure, while discussed as a type of slope failure in this profile, is intimately related with coastal hazards and coastal erosion, in particular; thus, it is discussed in additional detail in the Coastal Hazards Profile (Section 3.2.5).

Landslide

Landslides are the downward and outward movement of slopes composed of natural rock, soils, artificial fills, or combinations thereof and are classified into many different types based on the nature of the slope materials, type of movement, and speed of the failure. They range from slow-moving rotational slumps and earth flows, which can slowly distress structures but are less threatening to personal safety, to fast-moving rockfalls and debris flows that are a serious threat to structures and have been responsible for the most slope failure-related fatalities. Many large landslides are complex and a combination of more than one landslide type (Figure 3-52). (CalOES, 2018)

Debris Flow

According to NOAA, debris flows—also known as mudslides, mudflows, or debris avalanches—are the most common type of slope failure in Santa Cruz County. These fast-moving landslides occur when slope material becomes saturated with water. As such, they typically occur during or after intense rainfall.

Debris flows originate on steep hillsides as liquefied, shallow flows that become concentrated in steep canyons. They can accelerate from approximately 10 miles per hour to over 35 miles per hour and carry a variety of materials such as boulders, trees, and even vehicles. Debris flows vary in consistency from watery mud to thick, rocky mud with entrained debris, and can severely damage road surfaces and structures. As debris flows converge from adjacent channels, they accumulate more materials and muddy water, thus increasing in destructive force. From a geologic perspective, there are generally two types of debris flows.

- **Shallow Landslide Debris Flows:** These debris flows occur due to soil failure from oversaturation, causing the soil to liquify and run downhill. This type of debris flow generally results from a shallow landslide (less than 15 feet deep) and has a discrete initiation zone depositional area. Shallow landslides tend to occur in winter but are most likely after prolonged periods of heavy rainfall when soil materials are saturated.
- **Post-Wildfire Debris Flows:** This type of debris flow is a result of post-wildfire conditions, where burned and baked soil surfaces increase rainfall runoff that concentrates in a channel and picks up debris as it moves. Under extreme wildfire conditions, soils can be damaged to the point of becoming hydrophobic,

preventing water absorption or infiltration over large areas where the fire was most intense, such as steep hillsides and drainages with dense vegetation. Post-wildfire debris flows have a less discrete initiation zone but are otherwise similar in form to a debris flow derived from hillslopes.

An example of a catastrophic post-fire debris flow is the event that occurred in Santa Barbara County on January 9, 2018, when, after the Thomas Fire, numerous canyons deposited debris flows onto urbanized alluvial fans in Montecito and Carpinteria with little warning time resulting in significant fatalities. (CalOES, 2018)

Bluff Failure

Coastal bluff failure results from both marine and terrestrial processes. Marine forces such as wave action and coastal storms drive much of the erosion, while terrestrial forces—including rainfall, runoff, weathering, and earthquakes—are also contributing factors, though less recognized. Wave attack during periods of high tide or elevated sea level (e.g., during storm surge) is one of the most common triggers of episodic bluff and cliff failure. Climate patterns such as El Niño can intensify these drivers by increasing storm frequency, wave height, rainfall, and temporary sea level rise.

Figure 3-52: Landslide on Highway 9 Triggered by Heavy Rain in February 2023

Source: Santa Cruz County

A more extensive description of bluff failure and the coastal hazards that contribute to it can be found in Section 3.2.5, Coastal Hazards Profile, including discussions of the regulatory environment, past events, locations, frequency and probability, and severity, as well as an assessment of bluff failure vulnerabilities.

Bank Failure

Bank failure refers to the collapse or erosion of a stream or riverbank caused by hydraulic forces, geologic instability, or loss of vegetative cover. Failures can occur gradually through chronic undercutting and slumping, or suddenly during high-flow events when saturated soils give way. This hazard specifically includes stream bank failure, which is of particular concern in Santa Cruz County where many homes, businesses, and roads were developed prior to modern setback requirements. Development constructed close to streams, as well as roadways built directly along stream corridors, are especially vulnerable to erosion and failure, with numerous examples distributed throughout the county.

3.2.6.3 Policies, Plans & Regulatory Environment

Santa Cruz County General Plan

The Santa Cruz County General Plan sets forth objectives and policies relevant to slope failure in the Public Safety and Built Environment Elements, including to site and design development with the environment (Objective BE-4.2), and to reduce hazards and property damage caused by landslides and other ground movements affecting land use activities in areas of unstable geologic formations, potentially unstable slopes, and coastal bluff retreat (Objective 6.2). To meet these objectives, the General Plan includes the following key policies:

- **BE-4.2.2 Site Design for Environmental Protection:** Requires the siting and design of new development to minimize grading, avoid or provide mitigation for geologic hazards, conform to the physical constraints and topography of the site, and maintain natural drainage patterns.
- **Policy 6.2.1 Geologic Hazards Assessments for Slope Development:** Requires a geologic hazards assessment of all development, including grading permits, that is potentially affected by slope instability.
- **Policy 6.2.6 Location of Structures and Drainage Considerations in Unstable Areas:** Requires the location and clustering of structures away from potentially unstable slopes whenever feasible, and requires drainage plans that direct runoff away from unstable slopes.
- **Policies 6.2.12, 6.2.17, 6.2.20, and 6.4.3 Concerning Development on Coastal Bluffs:** These policies include requirements for coastal bluff setbacks and geologic hazard review, as well as limitations on the reconstruction of substantially damaged buildings and creation of new parcels in coastal hazard areas. These policies are discussed in more detail in the Coastal Hazards Profile (Section 3.2.5).

Santa Cruz County Code Title 16

Sana Cruz County Code Title 16, in combination with the California Building Standards Code adopted under Title 12, regulates geologic hazards including slope failure, both within and outside of coastal hazard areas,

as well as grading and erosion control. The title implements the policies of the General Plan relevant to geologic hazards, including requirements for geologic and geotechnical assessments to identify slope failure hazards and appropriate mitigation measures, limitations on reconstruction of substantially damaged structures and the creation of new parcels, adjustments to allowed density in high-hazard areas, and siting and design requirements for new development. Slope failures may be triggered not only by intense rainfall and erosion but also by earthquake ground shaking, which can destabilize steep hillsides and stream banks, further underscoring the need for design standards.

3.2.6.4 Past Events

Slope failures are a common occurrence in the Santa Cruz Mountains. The intense winter storms that often bring high rainfall amounts, especially during El Niño weather patterns, and steep terrain are conducive to landsliding. Earthquake activity also contributes to this hazard, as illustrated by the 1906 earthquake which set off dozens of large landslides in the mountains, some of which claimed human lives.

Most recent landslides in the Santa Cruz Mountains have been caused by a combination of human activity and natural factors. Human activities that can further destabilize slopes include old timber harvest roads and skid trails, conversion of land from forest to residential and agricultural uses, road building, grading and other construction, and any activity that alters normal drainage patterns or concentrates runoff. The likelihood that any of these factors will contribute to slope failure is dependent upon the existing conditions and also on the care with which activities are conducted in these locations.

Several periods of increased slope failure have occurred in Santa Cruz County in recent history. Some of the better-documented events include:

- **Mount Hermon Landslide:** The Mountain Hermon landslide moved in the late 1950s after the El Niño year of 1957 to 1958. This slope failure occurred in an area of suspected older landsliding and the new movement extended from the Kaiser Quarry to the bottom of Bean Creek, blocking Conference Drive and spurring the construction of the Mount Hermon bypass. At the time of the event, there was some concern that the quarry (and a small earthquake) may have contributed to the re-initiation of the older landslide.
- **Deadly 1982 Landslides and Debris Flows:** Severe storms in the winter of 1982 caused multiple slope failures throughout the Bay Area and especially in the Santa Cruz Mountains. One very large composite landslide along Love Creek, west of Loch Lomond Reservoir, killed ten people. This landslide was and continues to be an indicator of the potential severity of slope failure activity and the need for observation and mitigation. Other slope failures that occurred as a result of the winter storms that year included debris flows and destroyed 135 homes, damaged 300 homes, and killed five more people. In addition to damage to homes, widespread landslide damage occurred to roadways, driveways, and stream channels.
- **Loma Prieta Earthquake Landslides:** Landslides occurred throughout Santa Cruz County during and after the Loma Prieta earthquake on October 17, 1989. Most of the larger landslides moved only during the actual shaking, but others continue to creep even today. Smaller landslides were also triggered by the shaking along coastal bluffs and ridge tops.

- **El Niño Slope Failures of 1986, 1998, and 2005:** Severe winter storms formed during El Niño patterns in the years of 1986, 1998, and 2005 caused multiple slope failures, particularly debris flows, throughout the Santa Cruz Mountains. During the 1998 winter storms, many homes were affected by slope failures and several roadways were damaged including Highway 9, Branciforte Road, and Amesti Road. Winter rains also induced landsliding within the quarries throughout the county.
- **2017 Debris Flows:** In Winter 2017, 26 debris flow events were reported throughout Santa Cruz County. These events coincided with multiple atmospheric river events and resulted in road closures, both short-term and long-term.
- **2021 CZU Burn Scar Debris Flows:** In January and October of 2021, following the devastating CZU Lightening Complex Fire the previous August that burned more than 85,000 acres across Santa Cruz and San Mateo Counties (Figure 3-53), atmospheric river events delivered parades of severe storms and heavy rain to the burn scar area. In anticipation of both events, many mountain communities on the North Coast and in the San Lorenzo Valley areas of the county were ordered to evacuate. Although very few debris flows occurred in the county as a result of these events, some areas in the Santa Cruz Mountains picked up more than six inches of rain and damaging slope failures were triggered in neighboring counties.
- **2022-2023 Landslides:** Between December 27, 2022, and January 31, 2023, numerous landslides occurred in Santa Cruz County as a result of multiple atmospheric rivers. Prolonged and intense rainfall saturated soils across steep terrain, leading to widespread slope failures that blocked major transportation routes, damaged homes, and threatened utilities. Roadways in the Santa Cruz Mountains were particularly hard hit, with Highway 9, Soquel San Jose Road, and numerous local roads closed for extended periods due to slides and debris flows. These events underscored the county's high vulnerability to rainfall-induced slope failures during sequential storm systems.
- **2024 Mountain Charlie Road Landslide:** On February 26, 2024, the county became aware of a deep-seated landslide on Mountain Charlie Road in northern Santa Cruz County. The slide impacted dozens of households served by the road and was active for months, moving one foot per week on average during its peak, before the county was able to construct a temporary alternative access route.

Figure 3-53: Potential Debris Flow Area in CZU Lightening Complex Fire Burn Scar

Source: Santa Cruz County

3.2.6.5 Location

The best available predictor of where movement of slides and earth flows might occur is the location of past movements. Past slope failures can be recognized by their distinctive topographic shapes, which can remain in place for thousands of years. Most landslides recognizable in this fashion range from a few acres to several square miles, show no evidence of recent movement, and are not currently active. A small proportion of them may become active in any given year, with movements concentrated within all or part of the landslide masses or around their edges.

Recognizing ancient dormant mass movement sites is important to identify current areas susceptible to flows and slides, because they can be reactivated by earthquakes or exceptionally wet weather. Those ancient scars also consist of broken materials, frequently involve disruption of groundwater flow, and are vulnerable to construction-triggered sliding.

Slope failures occur throughout Santa Cruz County but are centered primarily along the steeper slopes in the hills and mountains, along stream corridors, and along coastal bluffs and inlets. Large areas of the county are subject to slope failure, as indicated in Figure 3-54, but isolated failures occur throughout the county. The locations and types of slope failures that occur in Santa Cruz can be summarized as follows:

- Coastal bluffs along the coastline experience shallow landslides, debris flows, and topples (locations prone to bluff failure are identified in the Coastal Hazards Profile, Section 3.2.5)
- Rivers and streams throughout the county experience shallow and rotational landslides and lateral spreading
- Steep slopes and drainages in the Santa Cruz Mountains experience large, deep composite landslides and debris flows

Figure 3-54 shows low, moderate, and high landslide susceptibility in Santa Cruz County from the California Geological Survey (CGS), and Table 3-48 describes these classifications. Most of the high susceptibility areas are in the Santa Cruz Mountains. However, this map should be used with caution, as site-specific conditions can make some locations in low to moderate instability areas highly unstable and some high instability locations more stable with the use of appropriate mitigation measures. Geologic or geotechnical investigation is often required to determine the stability of a given site.

Table 3-48: Slope Failure Susceptibility Classifications

Susceptibility	Native Class	Description
Low	**1-5**	These classes express the generalization that on very low slopes, landslide susceptibility is low even in weak materials, and that landslide susceptibility increases with slope and in weaker rocks.
Medium	**6-7**	Very high landslide susceptibility, classes VIII, IX, and X, includes moderate and steep slopes in hard rocks and weak rocks.
High	**8-10**	Very high landslide susceptibility, classes VIII, IX, and X, includes very steep slopes in hard rocks and moderate to very steep slopes in weak rocks.

Source: CGS Susceptibility to Deep-Seated Landslides in California



Figure 3-54: Santa Cruz County Slope Failure Risk

3.2.6.6 Frequency & Probability of Future Occurrences

Measuring the frequency and probability of slope failure hazards requires a combination of historical data analysis, geologic mapping, climate trends, and probabilistic modeling, as these hazards are influenced by factors such as precipitation, seismic activity, topography, and human development. To assess hazard frequency, researchers examine past events recorded in geological surveys, historical documents, and remote sensing data. For example, slope failure occurrences in Santa Cruz County are often linked to intense rainfall, and analyzing past precipitation patterns and climate change models helps estimate future probabilities. Probabilistic models, such as landslide susceptibility mapping, incorporate variables like slope gradient, soil composition, and vegetation cover to predict the likelihood of future events.

Slope failures are most frequently triggered in periods of high rainfall during the winter months, November to April, in Sana Cruz County. The hazard is greatest in steeply sloped areas, although slides may occur on slopes of 15% or less if the conditions are right. Slope steepness and underlying soils are the most important factors affecting the landslide hazard. However, surface and subsurface drainage patterns also affect the hazard, and vegetation removal can increase the likelihood of slope failure. Human activities contribute to instability through grading of steep slopes, overloading with artificial fill, extensive irrigation, construction of impermeable surfaces, and excessive groundwater withdrawal. (USGS, 2020)

As discussed in Section 3.2.6.1, other natural hazards such as earthquakes, heavy rain, flood, or wildfire, can also trigger slope failures or compound their impacts. As such, slope failure frequency is often related to the frequency of these other hazards. Seismic hazards, including fault movements and ground shaking, are assessed using data from the USGS and other monitoring networks. The probability of debris flows is often measured through field assessments and computer simulations that consider factors such as freeze-thaw cycles, extreme weather events, and wildfire burn scars, like the CZU Lightening Complex Fire, which has increased erosion and debris flow risks in affected areas.

Slope failures will continue to affect the county, especially during El Niño weather patterns and atmospheric river events. El Niño weather patterns will continue approximately every seven years, and the San Andreas Fault, as well as other faults, will generate earthquakes, which will contribute to the formation of landslides. The probability of slope failure occurring in Santa Cruz County is likely (between 10% and 100% annual probability). Failure is more likely in areas that have recently experienced flooding or wildfires, but it can occur on any susceptible terrain given the right conditions—such as “ideal” underlying geology, steeper slopes, and saturation. Areas with unstable conditions, like over-steepened slopes, may regularly experience debris flows during heavy rainfall. Additionally, decadal variance and climate change driving increase in frequency and intensity of heavy rain events as well as changes in vegetation composition and wildfire, which could impact slope stability in unpredictable ways.

3.2.6.7 Severity

Slope failures, including landslides, debris flows, and bluff failures, pose significant hazards in Santa Cruz County, often disrupting essential services and emergency response capabilities. The severity of slope

failure hazards depends on local geologic and soil conditions, including moisture content, slope, and vegetation cover.

The primary impacts from slope movement are on roads and any underlying or aboveground utilities including water and sewer infrastructure. While landslides occasionally threaten human life, their more common impact lies in blocking transportation routes, damaging buildings and infrastructure, damming creeks, and contaminating water supplies. The cleanup of these hazards on transportation routes can be costly and have substantial economic repercussions for the county. In coastal areas, transportation and utility infrastructure located at the top edge of coastal bluffs are highly vulnerable to damage because the rate of erosion and bluff retreat in unprotected areas, which is expected to increase in response to increased exposure to storm waves and intense rain events.

A significant amount of linear infrastructure (or lifelines) are exposed to slope failure, as further discussed in the vulnerability assessment section. Impacts to these lifelines can include:

- **Roads:** Access to major roads is crucial to life-safety, response, and recovery operations after a disaster event. Landslides can block egress and ingress on roads, causing isolation for neighborhoods, traffic problems, and delays for public and private transportation. This can also result in economic losses for businesses.
- **Bridges:** Landslides can significantly impact bridges, by knocking out bridge abutments or weakening the soil supporting them. Debris flows can also clog drainages at choke points such as bridges with downed trees, boulders, and other materials picked up along their path, triggering additional flooding impacts.
- **Power Lines:** Power lines are generally elevated above steep slopes, but the towers and poles supporting them can be subject to landslides. A landslide could trigger failure of the soil underneath support structures, causing them to collapse and rip down the lines. Power and communication failures due to landslides can create problems for first responders, vulnerable populations, and businesses.

3.2.6.8 Warning Time

Some slope failure hazards occur slowly, including creeping slides and bluff erosion, but can have significant property or health consequences. Identifying these hazards generally requires site-specific analysis to determine if the site's soil and geology are susceptible to failure and to identify the most relevant and prudent mitigation measures. For these types of slope failure hazards, warning time is long.

However, for other types of slope failure, such as sudden and fast-moving debris flows, warning time is often very short. Identifying areas with known hazards (i.e., where past events have occurred) or with characteristics conducive to these hazards can help with preparedness when triggering events like prolonged or intense rainfall occur. Post-fire debris flow mapping is one of the primary ways in which Santa Cruz County has worked to identify potential hazard areas for proactive mitigation and evacuation ahead compounding events like atmospheric rivers. While this identification does not increase the warning time

for an actual failure event, it does enhance proactive responses to potential triggers, save lives, and help prevent damage. (Manconi, 2016)

3.2.6.9 Slope Failure Vulnerability Assessment

Past experience has shown that many areas of the county are susceptible to the effects of slope failures. Most of the damage caused by landslides has been to privately-owned structures; although, a fair number of county roads are also at risk. Santa Cruz County's underlying seismic activity and diverse topography, which includes mountainous terrain, deep canyons, and steep coastal bluffs, makes certain communities and infrastructure particularly vulnerable to slope failure hazards. The exposure of both population and assets to these hazards depends on factors such as development patterns, land use, and the presence of critical facilities and infrastructure in high-risk areas. The 2025 Santa Cruz County Climate Adaptation and Vulnerability Assessment provides additional slope failure vulnerability assessment.

Figure 3-55 displays slope failure susceptibility for Santa Cruz County. Most of the unincorporated county is susceptible to landslides.



Figure 3-55: Exposure Summary - Santa Cruz County Slope Failure Risk

3.2.6.9.1 Population

Almost three-quarters of the county's total population is exposed to some degree of slope failure risk, as demonstrated in Figure 3-56 and Table 3-49. Of that, over 80,000 people are located in moderate to high risk areas, and another 15,000 are located in low risk areas.

Although the county's population is concentrated in urban centers like Santa Cruz and Watsonville, where slope failure susceptibility is lower, there are numerous smaller towns and rural communities situated in mountainous or coastal areas exposed to slope failure risk. Homes located near steep slopes or within wildfire burn scars, such as those from the CZU Lightening Complex Fire, face an increased risk of landslides and debris flows, and remote areas with limited evacuation routes may experience higher vulnerability, particularly in cases of sudden slope failures triggered by heavy rainfall or earthquake.



Figure 3-56 Santa Cruz County Population Exposed to Slope Failure Risk

Table 3-49: Santa Cruz County Population Exposed to Slope Failure Risk

	Total Population
Unincorporated County	131,149

Landslide Susceptibility	Population Count	% of Total
High	46,480	*35.44%*
Moderate	35,367	*26.97%*
Low	15,209	*11.60%*
Total	**97,056**	**74.00%**

3.2.6.9.2 Property

Property vulnerability to slope failure is influenced by factors such as location, construction materials, soil stability, and proximity to steep slopes or waterways. These hazards, including landslides and debris flows, can cause significant structural damage to homes and businesses, particularly in areas with high erosion or unstable terrain such as wildfire burn scars and coastal areas.

Buildings constructed on steep slopes or near fault lines are at high risk of structural failure due to ground movement. Landslides can undermine foundations, collapse retaining walls, and shift entire structures downslope, leading to costly repairs or total loss. Debris flows, especially in burn scar areas, pose a major threat to properties by burying structures under mud and rock or washing away roads and bridges.

Table 3-50 shows the number of parcels and value exposure in the slope failure risk areas of Santa Cruz County. Over 75% of parcels in the unincorporated county are exposed, totaling $41 billion in assessed building and content value. A wide range of land uses are located in landslide hazard areas, but 90% of the structures are residential. Homes built before 1989 (approx. 80% countywide) are particularly vulnerable to landslides, as some of these were constructed without the benefit of engineering or geologic investigations.

Table 3-50: Santa Cruz County Parcels Exposed to Slope Failure Risk

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

Landslide Susceptibility	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
High	13,621	*28.6%*	$10,480,677,999	$5,339,785,600	$15,820,463,599	*29.1%*
Moderate	14,990	*31.5%*	$11,152,453,196	$5,966,777,598	$17,119,230,794	*31.5%*
Low	7,507	*15.8%*	$5,251,975,198	$2,745,185,399	$7,997,160,597	*14.7%*
Total	**36,118**	**75.8%**	**$26,885,106,393**	**$14,051,748,597**	**$40,936,854,991**	**75.4%**

3.2.6.9.3 Critical Facilities & Infrastructure

Numerous critical county facilities and many miles of county infrastructure are located in areas that are exposed to slope failure risk.

Critical infrastructure, including highways, bridges, water supply systems, and utility networks, is at the highest risk from slope failure hazards. Key transportation corridors such as Highways 9 and 17, which traverse the Santa Cruz Mountains, are particularly susceptible to landslides, leading to periodic closures and increased maintenance costs. Scenic Highway 1 that runs along the Pacific Coast is also prone to closures from landslides and bluff failures.

Most of the roadways in the county were constructed many years ago with little consideration to slope stability and, in high-risk areas, are likely be affected by slope failures at some point in the future. Because

utilities follow these roads, damage to roads often disrupts sanitary sewers and water systems, gas and electricity transmission, and cable and telephone utilities. Slope failures can sever transportation routes, limiting emergency response and isolating communities, and water and sewer lines built on unstable ground may rupture, leading to service interruptions and environmental contamination. Power lines and communication networks are also at risk, increasing the likelihood of prolonged outages following a major event. These hazards pose significant risks to public safety, economic stability, and emergency response capabilities, particularly in unstable coastal, mountainous, and wildfire-affected areas.

As provided in Table 3-51, a total of nearly 3,000 miles of critical infrastructure is exposed to slope failure risk across the county, including almost 2,000 miles of roadways alone. Other lifelines exposed include approximately 31 miles of natural gas pipelines, 75 miles of transmission lines, and 131 miles of sanitary sewer pipes. For all these types of critical infrastructure, the major of miles are located in moderate to high susceptibility areas.

Table 3-51: Santa Cruz County Critical Infrastructure Exposed to Slope Failure Risk

Lifelines (miles) - Landslide Susceptibility			
Infrastructure Type (Linear)	High	Moderate	Low
County Maintained Roads*	164.1	196.2	107.8
Levee	-	1.0	-
Maintained Channel	7.6	18.1	3.6
NG Pipeline	10.4	16.8	4.3
Railroad	6.3	12.7	4.8
Sanitation Pipe	25.8	76.7	28.4
All Roads	877.7	683.0	430.2
Alley	0.2	1.0	0.3
Drive	236.4	172.2	110.8
Major Road	105.8	112.8	60.1
Ramp	3.5	5.5	2.0
Street	431.9	305.9	197.4
State Highway	30.5	40.9	32.5
Unnamed	69.5	44.7	27.1
Transmission Line	33.2	29.3	13.3
Grand Total	**1,125.3**	**1,033.6**	**592.5**

With almost the entire county exposed to slope failure, a significant number of critical facilities are at risk of impacts from these hazards. More than 4,000 critical facilities were identified as being in areas susceptible to slope failure hazards to some degree, including 22 fire stations, 36 schools, six dams, and 148 hazardous materials facilities. The majority of these critical facilities are within moderate to high susceptibility areas, further demonstrating the extent of slope failure hazards in the county. Childcare

centers and mobile home parks also make up a large portion of the high-potential-loss facilities located in these hazardous areas.

Table 3-52: Santa Cruz County Critical Facilities Exposed to Slope Failure Risk

Critical Facilities - Landslide Susceptibility			
Facility Type	High	Moderate	Low
Essential Facilities	6	18	4
Fire Station	6	12	4
Hospital	-	-	-
Law Enforcement	-	5	-
EOC	-	-	-
American Medical Response	-	1	-
High-Potential-Loss	67	176	95
Adult Care Facility	-	15	3
Child Care Center	1	20	9
Cell Tower	37	32	18
County Real Property Asset	13	48	35
Dam	1	3	2
Healthcare Facility	1	4	1
Historic Building	1	2	3
Library	-	3	-
Mobile Home Park	5	21	8
Power Generation	1	1	-
Radio Sites	4	4	6
School	3	23	10
Transportation and Lifeline	1,670	1,201	630
Airport	-	1	-
Substation	1	8	2
NG Station	-	-	2
Church	5	32	4
Stormwater Culvert	1,601	1,083	578
Parks	16	31	13
Bridge NBI	47	46	31
Hazmat	29	97	39
HWTS Active Facility	25	88	35
Geotracker Cleanup Site	4	9	4
Grand Total	**1,772**	**1,492**	**768**

**Real Property Assets are digitized insurance rolls for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.*

3.2.6.10 Development Trends

The potential for loss of life and property from slope failure is much greater today due to the increase in population residing in areas of possible instability. County Code Title 16, in combination with the California

Building Standards Code, requires careful consideration of landslide factors by both engineering geologists, soils engineers, and civil engineers. However, even with proper care, there remains a higher-than-normal potential for damage from landsliding in many areas of the county.

Santa Cruz County has a number of compact urban communities as well as extensive rural areas. As dictated by the Growth Management Ordinance, most new development has occurred within or adjacent to the urban services line (i.e., the boundary point for water and sewage service). As with most communities, increased housing costs have resulted in the need to provide higher density housing. In Santa Cruz County, all development of this type occurs where urban services are available. Other development is mostly in-fill or reuse development, and further development of existing rural residential properties.

Growth management policies prevent development from occurring where hazards are present and, in most cases, require substantial setbacks from potentially unstable slopes. Development on existing lots of record is required to avoid hazards and incorporate these setbacks and other requirements to mitigate potential impacts from slope failure hazards. No changes in these development regulation or patterns occurred that would affect the county's overall vulnerability since the previous plan in 2021.

Most of the critical structures within Santa Cruz County are located away from slope failure areas, but many homes and roadways are located on and around high-hazard slopes. Future infrastructure projects, including roads, bridges, and utility improvements, will need to incorporate geologic assessments. Engineering solutions such as slope stabilization, drainage improvements, and retaining structures will play a crucial role in reducing risks, especially to transportation infrastructure, and maintaining connectivity and public safety. Improvements in technology, including LiDAR mapping, remote sensing, and real-time monitoring systems, will also enhance the ability to predict and mitigate slope failure hazards.

3.2.6.11 Slope Failure Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing slope failure-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with slope failure hazards. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-53 presents the slope failure problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in in Table 4-1 and Table 4-2.

Table 3-53: Santa Cruz County Slope Failure Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Slope Failure	Victim	**ps-SF-SCC-01**	Residents in landslide-prone rural communities can become isolated if slope failures damage or block critical access routes, with elderly and dependent populations at heightened risk.
Slope Failure	Victim	**ps-SF-SCC-02**	Residents in known hazard areas have little warning of landslides or debris flows beyond weather alerts and may lack awareness of warning signs, mitigation options, or insurance coverage.
Slope Failure	Impact	**ps-SF-SCC-03**	Many mountain roadways – both publicly- and privately-owned and maintained – are built on or near unstable slopes where failures can cause culvert damage and roadbed collapse, leading to costly repairs, service interruptions, and prolonged loss of access.
Slope Failure	Impact	**ps-SF-SCC-04**	Aging, undocumented, or unmaintained drainage features can oversaturate adjacent slopes during storms, as clogged or undersized culverts and ditches can trigger localized slides.
Slope Failure	Threat	**ps-SF-SCC-05**	Homes on or near landslide-prone soils face chronic risk from both slow earth movement and sudden slope failure, including some mobile home parks, hillside subdivisions, and older homes with little to no riparian setback situated above stream banks.
Slope Failure	Threat	**ps-SF-SCC-06**	Lack of mapping, erosion control, stabilization measures, and coordination with private landowners increases the risk of post-fire debris flows during storms in burn-scarred areas.
Slope Failure	Impact	**ps-SF-SCC-07**	Water lines, especially those above ground, are vulnerable to damage from landslides and trees made unstable by slope failures, which can also eliminate access to the infrastructure (e.g., in Davenport). Additionally, landslide debris can increase turbidity in surface water sources, increasing treatment costs, reliance on reserves, and water purchases from the City of Santa Cruz.

3.2.6.12 Climate Change Impacts & Vulnerable Populations

Slope failures, including landslides and debris flows, are a persistent hazard in Santa Cruz County due to its steep terrain, unstable soils, and history of intense winter storms. Climate change is expected to worsen these risks by increasing the intensity of rainfall events, prolonging wet seasons, and compounding erosion in burn scar areas. These conditions increase the likelihood of both sudden slope failures and slow-moving ground deformation, threatening residents, infrastructure, and essential services. Vulnerable populations including seniors, people with disabilities, mobile home residents, and low-income households living in hillside subdivisions or rural areas are particularly at risk due to limited evacuation options, older housing stock, and reduced access to financial and technical resources for mitigation.

Direct Impacts: Landslides and debris flows can block or destroy mountain roads, both publicly and privately maintained, isolating communities and impeding emergency response. Failures often damage culverts, ditches, and other drainage features, while slope instability undermines roadbeds, homes, and mobile home parks located near stream banks. Water and wastewater infrastructure is also vulnerable, with landslides damaging exposed water lines and increasing turbidity in surface water supplies, driving up treatment costs and threatening system reliability.

Secondary Hazards: Post-fire debris flows in mountainous terrain present significant risks in burn scar areas, where slopes stripped of vegetation are more prone to failure during subsequent storms. Clogged, undersized, or unmaintained drainage features worsen these risks, allowing oversaturation that triggers localized slides. Landslide debris can also obstruct streams and culverts, worsening downstream flooding and erosion hazards.

Public Health and Social Impacts: Residents in landslide-prone rural communities often receive little warning beyond storm advisories, leaving those with limited mobility or transportation at risk of entrapment when access roads fail. Lower-income households and renters face additional challenges, as few have insurance coverage or financial capacity to recover from landslide damage or displacement. Communities with high social vulnerability such as those mapped in the San Lorenzo Valley and rural South County are disproportionately affected by slope failure events, compounding existing inequities in disaster recovery.

The mitigation strategy addresses slope failure by prioritizing drainage upgrades, slope stabilization, and improved mapping of unstable areas. It also emphasizes outreach and support for vulnerable populations, coordination with private road associations, and integration of slope stability measures into post-fire recovery and watershed management programs.

Dam Failure

3.2.7 Dam Failure Hazard Profile

Dam failure can be sudden and catastrophic to all life and property downstream. Hundreds of dam failures have occurred throughout U.S. history, mostly before safety legislation was passed in 1972, that caused immense property and environmental damages and took thousands of lives. As the nation's dams age and population increases, the potential for deadly dam failures grows. (Association of State Dam Safety Officials, 2024)

Timber, rock, concrete, earth, steel, or a combination of these materials may be used to build a dam. Dams must have spillway systems to safely convey normal stream and flood stage flows over, around, or through the dam. Spillways are commonly constructed of non-erosive materials such as concrete. Dams also have a drain or other water-withdrawal facility to control the reservoir level and to lower or drain the reservoir for normal maintenance and emergency purposes.

Dam failures can result from earthquakes, structural instability, or intense rain in excess of design capacity, but typically occur in one of four ways:

- **Overtopping** of the primary dam structure, which accounts for 34% of all dam failures, can occur due to inadequate spillway design, settlement of the dam crest, blockage of spillways, and other factors.
- **Foundation defects** due to differential settlement, slides, slope instability, uplift pressures, and foundation seepage can also cause dam failure. These account for 30% of all dam failures.
- Failure due to **piping**, or internal erosion caused by seepage, accounts for 20% of all failures. Piping occurs when seepage through a dam is not properly filtered and soil particles continue to progress and form sink holes within it. Seepage often occurs around hydraulic structures, such as spillways; through animal burrows; around roots of woody vegetation; and through cracks in dams, dam appurtenances, or dam foundations. (*Id.*)
- Failure due to **problems with conduits and valves**, typically caused by the intrusion of embankment material into conduits through joints or cracks, constitutes 10% of all failures.

3.2.7.1 Secondary & Compounding Hazards

The main secondary hazard posed by dam failure is rapid and severe downstream flooding, depending on the magnitude of the failure. Other potential secondary hazards of dam failure are landslides around the reservoir perimeter and bank erosion downstream.

Many historical dam failures have been secondary hazards triggered by other disasters, such as earthquakes, landslides, extreme storms, and sabotage. Poor construction, lack of maintenance and repair, and deficient operational procedures are preventable or correctable by a program of regular inspections; however, terrorism and vandalism are serious concerns that all operators of public facilities must plan for. These threats are under continuous review by public safety agencies. In Santa Cruz County, dam failure would most likely be a secondary hazard triggered by a major earthquake, excessive rainfall, or slope failure,

which are discussed in the Earthquake (3.2.3), Severe Weather (Section 3.2.4), and Slope Failure (Section 3.2.6) Hazard Profiles.

Climate Change

Dams are designed partly based on assumptions about a river's flow behavior, expressed as hydrographs. As such, changes in weather patterns can have significant effects on the hydrograph used for the design of a dam. Although climate change will not increase the probability of catastrophic dam failure, it may increase the probability of design failures. If the hygrograph changes, then dam operators may be forced to release increased volumes earlier in a storm cycle to maintain required margins of safety, increasing flood potential downstream. Throughout the western United States, communities downstream of dams are already experiencing increases in-stream flows from early releases.

3.2.7.2 Policies, Plans Regulatory Environment

Federal Regulatory Environment

National Dam Safety Act & Dam Safety Program

The potential for catastrophic flooding due to dam failures led to passage of the 1972 National Dam Safety Act (Public Law 92-367). Then, following a series of deadly dam failures between 1972 and 1977, President Jimmy Carter directed the U.S. Army Corps of Engineers to inspect non-federal, high-hazard dams around the nation. The findings of these inspections helped establish dam safety programs in most states, and, ultimately, resulted in the creation of the National Dam Safety Program. (*Id.*)

The National Dam Safety Program requires a periodic engineering analysis of every major dam in the country. The goal of this program, monitored by FEMA, is to identify and mitigate the risk of dam failure to protect lives and property.

U.S. Army Corps of Engineers (USACE)

Under the National Dam Safety Program, the U.S. Army Corps of Engineers (USACE) is responsible for safety inspections of some federal and non-federal dams in the United States that meet the size and storage limitations specified in the National Dam Safety Act. USACE has inventoried such dams and surveyed each state and federal agency's capabilities, practices, and regulations regarding design, construction, operation, and maintenance of the dams. USACE also develops guidelines for inspection and evaluation of dam safety.

USACE is also responsible for maintaining the National Inventory of Dams (NID) and works in close collaboration with dam regulating agencies, including FEMA and state agencies, to obtain accurate and complete information about dams in the database.

Federal Energy Regulatory Commission (FERC) Dam Safety Program

The Federal Energy Regulatory Commission (FERC) has the largest dam safety program in the United States. The FERC cooperates with a large number of federal and state agencies to ensure and promote dam safety and, more recently, homeland security. There are over 3,000 dams that are part of regulated hydroelectric projects in the FERC program. Two-thirds of these are more than 50 years old. As dams age, concern about their safety and integrity grows, so oversight and regular inspection are important. FERC staff inspects hydroelectric projects on an unscheduled basis to investigate:

- Potential dam safety problems;
- Complaints about constructing and operating a project;
- Safety concerns related to natural disasters; and
- Issues concerning compliance with the terms and conditions of a license.

Every five years, an independent consulting engineer, approved by the FERC, must inspect and evaluate projects with dams higher than 10 meters (32.8 feet), or with a total storage capacity of more than 2,000 acre-feet.

FERC staff monitors and evaluates seismic research in geographic areas where there are concerns about seismic activity. This information is applied in investigating and performing structural analyses of hydroelectric projects in these areas. FERC staff also evaluates the effects of potential and actual large floods on the safety of dams. During and following floods, FERC staff visits dams and licensed projects, determines the extent of damage, if any, and directs any necessary studies or remedial measures the licensee must undertake. The FERC publication *Engineering Guidelines for the Evaluation of Hydropower Projects* guides the FERC engineering staff and licensees in evaluating dam safety. The publication is frequently revised to reflect current information and methodologies.

The FERC requires licensees to prepare emergency action plans and conducts training sessions on how to develop and test these plans. The plans outline an early warning system if there is an actual or potential sudden release of water from a dam due to failure. The plans include operational procedures that may be used, such as reducing reservoir levels and reducing downstream flows, as well as procedures for notifying affected residents and agencies responsible for emergency management. These plans are frequently updated and tested to ensure that everyone knows what to do in emergency situations.

The only hydroelectric dam that poses an inundation risk in Santa Cruz County is the Leroy Anderson Dam owned and operated by the Santa Clara Valley Water District (SCVWD). This earthen-rock dam was constructed in 1950, has a total capacity of over 89,000 acre-feet, and supplies drinking water to Santa Clara County. It is jointly regulated by FERC and the California DWR, Division of Safety of Dams. As of winter 2024, the dam was still undergoing seismic retrofits to rebuild it in compliance with present-day safety standards. SCVWD initiated the project in 2012 following a seismic stability evaluation, then additional studies in 2016 revealed previously unidentified fault lines, requiring additional retrofits. In February 2020, FERC directed SCVWD to reduce water levels in Anderson Reservoir with the goal to speed up work to replace the dam, and the reservoir remains limited to about 3% of its capacity.

State Regulatory Environment

California Department of Water Resources (DWR), Division of Safety of Dams (DSOD)

The California Department of Water Resources (DWR) Division of Safety of Dams (DSOD) monitors the dam safety program at the state level. When a new dam is proposed, division staff inspects the site. DSOD reviews dam applications and building plans to ensure that the dam is designed to meet minimum requirements and that the design is appropriate for known geologic conditions. It also inspects construction to ensure that the work is done in accordance with the approved plans. Division staff inspects constructed dams on an annual basis to ensure they are performing as intended and are not developing problems. Roughly a third of these inspections include in-depth instrumentation reviews. DSOD periodically reviews the stability of dams and their major appurtenances in light of improved design approaches and requirements, as well as new findings regarding earthquake hazards and hydrologic estimates in California. (DWR, 2025)

California Senate Bill 92

Senate Bill 92 was signed into law in 2017 and provides new state requirements focused on dam safety. Specifically, it requires owners of significant and high hazard potential dams to submit inundation maps to the California DWR. After the map is approved, the dam owner must then submit an emergency action plan (EAP) to the California Office of Emergency Services (Cal OES). An EAP identifies the emergency notification protocols, response process, and responsibilities of the dam operator and other agencies should an incident occur. The plans also outline preparedness activities. EAPs must approved by Cal OES Dam Safety Planning Unit, and updated and resubmitted every 10 years and, in some cases, sooner. (CalOES, 2025)

California Senate Bill 854

Passed in 2018, Senate Bill 854 amended California Water Code Section 6161, clarifying requirements for dams with existing EAPs as of March 1, 2017. It stipulates that if the EAP lacked inundation maps for all critical appurtenant structures, dam owners must submit a schedule to the DSOD to complete these maps.

Local Regulatory Environment

Santa Cruz County General Plan Public Safety Element

Although dam safety is primarily regulated at the state and federal levels, the Santa Cruz County General Plan Public Safety Element sets forth policies relevant to dam failure under seismic hazards, including:

- **Policy 6.1.6 Siting of New Reservoirs:** Requires a full engineering geologic investigation prior to the construction of new reservoirs, and if an unmitigable hazard exists, relocation of the reservoir.
- **Policy 6.1.7 Dam Safety Act:** New dams must be constructed according to high seismic design standards of the Dam Safety Act and as specified by structural engineering studies.

3.2.7.3 Location

According to the California Division of Dam Safety, there are five dams in Santa Cruz County and six dams in adjacent counties, San Benito and Santa Clara, that have the potential to inundate portions of Santa Cruz County. The reservoirs range in capacity from 20 acre-feet to over 89,000 acre-feet, with the oldest dams being constructed in the late 1800s. These dams are summarized in Table 3-54, and Figure 3-57 shows inundation zones for the dams in Santa Cruz County and nearby counties that could impact the planning area.

Dam hazard classes, or hazard potential classifications, are used to categorize dams based on the potential consequences of a dam failure, not the risk of failure itself. The main categories are typically High-Hazard, where failure would likely cause loss of human life; Significant Hazard, where failure could cause economic loss or environmental damage but no probable loss of life; and Low Hazard, where failure would result in no loss of life and minor impacts.

Given its location, a major dam failure at the Newell Dam could result in extensive property damage and loss of life in the San Lorenzo Valley and City of Santa Cruz. A failure at the Mill Creek, Oak Site, or Sempervirens Dams could affect people and property in northern Santa Cruz County, to the east of the community of Boulder Creek. Soda Lake is a storage facility for fine-grained material or "fines" from the Wilson Quarry in San Benito County. Failure of the Soda Lake levees could potentially release this material and impact one or more nearby residences and encroach upon Highway 129.

Although located in neighboring counties, a failure of the Elmer J Chesbro, Uvas, or San Justo Dams could potentially impact people and properties along the Pajaro River in Santa Cruz County. In addition, the Leroy Anderson, Coyote, and Upper Howell Dams, located in Santa Clara County, have the potential to impact very limited areas and assets in the county.

Table 3-54: Dams in or Adjacent to Santa Cruz County

Name	Owner	County	Waterway	Year Built	Capacity (acre-feet)	Hazard Class
Mill Creek	Lockheed Missiles and Space Co.	Santa Cruz	Mill Creek	1889	223	**High**
Soda Lake	Granite Rock Co.	Santa Cruz	Tr. Pajaro River	1978	1,983	**High**
Newell	City of Santa Cruz	Santa Cruz	Newell Creek	1960	8,991	**High**
Elmer J. Chesbro	Santa Clara Valley Water District	Santa Clara	Llagas Creek	1955	8,086	**High**
Uvas	Santa Clara Valley Water District	Santa Clara	Uvas Creek	1957	10,000	**High**
Leroy Anderson	Santa Clara Valley Water District	Santa Clara	Coyote Creek	1950	89,073	**High**
Coyote	Santa Clara Valley Water District	Santa Clara	Coyote Creek	1936	22,541	**High**

Name	Owner	County	Waterway	Year Built	Capacity (acre-feet)	Hazard Class
San Justo	U.S. Bureau of Reclamation	San Benito	Offstream	1985	10,300	**High**
Sempervirens	California Department of Parks and Recreation	Santa Cruz	Sempervirens Creek	1951	78	**Significant**
Upper Howell	San Jose Water Company	Santa Clara	Rundell Creek	1878	243	**Significant**
Oak Site	California Department of Forestry and Fire Protection	Santa Cruz	Tr. Big Green	1969	20	**Low**

Source: National Inventory of Dams

In addition to the eight dams under the purview of DSOD, there are also a total of eight mining operations in Santa Cruz County that utilize ponds to hold processing plant wash water and storm water. These ponds are constructed using both artificial and natural barriers depending on whether the pond is created by a levee or dam, or excavation below grade. Because of their limited height and storage capacity, none of these ponds is within the jurisdiction of DSOD. In some cases, quarry ponds are non-jurisdictional because they are created by excavation, which means there is no artificial barrier that would qualify as a "dam" under state law.

There are also an unknown number of other dams in the county associated with agriculture, small water systems, and private ponds. These facilities are likely non-jurisdictional, and many are undocumented. Given their location, failure of one of these agricultural dams or levees at a quarry pond could affect a limited amount of people or property in downstream areas, but the extent of the hazard is unknown at this time.

3.2.7.4 Past Events

There have been no reported failures of dams located within Santa Cruz County to date, and previous occurrences of dam failure affecting the county are not known for any dams in adjacent counties. However, after the 1989 Loma Prieta Earthquake, an extensive set of cracks was observed at the crest of Soda Lake's west embankment and adjacent areas on the levee's interior face. The west levee was excavated to bedrock and reconstructed in 1997 with the approval of the California Division of Safety of Dams (DOSD). Additional stability issues involving the north levee tie-in to the hillside were addressed by the DOSD in a letter to the dam owner, Granite Rock Company, in 2000.

Based on available records, there have been no dam failures at any of the mines in Santa Cruz County. There have been rare events involving uncontrolled releases of water due to natural and human causes, but none of these events involved dam failure. Currently available information gives no indication that any of the dams within or adjacent to Santa Cruz County would fail or otherwise sustain damage, except by an act of terrorism.



Figure 3-57: Dam Inundation Zone Location Map

3.2.7.5 Frequency & Probability of Future Occurrences

Dams are constructed with safety features known as "spillways" that allow water to overtop the dam if the reservoir fills too quickly. Spillway overflow events, often referred to as "design failures," result in increased discharges downstream and increased flooding potential. The residual risk associated with dams is the risk beyond that for which safeguards have been implemented. However, the probability of any type of dam failure is low in today's regulatory and dam safety oversight environment. Dam failure events usually coincide with events such as earthquakes, landslides, or excessive rainfall.

Given the monitoring protocol at all the dams within and adjacent to the county with significant or high-hazard potential, the probability of dam failure is very low.

3.2.7.6 Severity

Even though the probability of dam failure is low in Santa Cruz County, a failure could be catastrophic to all life and property downstream. The highest-capacity dams that are located upstream from population centers, such as Newell Dam above the San Lorenzo Valley and City of Santa Cruz (Figure 3-58), pose the greatest risk.

FEMA developed a classification system for potential dam failures, as shown in Table 3-55. This classification system categorizes dams based on the probable loss of human life and the impacts on economic, environmental, and lifeline interests. Improbable loss of life exists where persons are only

Figure 3-58: Newell Dam and Loch Lomond Reservoir
Source: City of Santa Cruz

temporarily in the potential inundation area. For instance, this hazard potential classification system does not contemplate the improbable loss of life of the occasional recreational users of the river and downstream lands or passers-by.

In any classification system, all possibilities cannot be defined. High usage areas of any type should be considered appropriately, and judgment and common sense must ultimately be a part of any decision on classification. Further, no allowances for evacuation or other emergency actions by the population should be considered because emergency procedures should not be a substitute for appropriate design, construction, and maintenance of dam structures.

Table 3-55: FEMA Dam Hazard Potential Classifications

Hazard Potential Classification	Loss of Human Life	Economic, Environmental, Lifeline Losses
Low	None expected	Low and generally limited to owner
Significant	None expected	Yes
High	Probable; one or more expected	Yes (but not necessary for this classification)

Source: Federal Guidelines for Dam Safety, Hazard Potential Classification Systems for Dams, 2004

No dams have failed in Santa Cruz County to date and, as the risk assessment for Santa Cruz County illustrates, the chances of a dam failure area low, but the consequences of such an event are quite severe.

The most recent concerning dam failure in California was the 2017 collapse of a spillway on the Oroville Dam in Butte County, California. Oroville Dam is the largest facility within the State Water Project in California; the dam stores 3.5 million acre-feet of water, and serves as important flood control for the Feather River. In 2017, after substantial runoff from the Sierra Nevadas, Lake Oroville was full and the spillway was opened to release extra water downstream.

The force of the release gouged a large crater in the concrete spillway and required a halt to water releases via that conduit. The high lake level then created fear that erosion would compromise the integrity of the auxiliary spillway and flood the City of Oroville and surrounding communities. Thousands were evacuated, and eventually runoff receded without further issue. Ultimately, an independent analysis concluded that poor design and construction and inadequate state oversight contributed to the collapse of the concrete spillway. (Water Education Foundation, 2020)

The Oroville Dam spillway failure triggered the inspection of 93 dam spillways across California through the new Spillway Re-evaluation Program, including one in Santa Cruz County: Newell Dam. (DWR, 2025)

In the event of a dam or levee failure of an agricultural or quarry pond, significant environmental impacts and property damage could occur. Environmental impacts would likely be limited to temporary impacts on water quality and erosion. Property damage would likely be limited to impacts on downstream drains, culverts, roads, and bridges.

3.2.7.7 Warning Time

Warning time for dam failure depends on the cause of failure. In an event of extreme precipitation, such as during an atmospheric river event, evacuations can be planned with sufficient time, but in the event of a structural failure due to earthquake, there may be no warning time. A dam's structural type also affects warning time.

Earthen dams do not tend to fail instantaneously. Once a breach is initiated, discharging water erodes the breach until the reservoir water is depleted, or the breach resists further erosion. Concrete gravity dams also tend to have an initial partial breach. The time of breach formation ranges from a few minutes to a few hours. Several participating jurisdictions have established protocols in their emergency operations plans for warning and response to imminent dam failure. These protocols are tied to emergency action plans (EPA) created by the dam owner.

EAPs identify areas downstream from dams requiring warning and evacuation in the event of a failure. Documented cases have demonstrated that warning and evacuation time for EAPs can dramatically influence the loss of life, varying from 0.02% of the threatened population when the warning time is 90 minutes or more, to 50% when there is less than 15 minutes of warning. (Graham, 1988)

Dam failure inundation mapping studies usually assume one of two scenarios:

- Flows from a dam failure during "fair weather" or "sunny day" conditions with the reservoir at the normal pool level and receiving normal inflow (usually insignificant). A fair weather failure is generally considered to have the most potential for loss of human life, primarily due to the element of surprise.
- Flows from a dam failure during flood conditions or the inflow design flood. Failure during flood conditions is considered to show the upper limit of inundation and to have less potential for loss of human life because the operators and downstream population are on alert. However, the flood conditions scenario is used less frequently because of the expense in additional watershed and spillway analysis.

Inundation mapping shows a continuous line of inundation identifying the area potentially at risk. It starts at the dam and continues downstream to a point where the breach flood no longer poses a risk to life or property, such as a large river or reservoir with the capacity of storing the flood waters. The domino effect of a dam failure causing failures of any downstream dams is studied on a case-by-case basis.

EAPs are not publicly available but are on file with local emergency management agencies. Information provided on flooding conditions at downstream locations includes: distance downstream; arrival time of the leading edge of the breach flood wave; peak flow depth, incremental rise, or water surface elevation (as appropriate); and peak velocity.



Figure 3-59: Exposure Summary – Santa Cruz County Dam Failure Risk

3.2.7.8 Dam Failure Vulnerability Assessment

The primary danger associated with dam failure is high-velocity flooding downstream of the dam and limited warning times for evacuation. Vulnerability varies by community and depends on the particular dam and stream profiles, and the nature and extent of the failure. A summary of dam failure risk exposure in Santa Cruz County to people, property, and critical facilities and infrastructure is provided in Figure 3-59.

3.2.7.8.1 Population

The potential for loss of life from a dam failure is affected by the capacity and number of evacuation routes available to populations living in areas of potential inundation, but the entire population in a dam failure inundation zone is exposed to the risk. The estimated population exposed to dam failure risk is summarized in Table 3-56 and Figure 3-60.

Several dams pose risks to downstream populations, including Elmer J. Chesbro, Leroy Anderson, Mill Creek, Newell, Soda Lake, and Uvas, exposing about 2% of the total county population to dam failure risk. However, most of the populations exposed are very small. The dam that poses the highest risk in the unlikely event of a failure is Newell, which could impact about 2,300 people in the unincorporated county and thousands more within the City of Santa Cruz.

Vulnerable populations that are present directly below a dam may include those incapable of escaping the area within the allowable time frame. These populations include the elderly, young children, and other who may be unable to self-evacuate from the inundation area, as well as those who do not receive adequate warning due to cultural, language, or technological barriers.

Table 3-56: Santa Cruz County Population Exposed to Dam Failure Risk

	Total Population
Unincorporated County	131,149

Dam Inundation Zone	Population Count	% of Total
Elmer J Chesbro	6	*0.00%*
Leroy Anderson	48	*0.04%*
Mill Creek	6	*0.00%*
Newell	2,331	*1.78%*
Soda Lake	27	*0.02%*
Uvas	6	*0.00%*
Total*	**2,411**	**1.84%**

**Total population is not equal to sum of all dam inundation zones due to dissolved overlapping inundation areas.*



Figure 3-60: Santa Cruz County Population Exposed to Dam Failure Risk Chart

3.2.7.8.2 Property

Vulnerable properties are those within and adjacent to the dam inundation area. These properties would experience the largest, most destructive surge of water. Structures in low-lying areas where water would collect are also vulnerable.

Only about 2% of county parcels are exposed to dam failure risk, but the total value of exposed property is still almost $924 million. As with population exposure, Newell Dam poses the greatest risk to downstream property and makes up over $911 million of the total property value at risk. Table 3-57 displays parcel values at risk from dam inundation.

Table 3-57: Santa Cruz County Parcels Exposed to Dam Failure Risk

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

Dam Inundation Zone	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
Mill Creek	1	0.0%	$477,200	$238,600	$715,800	0.0%
Newell	1,009	2.1%	$580,496,000	$330,861,000	$911,357,000	1.7%
Soda Lake	9	0.0%	$6,068,000	$5,498,600	$11,566,600	0.0%
Uvas	1	0.0%	$896,000	$896,000	$1,792,000	0.0%
Dam Inundation Area*	**1,019**	**2.1%**	**$587,041,200**	**$336,598,200**	**$923,639,400**	**1.7%**

**Totals are not equal to sum of all dam inundation zones due to dissolved overlapping inundation areas.*

3.2.7.8.3 Critical Facilities & Lifelines

Critical facilities and infrastructure located downstream from a dam within its inundation zone are vulnerable to catastrophic damage. Assets in adjacent low-lying areas are also vulnerable to dam inundation. The most vulnerable critical facilities are those in poor condition that would have difficulty withstanding a large surge of water. There are few critical facilities located within dam inundation zones in the county; included are a fire station, 12 hazardous materials facilities, two childcare centers, and a mobile home park. Almost all of the exposed assets (76 out of 80) are within the Newell Dam inundation area; the remainder are located in the Leroy Anderson, Mill Creek, or Upper Howell zones.

Transportation infrastructure is especially vulnerable to impacts from dam failure, including roads, railroads, and bridges in the flow path of water. Utilities such as overhead power lines and communication lines could also be vulnerable. Loss of these utilities could create additional compounding issues for emergency management officials attempting to conduct evacuation and response actions. A total of 33 miles of critical infrastructure is located within dam failure inundation zones, including 21 miles of roads. Again, the majority of these lifelines—approximately 75%—are exposed to failure risk from the Newell Dam. Of the remaining mileage exposed, most is located within the inundation areas of the Soda Lake, Mill Creek, or Leroy Anderson Dams.

Table 3-58 through Table 3-59 summarize the county's critical facilities and infrastructure that are located in a mapped dam failure inundation area.

Table 3-58: Santa Cruz County Critical Infrastructure Exposed to Dam Failure Risk

Critical Infrastructure - Dam Inundation	
Infrastructure Type (linear)	Total Dam Exposure
County Maintained Roads*	7.1
Levee	1.1
Maintained Channel	3.6
NG Pipeline	0.0
Railroad	0.2
Sanitation Pipe	-
All Roads	21.0
Alley	0.1
Drive	2.3
Major Road	1.3
Ramp	-
Street	14.2
State Highway	2.6
Unnamed	0.5

Transmission Line	0.1
Grand Total	**33.1**

**Partially Overlaps "All Roads"*

Table 3-59: Santa Cruz County Critical Infrastructure Exposed to Dam Failure Risk by Dam

Infrastructure Type (linear)	TOTAL DAM EXPOSURE	Coyote	Elmer J Chesbro	Leroy Anderson	Mill Creek	Newell	Sempervirens	Soda Lake	Uvas
County Maintained Roads*	7.1	-	-	0.03	0.09	6.52	-	0.47	0.01
Levee	1.1	-	-	0.98	-	-	-	0.12	-
Maintained Channel	3.6	0.01	-	3.10	-	0.52	-	0.65	-
NG Pipeline	0.0	-	-	0.00	-	-	-	-	-
Railroad	0.2	-	-	-	-	0.19	-	-	-
Sanitation Pipe	-	-	-	-	-	-	-	-	-
All Roads	21.0	-	0.03	0.06	1.09	17.60	0.30	1.98	0.07
Alley	0.1	-	-	-	-	-	-	-	-
Drive	2.3	-	-	-	-	-	-	-	-
Major Road	1.3	-	-	-	-	-	-	-	-
Ramp	-	-	-	-	-	-	-	-	-
Street	14.2	-	-	-	-	-	-	-	-
State Highway	2.6	-	-	-	-	-	-	-	-
Unnamed	0.5	-	-	-	-	-	-	-	-
Transmission Line	0.1	-	0.03	0.11	-	-	-	0.04	0.03
Grand Total	**33.1**	**0.0**	**0.1**	**4.3**	**1.2**	**24.8**	**0.3**	**3.3**	**0.1**

Table 3-60: Santa Cruz County Critical Facilities Exposed to Dam Failure Risk

Critical Infrastructure - Dam Inundation	
Infrastructure Type	Total Feature Count
Essential Facilities	1
Fire Station	1
Hospital	-
Law Enforcement	-
EOC	-
American Medical Response	-
High-Potential-Loss	30
Adult Care Facility	-
Child Care Center	2
Cell Tower	-
County Real Property Asset	25
Dam	2
Healthcare Facility	-
Historic Building	-
Library	-
Mobile Home Park	1
Power Generation	-
Radio Sites	-
School	-
Transportation and Lifeline	36
Airport	-
Substation	-
NG Station	-
Church	4
Stormwater Culvert	17
Parks	3
Bridge NBI	12
Hazmat	13
HWTS Active Facility	12
Geotracker Cleanup Site	1
Grand Total	**80**

**Real Property Assets are digitized asset lists for demonstrating value and ownership and may have overlapping points with other categories such as fire stations and law enforcement.*

Table 3-61: Santa Cruz County Critical Facilities Exposed to Dam Failure Risk by Dam

Infrastructure Type	TOTAL FEATURE COUNT	Leroy Anderson	Mill Creek	Newell	Upper Howell
Essential Facilities	1	-	-	1	-
Fire Station	1	-	-	1	-
Hospital	-	-	-	-	-
Law Enforcement	-	-	-	-	-
EOC	-	-	-	-	-
American Medical Response	-	-	-	-	-
High-Potential-Loss	30	-	-	28	2
Adult Care Facility	-	-	-	-	-
Child Care Center	2	-	-	2	-
Cell Tower	-	-	-	-	-
County Real Property Asset	25	-	-	25	-
Dam	2	-	-	-	2
Healthcare Facility	-	-	-	-	-
Historic Building	-	-	-	-	-
Library	-	-	-	-	-
Mobile Home Park	1	-	-	1	-
Power Generation	-	-	-	-	-
Radio Sites	-	-	-	-	-
School	-	-	-	-	-
Transportation and Lifeline	36	1	1	34	-
Airport	-	-	-	-	-
Substation	-	-	-	-	-
NG Station	-	-	-	-	-
Church	4	-	-	4	-
Stormwater Culvert	17	1	1	15	-

Parks	3	-	-	3	-
Bridge NBI	12	-	-	12	-
Hazmat	13	-	-	13	-
HWTS Active Facility	12	-	-	12	-
Geotracker Cleanup Site	1	-	-	1	-
Grand Total	**80**	**1**	**1**	**76**	**2**

3.2.7.9 Development Trends

Very little new development within the county could be impacted by a dam failure since most of the inundation areas are rural and sparsely populated, with the exception of the communities downstream from Newell Dam. Land use within the planning area is guided by the county's Growth Management Ordinance, which directs most development into urban service areas where water and sewer are available, especially high-density development.

Most areas susceptible to impacts from dam failure overlap with mapped flood hazard zones. Consequently, flood-related policies and regulations contribute to mitigating risks associated with dam failure for future development in the planning area. Development on existing lots of record is required to avoid flood hazards and incorporate appropriate setbacks, structural elevation, floodproofing, and other requirements to mitigate potential impacts from flood hazards. However, flooding due to a dam failure event is likely to exceed a 100-year event, which is the minimum standard that development in a designated flood hazard area must be protected. Increased consideration of dam failure risk when permitting development in inundation zones and downstream of high-hazard and significant hazard dams could be incorporated to mitigate this hazard. Low hazard dams could become significant or high-hazard dams if development occurs below them.

In addition, there is limited potential for significant expansion of mining activities in Santa Cruz County. As quarry resources are depleted, the sites are reclaimed. Reclamation will include elimination of unnecessary water impoundments and eliminating any danger to public health and safety from failure of any remaining dams or levees.

3.2.7.10 Dam Failure Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing dam failure-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with dam failure hazards. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-62 presents the dam failure problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in Table 4-2.

Table 3-62: Santa Cruz County Dam Failure Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Dam Failure	Victim	**ps-DF-SCC-01**	Approximately 4.5% of the County's population (~12,000) lives within a dam inundation zone. Few residents are aware of dam failure risk or know their proximity to inundation zones, which are not clearly communicated to the public and lack consistent signage and educational outreach.
Dam Failure	Impact	**ps-DF-SCC-02**	Failure of a major dam in the Santa Cruz Mountains (e.g., Loch Lomond, Newell Creek) could rapidly and catastrophically inundate populated drainages downstream, potentially causing fatalities and extensive infrastructure damage.
Dam Failure	Threat	**ps-DF-SCC-03**	Numerous small, privately owned legacy dams and sediment basins in the County are unmanaged and lack regular inspection or maintenance, increasing the risk of structural failure and downstream impacts during extreme storm or seismic events.
Dam Failure	Threat	**ps-DF-SCC-04**	Multiple schools and other critical facilities are located within mapped inundation zones for multiple dams and could be cut off or damaged without adequate pre-event mitigation or response planning.

3.2.7.11 Climate Change Impacts & Vulnerable Populations

Dam failure is a low-probability but high-consequence hazard in Santa Cruz County. Approximately 12,000 residents, or 4.5 percent of the population, live within mapped dam inundation zones, yet public awareness of this risk remains limited. Climate change increases the stress on these systems by driving more extreme storm events that can accelerate erosion, increase sediment loads, and test the capacity of aging structures. Prolonged droughts followed by intense rainfall also create rapid shifts in reservoir levels that place additional strain on dams and spillways.

Direct Impacts: Failure of a major dam in the Santa Cruz Mountains, such as Loch Lomond or Newell Creek, could cause catastrophic flooding that damages infrastructure, disrupts essential services, and threatens downstream communities. Critical facilities, including schools and emergency operations sites, lie within inundation zones and face service disruption or isolation in the event of failure.

Secondary Hazards: Many small privately-owned dams and sediment basins lack regular inspection or maintenance, increasing their vulnerability to storm events and seismic activity. Climate change-driven storm intensity heightens the risk of structural failure and downstream flooding, while sediment release could reduce water quality and affect habitat.

Public Health and Social Impacts: Vulnerable populations within inundation zones, including low-income households, renters, and non-English speaking residents, face greater barriers to recovery due to financial constraints, lack of insurance, and limited evacuation awareness. Limited education and outreach further reduce preparedness for these communities, which are also more likely to experience disproportionate impacts from long-term displacement after an event.

The mitigation strategy addresses dam failure by improving risk communication, expanding outreach to vulnerable communities, and coordinating with dam operators to strengthen emergency planning for facilities and residents located in inundation zones.

PAGE INTENTIONALLY BLANK

Drought

3.2.8 Drought Hazard Profile

California's water resources have been stressed by periodic drought cycles, but climate change is expected to increase the frequency, severity, and duration of droughts across the state. While the length of drought periods is always in question, it is certain that California and Santa Cruz County will continue to be impacted by drought. (California Drought Contingency Plan, 2021)

Santa Cruz County surface and groundwater resources provide drinking water for residents and visitors, critical habitat to numerous plant and animal species, and opportunities for recreational and commercial activities. Like many other areas of California, the county faces water resource challenges, including inadequate water supply particularly during droughts, impaired water quality, over-drafted groundwater basins, depleted streams, and degraded riparian habitat. The overwhelming majority of Santa Cruz's water supply is locally derived—a unique situation in a state supported by large federal and state water projects. Domestic supply within the region is provided by five large public agencies, four medium water systems, 115 small water systems, and some 8,000 individual wells. Water use in 2024 is summarized in Table 3-63.

Table 3-63: Santa Cruz County Water Supplier Summary

Supplier	Connections	Service Area Population	Use (acre-feet/ year)	Source			
				Groundwater	Surface	Recycled	Imported
Santa Cruz City Water Department	24,957	95,017	7,612	1.2%	98.8%	0%	
Watsonville City Water Department*	14,602	65,231	6,389	99.6%	0.4%		
Soquel Creek Water District*	14,548	40,644	2,930	100%			
San Lorenzo Valley Water District	7,900	23,700	1,827	30.1%	69.9%		
Scotts Valley Water District*	3,945	11,147	1,110	85.8%		14.2%	
Central Water District	829	2,706	364	100%			
Big Basin Water Company[1]	540	1,120	160	100%	63%		
Mount Hermon Association	491	2,850	152	100%			
Forest Lakes Mutual Water Company	326	1,067	36	100%			
Smaller Water Systems	2,540	7,958	1,258	85%	6%		9%
Individual Users[1]	8,000	21,000	2,350	95%	5%		
Mid- & North County Agriculture[1]			2,400	90%	10%		
Pajaro Agriculture[2] (Unincorporated County Only)			19,960	95.3%	0.3%	4.4%	
Total	**78,589**	**273,132**	**44,845**	**78%**	**19%**	**3%**	**3.6%**
Summary by Water Source (acre-feet/year)				**34,057**	**9,111**	**1,624**	**62**
Summary of Non-Agricultural Use (percentage)			**53.6%**	**43.6%**	**97%**	**18.4%**	**100%**

*Notes: *Jurisdictions participating in the 2025 MJHMP. [1]Values are estimated. [2]Includes a small number of systems.*

Source: Santa Cruz County Water Resources Annual Report, 2024

Nearly all of Santa Cruz County's domestic water supply is derived from local surface water (streams and reservoirs, accounting for 20% of supply) and groundwater (80% of supply), which are fed entirely by precipitation and the county does not receive any imported water. A small amount of recycled water is produced for irrigation (4%). Partially because Santa Cruz County obtains all its own water, it is somewhat insulated from drought that has a greater impact on portions of the state that rely on state or federal water projects. However, the county continues to face major water supply challenges in that most groundwater basins have more water removed on an annual basis than is replaced and the major water supply agencies do not have sufficient sustainable supplies to meet current and future demand, even with very effective water conservation programs already in place.

The San Lorenzo Valley Water District (SLVWD), Scotts Valley Water District (SVWD), City of Santa Cruz Water Department (CSCWD), Soquel Creek Water District (SqCWD), Central Water District (CWD), City of Watsonville Department of Public Works and Utilities, and the Pajaro Valley Water Management Agency (PVWMA) are the major water agencies in the county. Except for their recycled water project, the PVWMA does not provide residential drinking water but rather is a management agency tasked with developing supplemental supplies and bringing the aquifers within its boundary into sustainable yield. Of these water agencies, four are participating jurisdictions in this plan: SVWD, SqCWD, City of Watsonville, and PVWMA.

Figure 3-61: Watsonville Slough

Source: Pajaro Valley Water Management Agency

While there are numerous small water diversions on many of the county streams, most of the stream water used is diverted from the San Lorenzo River Watershed, North Coast streams, and Corralitos Creek. Most groundwater is contained in permeable geologic basins, typically referred to as aquifers. There are three major groundwater basins in the county: the Santa Margarita, Santa Cruz Mid-County, and Pajaro.

The major water purveyors share the water resources in the county and most obtain water from multiple sources. While most depend solely on groundwater for potable supply, the CSCWD, CWWD and SLVWD get a large portion of their water supply from local streams. The CSCWD is the largest user of surface water in the county, deriving approximately 90% of their supply from the San Lorenzo River Watershed and North Coast

streams. The water purveyors actively work together to make the county's limited water resources sustainable for current and future generations of Santa Cruz residents.

Outside of the municipal service areas, individual parcels and communities rely on private wells and stream diversions for their water supply. Santa Cruz County, acting as a Local Primacy Agency for the State Water Resources Control Board, oversees small water systems serving between five and 199 water connections. The Small Water System Regulatory Program is designed to ensure that small public water supply systems deliver a reliable and adequate supply of groundwater or surface water to their customers. There are approximately 130 small water systems in the county serving roughly 2,500 households. Additionally, there are at least 8,000 private wells in Santa Cruz County that serve between one and four households.

Table 3-62 depicts the service areas of the major water suppliers in Santa Cruz County.

3.2.8.1 Secondary & Compounding Hazards

Drought is compounded by climate change and contributes to secondary hazards like wildfire. These hazards are briefly discussed in this section in relation to drought; detailed assessments of wildfire and climate change are found in their respective profiles, in Sections 3.2.1 and 3.2.10.

Climate Change

The long-term effects of climate change on regional water resources are unknown, but global water resources are already experiencing stresses without climate change, including growing populations, increased competition for available water, poor water quality, groundwater overdraft, and aging urban water infrastructure. With a warmer climate, droughts could increase in severity, frequency, and duration, contributing to declining streamflow in surface waterbodies, which in turn, reduces groundwater recharge as well as water availability for humans, wildlife, and vegetation. It can also contribute to sea level rise-driven seawater intrusion into aquifers. Refer to 3.2.10 Climate Change Hazard Profile for more information.

Wildfire

The secondary hazard most associated with drought is wildfire. A prolonged lack of precipitation stresses and dries out vegetation, which becomes increasingly susceptible to ignition as the duration of the drought extends. Increased temperatures from climate change during drought conditions further intensify wildfire danger by warming and accelerating the desiccation of vegetative fuels. As climate conditions shift toward longer fire seasons and drier fuels, secondary wildfire effects from drought are expected to increase in both frequency and severity across Santa Cruz County. A changing climate is expected to subject forests to increased stress due to drought, disease, invasive species, and insect pests (e.g., shothole borer and sudden oak death). These stressors are likely to make forests more vulnerable to catastrophic fire.



Water Districts and Service Areas

Source: Santa Cruz County

Figure 3-62: Water Districts and Service Areas

3.2.8.2 Policies, Plans & Regulatory Environment

State Regulatory Environment

State Water Resources Control Board

Through a ballot initiative in the early 20th century, state law-makers passed a Constitutional amendment declaring that California's water resources "shall put water to the highest beneficial use possible and shall not waste water or use it unreasonably." In 1967, the State Legislature recognized that California would not have enough clean water for agricultural, municipal, industrial, environmental, and other uses unless water quality and quantity decision-making were coordinated. It was at that time that the State Water Resources Control Board (State Water Board) was created and given the broad authority and responsibility to protect water quality, balance competing demands on water resources, and attempt to resolve decades-long water disputes.

This new regulatory board merged the functions of two previous state boards: the State Water Quality Control Board and the State Water Rights Board. The former had its roots in the late 1940s, when legislators created a streamlined regulatory agency to address rising water quality problems with the state's explosive industrial and population growth. A water rights commission, which preceded the water rights board, was created in the early 1900s to arbitrate and resolve the state's water battles, which began during the 1849 Gold Rush. Back then, prospectors from throughout the world raced to the Sierra Nevada Mountains to stake their claims, using the cold mountain streams as a tool to unearth gold.

Today the five-member State Water Board allocates water rights, adjudicates water right disputes, develops statewide water protection plans, establishes water quality standards, and guides the nine Regional Water Quality Control Boards located in California's major watersheds. The Regional Boards, each comprised of seven members, serve as the front-line for state and federal water pollution control efforts. In Santa Cruz County, the Central Coast Regional Board has jurisdiction.

Today's challenges are California's rapid population growth, and the continuing struggle over water flows. The State Water Board faces tough demands: to fix ailing sewer systems; build new wastewater treatment plants; and tackle the cleanup of underground water sources harmed by the technology and industry that has catapulted the state into global prominence. (State Water Board, 2018)

California Sustainable Groundwater Management Act (SGMA)

In 2014, Governor Brown signed into law a package of senate bills (SB) and assembly bills (AV), including SB 1168, AB 1739, and SB 1319, collectively called the Sustainable Groundwater Management Act (SGMA). SGMA requires governments and water agencies of high and medium priority basins to halt overdraft and bring groundwater basins into balanced levels of pumping and recharge. Under SGMA, these basins should reach sustainability within 20 years of implementing their sustainability plans. For critically overdrafted basins, that will be 2040. For the remaining high and medium priority basins, 2042 is the deadline.

Executive Order B-37-16

Governor Brown issued Executive Order B-37-16, Making Water Conservation a California Way of Life, in 2016 that included, among other directives, drought hazard and planning related actions. The order established long-term, permanent water conservation measures in response to the ongoing drought and changing climate, and mandated the California State Water Resources Control Board permanently prohibit practices like using hoses to clean driveways and sidewalks, overwatering lawns, and serving water by default in restaurants, with a focus on urban water use. In addition, directive number 10 in the order specified that, "for areas not covered by a Water Shortage Contingency Plan, the [board] shall work with counties to facilitate improved drought planning for small water suppliers and rural communities."

In 2016, the State Water Board adjusted emergency water conservation regulations indefinitely in recognition of the differing water supply conditions and ongoing drought across the state. Executive Order B-37-16 updates temporary emergency water restrictions and transitions to permanent, long-term improvements in water use by using water more wisely; eliminating water waste; strengthening local drought resilience; and improving agricultural water use efficiency and drought planning.

California Water Plan

The California Water Plan, which dates back to the late 1800s, is the state's strategic plan for sustainably managing and developing water resources for current and future generations. As required by State Water Code Section 10005(a), the California Department of Water Resources (DWR) presents in the plan the status and trends of California's water-dependent natural resources; water supplies; and agricultural, urban, and environmental water demands for a range of plausible future scenarios. The plan is updated every five years and provides a framework for collaboration among local government officials, tribes, water suppliers and resource managers, businesses, academia, and the general public. Although the plan does not mandate actions, authorize spending,



Figure 3-63: Zayante Creek

Source: Resource Conservation District of Santa Cruz County

or make project-specific recommendations, it does require policy-makers to take definitive steps to authorize specific actions proposed in the plan and appropriate the funding needed for their implementation.

The plan was last updated in 2023. This update promotes a vision where "all Californians benefit from water resources that are sustainable, resilient to climate change, and managed to achieve shared values and connections to our communities and the environment." To tackle this ambitious vision, the 2023 update focuses on three intersecting themes: addressing climate urgency, strengthening watershed resilience, and achieving equity in water management. (DWR, 2025)

Local Regulatory Environment

Santa Cruz County Authority & Role

Santa Cruz County has no direct authority over the entities that provide water supply to county residents. The two largest suppliers are governed by the city councils elected by those city residents. Independently elected agency boards govern the other public entities, and the California Public Utilities Commission oversees privately-owned water systems to some extent. All water systems are governed by state and federal safe drinking water regulations. The larger systems, with more than 200 connections, are regulated directly by the California Department of Public Health.

The county serves as an agent of the state, ensuring compliance with the state regulations for small water systems with between five and 199 connections. The county also permits individual water systems to serve new homes in rural areas, typically on wells. Although well yield standards for new development are conservative, it is possible that individual wells and older wells serving small water systems may experience diminished yield or go dry during an extended drought. The county has no ongoing oversight of water use for individual water systems after the initial development permit is approved.

Santa Cruz County Code Chapter 7.69

Water conservation requirements for new development are established in Santa Cruz County Code Chapter 7.69 to prevent waste of water and reduce long-term demand for water supply. The chapter prohibits certain uses of water, such as for washing sidewalks or running ornamental fountains, unless measures are taken to reduce waste. It also requires high-efficiency plumbing fixtures in all new structures, and for older fixtures to be upgraded upon redevelopment or change of property ownership.

Groundwater Sustainability Plans

The Sustainable Groundwater Management Act (SGMA) requires local groundwater basin agencies in the state's high and medium priority basins to develop and implement Groundwater Sustainability Plans (GSPs) or alternative plans, which provide roadmaps for how groundwater basins will reach long-term sustainability. Basin agencies are required to submit annual reports to the California Department of Water

Resources (DWR) following adoption of their GSP, and periodic evaluations are also due to DWR every five years. Priority basins in Santa Cruz County that have a GSP or alternative plan include:

- **Santa Margarita Groundwater Basin:** A roughly triangular basin between Felton, Ben Lomond, and Scotts Valley, providing drinking water for the Scotts Valley and San Lorenzo Valley Water Districts, over a dozen small water systems, and roughly 1100 parcels served by private wells. The groundwater table also influences surface water in the San Lorenzo River, a primary drinking water source for the City of Santa Cruz and a home for endangered species. The GSP for this basin was approved by DWR in 2023.
- **Mid-County Groundwater Basin:** This basin is located at the northern end of the Central Coast hydrologic region, extending from the Santa Cruz Mountains to the Pacific Ocean and from Live Oak to La Selva Beach along the Pacific coast, including a portion of the City of Santa Cruz, all of the City of Capitola, and unincorporated areas of Santa Cruz County. The land uses served by the basin are predominantly residential (50%) and open space/parks (34%), with limited commercial (8%) and agriculture (2%). The basin has been classified as in critical overdraft due to seawater intrusion. The GSP for the basin was approved by DWR in 2021.
- **Pajaro Valley Groundwater Basin:** The basin encompasses approximately 75,000 acres in portions of Santa Cruz, Monterey, and San Benito Counties adjacent to the Monterey Bay. Total water use in the Pajaro Valley tends to range between about 47,000 and 55,000 acre-feet/year, with the Aromas Red Sands as the principal aquifer and providing the majority of pumped groundwater. Long-term groundwater overdraft in the 20th century lowered water levels throughout the basin and led to seawater intrusion. The GSP-Alternative Plan for this basin was approved by DWR in 2019.

Integrated Regional Water Management Plan

The water purveyors within Santa Cruz County work together to make the county's limited water resources sustainable for current and future generations through an Integrated Regional Water Management Plan (IRWM). This plan covers the entire county and has provided for ongoing collaboration among agencies, as well as facilitated grant funding for project implementation. Some of the most progressive water conservation programs in the country have been implemented by local Santa Cruz agencies, resulting in the county's per-capita water use being far below state or national averages. Water purveyors also work cooperatively and individually to develop additional sources of water, such as desalted sea water and recycled wastewater.

Urban Water Management Plans (UWMP)

Jurisdictions either supplying over 3,000 acre-feet of water annually or serving more than 3,000 urban connections are required to submit an Urban Water Management Plan (UWMP) for review and approval by the California Department of Water Resources (DWR), pursuant to California Water Code, § 10610-10656 and § 10608. The plans must be updated every five years and support the suppliers' long-term resource planning to ensure that adequate water supplies are available to meet existing and future water needs. The information collected for UWMPs is useful for local, regional, and statewide water and drought planning.

UWMPs also explore stormwater capacity and assist in planning and funding future stormwater needs. (DWR, 2025)

All jurisdictions participating in this MJHMP which are also water suppliers have an UWMP, including the City of Watsonville and the Soquel Creek and Scotts Valley Water Districts. These jurisdiction-specific plans are explored in more detail in the annexes in Volume 2.

Sana Cruz County General Plan Agriculture, Natural Resources & Conservation Element

The Santa Cruz County General Plan Agriculture, Natural Resources, and Conservation Element sets forth Goal ARC-4, several objectives, and many policies relevant to mitigation of and resiliency to drought. Goal ARC-4 directs the county to protect and manage water resources in order to preserve the quality and quantity of water supplies and protect natural habitats for current and future generations. The following objectives and policies support this goal:

- **Objective ARC-4.2 Watershed Protection:** To protect and manage watersheds, including least disturbed watersheds and those that provide surface water supplies, to preserve the quality and quantity of water as well as habitat [and recreational] values, and meet the needs of county residents, local industry, agriculture, and the natural environment while taking into account the projected effects of climate change. Policies under this objective designate critical watersheds; limit new development, including subdivision and allowed density, within some of these watersheds and additional areas crucial for maintaining water quality; and require proper stormwater management.
- **Objective ARC-4.3 Adequate Streamflows:** To protect and restore in-stream flows to ensure a full range of beneficial uses including recreation, fish and wildlife habitat, and visual amenities, as part of an ecosystem-based approach to watershed management and groundwater management that also takes into account the projected effects of climate change. Policies under this objective designate critical water supply streams; prohibit new diversions and seek to restore in-stream flows to support beneficial uses; and require mitigation measures for new water supply projects.
- **Objective ARC-4.4 Surface Water Quality:** To protect and enhance surface water quality in the county's streams, coastal lagoons, and marshes by establishing best management practices on adjacent land uses. Policies under this objective limit development near and alterations to these water resource areas; establish setbacks for septic systems; and require stormwater management and erosion control measures.
- **Objective ARC-4.5 Groundwater Protection and Overdraft:** To protect the quantity and quality of the county's groundwater resources through an integrated program of land use regulation and runoff management in groundwater recharge areas and karst areas, careful water quality monitoring and management of extractions consistent with long-term sustainable water supply yields and projected effects of climate change. The objective also directs the county to coordinate and work with water agencies to eliminate long-term overdraft in all basins where it has been documented. Policies under this objective designate primary recharge areas and protection zones; limit new land uses and development within recharge areas, including subdivision and allowed density; direct the study and protection of highly permeable karst areas; and require new wells to meet certain standards.

Santa Cruz County Climate Action & Adaption Plan (CAAP)

The Santa Cruz County Climate Action and Adaption Plan (CAAP) provides a comprehensive roadmap to address the challenges of climate change in unincorporated Santa Cruz County. The CAAP identifies drought as one of the three most concerning hazards for the county that will be compounded by climate change and establishes strategies and objectives to address this hazard. These include protecting and managing local county aquifers and increasing the use of recycled wastewater and stormwater for both irrigation and general use.

3.2.8.3 Past Events

A drought is a period of dry weather that persists long enough to cause serious problems such as crop damage and water supply shortages. In recent history, Santa Cruz County has experienced three main drought periods: 1976 to 1977, 1987 to 1992, 2007 to 2009, and 2012 to 2016. It is expected that the effects of climate change will result in more severe droughts of longer duration.

Figure 3-64 shows a time series of the level of drought in Santa Cruz County between 2002 and 2024 according to the National Drought Monitor. The National Drought Monitor provides drought data and maps nationally and on a localized, watershed-scale. The National Drought Monitor is the product of 11 agencies, including the National Drought Mitigation Center (NDMC) at the University of Nebraska-Lincoln, National Oceanic and Atmospheric Administration (NOAA), and U.S. Department of Agriculture (USDA). The National Drought Monitor categorizes the level of drought from D0 through D4, with D4 being the highest "exceptional drought." Table 3-64 depicts drought classifications and impacts from the level of drought occurrence in California.



Figure 3-64: County-Wide Drought History and Severity Chart

Table 3-64: Drought Classifications and Impacts for California

Category	Description	Possible Impacts
D0	Abnormally Dry	▪ Soil is dry; irrigation delivery begins early ▪ Dryland crop germination is stunted ▪ Active fire season begins ▪ Winter resort visitation is low; snowpack is minimal
D1	Moderate Drought	▪ Dryland pasture growth is stunted; producers give supplemental feed to cattle ▪ Landscaping and gardens need irrigation earlier; wildlife patterns begin to change ▪ Stock ponds and creeks are lower than usual
D2	Severe Drought	▪ Producers increase water efficiency methods and drought-resistant crops ▪ Grazing land inadequate ▪ Fire season is longer, with high burn intensity, dry fuels, and large fire spatial extent; more fire crews on staff ▪ Lake- and river-based tourism declines; boat ramps close ▪ Trees are stressed; plants increase reproductive mechanisms; wildlife diseases increase ▪ Water temperatures increase; programs to divert water to protect fish begin ▪ River flows decrease; reservoir levels are low and banks are exposed
D3	Extreme Drought	▪ Federal water not adequate to meet irrigation contracts; extracting supplemental groundwater is expensive ▪ Fire season lasts year-round; fires occur in typically wet parts of the state; burn bans are implemented ▪ Ski and rafting business is low; mountain communities suffer ▪ Low water levels impede fish migration and cause lower survival rates ▪ Wildlife encroach on developed areas; little native food and water is available for bears, which hibernate less ▪ Water sanitation is a concern; reservoir levels drop significantly; surface water is nearly dry, flows are very low; water theft occurs ▪ Livestock need supplemental feed, cattle and horses are sold; little pasture remains ▪ Well and aquifer levels decrease; homeowners drill new wells
D4	Exceptional Drought	▪ Fire season is very costly; number of fires and areas burned are extensive ▪ Many recreational activities are affected ▪ Fields are left fallow; orchards are removed; vegetable yields are low; honey harvest is small; agricultural unemployment is high, food aid is needed ▪ Fish rescue and relocation begins; pine beetle infestation occurs; forest mortality is high; wetlands dry up; wildlife death is widespread; algae blooms appear ▪ Poor air quality affects health; greenhouse gas emissions increase as hydropower production decreases; West Nile outbreaks rise ▪ Water shortages are widespread; surface water is depleted; federal irrigation water deliveries are curtailed; water prices are extremely high; wells are dry, more and deeper wells are drilled; water quality is poor

Source: Adapted from U.S. Drought Monitor Drought Classifications and Impacts

3.2.8.4 Location

Drought is one of the few hazards with the potential to directly or indirectly impact the entire population of Santa Cruz County, be it from water restrictions, higher water and food prices, reduced air or water quality, restricted access to recreational areas, or secondary impacts like wildfire. No portion of the county is immune from drought conditions.

3.2.8.5 Frequency & Probability of Future Occurrences

Droughts may not be predictable, but they should be expected. They occur with some regularity and varying levels of severity. The magnitude and duration of a drought, as shown in Figure 3-64, is something that can be predicted based on historical records and should be taken into account in water resources planning. According to the results of the hazard risk ranking exercises conducted by the participating jurisdictions, the probability of drought occurring in Santa Cruz County is likely (between 10% and 100% annual probability).

Currently there is no data on the probability of drought akin to data for predicting earthquakes or flood probability. Empirical studies conducted over the past century have shown that meteorological drought is never the result of a single cause. It is the result of many causes, often synergistic in nature; these include global weather patterns that produce persistent, upper-level high-pressure systems along the West Coast with warm, dry air resulting in less precipitation.

The expected effects of climate change will also increase the risk of drought. Numerous climate models have been run with various predictions for the Santa Cruz County area. Although it is unclear whether the average amount of rainfall will increase, it is apparent that the timing and intensity of rainfall will change, which will lead to more severe and extended droughts. More intense rainfall (as opposed to longer, less intense events) will not contribute as much to groundwater recharge or dry season stream baseflows and will ultimately have adverse impacts on water supply quality through flooding and erosion.

3.2.8.6 Severity

The severity of a drought depends on the degree of moisture deficiency, the duration, and the size and location of the affected area. The longer the duration of the drought and the larger the area impacted, the more severe the potential impacts. Droughts are not usually associated with direct impacts on people or property, but they can have significant impacts on agriculture, local economies, and natural resources, impacting people indirectly.

Drought eventually affects groundwater sources but generally not as quickly as surface water supplies, but groundwater supplies take longer to recover. Reduced precipitation during a drought means that groundwater is not replenished at a normal rate, leading to problems such as reduced pumping capacity, wells going dry, seawater intrusion, and land subsidence. Shallow wells are more susceptible than deep wells. Reduced replenishment of groundwater also affects streams and other surface water supplies. Much

of the flow in streams comes from groundwater, especially during the summer when there is less precipitation. Reduced groundwater levels mean that even less water will enter streams when steam flows are lowest.

On average, the nationwide annual impacts of drought are greater than the impacts of any other natural hazard. They are estimated to be between $6 billion and $8 billion annually in the United States and occur primarily in the agriculture, transportation, recreation and tourism, forestry, and energy sectors. Water-dependent industries are commonly forced to shut down all or a portion of their facilities, resulting in layoffs. Social and environmental impacts are also significant, although it is difficult to put a precise cost on these impacts. Droughts that occur in populated areas may not have direct effects to the residents but may increase the threat of wildfire.

Impacts on Agriculture

The agricultural sector demonstrates the potential site-specific impacts of drought. Droughts of just a few weeks during critical periods of plant development can have disastrous effects on agriculture production. A drought can result in farmers not being able to plant crops or the failure of planted crops, leading to loss of work for agricultural workers and those in food industries.

Agricultural drought impacts are normally felt earliest by those relying on unmanaged water supplies: entities carrying out dryland grazing and non-irrigated crop production, usually grain crops. Impacts to irrigated agriculture depend on the source and nature of the irrigation water supply, whether it be local groundwater, local surface water, or imported surface water, and any water rights or contractual provisions that may be associated with the source. The extent to which producers may mitigate water shortage impacts depends on multiple factors but is heavily influenced by economic considerations. Factors involved in making decisions about mitigating irrigation water shortages include availability and costs of pumping groundwater, price of alternative surface water sources, capital investments associated with maintaining permanent plantings, and status of international crop markets. (California Drought Contingency Plan, 2021)

The 2023 Economic Contributions of Santa Cruz County Agriculture Report indicates that agriculture contributed $1.558 billion to the county economy. This includes approximately $655 million in crop value and economic activity associated with agriculture. The report indicated agriculture directly employed nearly 9,000 people in Santa Cruz County. It should be emphasized that 2023 was above-average water year for Santa Cruz County and, thus, a single-year drought or a multi-year drought has the potential to deleteriously affect the county's agricultural economy.

Reduced reservoir storage from decreased runoff in the mountains can lead to water shortages. Stream flow is inadequate to meet demands during a drought and all the major groundwater basins in Santa Cruz County are in some level of overdraft (i.e., more water is being extracted from the aquifers than is naturally recharged through the soils and stream valleys). In the Pajaro Valley, agricultural use far exceeds sustainable yield. In other parts of the county, historical development contributes to the overdraft both through demand but also because development covers the ground surface with impervious layers that

greatly reduce groundwater recharge. Drought conditions sometimes encourage agricultural producers who historically used surface water to switch to groundwater, which can further deplete the resource. Negative consequences of overdraft include declining groundwater levels, a decrease in groundwater quality, reduced streamflow, and seawater intrusion along the coast that destroys wells.

The projected increase in temperatures from climate change will also lead to an increase in water demand for irrigation, particularly in the inland parts of the county that are less influenced by coastal fog. Further, elevated temperatures will lead to greater rates of evapotranspiration, exacerbating reduced stream flow. The water agencies in the county provide detailed assessments of water supplies, which help to better quantify the expected impacts of climate change.

3.2.8.7 Warning Time

Unlike most disasters, droughts normally occur slowly but last a long time. Droughts are climatic patterns that occur over extended periods of time. Only generalized warning can take place due to the numerous variables that scientists have not pieced together well enough to make accurate and precise predictions.

Scientists at this time do not know how to predict drought more than a month in advance for most locations. Predicting drought depends on the ability to forecast precipitation and temperature. Anomalies of precipitation and temperature may last from several months to several decades. How long they last depends on interactions between the atmosphere and the oceans, soil moisture and land surface processes, topography, internal dynamics, and the accumulated influence of weather systems on the global scale.

3.2.8.8 Drought Vulnerability Analysis

Vulnerability to drought varies with the different water agencies and their water sources. Agencies with a greater reliance on surface water are more vulnerable than those that rely entirely on groundwater. For this reason, many county water agencies have installed interties among jurisdictions to be able to exchange water in the event of an emergency or shortage.

The county-wide decline in groundwater levels and streamflow is indicative of the continuing need to reduce any non-essential water use throughout the planning area by small and large water systems, private wells, and stream diversions. Conservation programs, curtailment programs, and plans to increase water supply are all components that will decrease the vulnerability of the community to drought.

3.2.8.8.1 Population

The entire population of Santa Cruz County is either directly or indirectly susceptible to drought hazards. Direct susceptibility includes reduced water availability and health impacts. Indirect susceptibility includes higher water rates, less food supply, fewer water recreational opportunities, and local economic impacts. With agriculture being a major piece of Santa Cruz County's economy, reduced employment in this sector is one of the primary indirect impacts to the population.

According to the Center for Disease Control and Prevention, a number of adverse public health effects and conditions can be attributed either directly or indirectly to drought. For example, people exposed to dust clouds are at increased risk for acquiring "dust pneumonia," an often fatal type of pneumonia caused when dust fills the lungs and inflames them. During droughts, dry soils and secondary wildfires increase the amount of airborne particles such as dust and smoke. These particles can irritate the airways and worsen chronic respiratory illnesses such as asthma.

Drought can affect vulnerable populations as well as economic productivity throughout Santa Cruz County and is likely to exacerbate water affordability concerns, through the context of availability, for low-income populations. During drought years, property owners with shallow wells can be impacted by drought with increased demand on groundwater resources. Surface water supplies are often lower, which can reduce availability and increase costs. If groundwater levels drop too far during extended periods of drought, then wells may run dry. Many rural residents are on single well or small water systems that do not have water supply resiliency components built into their maintenance and operations plans; these populations are highly vulnerable to direct drought impacts.

Drought can also have significant impacts on landscapes from reduced water availability and imposed conservation restrictions. While this could cause a financial burden to property owners, especially low-income populations who may not be able to afford to maintain their properties during water shortages, the main impact from drought on landscaping is the emergent wildfire threat induced by dried vegetation. Further, the impacts to surrounding natural plant communities (and wildlife) that occur as the result of severe drought conditions also increase the risk of wildfire and subsequent impacts on people and damage to structures as a result.

3.2.8.8.2 Property

No structures will be directly affected by drought conditions, though some structures may become more vulnerable to indirect effects such as those from wildfires, which are highly likely to follow years of drought. Physical property losses are mostly limited to public and private landscaping.

While structures are not at risk, significant economic losses may occur as a result of severe rationing during a water shortage. One of the county's major industries is tourism. The vulnerability to drought (or more specifically water shortages as a result of drought) reaches its peak during the summer tourism season. Restaurants, hotels, amusement parks, and other tourist serving businesses would all be at risk of closing from severe restrictions during a critical drought. This, in turn, impacts the funding of county services because of the county's reliance on the Transient Occupancy Tax (TOT).

Other industries such as agriculture, food processing, contractors, landscapers, nurseries, golf courses, public landscaping and school grounds would all experience losses, and other water-dependent businesses would suffer economic damages. The agricultural sector is particularly susceptible to drought impacts, as discussed in Section 3.2.8.6.

3.2.8.8.3 Critical Facilities & Infrastructure

Although critical facilities and infrastructure, as defined for this plan, will continue to be operational during a drought, some of these systems and the essential services they support are vulnerable to and can be impacted by severe drought. According to the U.S. Department of Homeland Security, Office of Cyber and Infrastructure Analysis (OCIA), these include water, wastewater, energy, and communications systems and emergency services. In addition, the facilities and lifelines themselves may be impacted by secondary hazards caused by drought, such a damage from wildfire.

Besides physical scarcity of water for the operation of water and wastewater systems, contamination of water sources can occur during drought conditions. Water reservoirs may experience increased pollutant levels and lower levels of oxygen, contributing to higher concentrations of illness-causing bacteria and protozoa, as well as toxic blue-green algae blooms. Reduced flow levels in rivers and aquifers can allow saltwater to move inland and also contaminate the water supply. Most water treatment plants are not equipped to remove salts, which can cause problems not only for potable water but also for industrial uses. (OCIA, 2015)

In Santa Cruz County, which has relatively shallow underground karst aquifers, droughts may also increase the likelihood of land subsidence or sinkhole formation, as aquifers are depleted and unsupported ground collapses. When these collapses occur, they may result in water or wastewater pipe breaks buried nearby, leading to unfiltered water entering from lakes and streams and, eventually, aquifers used as drinking water sources, sullying the drinking water supply.

In today's economies, water systems are tightly linked to energy and communications systems, and recent droughts have focused national attention on these infrastructure connections. For example, when severe drought affected more than a third of the United States in 2012, limited water availability constrained the operation of some power plants and other energy production activities. All sources of energy (including electricity) require water in their production processes for things such as cooling, cleaning, and powering turbines. Because of the interdependency between the energy sector and availability of water, drought greatly affects the resilience of these systems. (*Id.*)

Communications equipment and information technology data centers use water for cooling. Data centers, for example, often use high-tonnage heating, ventilating, and air conditioning systems that require drinkable water to operate. A sustained loss of water to a communications facility during a drought can cause equipment shutdown or failure, resulting in a degradation of communication capabilities and the disruption of some services for minutes to hours.

During extraordinary dry conditions, fire services especially are met with challenging restraints. Reduced water availability can complicate firefighting efforts in urban and suburban areas where standard wildfire-fighting tactics, such as chemical retardants and controlled burns, are less suitable. Some fire suppression equipment, including hydrants, requires a minimum level of water pressure to activate and work properly, which may not always be available during severe drought periods. (*Id.*)

3.2.8.9 Development Trends

The greater Santa Cruz area is a compact urban area surrounded by mountains, greenbelt, and the Pacific Ocean. The sizes of the water service areas are generally fixed by the county's urban services line via its Growth Management Ordinance. Water service areas for all jurisdictions have generally remained constant over time due to policies limiting water main extensions to unserved areas. The only extensions of service or agency boundaries have involved incorporating an existing developed area into a larger district, which has better capabilities for providing reliable water service. Accordingly, any growth and redevelopment that does happen going forward is expected to be concentrated within the confines of the existing service area boundaries.

Only a relatively small amount of land remains undeveloped in the county; consequently, the majority of future growth is likely to be achieved through redevelopment, remodeling, in-fill, and increased density on underutilized land, along with new construction on the little amount of vacant land remaining. In other words, the service areas are relatively fixed and not growing outward. There has not been a residential subdivision in rural areas of the county since the adoption of Measure J, the county's growth management plan, in the late 1970s. A few other municipalities have also established urban growth boundaries.

The general plan housing elements of the county and incorporated cities set forth goals and objectives for housing production, rehabilitation, and conservation, and must address water needs to support their allocation of units. The plans identify generally where sites are available for housing to be built and describe programs to facilitate new housing opportunities; however, this does not necessarily mean such housing will be constructed. Regardless, all new development is required to incorporate water conservation measures to mitigate potential impacts from drought.

3.2.8.10 Drought Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing drought-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with drought hazards. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-65 presents the drought problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in Table 4-1 and Table 4-2..

Table 3-65: Santa Cruz County Drought Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Drought	Victim	**ps-DR-SCC-01**	Prolonged drought can reduce surface water supplies and force greater reliance on groundwater for irrigation, leading to lower crop yields, higher production costs, and economic losses that ripple through the broader regional economy.
Drought	Victim	**ps-DR-SCC-02**	Many residents—particularly renters, low-income households, and non-English speakers—face barriers to implementing drought-related water conservation measures due to limited control over property infrastructure, financial constraints, and lack of accessible information in multiple languages.
Drought	Impact	**ps-DR-SCC-03**	Prolonged droughts reduce aquifer recharge, particularly in the Mid-County and Pajaro Valley basins, leading to increased groundwater pumping and risk of seawater intrusion and land subsidence.
Drought	Impact	**ps-DR-SCC-04**	Reduced streamflow and reservoir levels during drought lead to higher water temperatures, lower dissolved oxygen, and contaminant concentration, threatening watershed health, coastal water quality, ecological and public health, while increasing treatment costs.
Drought	Impact	**ps-DR-SCC-05**	Drought can severely reduce the reliability of small and private water systems, especially shallow residential wells that often lack contingency plans or interties to larger water systems, leaving residents without water for extended periods and facing costly emergency hauling.
Drought	Threat	**ps-DR-SCC-06**	Drought compounds wildfire hazards by intensifying fuel drying and increasing ignition potential and fire spread, heightening risk in WUI areas and across the State Responsibility Areas within the County.
Drought	Threat	**ps-DR-SCC-07**	In Davenport, where the County supplies water through a County Service Area (CSA), there is no groundwater supply option. If creek source water dries up, the community must rely on limited storage tanks and purchased water from the City of Santa Cruz.

3.2.8.11 Climate Change Impacts & Vulnerable Populations

Drought is a recurring hazard in Santa Cruz County and is projected to worsen with climate change. Rising temperatures, reduced snowpack, and shifting precipitation patterns are leading to more frequent and severe multi-year droughts that strain groundwater basins, stress ecosystems, and reduce the reliability of surface water supplies. These pressures increase dependence on groundwater pumping, heighten the risk of seawater intrusion, and accelerate long-term challenges to agricultural production and drinking water availability.

Direct Impacts: Drought reduces water available for crops, irrigation, and household use, with cascading impacts on the regional economy and food security. Reduced streamflow and reservoir levels threaten watershed health, increase contaminant concentrations, and raise the costs of treatment and delivery. Small and private water systems, especially shallow residential wells, face high risks of running dry, leaving households without reliable access to water.

Secondary Hazards: Drought intensifies wildfire hazards by drying vegetation, extending the fire season, and increasing ignition potential across the county. In addition, drought reduces the capacity of streams and aquifers to recharge, compounding risks of land subsidence and saltwater intrusion in the Mid-County and Pajaro Valley groundwater basins.

Public Health and Social Impacts: Vulnerable populations including renters, low-income households, non-English speakers, and farmworker communities face disproportionate drought impacts. Many lack control over property infrastructure, have limited financial resources, or do not have access to conservation information in multiple languages. These barriers reduce the ability of households to comply with conservation mandates or prepare for water shortages. In communities such as Davenport, where the County supplies water through a County Service Area (CSA), drought threatens local supply reliability because there is no backup groundwater option.

The mitigation strategy addresses drought by improving conservation outreach in multiple languages, strengthening coordination with small and private water systems, enhancing drought contingency planning, and expanding water supply resilience projects that reduce reliance on over-drafted aquifers and support equitable access to safe, reliable water.

Extreme Heat

3.2.9 Extreme Heat Profile



Extreme heat is defined as temperatures that are much hotter and/or more humid than average for a particular location and the time of year. In Santa Cruz County, an extreme heat day that exceeds the 98th percentile of daily maximum temperatures is one at or above 90°F, and a warm night (also exceeding the 98th percentile) is one at or above about 55°F. A heat wave is an extended period of extreme heat days or warm nights, lasting days to weeks.

As a climate change-driven hazard, unusually hot and humid summer days and warm nights have become more common since the 1960s. (Bole, et al., 2018) The effects of extreme heat are amplified in urban centers such as in an around the Cities of Watsonville and Santa Cruz, with consequences for health, air quality, and utilities.

Studies show that by the end of this century, the number of days with temperatures reaching 100°F or more is projected to increase dramatically across the United States as a result of climate change. What the public now considers to be an exceptional event could become routine across much of the country. As temperatures rise and extreme heat events become longer, more severe, and more frequent, experts expect to see more health problems and deaths caused by heat.

Heat has a greater toll on human health—as measured by deaths (mortality) and negative health outcomes (morbidity)—than all other natural disasters combined. (NIHHIS, 2021) In California, a high number of heat-related deaths occurred in 2006, when a record-breaking heat wave between July 15 and August 1 in Northern California was linked to 650 deaths and 16,000 excess emergency room visits. (California Office of Environmental Health Hazard Assessment, 2019) Although Santa Cruz County has rarely experienced extreme heat in the past, heat waves and events are anticipated to increase in frequency, severity, and duration as climate change progresses in the coming decades, even in the areas like the City of Capitola where marine influences generally provide moderate temperatures.

Heat-related death and illness are widely regarded as preventable within the public health community; despite this, extreme heat kills over 600 people in the U.S. annually. (CDC, 2021) The following populations face specific vulnerability to heat-related illness:

- Seniors aged 65+, especially those who live alone;
- Infants and children;
- Low-income households;
- Unhoused people;
- Individuals with chronic underlying medical conditions;
- Athletes; and
- Agricultural and other outdoor workers.

The cumulative impacts of extreme heat events, along with smaller, longer-term differences in seasonal average temperatures, exacerbate inequities in health outcomes among already at-risk groups. (NIHHIS,

2021) Heat impacts are distributed inequitably among low-income communities of color in the United States. On average, Black and Latino households are more cost-burdened, occupy denser housing stock, and have lower access to heat-coping strategies, such as air conditioning and access to green space.

Within Santa Cruz County, geographic patterns in extreme heat are mostly influenced by topography. The coastal areas of the county are heavily influenced by marine temperature gradients. While extreme heat days are defined by localized variation from norms, the inland valley areas tend to experience higher temperatures than the coastal or mountain areas. That being said, air conditioning systems are less prevalent in the county and the population may be less adapted to higher temperatures compared to regions which regularly experience high heat events.

According to the Santa Cruz County Climate Action and Adaption Plan (CAAP), the average maximum and minimum temperatures in the county are expected to increase 3.2°F to 4°F by mid-century and 4.3°F to 7°F by end of the century.

Although Santa Cruz County is predominantly rural, there are clusters of highly urbanized areas. Urbanized areas experience higher temperatures than natural landscapes, creating localized pockets of higher temperatures known as heat islands. Roads and conventional building materials reflect less solar energy and absorb and re-emit more heat compared to trees and other vegetation. Heat islands can build throughout the day and worsen immediately after sunset as heat is slowly released from pavement and building material. The graph in Figure 3-65 demonstrates the impact of increased urbanization in relation to diurnal fluctuation of temperature extremes, with urban areas sometimes experiencing daytime highs 7°F greater than surrounding non-urban environments. (EPA, 2024)

Urban heat islands disproportionately affect low-income urban populations and people of color, communities who are more likely to occupy older (see section Figure 1-7: Age of Countywide Building Stock), higher density housing stock with lower urban forest cover and less access to air conditioning. A 2020 study of 108 urban areas across the U.S. found that neighborhoods subjected to federal redlining policies in the first half of the 20th century, which discouraged investment in neighborhoods with high minority populations, currently experience surface temperatures approximately 5°F higher than their non-redlined counterparts. (Hoffman, Shandas, & Pendleton, 2020)



Figure 3-65: Day and Night Urban Heat Island Effect Across Natural and Built Landscapes

Source: U.S. Environmental Protection Agency

3.2.9.1 Secondary & Compounding Hazards

The most significant secondary hazards associated with extreme heat events are increased public health risks from heat-related and vector-borne illness (discussed in Section 3.2.9.6), wildfires fueled by heat-related vegetation die-off and stress, and power outages. Climate change is the main driving force behind the increase in extreme heat events and is further discussed in Section 3.2.10.

Wildfire & Air Quality

Extreme heat often coincides with conditions favorable to wildfires and contributes to vegetation stress and mortality, fueling these hazards. Wildfires during extreme heat events can place excess health burdens on wildland firefights, impeding fire containment. Extreme heat further increases the negative effects of poor air quality from particulates like smoke as well as ozone-related sensitivities. While wildfires do not always present during extreme heat events, extreme heat always increases the risk of human health impacts to

poor air quality. Climate change has a long-term negative effect on air quality metrics, including ozone. (State of California, 2018)

Power Outages

High temperatures may increase peak electricity demand beyond system capacity as residents switch on air conditioning units. Loss of power during a high heat poses a risk to human health by limiting access to air conditioning and disrupting continuous power supply for medical equipment. In California, high heat days may also coincide with conditions that trigger Public Safety Power Shutoff (PSPS) events by utility providers to curb wildfire ignition risk from faulty powerline equipment, which could disrupt residential power supply for air conditioning and at-home medical equipment.

Climate Change

The state and county have seen increased average temperatures, more extremely hot days, fewer cold nights, and shifts in the water cycle from climate change. Increased greenhouse gases in the atmosphere raises temperatures and alters seasonal temperature patterns. Effects can include changes in average temperature, the timing of seasons, and the degree of cooling that occurs in the evening. In addition to new seasonal temperature patterns, extreme events such as heat waves are projected to occur more frequently and last for longer periods of time. Though extreme heat may be moderated in the county's coastal location, inland areas can experience much higher temperatures, and even under reduced emissions scenarios, climate change is expected to increase the frequency, intensity, and duration of extreme heat events in the Santa Cruz County region.

3.2.9.2 Policies, Plans & Regulatory Environment

Very few formal regulations exist which pertain to extreme heat, except for workplace safety standards for outdoor workers. There are no state or local regulations pertaining to cooling technology standards for general residential buildings, but places of work, senior residential facilities, schools, and childcare centers are subject to state regulations for indoor air temperature standards. However, there is an extensive regulatory environment concerning climate change in that profile under Section 3.2.10.

State Regulatory Environment

California Outdoor Heat Illness Prevention Standard

Title 8, Section 3395 of the California Code of Regulations establishes an Outdoor Heat Illness Prevention Standard for employers of outdoor workers. Established in 2006, it requires employers to provide water and shade access; to develop a heat illness prevention plan; and provide heat illness prevention and response training to employees. Specific procedures must be followed for temperatures exceeding 80°F and 95°F. Employers must provide shade, water, and monitor for signs of heat illness. Workers also have a right to request breaks to cool off.

Local Regulatory Environment

Santa Cruz County General Plan Built Environment Element

The Santa Cruz County General Plan Built Environment Element contains objectives, policies, and implementation strategies related to extreme heat events, including designing new development with the environment (Objective BE-4.2) and fostering safe public spaces (Objective BE-4.3). A few key policies and strategies related to extreme heat include:

- **Policy BE-3.5.9:** Plan for evolving visitor accommodation needs related to climate change, including an influx of visitors to the county from hotter inland regions during extended and more frequent heat waves.
- **Strategy BE-4.2f:** Strengthen the county's design criteria regarding urban heat islands, such as establishing maximum impervious area limits and greening requirements.
- **Strategy BE-4.3.9:** Incorporate more street trees to provide shade at regular intervals and for parking areas, buildings, and the public realm to improve the pedestrian experience and reduce the urban heat island effect.

3.2.9.3 Past Events

The rarity of extreme heat events in the past is largely a result of the county's coastal climate; however, climate change is expected to increase the number of events experienced in the county, and more recent data shows a trend toward increasing temperatures, especially in the Santa Cruz Mountains. Figure 3-66 identifies the maximum annual temperatures and number of days exceeding 89°F at the Ben Lomond and Watsonville Weather Stations between 2000 and 2024.

Some populations are already exposed, namely, agricultural and outdoor workers, and most residents in Santa Cruz County are not equipped with air conditioning to address these events. The 2022 Santa Cruz County CAAP indicates that the county has historically experienced 11 warm nights a year and is projected to experience a mid-century total of 46 warm nights and an end-century total of 50 to 90 warm nights.



Figure 3-66: Number of Days Above 89°F at Ben Lomond and Watsonville Weather Stations, 2000-2024

Source: NOAA National Centers for Environmental Information

3.2.9.4 Location

Extreme heat events have the potential to happen anywhere in Santa Cruz County but are likely to be most pronounced in and around dense urban centers and upper elevation inland valleys above the marine layer. Observed ground temperatures and impacts during extreme heat events may vary widely based on surface materials and due to differences in housing density, building type, year of construction, access to air conditioning, and presence of tree canopy.

3.2.9.5 Frequency & Probability of Future Occurrences

Santa Cruz County is expected to experience an increase in the frequency and probability of extreme heat events as the climate warms. Rather than only tracking changes in average annual temperatures, current best practice focuses on the number of days exceeding defined thresholds, such as daily maximums above 95°F and nights that remain above 65°F. These indicators provide a more practical measure of community exposure to harmful heat conditions. Projections indicate that both hot days and warm nights will occur with greater regularity throughout the century, creating heightened risks for public health, energy systems, and vulnerable populations.

The Santa Cruz County Climate Action and Adaption Plan (CAAP) indicates the county has an average maximum temperature of 67.4°F and an average minimum temperature of 43.1°F. However, the average maximum and minimum temperatures in the county are expected to increase with mid-century projections showing a 3.2°F to 4°F increase in temperature maximum and minimums, and end-century projections show a 4.3°F to 7°F increase.

The CAAP uses Cal-Adapt data based on the localized constructed analogs (LOCA) downscaled climate model ensemble, consistent with state guidance. Expressed in terms of extreme heat thresholds, these projections translate into a substantial increase in the number of days above 95°F and warm nights above 65°F, indicating not only hotter summers but also reduced nighttime cooling. This shift will amplify risks to public health, energy demand, and sensitive populations.

3.2.9.6 Severity

Extreme heat kills by taxing the human body beyond its abilities. In a normal year, about 175 Americans succumb to the demands of heat during the summertime. In the 40-year period from 1936 through 1975, nearly 20,000 people were killed in the United States by the effects of heat and solar radiation. In the heat wave of 1980, more than 1,250 people died. (Disasters Are Us, n.d.) Although these events preceded the boom in residential use of air conditioning nationwide, they demonstrate the severity of extreme heat events when people are left without such protections.

Because the human body is capable of acclimating to local climate conditions, there is no single temperature that serves as a definition of extreme heat. This MJHMP uses the definitions set forth by Cal-Adapt (a data download interface provided by the CEC) for extreme heat events, warm nights, and heat waves, with descriptions and threshold values for Santa Cruz County outlined in Table 3-66.

Table 3-66: Cal-Adapt Extreme Heat Terms

Term	Cal-Adapt Definition	Thresholds for Santa Cruz County
Extreme Heat Day	Defined as a day in a year when the daily maximum/minimum temperature exceeds the 98th percentile of daily maximum/minimum temperatures based on observed historical data from 1961-1990 between April and October.	**90°F**
Warm Night	Defined as a day in April through October when daily minimum temperature exceeds the 98th historical percentile of daily minimum temperatures, based on observed data from 1961-1990 between April and October.	**55.2°F**
Heat Wave	Defined as four consecutive days or nights above the extreme heat / warm night threshold.	**3 days ≥ 90°F** or **4 nights ≥ 55.2°F**

Source: Cal-Adapt Extreme Heat Days and Warm Nights Tool

Heat Stress Indicators

Humidity plays a large role in determining how hot conditions actually feel. As the air becomes saturated with moisture, the body loses its ability to shed excess heat through sweating. Warm and humid nights contributed to the fatal nature of the July 2006 heatwave in California. (Hulley, Dousset, & Kahn, 2020)

A heat index describes what temperatures feel like to the human body, accounting for both air temperature and humidity. Figure 3-67 shows the Nation Weather Service's (NWS) heat index classifications and calculation chart based on temperatures at different relative humidities, which are used to forecast the heat watches, warnings, and advisories for local areas described in Table 3-69. The heat index was developed for shaded, light wind conditions; it does not capture hazards from exposure to direct sunlight and hot, dry winds, which may be relevant to populations who exercise or perform physical work in direct sun.

The wet bulb global temperature (WBGT) is an indicator of heat stress for active populations that incorporates temperature, humidity, wind, solar radiation, and other weather parameters. (National Weather Service, 2022) Different heat stress indicators are useful for different applications; the WBGT may be more useful for workplace safety or athletic programs, but the heat index can help reveal community-wide vulnerabilities for inactive populations who are able to seek shade during an extreme heat event.

HEAT INDEX CLASSIFICATION

Caution	80°F - 90°F	Fatigue possible with prolonged exposure and/or physical activity
Extreme Caution	90°F - 103°F	Heat stroke, heat cramps, or heat exhaustion possible with prolonged exposure and/or physical activity
Danger	103°F - 124°F	Heat cramps or heat exhaustion likely, and heat stroke possible with prolonged exposure and/or physical activity
Extreme Danger	125°F or higher	Heat stroke highly likely

National Weather Service Heat Index Classifications. National Oceanic and Atmospheric Administration. Values are for shaded areas, sunny locations can increase value by up to 15°F. The **heat index** is what temperature the human body feels in relation to both humidity and temperature.

HEAT INDEX CALCULATION CHART

Relative Humidity (%) \ Temperature (°F)	80	82	84	86	88	90	92	94	96	98	100	102	104	106	108	110
40	80	81	83	85	88	91	94	97	101	105	109	114	119	124	130	136
45	80	82	84	87	89	93	96	100	104	109	114	119	124	130	137	
50	81	83	85	88	91	95	99	103	108	113	118	124	131	137		
55	81	84	86	89	93	97	101	106	112	117	124	130	137			
60	82	84	88	91	95	100	105	110	116	123	129	137				
65	82	85	89	93	98	103	108	114	121	128	136					
70	83	86	90	95	100	105	112	119	126	134						
75	84	88	92	97	103	109	116	124	132							
80	84	89	94	100	106	113	121	129								
85	85	90	96	102	110	117	126	135								
90	86	91	98	105	113	122	131									
95	86	93	100	108	117	127										
100	87	95	103	112	121	132										

Source: National Weather Service.

Figure 3-67: Head Index Classification and Calculation

Health Impacts

The human body possesses a variety of adaptations to regulate internal temperature under warm conditions, including sweat glands, exposed skin, and walking on two legs. Above-average temperatures, even outside summer months, compromise the body's ability to internally regulate, leading to excess illness and death. Heat-related health impacts include exacerbating existing medical conditions and acute illness related to direct exposure to high temperatures, such as heat cramps, heat exhaustion, and heat stroke, as described in Table 3-67.

Table 3-67: Heat-Related Illnesses

Heat-Related Illness	Symptoms
Heat Cramps	▪ Symptoms include muscular pains and spasms, usually in the stomach, arms, and leg muscles. ▪ Usually results from heavy exertion, such as exercising during extreme heat. ▪ Although heat cramps are the least severe of all heat-related problems, they are usually the first signal that the body is having trouble coping with hot temperatures.
Heat Exhaustion	▪ Heavy sweating ▪ Pale, clammy, moist skin ▪ Extreme weakness or fatigue ▪ Muscle cramps ▪ Headaches ▪ Dizziness or confusion ▪ Nausea or vomiting ▪ Fast and shallow breathing ▪ Fainting
Heat Stroke	▪ Flushed, hot, dry skin (no sweating) ▪ Body temperature above 103˚F ▪ Confusion or dizziness ▪ Throbbing headache ▪ Rapid or strong pulse ▪ Unconsciousness Heat stroke is the most severe heat-related illness and occurs when a person's temperature control system, which produces sweat, stops working. Heat stroke may lead to brain damage and death.

Many chronic medical conditions are exacerbated by high temperatures, including cardiovascular and respiratory diseases. Extreme heat days are associated with increases in hospital visits and emergency medical service (EMS) calls for heat-related illnesses along with cardiovascular and respiratory complications, renal failure, electrolyte imbalance, kidney stones, preterm birth, and negative fetal health outcomes. (Ebi, et al., 2018) Warm nighttime temperatures may also reduce the body's ability to recover from extreme heat during the day, especially for people with underlying chronic ischemic conditions such as coronary heart disease. (Sarofim, et al., 2016) The annual number of extreme heat days and warm nights the Santa Cruz County region is expected to increase over the next century, driven by climate change, which is discussed further in its hazard profile (Section 3.2.10).

3.2.9.7 Warning Time

Meteorologists can often predict the likelihood of an extreme heat event up to 10 days in advance. This can give several days of warning time. However, meteorologists cannot predict the exact time of onset or severity of the event and some may come on more quickly or severely than expected.

Since 2014, the National Weather Service (NWS) has issued heat-related alerts for local areas based on its HeatRisk index that are then propagated in California by Cal OES. The NWS's HeatRisk index assigns a numerical value ranging from 0 to 4 based on average historical conditions for a given local area and time of year and also accounts for the vulnerability of specific groups such as outdoor workers, children, and the

elderly (Table 3-68). This tool accounts for differences in local adaptations to climate identifies unusual heat (defined as the warmest 5% of temperatures) specifically for a particular date and location, resulting in daily thresholds that are unique for each location and date. For example, the index recognizes that residents of Florida are better prepared for 90°F weather than residents of Alaska.

Each HeatRisk level is accompanied by recommendations for heat protections and serves as a useful tool for planning for upcoming heat events. Based on the index and other forecasting tools, NWS issues watches, advisories, and warnings for heat events, depending on confidence and imminence factors (Table 3-69).

Table 3-68: NWS HeatRisk Categories and Related Impacts

Category	Risk	Heat-Related Impacts
0 Green	**Little / None**	Little to no risk from expected heat.
1 Yellow	**Minor**	Primarily affects those who are extremely sensitive to heat and without cooling/hydration.
2 Orange	**Moderate**	Affects those who are sensitive to heat, especially those without cooling/hydration, and some health systems and industries.
3 Red	**Major**	Affects anyone without cooling/hydration as well as health systems and industries.
4 Magenta	**Extreme**	Rare and/or long-duration extreme heat with no overnight relief affecting anyone without cooling/hydration as well as health systems, industries, and infrastructure.

Source: National Weather Service

Table 3-69: NWS Heat Forecast Terms and Definition

Alert Type	Criteria	HeatRisk Category
Heat Advisory	Issued for dangerous heat conditions not expected to reach warning criteria. Consider postponing or rescheduling outdoor activities. Stay hydrated and find a cool indoor place during the heat of the day.	**2-3** (Orange to Red)
Excessive Heat Watch	Issued when an extreme heat event is possible but its occurrence and timing are still uncertain. Reschedule outdoor activities in the coming days. Make sure that children, elderly, and pets have a place to cool off during the heat.	**3-4** (Red to Magenta)
Excessive Heat Warning	Issued when extremely dangerous heat conditions are expected or occurring. Avoid heavy activity and direct sunlight. Stay hydrated, find a cool indoor place, and check on children, elderly, and pets.	**3-4** (Red to Magenta)

Source: National Weather Service

3.2.9.8 Extreme Heat Vulnerability Analysis

3.2.9.8.1 Population

Santa Cruz County has historically been buffered by the impacts of extreme heat due to the colder marine and fog influence cooling down evening temperatures and tempering early to mid-morning temperatures. However, the average maximum and minimum temperatures in the county are expected to increase with mid-century projections showing a 3.2°F to 4°F increase in temperature maximum and minimums, and end-century projections show a 4.3°F to 7°F increase. The planning area has historically experienced 11 warm nights a year, but is projected to experience a mid-century total of 46 warm nights and an end-century total of 50 to 90 nights, which will further exacerbate the risk of heat illness because they affect the body's ability to cool after a day of heightened temperatures.

Health impacts of extreme heat are not distributed equally, with certain groups facing compounding vulnerability to extreme heat, particularly populations such as older adults, young children, individuals experiencing homelessness, and individuals with underlying chronic diseases. Areas with higher populations of seniors and low-income households, and low cover of trees and green surfaces, face the highest exposure to extreme heat hazards. Most residents in Santa Cruz County are not equipped with air conditioning to address these events. The most sensitive populations in the county reside in the areas surrounding the City of Watsonville, north of Soquel Village between Soquel San Jose Road and North Rodeo Gulch Road, and in some parts of the Live Oak region.

3.2.9.8.2 Property

Although extreme heat days in Santa Cruz County are not expected to reach temperatures that would affect most buildings, older structures (see Figure 1-7: Age of Countywide Building Stock) are generally more vulnerable to the impacts of extreme heat. High temperatures can cause roofs and other structural components to expand and warp, weakening the structural integrity of buildings. Aging pipes are vulnerable to leaks or breakage during periods of increased water demand, as residents seek relief from heat by turning on sprinklers, filling pools, or using hoses.

In addition, agricultural crops may suffer during extreme heat events. This can result in reduced crop yields and cause a reduction in the nutritious value of the crops for the consumer. Heat events also negatively affect livestock, causing reductions in fertility, less resilience to disease, and lower production of goods such as eggs and milk. (NOAA, 2023) In Santa Cruz County, these impacts on the agricultural sector would have rippling effects from farm and food industry workers to the other sectors that support them.

3.2.9.8.3 Critical Facilities & Infrastructure

Many types of infrastructure are impacted by prolonged exposure to extreme heat including rails, roads, and aviation. High temperatures can lead to deterioration of pavement and expansion or buckling of sidewalks and roads. (Federal Highway Administration, 2013) Railroad tracks are at risk of buckling at temperatures

exceeding 100°F. (Union of Concerned Scientists, 2018) However, in Santa Cruz County, it is unlikely that temperatures will get high enough to cause direct damage to most types of critical facilities or infrastructure, but there may still be impacts to structural integrity, system operations, and public services.

The most common problems associated with extreme heat are loss of utilities. Public safety power shutoffs during high heat conditions combined with fire weather or increased demand on the grid from cooling systems can cause brownouts or blackouts that leave vulnerable populations without electricity and expose them heat-related illness. While those in poverty, children, and the elderly are the most at risk, no one is completely safe without the ability to stay cool. And without power, other utility systems that lack backup generation may not function. Energy demand and grid vulnerability is expected to increase across the nation and in California. (California Energy Comission, 2018) Increased energy usage and higher demand peaks can stress electricity grid system, while extreme temperatures can decrease the safe operating capacity of hardware. (US Department of Energy, 2019, p. 12)

Extreme heat events are also increasingly disruptive to educational opportunities for children. Research has shown that up to 41% of schools in the country may not have proper cooling or ventilation systems, which have already caused early school dismissals and cancellations. (NOAA, 2023) Early class dismissals or cancellations due to heat put more strain on worker attendance and productivity for some parents as they scramble to find childcare, and these conditions expose children to heat-related health risks as well as lower test scores in some instances.

3.2.9.9 Development Trends

Although population growth and new development continues to occur across the county, energy efficiency and worker safety regulations help address heat-related hazards by limiting exposure, and local services include providing community cooling centers. The county's General Plan also establishes objectives and policies aimed at protecting its communities from the impacts of extreme heat, especially in the few urbanized areas. In particular, the General Plan calls for several strategies to mitigate extreme heat hazards through activities such as urban forestry and greening to reduce urban heat islands. Additionally, the City of Watsonville has an adopted Urban Greening Plan that sets specific goals for increasing tree cover.

California residential and building codes require residential units to have heating, but this requirement does not exist for air conditioning. The California Building Standards Code, which has been adopted by the county and other participating municipalities, includes provisions for energy efficiency that may help increase power grid resilience to peak demand during heat events.

3.2.9.10 Extreme Heat Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing extreme heat-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and

experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with extreme heat. Instead, they highlight the most urgent concerns that can be addressed within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3-70 presents the extreme heat problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in in Table 4-1 and Table 4-2.

Table 3-70: Santa Cruz County Extreme Heat Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Extreme Heat	Victim	**ps-EH-SCC-01**	Farmworkers and other outdoor workers are routinely exposed to extreme heat, often compounded by drought and wildfire smoke, which can cause illness and exacerbate underlying respiratory and other health conditions, with disproportionate impacts on already vulnerable populations.
Extreme Heat	Threat	**ps-EH-SCC-02**	While the County has planning and coordination in place for severe weather response (low temperature and heavy rain), it lacks a formal strategy with partners for a network of cooling centers during extreme heat events, particularly for unsheltered and medically vulnerable populations. The few public facilities that could serve as resilience centers often require upgrades, backup power, air filtration, and ADA-accessible services.
Extreme Heat	Threat	**ps-EH-SCC-03**	Cal-Adapt climate models project an increase in extreme heat days and warm nights County-wide but especially in inland mountain areas, including for areas with historically mild microclimates which are less prepared with cooling strategies and infrastructure investment.
Extreme Heat	Impact	**ps-EH-SCC-04**	Heat emergencies increase demand for EMS and hospital services, particularly during extended events, and the county has limited surge capacity and real-time monitoring of heat-related illness.
Extreme Heat	Victim	**ps-EH-SCC-05**	Seniors, those with underlying health conditions, people experiencing homelessness, and households without HVAC systems face heightened, and sometimes life-threatening, risks during extreme heat events, particularly when compounded by underlying health conditions or limited access to medical care.

3.2.9.11 Climate Change Impacts & Vulnerable Populations

Extreme heat is an emerging hazard in Santa Cruz County and is projected to become more frequent and severe as climate change accelerates. Rising temperatures, longer heatwaves, and warmer nights will increase health and safety risks, particularly in inland and mountain areas that have historically had mild microclimates and are less prepared with cooling strategies or resilient infrastructure. Extreme heat often compounds other hazards such as drought and wildfire smoke, amplifying risks for both human health and critical infrastructure.

Direct Impacts: Extreme heat threatens public health, energy reliability, and continuity of essential services. Increased electricity demand for cooling raises the risk of brownouts or blackouts, which can disrupt public safety operations and limit access to indoor cooling. Heat also stresses critical systems such as water supply, stormwater infrastructure, and transportation networks, with prolonged events creating additional maintenance and operational challenges.

Secondary Hazards: Extreme heat often coincides with drought, wildfire, and poor air quality, creating cascading risks. Farmworkers and outdoor laborers face simultaneous exposure to heat and wildfire smoke, heightening risks of illness, dehydration, and long-term respiratory damage. Extended periods of high temperatures also reduce nighttime cooling, placing chronic stress on vulnerable populations and increasing the likelihood of medical emergencies.

Public Health and Social Impacts: Vulnerable populations including seniors, individuals with underlying health conditions, people experiencing homelessness, low-income households, renters, and non-English speakers face the greatest risks during extreme heat events. Many households lack air conditioning, financial means to absorb higher energy costs, or reliable access to cooling centers. The County does not yet have a fully developed strategy for cooling centers or resilience hubs, and existing facilities often lack backup power, air filtration, or accessibility upgrades. As a result, those most at risk may be unable to access safe, reliable shelter during extended heat events.

The mitigation strategy addresses extreme heat by expanding access to cooling centers, improving outreach to vulnerable populations in multiple languages, strengthening monitoring of heat-related illness, and investing in resilience upgrades for public facilities. These actions aim to reduce inequities and enhance the County's overall preparedness for a warming climate.



Climate Change

3.2.10 Climate Change Hazard Profile

Santa Cruz County has experienced seven federally declared disasters since 2017 tied to climate-driven hazards such as coastal storms, wildfires, flooding, and extreme wind events. Climate change is increasing the frequency, severity, and unpredictability of these disasters, intensifying long standing risks and expanding their reach into areas and populations that have not been as exposed in the past.

Throughout this plan, each hazard section includes an assessment of how climate change is expected to alter frequency, severity, and cascading impacts. This integrated approach ensures that mitigation strategies are informed by the best available climate science and address the ways climate change is making existing hazards more damaging and harder to manage.

This stand-alone section on climate change focuses specifically on sea level rise, a subhazard that requires unique attention due to its long-term and irreversible impacts. Unlike other hazards that can ebb and flow with weather cycles, sea level rise will steadily increase exposure for coastal communities, infrastructure, and ecosystems. Rising seas compound flood risk, accelerate coastal erosion, and threaten the stability of underground utilities, transportation corridors, and low-lying neighborhoods. Vulnerable populations, including low-income residents and those living near the shoreline, will face disproportionate impacts from displacement, loss of access, and reduced public safety.

It is important to emphasize that this Multi Jurisdiction Hazard Mitigation Plan is not a climate change plan. Broader strategies to reduce greenhouse gas emissions and plan for long-term climate adaptation are addressed in the County's 2022 Climate Action and Adaptation Plan (CAAP). Instead, this plan highlights how climate change drives hazard risk, while treating sea level rise as a stand-alone hazard due to its unique and compounding challenges.

Climate Projections: Representative Concentration Pathways (RCP)

Climate change projections must account for many different variables besides greenhouse gas emissions (GHG), including changes in energy generation and land use, global and regional economic circumstances and population growth. So that research among different groups is complementary and comparable, a standard set of scenarios was developed to ensure that starting conditions, historical data, and projections are employed consistently.

These scenarios are referred to as Representative Concentration Pathways (RCP), which show the time-dependent trajectories of GHG concentrations in the atmosphere and corresponding global temperature outcomes. A range of RCPs has been developed that reflect the potential timing of global action or inaction in decreasing GHGs, resulting in a lower or higher global average temperature.

Location is a key factor in determining the range of impacts from climate change. In California, the University of California Berkeley Geospatial Innovation Facility developed a platform called Cal-Adapt funded by the California Energy Commission (CEC). This platform provides tools and data on climate change

across the state, including for Santa Cruz County, from global scale models that have been localized (downscaled) to 3.7-mile by 3.7-mile grids.

Cal-Adapt data combined with information from the California Fourth Climate Change Assessment was used to model future changes in specific types of hazards in the 2022 CAAP consistent with the information presented in this section; projections are outlined by two separate RCPs:

- **RCP 4.5** is a medium emissions scenario where global emissions peak by the year 2040 and then decline.
- **RCP 8.5** is a high emissions scenario in which global emissions continue to rise through the end of the twenty-first century.

Sea Level Rise

While the sea level rose a little less than a foot over the past century, most scientists are concerned that due to the increase in greenhouse gases from human activity, warming will accelerate. As a result, glaciers will continue to retreat and the rate of sea level rise will increase, with the best estimate being about three feet higher by 2100.

As stated in other hazard profiles projected impacts from rising sea level will accelerate coastal erosion, increase the extent of coastal inundation, increase localized elevated groundwater levels, and magnify the impacts of severe storm and wave events including El Niño and atmospheric river events. The State of California Sea Level Rise Guidance: 2024 Science and Policy Update projects a statewide average of 0.8 feet of rise by 2050. By 2100, statewide sea levels are expected to rise between 1.6 feet and 3.1 feet.

The State of California Sea Level Rise Guidance: 2024 Science and Policy Update is considered the best available science and provides sea level rise projections that have been refined for 12 tide gauges throughout California. The report provides projections for planning purposes based on probability of occurrence and the level of risk aversion. Low risk aversion means a high risk of occurrence, and extreme risk aversion means an extremely low risk of occurrence.

3.2.10.1 Policies, Plans & Regulatory Environment

Successful efforts to address the challenges of climate change begin at the local level and include the implementation of environmentally sustainable practices designed to meet present and future energy needs.

State Regulatory Environment

California Green Building Standards

The County has adopted the California Green Building Standards, also known as CALGreen Code. CALGreen Code establishes regulations for green building, nonresidential and residential buildings. Topics covered in the regulations include planning and design, energy efficiency, water efficiency and conservation, material

conservation and resource efficiency and environmental quality. The code also includes voluntary measures for residential, nonresidential and health facilities.

California Sustainable Communities and Climate Protection Act

The Sustainable Communities and Climate Protection Act of 2008 (Sustainable Communities Act, SB 375, Chapter 728, Statutes of 2008) looks to reduce GHG emissions through coordinated transportation and land use planning with the goal of more sustainable communities. Regional targets are established for GHG emissions reductions from passenger vehicle use by the sustainable communities strategy (SCS) established by each metropolitan planning organization (MPO). The SCS is an integral part of regional transportation plans (RTP) and contains land use, housing, and transportation strategies to meet GHG reductions targets.

SB 375 also supports state requirements that a city or county General Plan contains a Safety Element in addition to a Hazard Mitigation Plan. AB 2140 also requires a vulnerability assessment, adaptation goals, policies and objectives, and a set of feasible implementation measures.

California Adaptation Planning Guide (APG)

California has been taking action to address climate change for over 20 years, focusing on both greenhouse gas emissions reduction and adaptation. The California APG provides guidance and support for communities addressing the unavoidable consequences of climate change.

California Coastal Commission Sea Level Rise Guidance

The California Coastal Commission Sea Level Rise Guidance provides guidance for addressing sea level rise in coastal programs and development permits. The guidance includes interpretive guidelines for LCPs and is based on updated scientific knowledge of statewide sea level rise and coastal hazards. It offers practical approaches for state agencies, local governments, and communities to enhance coastal resilience and protect vital ecosystems. The guidance emphasizes the importance of sustainable adaptation strategies to manage the impacts of rising sea levels.

Local Regulatory Environment

Santa Cruz County 2022 Climate Action & Adaption Plan (CAAP)

The Climate Action and Adaption Plan (CAAP) provides a comprehensive roadmap to address the challenges of climate change in unincorporated Santa Cruz County. The 2022 CAAP includes the most current data on climate impacts for unincorporated Santa Cruz County. The 2022 CAAP is comprised of actionable steps towards reducing the causes of global warming, adapting our communities to climate hazards, and ensuring the safety and well-being of those most vulnerable to climate change.

The CAAP indicated that the Santa Cruz mass emissions budget for 2019 was 691,262 metric tons of carbon dioxide equivalents (CO_2e). The CAAP identified the top three Santa Cruz County greenhouse gas emissions sources as 1) passenger vehicles (51%); 2) residential natural gas (15%); and 3) commercial vehicles (13%).

The CAAP sets forth a greenhouse gas emissions target of 448,762 metric tons of CO_2e by 2045 for unincorporated Santa Cruz County. To reach this target, the CAAP sets for a target of reducing mass emissions from 1990 levels by 191,111 metric tons of CO_2e by 2030 and an additional 257,651 metric tons of CO_2e by 2045. The CAAP indicated that the Santa Cruz Mass Emissions for 2019 was 691,262 metric tons of CO_2e by 2045.

The CAAP proposes to meet this 2045 target through the following goals: 1) affordable housing; 2) healthy ecosystems; 3) healthy communities; 4) decarbonization; 5) resilience; 6) staff engagement; and 7) programmatic approach. The CAAP sets forth 29 strategies that pertain to energy, transportation, water, waste, wildfire prevention & mitigation strategies, and government operations to implement the goals.

Santa Cruz County General Plan

The 2024 Santa Cruz County General Plan Update sets forth the following goal and objectives relevant to climate change. Goal ARC-3 is to Protect and restore biological resources, including unique, rare, threatened, and endangered plant and animal species and their habitats, that warrant preservation because of their biological and scientific values, contributions to open space, and importance in maintaining a healthy environment and mitigating the effects of climate change. Climate change-related objectives include:

- **Objective ARC-4.2:** To protect and manage watersheds, including least disturbed watersheds and those that provide surface water supplies, to preserve the quality and quantity of water as well as habitat values, and to meet the needs of county residents, local industry, agriculture, and the natural environment while taking into account the projected effects of climate change.
- **Objective ARC-4.3:** To protect and restore in-stream flows to ensure a full range of beneficial uses including recreation, fish and wildlife habitat and visual amenities, as part of an ecosystem-based approach to watershed management and groundwater management that also takes into account the projected effects of climate change.
- **Objective ARC-4.5:** To protect the quantity and quality of the County's groundwater resources through an integrated program of land use regulation and runoff management in groundwater recharge areas and karst areas, careful water quality monitoring and management of extractions consistent with long-term sustainable water supply yields and projected effects of climate change. To act directly and coordinate and work with relevant water purveyors and agencies to eliminate long-term groundwater overdraft in all water basins where overdraft has been documented.

3.2.10.2 Past Events

Climate change is currently affecting California and Santa Cruz County, where global mean sea level has risen by as much as seven inches along the coast over the last century, increasing pressure on the state's

and county's infrastructure, water supplies, and natural resources. The state and county have seen increased average temperatures, more extreme hot days, fewer cold nights, shifts in the water cycle with less winter precipitation falling as snow, and snowmelt running off sooner in the year (California Natural Resources Agency, 20189).

There is consensus among the world's leading climate change scientists that human-generated emissions of heat-trapping greenhouse gases (GHGs) are the primary cause of the warming trend. Projections indicate that atmospheric concentrations of GHGs will continue to increase throughout this century. Data describing atmospheric GHG concentrations over the past 800,000 years demonstrates that concentrations of carbon dioxide (CO2), the primary anthropogenic GHG, have increased substantially since pre-industrial times, driven largely by economic and population growth, and are now higher than ever. This has led to atmospheric concentrations of carbon dioxide, methane and nitrous oxide that are unprecedented in at least the last 800,000 years. Their effects, together with those of other anthropogenic drivers, have been detected throughout the climate system and are extremely likely to have been the dominant cause of the observed warming since the mid-20th century. (IPCC,2014).

The Intergovernmental Panel on Climate Change (IPCC) described potential global emission scenarios for the coming century. The scenarios vary from a best-case, characterized by low population growth, clean technologies, and low GHG emissions; to a worst-case, wherein high population and fossil-fuel dependence result in extreme levels of GHG emissions. Continued emission of greenhouse gases will cause further warming and long-lasting changes in all components of the climate system, increasing the likelihood of severe, pervasive, and irreversible impacts for people and ecosystems. Limiting climate change would require substantial and sustained reductions in greenhouse gas emissions which, together with adaptation, can limit climate change risks.

Many aspects of climate change and associated impacts will continue for centuries, even if anthropogenic emissions of greenhouse gases are stopped. The risks of abrupt or irreversible changes increase as the magnitude of the warming increases (IPCC 2014) Our natural, economic, and cultural systems are closely tied to the climate. Significant changes in the climate will impact the way people live: the food we grow, our health and safety, the availability of water, our economy, wildlife and vegetation, and many other aspects of our lives.

3.2.10.3 Location

The effects of climate change are not limited by geographical borders. Santa Cruz County, the State of California, the United States, and the rest of the world are all at risk of climate change. As such, the entire county is at risk to the effects of climate change. Sea level rise will directly impact areas along the county's coastline; however, it is also likely to impact other areas of the county secondarily, such as saltwater intrusion into aquifers affecting drinking water. See a summary of exposure to sea level rise in Figure 3-68.



Sea Level Rise Exposure

Unincorporated County

*Data sources: COSMOS v3.1.

Sea Level Rise

Figure 3-68 Unincorporated County - Standard Layout - Sea Level Rise Exposure

3.2.10.4 Frequency & Probability of Future Occurrences

In terms of how likely and quickly impacts will occur, temperature related impacts are the most likely near-term climate change exposure facing the county and should be addressed and prioritized in future adaptation planning efforts. While sea level rise has a high certainty rating and is already occurring, its onset is not expected to occur until closer to the end of the century in terms of changes in areas already vulnerable to flooding or causing permanent inundation in tidally-influenced areas of the County. Addressing increases in flooding and wildfire risk have mid-term onsets and should be prioritized accordingly.

Climate change is one of the few natural hazards where the probability of occurrence is influenced by human action. In addition, unlike earthquake and floods that occur over a finite time period, climate change is an ongoing hazard. The California Climate Adaptation Strategy delineated how climate change may impact and exacerbate natural hazards in the future, including wildfires, extreme heat, floods, drought, and levee failure:

- Climate change is expected to lead to increases in the frequency, intensity, and duration of extreme heat events and heat waves in Santa Cruz County and the rest of California, which are likely to increase the risk of mortality and morbidity due to heat-related illness and exacerbation of existing chronic health conditions. Those most at risk and vulnerable to climate-related illness are the elderly, individuals with chronic conditions such as heart and lung disease, diabetes, and mental illnesses, infants, the socially or economically disadvantaged, and those who work outdoors.
- Droughts are likely to become more frequent and persistent in the 21st century.
- Intense rainfall events, periodically ones with larger than historical runoff, will continue to affect California with more frequent and/or more extensive flooding.
- Winter storms may produce higher runoff from the landward side, while accelerating sea-level rise will produce higher storm surges during coastal storms.

Droughts and warmer and more severe weather can be expected to increase wildfire through fuel hazards and ignition risks. These changes can also increase plant moisture stress and insect populations, both of which affect forest health and reduce forest resilience to wildfires. An increase in wildfire intensity and extent will increase public safety risks, property damage, fire suppression and emergency response costs to government, watershed and water quality impacts, vegetation conversions, and habitat fragmentation.

Sea Level Rise

In 2017, the Central Coast Wetlands Group conducted a study of future sea level rise impacts along the Santa Cruz County coast. The report, titled Coastal Climate Change Vulnerability Report, was funded through a grant from the Ocean Protection Council through the Local Coastal Program (LCP) Sea Level Rise Adaptation Grant Program. This grant program is focused on updating LCPs and other plans authorized under the Coastal Act, such as Port Master Plans, Long-Range Development Plans and Public Works Plans (other

Coastal Act authorized plans) to address sea-level rise and climate change impacts, recognizing them as fundamental planning documents for the California coast.

An update to the original study was initiated in 2025, called the Sea Level Rise Vulnerability Assessment Project, and aims to achieve the same objectives and more from the 2017 project to further regional planning for the inevitable impacts associated with sea-level rise (SLR):

- Identify what critical coastal infrastructure will be compromised due to SLR and estimate when those risks may occur; and
- Define appropriate response strategies for these risks and discuss with regional partners the programmatic and policy options that can be adopted for LCP updates.

The 2017 project incorporated the most complete inventory of coastline revetment and seawalls for the Monterey Bay with coastal hazard GIS layers to account for existing protections from current and future coastal hazards. The project evaluated the impacts of sea level rise, coastal flooding, and coastal erosion on municipal infrastructure, private properties, and natural resources, and also evaluated relevant state policies and adaptation response alternatives ranging from "grey to green" for integration into municipal planning. The results of the study identified Pajaro Dunes and East Cliff and Opal Cliffs Drives as particularly vulnerable locations.

Both the 2017 and 2025 projects have fostered regional discussions about the integration of appropriate adaptation strategies.

Santa Cruz County Sea Level Rise Vulnerability Assessment & LCP Amendment

The 2025 Santa Cruz County Sea Level Rise Vulnerability Assessment (SLRVA) Project is a comprehensive planning effort to identify potential risks and adaptation strategies along the county's roughly 32-mile shoreline which will be used to inform future decisions to enhance long-term resilience to climate change. The project aims to address challenges like sea-level rise and erosion while safeguarding property values, natural resources, and equitable access to recreation.

The SLRVA will provide technical analyses related to coastal hazard vulnerabilities, economics, and adaptation planning at the county-wide and neighborhood scales, culminating in an amendment to the county LCP. The evaluation of adaptation options will be heavily based on community outreach, including with marginalized populations, and will be incorporated into the LCP Land Use and Implementation Plans

3.2.10.5 Severity

The State of California has been addressing climate change impacts projected severity of impacts for more than two decades through policies that reduce greenhouse gas emissions and promote climate adaptation. To support local governments, the California APG provides a framework for assessing climate risks and developing adaptation strategies across 11 climate impact regions defined by geographic and environmental factors. Santa Cruz County is part of the Central Coast region, characterized by its Pacific Ocean coastline

and the Santa Cruz Mountains, with most urban development concentrated on the coastal plain. At the county level, the Santa Cruz Climate Action and Adaptation Plan (CAAP) provides projections for climate-related changes including temperature, precipitation, coastal fog, sea level rise, riverine and stormwater flooding, extreme heat, drought, wildfire, and air quality.

Sea Level Rise

Sea level rise can negatively impact the coastal area of Santa Cruz County through related hazards including tidal inundation, coastal storm flooding, coastal erosion, and dune erosion. Tidal inundation occurs when sea level rises (due to storm events or climate change) and high tide events become co-occurrent, allowing water levels to reach higher points on beaches, and occasionally cause localized coastal flooding or our low-lying areas.

Coastal storm flooding, also known as storm surge, refers to the phenomena of water rising to abnormal and unpredicted elevations during a storm. When coupled with high tide, storm surge can cause extreme flooding and coastal erosion. The Santa Cruz County coastline is dominated by sandstone cliffs which are susceptible to cliff erosion. When sea level rise causes waves to break against the base of the cliffs, it can cause the cliff face to become unstable and to erode.

In Santa Cruz County, dunes provide protection to agricultural fields, residences, and commercial areas from sea level rise related hazards in the southern part of the county. When sea levels rise, dunes are not able to function naturally and can more easily be eroded, leading to more tidal inundation, slope stability for coastal bluff top development and coastal flooding.

The State of California Sea Level Rise Guidance: 2024 Science and Policy Update projects a statewide average of 0.8 feet of rise by 2050. By 2100, statewide sea levels are expected to rise between 1.6 feet and 3.1 feet. Sea level rise will have impacts to coastal critical facilities and many residential properties will be at high risk. Sea level rise in the county has the potential to negatively impact both private and public infrastructure including the wastewater treatment plant, sewer infrastructure, coastal transport infrastructure, critical facilities including fire stations and schools, the County Jail, oceanfront residences, and commercial properties.

Other Projected Impacts

Beyond the stand-alone discussion of sea level rise, climate change is expected to intensify multiple hazards that are already present in Santa Cruz County. This section introduces projected impacts to precipitation and coastal fog, riverine and stormwater flooding, extreme heat, drought, wildfire, and air quality. These impacts are not entirely new hazards but rather shifts in the frequency, severity, and extent of events that communities already experience. Each hazard profile in this plan contains its own discussion of climate change impacts and vulnerable populations. The following material highlights the broader

scientific projections that tie these hazards together, showing how climate change will increasingly challenge public health, infrastructure, ecosystems, and the resilience of vulnerable communities across the county.

Precipitation & Coastal Fog

In the Central Coast of California, precipitation variability is expected to increase substantially. Santa Cruz County can expect longer and more frequent dry spells as well as an increase in the number of years with below average rainfall totals. Santa Cruz County has already experienced damaging extreme precipitation events in 2017 and again in 2021. It is projected that the wettest day every year will increase by up to 35 percent for some Coastal California locations by the end of the century. Maximum 1-day precipitation values are projected to increase between 0.2 inch and 0.3 inch by mid-century and between 0.3 inch and 0.6 inch by the end of the century.

On average, the projections show little change in total annual precipitation in California. Furthermore, among several models, precipitation projections do not show a consistent trend during the next century. The Mediterranean seasonal precipitation pattern is expected to continue, with most precipitation falling during winter from North Pacific storms. However, even modest changes would have a significant impact because California ecosystems are conditioned to historical precipitation levels and water resources are nearly fully utilized. (Cal-Adapt, 2018)

In Santa Cruz County, summertime coastal fog reduces temperatures, increases water availability, and reduces evapotranspiration and respiration by plants. Fog moisture is transported from the ocean and can provide up to 33 percent of the water received by the neighboring ecosystems. In the county many native species, including coastal redwood trees and the ecosystems beneath their canopy, rely on high summertime fog frequency to maintain their habitat. Agriculture depends on coastal fog to reduce summer temperature extremes and to reduce crop demand for water and irrigation. Changes in air patterns, urban heat, and air quality all can cause changes in fog prevalence. Additionally, vectors, including Shothole bore and mosquitos are expected to be more prevalent.

Riverine & Stormwater Flooding

Low-lying areas throughout Santa Cruz County are expected to experience more frequent flooding as a result of climate change. Riverine flooding is projected to increase as precipitation extremes increase. Stormwater systems may be overwhelmed more frequently as more extreme rain events occur, causing localized flooding which could impact properties and close streets. Data from the Santa Cruz County MJHMP identifies over 2,000 1 to 4-unit residential structures, over 200 other habitable structures, and approximately 16,000 permanent Santa Cruz County residents living in flood hazard areas. Several schools, fire stations, hospitals, and police stations are located within the flood plains, as shown in Figure 11. Flooding impacts create physical damage directly through inundation. Flooding can also trigger cascading impacts to power, water, and wastewater services and stormwater drainage infrastructure which may exacerbate public health concerns for vulnerable populations.

Extreme Heat

Santa Cruz County has an average maximum temperature of 67.4°F and an average minimum temperature of 43.1°F. The average maximum and minimum temperatures are expected to increase in the county with mid-century projections showing a 3.2°F to 4.0°F increase in temperature maximum and minimums.

For Santa Cruz County, the threshold temperature is 90°F. Increased frequency of extreme heat days can result in increased public health risks through an increase in heat-related and vector-borne illnesses. Particularly vulnerable populations include older adults, young children, and individuals with underlying chronic diseases. Santa Cruz County has historically been buffered by the impacts of extreme heat due to the colder marine and fog influence cooling down evening temperatures and tempering early to mid-morning temperatures. Warm nights will further exacerbate the risk of heat illness because they affect the body's ability to cool after a day of heightened temperatures.

Figure 3-69 depicts California historical and projected temperature between 1961 and 2099. Overall temperatures are projected to rise substantially throughout this century. These projections differ depending on the time of year and the type of measurement (highs vs. lows), all of which have different potential effects to the county's ecosystem health, agricultural production, water use and availability, and energy demand.



Figure 3-69: California Historical and Projected Temperature Increases, 1961 to 2099

Source: Dan Cayan, California Climate Adaptation Strategy

Drought

Climate change will increase the likelihood that low-precipitation years will coincide with above-average temperature years. Warming temperatures increase seasonal dryness and the likelihood of drought due to

decreased supply of moisture and increased atmospheric demand for moisture as evaporation from bare soils and evapotranspiration from plants increases. The increased moisture loss from soils and vegetation amplifies dryness during periods without precipitation. In California's highly variable climate setting, climate models project less frequent but more extreme daily precipitation, with year-to-year precipitation becoming more volatile and the number of dry years increasing. The duration of dry spells is projected to vary depending on which emissions scenario is used. Like precipitation patterns, some of the annual variability is obscured within 30-year averages. Despite this, the clear trend is for maximum lengths of dry spells to increase through the end of century.

Wildfire

The occurrences of wildfires have increased significantly within California in frequency and intensity over the past two decades. Santa Cruz County is projected to experience increasing wildfire risk through the end of the century. An increase in temperatures and prevalence of drought conditions are projected to result in increased wildfire risk through decreases in ground and ladder fuel moisture levels. Wildfires in the Central Coast region are influenced by wind events, utility infrastructure, topography, humidity, fuel availability, and lightening or other severe weather (Langridge 2018). From 1948 to 2019, 15 wildfires were responsible for burning 61,455 acres in the county. The 2020 CZU Lightening Complex Fire burned a total of 85,509 acres and 1431 structures.

There are many areas in the county categorized by CAL FIRE as Moderate, High, and Very High Fire Hazard Severity Zones (FHSZs). Some areas in the county that border fire hazard zones are considered WUI areas, which are zones of transition between open space and residential or commercial development. These areas are particularly at risk to damage because they often have significant quantities of vegetative fuels for fire near buildings and facilities that are vulnerable to fire. The county is projected to experience an increase in the decadal probability of wildfire by 20 percent by the end of the century.

Air Quality

In Santa Cruz County, good ambient air quality is typically maintained by the mountains and breezy coastal environment. However, the San Lorenzo Valley and other inland areas can experience poor air quality more frequently due to a lessening coastal wind influence and local topography. Worsening air quality due to climate change can create respiratory issues for vulnerable populations and impact indoor areas without adequate air filtration systems. There are several types of air quality decline sources found below:

- **Dust:** Dry, dusty conditions also associated with drought and increased evaporation.
- **Smog:** Increases in ambient temperature can lead to higher rates of smog also referred to as ozone. Ground-level ozone specifically will be experienced at higher rates leading to raised cardiovascular and respiratory morbidity and mortality rates. Ground-level ozone has also been shown to have particularly disproportionate adverse impacts on populations experiencing homelessness and lower median income. Santa Cruz County is expected to experience increases in ozone concentrations in tandem with temperature increases.

- **Wildfire Smoke:** Temperature, severe wildfire conditions, and the area burned by wildfires throughout the state has increased and will continue to increase. Higher temperatures accompanied by an increase in the incidence and extent of large wildfires will lead to increased wildfire smoke and associated toxins and air pollution. Poor air quality can force school and business closures and limit healthy outdoor activity.

3.2.10.6 Warning Time

As this section as described, many existing hazards could be intensified as a result of climate change, decreasing warning times and exacerbating impacts. Warning times are discussed under the various other hazards. Other climate change impacts are more long-term; scientists have a high confidence in predicting the rise in global temperatures and have reached a consensus on the future impacts of climate change and the time frame in which they will occur.

3.2.10.7 Vulnerability Assessment

This section outlines vulnerabilities of Santa Cruz County to impacts from climate change and focuses on sea level rise in particular, as many of the other impacts are secondary and outlined in other hazard profiles.

3.2.10.7.1 Population

The predicted health effects of climate change include increased incidence of emerging diseases and vector-borne disease if ecological changes lead to migration of insect and animal disease vectors, and physical and mental health impacts associated with severe weather events, such as flooding, when they cause population dislocation and infrastructure loss. Though extreme heat may be moderated in our coastal location, inland areas of the county can experience much higher temperatures. An increase in temperature can exacerbate existing respiratory disease, cardiovascular disease, and stroke. Wildfires are also expected to increase in frequency and severity as drought takes hold, which may cause respiratory distress, exacerbation of existing disease, physical and mental dislocation, as well as some number of direct fatalities.

While all Santa Cruz County residents will experience climate change, some may be disproportionately more affected than others. For example, older adults and young children may be more at-risk to heat illness during an extreme heat event. Many factors can influence sensitivity to climate hazards including an individual's health, age and ability, societal disadvantages, access to health care, economic opportunity, education and other resources, access to basic needs, and exposure to environmental stressors

The Santa Cruz County CAAP conducted a social sensitivity index scoring and found the most sensitive populations in the county are in the areas surrounding the City of Watsonville, north of the Soquel between Soquel San Jose Road and North Rodeo Gulch Road, and in some parts of the Live Oak region. Most moderate

risk populations are in south Santa Cruz County, north of the City of Watsonville, with others located in the Ben Lomond and Scotts Valley areas. Table 3-71 summarizes the population susceptible to sea level rise.

Table 3-71: Population Susceptible to Sea Level Rise

	Total Population
Unincorporated County	131,149

Sea Level Rise (Feet Above Mean High Water)	Population Count	% of Total
50cm 100yr COSMOs	875	*0.67%*

3.2.10.7.2 Property

The structures and buildings that occupy wildfire hazard zones are at risk of structural damage from wildfires. There are several areas of the county that are classified as moderate and high severity wildfire zones. Cal-Adapt projections indicate that wildfire risk will increase most in Northeastern portion of the county in the Castle Rock State Park area and South towards State Route 17, which will put many buildings and facilities in these areas at high future risk. There are several residential structures and critical facilities situated within moderate and high fire hazard zones in the county including schools, fire stations, sheriff stations, and healthcare facilities. There are at least two schools located in very high severity wildfire zones.

The location of floodplains along the San Lorenzo River, Bear Creek, Zayante Creek, Soquel Creek, Corralitos Creek, the Pajaro River, and along the coastline that will impact critical buildings and facilities. The following features are located in FEMA flood hazard zones: 6,646 parcels, 4,061 structures, 2 schools, and 3 fire stations. Additionally, some government buildings and the County Jail are in the flood zone along the San Lorenzo River and will likely be damaged in the case of a 100-year flood event. Flooding can cause structure damage due to flowing debris, saturation of building materials, and collapse of water-logged structures. High-velocity and high-pressure flooding may also cause structures to wash away.

Climate change could significantly impact the county's agricultural industry, which is a significant driver of the county's economy. A 2025 report issued by the Santa Cruz County Agricultural Commissioner indicated that agriculture contributed approximately $1.5 billion to the county's economy in 2023. The same report indicated that agriculture directly employed 8,744 persons. Santa Cruz County is one of the leading counties for berry production, with strawberry, raspberries, and blackberries accounting for approximately $384 million in production value in 2023.

Increases in temperature and changes in precipitation and soil moisture could impact the growing of berries by causing late or irregular blooming and affecting yields. The increased likelihood of extreme floods could lead to the destruction of crops, erosion of topsoil, and deposits of debris and sediment on crop lands. Conversely, as average temperatures increase with climate change, agricultural demand for water could intensify under extreme heat conditions, under which water evaporates faster and plants need more water to move through their circulatory systems to stay cool. More specifically, attempts to maintain berry

productivity and quality in the face of warming may be associated with increased water use for irrigation. As noted earlier, increased average temperatures and changes in timing and amounts of precipitation could affect local aquifer recharge for groundwater supplies in the future, which could in turn affect water supplies for agricultural uses. Table 3-72 summarizes the property susceptible to sea level rise.

Table 3-72: Population Susceptible to Sea Level Rise

	Total Parcels	Total Market Value ($)	Total Content Value ($)	Total Value ($)
Unincorporated County	47,630	$35,189,614,790	$19,116,504,796	$54,306,119,586

Sea Level Rise	Parcel Count	% of Total	Market Value Exposure ($)	Content Value Exposure ($)	Total Exposure ($)	% of Total
50cm 100yr COSMOS	41	*0.1%*	$31,615,200	$15,999,600	$47,614,800	*0.1%*

3.2.10.7.3 Critical Facilities

Within Santa Cruz County, there is a complex network of infrastructure and services that are vulnerable to climate change. Assets within this category include water services, wastewater, airports, emergency services, utilities, roadways, public transit lines, public transportation, and communication services. Natural gas and electricity services are provided by Pacific Gas and Electric (PG&E) and distributed to Santa Cruz County residents through two major transmission lines. In addition, utility companies provide electricity, natural gas, water, and sewer services to residents, though residents not utilizing a community or municipal water provider depend on wells and/or surface water to meet their water needs. Wastewater infrastructure is provided by Santa Cruz County Sanitation District, and the Davenport Sanitation District provides water supply infrastructure in addition to wastewater. Numerous pump stations and associated sanitary sewer infrastructure are in locations vulnerable to severe weather damage, as well as sea level rise. Table 3-73 and Table 3-74 summarize critical facilities susceptible to sea level rise. Sea level rise has the potential to adversely impact the following types of public and private infrastructure:

- **City of Santa Cruz Neary Lagoon Wastewater Treatment Plant:** The Santa Cruz County Service District provides wastewater collection to the City of Capitola and unincorporated communities of Aptos, Live Oak, and Soquel, and conveys effluent to the City of Santa Cruz Neary Lagoon Wastewater Treatment Plant. Groundwater level at the Neary Lagoon Wastewater Treatment Facility is very high. The anticipated rise in groundwater due to sea level rise may adversely impact the facility by impacting storage tanks and associated infrastructure (City of Santa Cruz, 2018). A large underground pump gallery is also susceptible to groundwater impacts through infiltration of groundwater through electrical conduits and cracking walls (City of Santa Cruz 2018).
- **Santa Cruz County Sanitation District Sewer Infrastructure:** Numerous pump stations and associated sanitary sewer infrastructure operated by the Santa Cruz County Sanitation District are situated in locations vulnerable to winter storm damage. The primary sewer force main transports three to five million gallons of raw sewage per day under dry weather conditions and up to 23 million gallons during

wet weather. The force main crosses the face of Schwan Lake to the Neary Lagoon Wastewater Treatment facility and is susceptible to sea level rise. It is expected that several of these facilities may be increasingly impacted as sea level rises and storms increase.

- **Coastal Transportation Infrastructure:** Roads at the top edge of coastal bluffs are vulnerable to damage because the rate of retreat of unprotected coastal bluffs is expected to increase in response to increased exposure to storm waves and intense rain events. Roads at low elevations at the back beach and the subsurface infrastructure within the roads are also particularly vulnerable to coastal erosion.
- **Oceanfront Residential and Commercial Properties:** The projected rise in sea level would put most Santa Cruz County oceanfront properties at greater risk from either inundation and/or coastal flooding, or from increased bluff erosion. Unincorporated Santa Cruz County has approximately 29 miles of coastline. Approximately 3 miles of the most intensively developed coastline with primarily residential uses is located in the mid-county community of Live Oak. An additional 3 miles of vulnerable beaches with extensive coastal residential and commercial development occurs from Seacliff to Rio Del Mar.

Table 3-73: Critical Facilities Susceptible to Sea Level Rise

Lifelines (miles) - Sea Level Rise	
Infrastructure Type (Linear)	50cm 100 YR COSMOS
County Maintained Roads*	0.4
Levee	1.2
Maintained Channel	2.4
NG Pipeline	0.2
Railroad	0.0
Sanitation Pipe	0.4
All Roads	3.6
Alley	-
Drive	0.4
Major Road	0.2
Ramp	-
Street	1.9
State Highway	0.1
Unnamed	1.0
Transmission Line	0.0
Grand Total	**8.2**

Table 3-74: Detailed Inventory of Critical Facilities Susceptible to Sea Level Rise

Critical Infrastructure - Sea Level Rise	
Infrastructure Type	50cm 100yr COSMOs
Essential Facilities	-
Fire Station	-
Hospital	-
Law Enforcement	-
EOC	-
American Medical Response	-
High-Potential-Loss	1
Adult Care Facility	-
Child Care Center	-
Cell Tower	-
County Real Property Asset	1
Dam	-
Healthcare Facility	-
Historic Building	-

Critical Infrastructure - Sea Level Rise	
Infrastructure Type	50cm 100yr COSMOs
Library	-
Mobile Home Park	-
Power Generation	-
Radio Sites	-
School	-
Transportation and Lifeline	10
Airport	-
Substation	-
NG Station	-
Church	-
Stormwater Culvert	3
Parks	5
Bridge NBI	2
Hazmat	-
HWTS Active Facility	-
Geotracker Cleanup Site	-
Grand Total	**11**

3.2.10.8 Future Trends in Development

The County is committed to continuing efforts to address and reduce existing climate-related risks and future impacts on a holistic and programmatic level. Two examples are the LCP and Climate Action and Adaption Plan. With several ordinances and programs that cover a range of climate exposures and related impacts, the County is well equipped to handle current issues of extreme heat events and water supply issues, but could still likely face increasing challenges as projected changes occur.

3.2.10.9 Climate Change Hazard Problem Statements

As part of the mitigation action identification process, the Santa Cruz County Planning Team developed areas of concern (i.e., problem statements) that summarize the county's most pressing climate change-related vulnerabilities and challenges. The problem statements were developed based on the updated risk assessment and vulnerability analysis contained herein, as well as the team's local knowledge and experience and community input. The problem statements address a broad spectrum of concerns, from direct impacts on residents and vulnerable populations to threats to critical infrastructure and long-term recovery.

These problem statements are not intended to be all-encompassing or to describe each and every issue associated with climate change. Instead, they highlight the most urgent concerns that can be addressed

within the scope of this MJHMP. Each statement will be linked to at least one mitigation action, ensuring that identified needs are met with specific, measurable, and equitable solutions. Table 3 75 presents the climate change problem statements for Santa Cruz County, along with their associated areas of concern and reference numbers for cross-linking to the mitigation actions in Table 4-1 and Table 4-2.

Table 3-75: Santa Cruz County Climate Change Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
Climate Change	Victim	**ps-CC-SCC-01**	Climate change is expected to intensify a range of hazards in Santa Cruz County—including extreme heat, wildfire, flooding, and drought—which may disproportionately affect lower-income residents living in high-risk areas, where adaptive capacity, home retrofitting options, and relocation opportunities are limited.
Climate Change	Impact	**ps-CC-SCC-02**	Climate-driven hazards place overlapping stress on emergency response systems, infrastructure, and communities, yet planning and coordination efforts remain fragmented across multiple County and regional initiatives, limiting efficiency and unified action.
Climate Change	Impact	**ps-CC-SCC-03**	Climate change is degrading ecosystems that offer flood protection, carbon sequestration, and biodiversity. Shifts in coastal, estuarine and inland habitats can reduce natural resilience to wildfire, flood, drought, and erosion.
Climate Change	Threat	**ps-CC-SCC-04**	Fragmented land ownership / governance and short grant cycles hinder implementation of long-term climate resilience programs which demand cross-jurisdictional coordination and sustained investment.
Climate Change	Threat	**ps-CC-SCC-05**	County facilities and infrastructure were not designed for the frequency and severity of severe weather, drought, wildfire, and coastal hazard events now expected under current climate trajectories.
Climate Change	Impact	**ps-CC-SCC-06**	Climate change is expected to worsen water quality impacts, including harmful algal blooms, due to higher temperatures, increased evapotranspiration, altered precipitation patterns, and more frequent drought conditions.
Climate Change	Threat	**ps-CC-SCC-07**	Climate change is expanding the range and prevalence of vectors, including plant pathogens, invasive pests such as shothole borer, and disease-carrying mosquitos, increasing risks to ecosystems, agriculture, and public health.
Sea Level Rise	Threat	**ps-SLR-SCC-01**	Sea level rise projections of 2–5 feet by 2100 are expected to exacerbate coastal hazards—including both bluff retreat and episodic flooding—threatening hundreds of structures; roads and bridges; sewer, water,, stormwater, flood control infrastructure; and public coastal access in areas such as Pleasure Point/E Cliff, Seacliff/Rio Del Mar, and Pajaro Dunes.

3.3 All Hazard Problems

Santa Cruz County faces several systemic vulnerabilities that increase risk across all hazard types (Table 3-76). Threats stem from gaps in emergency warning systems, constrained capacity for infrastructure hardening, and an underdeveloped sheltering network.

The county's communication systems, including cellular networks, radio towers, and public alert infrastructure, are susceptible to disruption during hazard events. Limited cellular coverage in remote areas of the Santa Cruz Mountains impedes timely dissemination of emergency alerts, while the county's public safety radio system is aging and experiencing coverage gaps that compromise first responder coordination and response capabilities. At the same time, there are numerous vulnerable evacuation routes, particularly in mountains, that pose risks during fast-moving events like wildfires and flash floods.

Small utility providers, including water and wastewater agencies, also face significant challenges due to constrained financial and staffing resources, limiting their ability to recover from and adapt to repeated hazard events. Damage to these systems during hazard events can lead to a catastrophic loss of water, given the county's isolated supplies, and sewage spills that threaten public health and environmental quality.

Populations such as older adults, individuals with medical or mobility limitations, and people who are homeless, are disproportionately exposed to hazard impacts due to economic, health, and accessibility barriers, as well as challenges in outreach and communication. Even so, the county's network of emergency shelters and resilience hubs remains underdeveloped, with deficiencies in backup power, air filtration, and ADA accessibility, limiting protection for vulnerable and unhoused populations during disaster events.

Table 3-76: Santa Cruz County All Hazard Problem Statements

Hazard	Area of Concern	Problem ID	Description
All Hazard	Impact	**ps-AH-SCC-01**	Communications systems, including wireless telecommunications facilities, radio towers, and other emergency communications infrastructure, are vulnerable to damage during hazard events, and public alerts may not reach community members due to limited cellular service in geographically isolated areas of the county.
All Hazard	Victim	**ps-AH-SCC-02**	Small utility providers, including water and wastewater agencies, are disproportionally impacted by natural hazard events due to limited resources, straining recovery efforts and adaptive capacity to mitigate against future events.
All Hazard	Victim	**ps-AH-SCC-03**	The population of unincorporated Santa Cruz County is predominantly older, with a significant number of seniors at risk to disproportionate impacts from hazards due to often being on fixed incomes, having medical conditions or mobility limitations, and restricted transportation access.
All Hazard	Victim	**ps-AH-SCC-04**	People living in homeless encampments along riparian corridors are at higher risk of impacts from hazard events, including due to limitations in communication and outreach and resistance to mitigation efforts.
All Hazard	Threat	**ps-AH-SCC-05**	Santa Cruz County's VHF public safety radio system is aging, with components at or near end-of-life and limited manufacturer support, and it has significant coverage gaps that affect first responder communications.
All Hazard	Threat	**ps-AH-SCC-06**	Spilled sewage due to wastewater infrastructure damage from hazard events endangers public health, waterways/water supplies, and ecosystems.

Hazard	Area of Concern	Problem ID	Description
All Hazard	Threat	**ps-AH-SCC-07**	Gaps in emergency warning systems and limited evacuation routes, especially in mountainous areas, threaten communities with delayed response to rapid-onset hazard events such as wildfire and inundation from flash flooding or dam failure.
All Hazard	Threat	**ps-AH-SCC-08**	The County lacks a fully developed network of emergency shelters, including cooling and warming centers, and many public facilities lack backup power, air filtration, and ADA-accessible services to protect medically vulnerable, unhoused, and other populations during hazard events.

3.4 Planning for Hazards & Growth

Santa Cruz County and its incorporated cities each maintain general plans that serve as the foundation for guiding land use, development, and long-term community priorities. Santa Cruz County is a general law county, which means it establishes and enforces its own development regulations in compliance with the State of California's stringent planning, zoning, subdivision, building, and environmental standards. This framework ensures that future development in the unincorporated areas is carefully managed, with a strong emphasis on recognizing and mitigating the impacts of natural hazards.

The county's General Plan, alongside the general plans of participating jurisdictions such as Capitola, Santa Cruz, Scotts Valley, and Watsonville, provide comprehensive planning frameworks that integrate hazard mitigation strategies into land use decisions, community safety, and infrastructure investments. These plans address long-term issues such as sustainable growth, climate change resilience, and protection of vulnerable populations.

Incorporating hazard analysis into general plans and development regulations enables both the County and its cities to meet state requirements while reducing risks from natural hazards such as wildfire, flooding, drought, and extreme heat. Climate change is increasing the frequency and severity of these hazards, underscoring the importance of proactive planning and durable mitigation strategies.

Through coordinated planning, adherence to strict environmental regulations, and investment in resilience measures, the County and its jurisdictions are working to foster sustainable, safe, and adaptable communities. Together, these efforts provide a consistent and comprehensive approach to balancing growth with hazard risk reduction and climate adaptation across the region.

3.4.1 Long-Range Planning & Growth Management

Anticipating future growth in Santa Cruz County requires a proactive approach that balances state housing mandates with local hazard mitigation priorities. Growth management has long been a defining feature of the county's planning framework. Since 1978, voter-approved Measure J has directed new development inside the USL and RSL, concentrating growth within incorporated cities and established unincorporated communities while limiting sprawl into rural and hazard-prone areas. This framework, combined with California's stringent planning, zoning, subdivision, building, and environmental standards, helps ensure that future development occurs in areas with appropriate infrastructure and lower hazard exposure.

At the same time, all jurisdictions in Santa Cruz County are subject to the State's Regional Housing Needs Allocation (RHNA), which requires each to plan for a fair share of new housing across all income levels. Accommodating RHNA targets in a county constrained by coastal regulations, agricultural preservation, steep topography, and hazard-prone landscapes creates both opportunities and challenges. Most new housing will need to be located within existing urban centers such as Santa Cruz, Capitola, Scotts Valley, Watsonville, and nearby unincorporated communities, where infrastructure is already in place. Concentrating growth in these areas helps to preserve rural lands and environmentally sensitive habitats,

but also underscores the importance of investing in resilient infrastructure and retrofitting older housing stock that remains vulnerable to natural hazards.

The Santa Cruz County General Plan, updated in 2024, serves as the overarching blueprint for managing this growth while addressing hazard resilience. Its Public Safety Element establishes policies for natural hazards including flood, wildfire, earthquake, and coastal hazards, and is being further updated to integrate this MJHMP. Other General Plan elements, such as the Built Environment and Housing Elements, direct land use and housing decisions in a way that complements hazard mitigation goals. Together, these planning frameworks ensure that decisions about future development are informed by the most current hazard data and mitigation strategies.

By aligning growth management tools such as Measure J, the General Plan, and RHNA compliance with hazard mitigation priorities, Santa Cruz County and its jurisdictions are working to achieve two critical goals: meeting the region's pressing housing needs and reducing long-term risk to people, property, and natural systems. As one more step toward reducing hazard risk, the County and participating jurisdictions will adopt this MJHMP by reference into their general plans pursuant to AB 2140, ensuring stronger integration between hazard mitigation and long-range land use planning.

3.4.2 Building Codes & Development Standards

Santa Cruz County's development strategies integrate comprehensive planning frameworks and regulatory measures to guide growth while minimizing risks from natural hazards. Nationally, building codes have continually improved disaster resilience and, since 1990, those great improvements have added approximately one percent to construction costs. (National Institute of Building Sciences, 2019) In addition, California's building codes are considered some of the world's most robust and set minimum standards to safeguard against many of the natural hazards that affect communities within the state. These codes form a strong foundation for safe construction practices which the county enforces.

The county is required to regularly update its building and development codes to meet the minimum standards required by California, including the CBC which was last updated in 2022. California's minimum code requirements provide some of the safest construction standards in the world and are meant to reduce risk to occupants from high wind, seismic activity, landslides, flood, wildfire, and other natural hazards. Further, climate change impacts are also required to be addressed through the adoption and regular updating of California's Green Building Standards and Energy Codes.

For flood hazards, specifically, Santa Cruz County participates in the National Flood Insurance Program (NFIP) and Community Rating System (CRS), in addition to adhering to other California minimum floodplain development standards. All development within designated flood hazard areas must meet minimum flood protection standards as set forth by FEMA; however, the county has adopted higher standards than the NFIP minimums, including a requirement to elevate the lowest flood of structures multiple feet above the base flood elevation, known as a "freeboard." A freeboard is a factor of safety for purposes of floodplain management to compensate for the many unknown factors that could contribute to flood heights or

elevations greater than what is anticipated on regulatory flood maps, such as wave action, bridge openings, climate change, sea level rise, and the hydrological effect of watershed urbanization. The freeboard in the county is two feet.

The Santa Cruz County Code (SCCC) incorporates stringent building and development regulations to mitigate hazards for both new and existing structures, and many chapters of the SCCC recognize the diverse terrain found throughout the county by differentiating between coastal, inland, and other areas where hazard risks and impacts may vary greatly. These code sections include:

- 2022 California Building, Mechanical, Plumbing, Electrical, Existing Building, Residential, Green Building Standards, Energy, and Historical Building Codes (SCCC Chapter 12.10)
- Fire Code (SCCC Chapter 7.92), including construction and design, defensible space, vegetation management, and emergency access requirements in compliance with the 2022 California Fire Code
- Planning and Zoning Regulations (SCCC Title 13), including coastal and geologic hazards zone designations and development standards, tree preservation and water-efficient landscaping requirements, and specific plan criteria related to General Plan conformity and public safety
- Subdivision Regulations (SCCC Title 14), including General Plan conformity requirements and design standards that prohibit subdivision in flood, geological, or other hazard areas without adequate mitigation
- Floodplain Management Regulations (SCCC Chapter 16.13), in compliance with NFIP requirements and including higher standards such as a two- to three-foot freeboard
- Water Conservation (SCCC Chapter 7.69), which prohibits wasteful water uses and establishes requirements for water-efficient plumbing fixtures
- Geologic Hazards (SCCC Chapter 16.10), which implements the California Alquist-Priolo Earthquake Fault Zoning Act by setting development standards to minimize injury, loss of life, and damage to public and private property caused by earthquakes, floods, slope failures, and coastal hazards
- Grading Regulations (SCCC Chapter 16.20), which sets forth regulations controlling all grading and earthwork activities, including road construction, to minimize unnecessary disturbance and erosion
- Erosion Control (SCCC Chapter 16.22), which requires control of all existing and potential conditions of human-induced erosion to prevent increased danger from flooding, slope failure, or water quality degradation

These regulations are designed to protect public health, safety, and welfare, and to limit the impacts of natural disasters on development. In the county's hazard-prone areas, new development is very limited and, where development is feasible and permitted, these codes emphasize minimizing exposure and vulnerability to hazard risks through appropriate siting, advanced construction techniques, maintaining adequate access for emergency services, and other mitigation methods.

3.4.3 Environmental Regulations

Santa Cruz County anticipates and plans for its future growth while maintaining a robust regulatory framework to mitigate exposure and vulnerability to hazards. Further, the State of California has some of

the most rigorous environmental regulations in the nation to which the county and all new development within it are bound.

California Environmental Quality Act (CEQA)

Under the California Environmental Quality Act (CEQA), the county's General Plan and any specific plans that propose land use changes or significant development projects must include extensive evaluations of hazards and potential impacts. CEQA analysis requires consideration of factors such as proximity to floodplains, wildfire-prone areas, or seismic zones. Additionally, mitigation measures proposed in CEQA documents aim to reduce environmental and hazard-related risks, including updates to infrastructure, evacuation planning, or restrictions on development in high-risk areas.

For example, if a specific plan proposes rezoning to allow residential development in a previously undeveloped area near the wildland-urban interface (WUI), CEQA would necessitate an assessment of wildfire risk to the development. The resulting analysis might recommend increased setbacks, advanced fire-resistant construction materials, and enhanced emergency access to mitigate identified hazards.

CEQA also requires analysis and mitigation of environmental impacts related to climate change. As part of the review process, for example, the proposed development's contributions to greenhouse gas (GHG) emissions must be evaluated and mitigation techniques or other alterations to the project may be required to reduce future emissions that could result from the project.

California Climate Change Legislation

In California, counties like Santa Cruz are required to address climate change through various state laws and policies designed to promote sustainability, reduce GHG emissions, and increase resilience to climate-related hazards. In addition to applicable CEQA requirements and the county's adopted sustainability standards outlined in Section 3.4.2, key senate bills (SB), assembly bills (AB), executive orders (EO), and other state environmental legislation includes:

- **SB 375 – Sustainable Communities and Climate Protection Act:** Requires cities to integrate regional transportation planning and land use to reduce GHG emissions, particularly by fostering development near transit hubs and reducing vehicle miles traveled.
- **AB 32 and SB 32 – Global Warming Solutions Act and Amendments:** Mandates that cities contribute to California's broader goals of reducing GHG emissions to 40% below 1990 levels by 2030 and achieving carbon neutrality by 2045.
- **SB 379 – General Plan Safety Element:** Requires jurisdictions to incorporate climate adaptation and resilience strategies into the safety element of their general plan to address risks such as wildfires, extreme heat, drought, and sea-level rise.
- **SB 1000 – General Plan Environmental Justice Element:** Mandates the inclusion of an environmental justice element in general plans for communities which have been (or are anticipated to be) disproportionately impacted by environmental hazards, often compounded by climate change.

- **Title 24 – California Building Code (CBC):** Establishes energy efficiency and renewable energy requirements to reduce GHG emissions from the built environment, which jurisdictions enforce through local permitting processes.
- **EO B-30-15 and EO N-79-20:** Establish statewide targets for climate resilience and decarbonization of transportation and energy sectors, influencing local and regional planning efforts.

Santa Cruz County incorporates these state mandates into its local planning, leveraging the General Plan and hazard mitigation strategies to prepare for the increasing risks of wildfires, drought, flooding, coastal hazards, severe weather, and extreme heat caused and compounded by climate change. By aligning with state goals, the county ensures its development contributes to a sustainable and resilient future for its communities.

3.4.4 County-Wide Resilience Planning

An overview of current resilience planning initiatives is essential for identifying effective strategies, coordinating efforts, and ensuring the efficient utilization of resources to protect communities from natural hazards and impacts associated with environmental shifts. This section covers strategies from current and previous planning efforts of several participating jurisdictions as well as the City of Santa Cruz (not participating), including the 2021 Santa Cruz County HMP, 2022 Santa Cruz County Climate Action and Adaptation Plan (CAAP) and Vulnerability Technical Compendium, HMPs for the Cities of Capitola (2020), Watsonville (2020), and Santa Cruz (2018), and the 2018 and 2022 City of Santa Cruz Climate Adaptation Plans (CAP).

As described throughout this 2025 MJHMP, this first effort to plan for hazards across multiple jurisdictions in Santa Cruz County will enhance regional collaboration and resilience. Table 3-77 summarizes the key resilience strategies outlined in these current and previous planning documents, as further detailed in the 2025 AT&T Hazard Scenarios report which is incorporated into this MJHMP by reference.

Table 3-77: Resilience Planning Initiatives in Santa Cruz County

Resilience Strategy	Current & Previous Plans Mentioning Strategy	Hazards Addressed
Seismic Retrofitting of Critical Facilities and Infrastructure	County, Capitola, Watsonville, and City of Santa Cruz HMPs	Earthquake and Liquefaction
Wildfire Defensible Space and Vegetation Management	County, Capitola, Watsonville, and City of Santa Cruz HMPs	Wildfire
Stormwater Infrastructure Upgrades and Flood Management Improvements	County CAAP, City of Santa Cruz CAP, and County, Capitola, Watsonville, and City of Santa Cruz HMPs	Flood, Coastal Storm, and Sea-Level Rise
Water Conservation Programs and Groundwater Management Plans	County CAAP, City of Santa Cruz CAP, and County, Capitola, Watsonville, and City of Santa Cruz HMPs	Drought
Tsunami Inundation Mapping and Early Warning Systems	County, Capitola, and City of Santa Cruz HMPs	Tsunami

Resilience Strategy	Current & Previous Plans Mentioning Strategy	Hazards Addressed
Coastal Erosion Management and Shoreline Protection Measures	County CAAP, City of Santa Cruz CAP, and County, Capitola, and City of Santa Cruz HMPs	Coastal Erosion and Sea-Level Rise
Dam Infrastructure Inspections and Maintenance Programs	County, Capitola, and City of Santa Cruz HMPs	Dam Failure
Landslide and Debris Flod Stabilization and Drainage Infrastructure Improvements	County, Capitola, Watsonville, and City of Santa Cruz HMPs	Slope Failure
Community Education and Outreach for Hazard Preparedness and Resilience	County CAAP, City of Santa Cruz CAP, and County, Capitola, Watsonville, and City of Santa Cruz HMPs	All Hazards
Climate Adaption Strategies Integration into Local Plans	County CAAP, City of Santa Cruz CAP, and County, Capitola, Watsonville, and City of Santa Cruz HMPs	Flood, Drought, Wildfire, Extreme Heat, Sea-Level Rise, and Climate Change
Energy Resilience Initiatives (Renewable Energy and Microgrid Development)	County CAAP, City of Santa Cruz CAP, and County, Capitola, Watsonville, and City of Santa Cruz HMPs	Wildfire, Extreme Heat, High Wind, and Climate Change
Infrastructure Backup Systems (Power, Communications, Redundancy)	County, Capitola, Watsonville, and City of Santa Cruz HMPs	High Wind, Wildfire, Earthquake, and Flood
Community Gardens and Local Food Security Initiatives	County and Watsonville HMPs	Drought, Flood, Extreme Heat, and Climate Change
Green Infrastructure Projects (Bioswales, Urban Tree Canopy)	City of Santa Cruz CAP and County, Capitola, Watsonville, and City of Santa Cruz HMPs	Flood, Coastal Storm, and Climate Change

Source: 2025 AT&T Hazard Scenarios: A Roadmap to Resilience for Santa Cruz County (Project Report 2025-006)

3.5 Capabilities & Opportunities

This section provides a detailed assessment of the current capabilities of Santa Cruz County to support hazard mitigation, as well as future opportunities and funding options. This consists of describing how the county is planning for hazards and growth (Section 3.3) and a summary of its existing capabilities and the potential for enhancement (Section 3.5.1).

A summary of funding opportunities to advance the goals of this MJHMP is also provided in this section (Section 3.5.2), including local, state, and federal mechanisms and ways the participating jurisdictions can leverage their shared resources to fund coordinated mitigation efforts.

Volume 2 of this MJHMP describes the planning efforts, existing capabilities, and future opportunities for each of the other participating jurisdictions as part of their annexes. Additional details about the regulatory environment surrounding each hazard are found in the hazard profiles in Section 3.2.

3.5.1 Capabilities & Opportunities Assessment

To develop a realistic and actionable mitigation strategy, it must account for existing jurisdictional capabilities and what future opportunities there are to enhance those capabilities for purposes of hazard mitigation. This section provides an assessment of Santa Cruz County's existing capabilities and future opportunities, including planning and regulatory, administrative and technical, fiscal, and public outreach and education capabilities. This assessment also identifies opportunities to integrate this MJHMP into future planning, policies, or programs to weave mitigation efforts into daily operations and address hazard problems wholistically. Capabilities are categorized into four groups and include various mechanisms.

- **Planning and Regulatory Capabilities:** Existing long-range plans, emergency response plans, hazard-specific plans, land use policies, and building and development standards.
- **Administrative and Technical Capabilities:** Available expertise in emergency services, engineering, grant management, and community planning.
- **Fiscal Capabilities:** Budgetary capacity, taxing authority, grants, and other funding mechanisms that can support mitigation projects.
- **Outreach and Education Capabilities:** Existing programs for providing technical assistance, community education, public warnings, and stakeholder engagement.

A full description of the process used to develop the capabilities assessments is provided in Section 2.3.3. The capabilities and opportunities assessments for other participating jurisdictions are found in the annexes in Volume 2 of this plan.

Expanding & Improving Existing Capabilities

The capabilities assessment exercise presents an opportunity for Santa Cruz County and the other participating jurisdictions to examine what capabilities they do and do not currently have and where it makes the most sense to expand and improve upon those capabilities in the future. These assessments shaped mitigation actions for all-hazards as well as for specific hazards that focus on expanding and improving existing policies and programs. The expansions and improvements were based upon identified vulnerabilities and areas of concern specific to each jurisdiction, as profiled in Volume 1, Section 3.2, and each jurisdiction's annex in Volume 2.

3.5.1.1 Santa Cruz County Capabilities & Opportunities Assessment

This Capabilities and Opportunities Assessment for Santa Cruz County lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present at all and what level of use it has generally.

- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

CAPABILITY ASSESSMENT LEGEND
HMP Integration

Status	Current Mitigation Use	Future Opportunity
Currently in use or present.	Used widely for mitigation.	Opportunity to expand and integrate.
(Sort of) Seldomly used or limited presence.	Limited use in mitigation planning.	Limited opportunity to expand and integrate.
(No) Not present or available.	Not used in mitigation planning.	No opportunity to expand or integrate.

Table 3-78: Santa Cruz County Capabilities Assessment

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Construction and Future Development Regulations				
Building Codes				Santa Cruz County Code (SCCC) Ch 12.10, Building Regulations, adopts the latest version (2022) of the California Building Code (California Code of Regulation, Title 24), including Chapter 7A for WUI
Building Code Effectiveness Grading Schedule (BCEGS) Rating				2019: Class 4 for 1 & 2 family residential, Class 4 for commercial / industrial. Will prepare submittal in 2025.
Hazard-Related Development Standards				The County General Plan and SCCC Titles 12, 13, and 16 contain land use and development standards for areas with wildfire, earthquake, coastal, geologic, and flood hazards.
Zoning Ordinance				SCCC Title 13, Planning and Zoning Regulations, includes overlay districts for geological, coastal, and flood hazard areas
Hazard-Specific Ordinance				SCCC Titles 12, 13, and 16 contain chapters and sections specific to wildfire, earthquake, coastal, geological, and flood hazards.

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Growth Management Ordinance				The County General Plan and Measure J, implemented by SCCC Ch 17.01, Growth Management), Ch 17.04 (Annual Population Growth Goal for Santa Cruz County), and Ch 12.02 (Residential Permit Allocation System) limit growth across the county, but especially in rural and hazard-prone areas, via residential building permit allocations
Hazard Reduction Programs (Annually Conducted)				
Capital Improvements Program (CIP) or Plan				2025-2030 CIP includes improvements and repairs to roads, bridges, stormwater systems, and county facilities
Erosion/Sediment Control Program				SCCC Ch 16.20 and 16.22 establish standards for grading and erosion control, including requiring BMPs and construction inspections for compliance
Hazard-Related Public Outreach Program				County Office of Response, Recovery & Resilience (OR3) runs engagement programs and campaigns, including general disaster preparedness, hazard-specific resources, and educational partnerships.
Urban Water Management Plan				Not a water provider, but coordinates with water agencies in management planning
Stormwater Management Program (Annual Inspections)				Community Development and Infrastructure Department (CDI) oversees Storm Drain Master Plan (updated 2023), including enforcing design criteria and NPDES requirements, and performing annual MS4 inspections
Seismic Safety Program (Non-structural)				CD/OR3 includes seismic information as a part of regular public outreach efforts; CDI enforces and inspects for seismic safety during permit review and post-earthquake recovery
Earthquake Modernization Plan (Building Safety)				No formal URM program, but CDI enforces and inspects for seismic safety during permit review and post-earthquake recovery
Hazard Plans				
General Plan Safety Element				2020 Public Safety Element profiles wildfire, earthquake, flood, slope, and coastal hazards
Site Plan Review Requirements				SCCC Ch 13.10 establishes site plan review requirements enforced by CDI-PLN, including hazard constraints review
General Plan Environmental Justice Element				2024 General Plan Appendix E addresses Environmental Justice (EJ) policies and implementation measures
Community Wildfire Protection Plan (CWPP)				2022 CWPP is maintained by Cal Fire CZU Unit and will be updated in 2026
Economic Development Plan				No stand-alone plan, but economic development is addressed in the 2024 General Plan, 2018 Strategic Plan (being updated in 2025), and 2022 CAAP

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Floodplain Management Plan				No formal plan, but addressed in 2024 General Plan Public Safety Element, 2021 LHMP, 2022 CAAP, and SCCC Ch 16.13 (Floodplain Management Regulations)
Stormwater Management Plan				2023 Zone 5 Storm Drain Master Plan maintained by CDI (only applicable within Zone 5 – mid-County & Capitola)
Emergency Operations Plan				2023 EOP as well as 2019 Winter Storm Response Plan and Emergency Shelter Management and Operations Plan managed by OR3/OES support multi-hazard response, evacuation planning, sheltering, and alerts
Climate Action Plan				2022 CAAP includes climate impact data, mitigation and adaptation strategies, equity guardrails, and GHG targets
Climate Vulnerability Assessment				2022 CAAP includes a Climate Vulnerability Technical Compendium; also embedded in 2021 LHMP
Urban Greening Plan				No formal plan, but addressed in 2022 CAAP and 2024 General Plan
Ground Water Management Planning / Plans				Not a water provider, but coordinates with water agencies in management planning
National Flood Protection Program (NFIP)				
Floodplain Management Regulations				SCCC Ch 16.13, Floodplain Development Regulations, establishes requirements for development in flood hazard areas in compliance with FEMA and NFIP standards
Flood Insurance Education and Technical Assist.				OR3 and CDI provide flood education, outreach, and technical assistance
Flood Insurance Study				2017 FEMA FIS and best available data, per Ch 16.13
Elevation Certificates				CDI maintains elevation certificates; required during permitting
Flood Hazard Mapping / Re-Mapping				2012 and 2017 FEMA FIRM panels and best available data, per Ch 16.13 (including new mapping for post-CZU flood and debris flow hazards)
Community Rating System (CRS)				Active CRS participant; Class 8 rating
Administrative and Technical				
Community Planning and Development Services				
Community Planner				CDI Planning Division includes development review and long-range community planners
Planner/Engineer (Land Development)				CDI Planning and Public Works Divisions include land development planning and engineering staff
Engineer/Professional (Construction)				CDI Public Works Division includes licensed civil and construction engineers

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Planner/Engineer/Scientist (Natural Hazards)				CDI Planning Division includes development and environmental review staff (geologists, biologists, and planners with direct hazard mitigation roles)
Transportation Planner				CDI Public Works Division includes transportation planners; Regional Transportation Commission (RTC) manages public transportation planning
Resiliency Planner				OR3 includes 2 analyst roles focused on long-term planning for climate change / hazard mitigation and resiliency
Building Official (Full-time or Augmented)				CDI Planning Division houses County Building Official
Floodplain Administrator				Planning Director housed in CDI is designated Floodplain Administrator, per SCCC Sec 16.13.190
Fire Marshal				Fire Marshall housed in County Fire Department (operating under CAL FIRE contract)
Dedicated Public Outreach Personnel				CDI Public Works Division houses a Communications Officer; CDI Planning Division and OR3 include public outreach and equity engagement staff, but no dedicated role. Health Services Agency (HSA) has dedicated Emergency Preparedness staff.
GIS Specialist and Capability				Geographic Information Services team supports all-hazards planning and response efforts
Emergency Manager				OR3 houses Emergency Services Administrator
Dedicated Grant Manager, Writer, or Specialist				OR3 includes grant management staff, but no dedicated role
Other	N/A	N/A	N/A	
Warning Systems and Services				
General				In coordination with Santa Cruz Regional 9-1-1, SCC provides a county-wide alert system, CruzAware, which sends emergency and non-emergency alerts and warnings. Weather radios encouraged rural areas with limited cell reception due to local terrain + households reliant on landlines encouraged.
Flood				CruzAware alerts
Tornado				CruzAware alerts
Wildfire				CruzAware alerts
Geological Hazards				CruzAware alerts
Fiscal Capabilities				
Financial Resources (for Hazard Mitigation)				
Levy Taxes for Specific Purposes				Used historically to fund mitigation efforts (e.g., Measure Q parcel tax for water quality, wildfire prevention, and habitat restoration)
Utilities Fees	N/A	N/A	N/A	The County is not a utility provider except for limited CSAs
Benefit Assessments				Used in limited zones (e.g., flood zones, CSA districts)

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Community Development Block Grants (CDBG)				Receives CDBG funds for infrastructure and resilience improvements
System Development Fee				Imposed on new development for capital needs (e.g., drainage, roads)
General Obligation Bonds to Incur Debt				Not recently used for hazard mitigation; potential exists for future resilience bonds or match for federal mitigation grants
Special Tax Bonds to Incur Debt				Rarely used directly; future opportunity in partnership with special districts for mitigation projects
Withheld Spending in Hazard-Prone Areas				Measure J growth policies discourage capital investment in high-hazard zones
Stormwater Service Fees				Imposed on new development for drainage, grading, and erosion control plan reviews
Capital Improvement Project Funding				2025-2030 CIP includes improvements and repairs to roads, bridges, stormwater systems, and county facilities
Education / Outreach Capabilities				
Education/Outreach Resources				
Website Dedicated to Hazard Topics				OR3 and CDI Planning Division websites host hazard-specific pages on wildfire, flooding, earthquake, extreme temps, CZU recovery, evacuation, alerts, etc.
Dedicated Social Media				OR3, Fire Dept, Sheriff's Office, and other departments use Facebook, Twitter/X, and Instagram for emergency alerts and preparedness campaigns
Local Citizen Groups That Communicate Hazard Risks				Santa Cruz County Long-Term Recovery Group (LTRG), Fire Safe Councils, neighborhood associations, and recovery networks support education on wildfire, erosion, evacuation, and CZU rebuilding
Hazard Info. Avail. at Library/ Planning Desk				Hazard brochures available from CDI planning desk and at libraries, including flood and wildfire flyers
Annual Public Safety Events				Current OR3 outreach involves partnering with established events such as farmworker outreach fairs, Trunk or Treat, National Night Out (NNO); opportunity for expansion
Ability to Field Public Tech. Assistance Requests				Assistance provided through OR3 and CDI
Public Safety Newsletters or Printed Outreach				Regular newsletters from OR3 and Fire Safe Council on preparedness and hazard topics
Community Emergency Response Team (CERT)				Active CERT program in partnership with OR3 and local fire districts
Fire Safe Councils				County-wide Fire Safe Council plus local chapters (e.g., Bonny Doon, South Skyline, Boulder Creek)

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Firewise				70+ Firewise communities across the county
StormReady				Use both StormReady and TsunamiReady
Resource Conservation Districts				RCD of Santa Cruz County supports groundwater recharge, fire fuel management, and climate education
Other	N/A	N/A	N/A	

3.5.2 Funding Opportunities

The federal, state, and local funding opportunities listed in Table 3-79 are provided as potential options to leverage and increase the capabilities and adaptive capacities of Santa Cruz County and the other participating jurisdictions. This includes the FEMA Hazard Mitigation Assistance (HMA) grant program as well as other national, state, and local programs and grants. Note that this list serves as a resource and is not exclusive or exhaustive.

Table 3-79: Federal, State, and Local Funding Opportunities

Agency / Program Name	Potential Programs / Grants
Federal Funding Opportunities	
FEMA HMA and Other Programs	FEMA HMA grant programs include: ▪ Hazard Mitigation Grant Program (HMGP): fema.gov/hazard-mitigation-grant-program ▪ Building Resilient Infrastructure and Communities (BRIC)* Program: fema.gov/grants/mitigation/building-resilient-infrastructure-communities ▪ Flood Mitigation Assistance (FMA) Program: fema.gov/flood-mitigation-assistance-grant-program For more information on current HMA grants visit fema.gov/hazard-mitigation-assistance
	Assistance to Firefighters Grant (AFG) Program: Grants for firefighting resources, fire prevention and safety, and staffing for adequate response. fema.gov/welcome-assistance-firefighters-grant-program
	Fire Prevention and Safety (FP&S) Program: Grants to enhance the safety of the public and firefighters and administered as part of the AFG Program. FP&S Grants are offered to support projects that cover fire prevention and safety activities and research and development activities. fema.gov/fire-prevention-safety-grants

Agency / Program Name	Potential Programs / Grants
	Emergency Management Performance Grants (EMPG): Grants for equipment such as backup generators. fema.gov/emergency-management-performance-grant-program
	Regional Catastrophic Preparedness Grant Program (RCPGP): Grants for housing, logistics, and supply chain management encouraging innovative regional solutions to issues related to catastrophic incidents. fema.gov/regional-catastrophic-preparedness-grant-program
	The Flood Mitigation Assistance Swift Current (Swift Current) effort provides funding to mitigate buildings insured through the NFIP after a major disaster declaration following a flood-related disaster event to reduce risk against future flood damage. fema.gov/grants/mitigation/learn/flood-mitigation-assistance/swift-current
Office of State and Community Energy Programs (SCEP)	The Office of State and Community Energy Programs (SCEP) is part of a concerted effort at the DOE to extend the capacity and capability of states, tribes, local governments, schools, and community-serving organizations to implement high-impact, self-sustaining clean energy projects that center the needs of low-income and disadvantaged communities. SCEP does this through the management and oversight of over $16 billion in formula grants, competitive grant awards, consumer rebate grants, and technical assistance. energy.gov/scep/office-state-and-community-energy-programs
U.S. Department of Agriculture (USDA) Programs	USDA offers a variety of programs to help farmers, ranchers, communities, and businesses that have been hard hit by natural disaster events. Available FSA programs; are available at farmers.gov. For additional USDA programs visit: fsa.usda.gov/programs-and-services/disaster-assistance-program
U.S. Bureau of Reclamation (BOR) Programs	BOR has annual funding available through the WaterSMART grant program, including for Water Reclamation and Reuse, Drought Resiliency Project, and Water and Energy Efficiency Grant. usbr.gov/watersmart/
State Funding Opportunities	
California Department of Housing and Community Development (HCD) Programs	Community Development Block Grants (CDBG) include: ▪ Community Development (CD) ▪ Economic Development (ED) ▪ Neighborhood Stabilization Program (NSP) ▪ Disaster Recovery Initiative (DRI) ▪ Emergency Solutions Grant (ESG) Program: Funds projects that serve homeless individuals and families with emergency housing and supportive services or that provide homelessness prevention assistance. The Homeless Emergency Assistance and Rapid Transition to Housing (HEARTH) Act of 2009 places new emphasis on assisting people to quickly regain stability in permanent housing after experiencing a housing crisis or homelessness. For more information on current grants visit hcd.ca.gov/grants-and-funding

Agency / Program Name	Potential Programs / Grants
California Governor's Office of Emergency Services (Cal OES) Programs	Get notified via email when a new Competitive Funding Opportunity (CFO) or Public Meeting Notice is released: Join the Cal OES Grants Management Mailing List Search for active Cal OES grant programs here: caloes.ca.gov/office-of-the-director/policy-administration/finance-administration/grants-management/search-for-grants/
California Department of Forestry and Fire Protection (CAL FIRE)	Wildfire Prevention and Forest Health Grants: Supports CWPPs and collaborative wildfire risk reduction. fire.ca.gov/what-we-do/grants
California Water Resources Control Board Programs	The Division of Financial Assistance (DFA) has the lead in administering the State Water Resources Control Board's financial assistance programs. These programs include loan and grant funding for construction of drinking water treatment and distribution systems, municipal sewage conveyance and treatment systems; water recycling facilities; remediation for underground storage tank releases and groundwater contamination; technical assistance for small communities; nonpoint source pollution control projects; interim water, and operation and maintenance/Administrator support for small, disadvantaged community water systems; and drought support for individual households. DFA coordinates closely with the Division of Administrative Services, Office of Chief Counsel, Division of Drinking Water, Division of Water Quality, and the Regional Water Quality Control Board, as well as other State, federal, local, and non-governmental organizational partners. DFA administers the Operator Certification Program, which oversees the certification of all wastewater treatment plant and drinking water treatment plant and distribution system operators in California. For more information visit: waterboards.ca.gov/water_issues/programs/grants_loans/
California Department of Transportation (CalTrans) Programs	Caltrans' Local Assistance Program oversees more than one billion dollars annually available to over 600 cities, counties and regional agencies for the purpose of improving their transportation infrastructure or providing transportation services. This funding comes from various Federal and State programs specifically designed to assist the transportation needs of local agencies. Annually, over 1,200 new projects are authorized through the Local Assistance Program of which approximately 700 are construction projects. dot.ca.gov/programs/local-assistance
California Community Emergency Response Team (CERT) Program Manager Course	There are over 450 CERT programs in California. The State CERT Administrator provides technical support and CERT updates to programs in California. caloes.ca.gov/office-of-the-director/operations/planning-preparedness-prevention/community-emergency-response-team/

Agency / Program Name	Potential Programs / Grants
California Residential Mitigation Program	The California Residential Mitigation Program (CRMP): Established to carry out mitigation programs to assist California homeowners who wish to seismically retrofit their houses. californiaresidentialmitigationprogram.com/ ▪ Earthquake Brace + Bolt (EBB) Program: Developed as part of the CRMP to help homeowners lessen the potential for damage to their houses during an earthquake by offering eligible homeowners up to a $3,000 incentive to seismically retrofit their homes. earthquakebracebolt.com/
California Air Resources Board (CARB) Incentives, Grants, and Credit Programs	These programs have hundreds of millions of dollars in grants available over the next several years to reduce emissions from on- and off-road vehicles and equipment. arb.ca.gov/ba/fininfo.htm
California Department of Water Resources (DWR) Grants and Loans	Agency offers a variety of grants and loans related to integrated regional water management, flood mitigation, water conservation and efficiency, environmental restoration, groundwater, water quality, and water supply. water.ca.gov/Work-With-Us/Grants-And-Loans
California Department of Conservation (DOC)	Funds projects that improve soil, water, and habitat conservation at the local level. conservation.ca.gov/information-for/funding-grants-easements
California State Coastal Conservancy	Provides support for nature-based solutions, shoreline protection, and community resilience. scc.ca.gov/grants/
2024 Climate Bond (Proposition 4)	Voters passed the 2024 Climate Bond (Proposition 4) in November 2024, a general obligation bond that will yield $10 billion for a variety of climate resilience efforts, including flood, wildfire, coastal, watershed, water supply, and natural resource management programs. resources.ca.gov/Bonds-Oversight/Proposition-4-Climate-Bond
Local Funding Opportunities	
Santa Cruz County Safe Drinking Water, Clean Beaches, Wildfire Risk Reduction, and Wildlife Protection Initiative (Measure Q)	Approved by Santa Cruz County voters in November 2024, the Santa Cruz County Safe Drinking Water, Clean Beaches, Wildfire Risk Reduction, and Wildlife Protection Initiative (Measure Q) aims at protecting and enhancing the county's precious natural resources. The initiative prioritizes water quality, wildfire prevention, habitat restoration, and the creation of resilient ecosystems to ensure the health and well-being of Santa Cruz County's environment and residents. Measure Q funds support projects such as: ▪ Water Conservation and Quality ▪ Wildfire Risk Reduction ▪ Wildlife and Habitat Protection ▪ Clean Beaches and Coastal Protection ▪ Community Resilience

*Notes: *If reinstated; BRIC funds were not allocated for 2025*

Section 4. Mitigation Strategy

This section describes the mitigation strategies developed for the 2025 MJHMP to reduce or eliminate the long-term risks of high-priority hazards impacting Santa Cruz County. Building upon the findings of the risk assessment detailed in Section 3, the strategies in this plan outline prioritized mitigation actions, projects, and policies aimed at safeguarding vulnerable populations, protecting property and critical infrastructure, and enhancing overall community resilience.

4.1 Mitigation Goals

Hazard mitigation plans must define clear goals for reducing long-term vulnerabilities to natural hazards. For this plan, the county-wide Hazard Mitigation Planning Team (HMPT) established goals using findings from the risk assessment, input from the planning team, and feedback from the public gathered through surveys, stakeholder interviews, and document review. The four goals, developed by the Planning Team and confirmed by jurisdictional teams, outline broad priorities for protecting people, property, services, infrastructure, and the environment. These goals provide the framework for the 2025 Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) Mitigation Strategy. The mitigation actions that follow are specific and measurable steps designed to achieve these goals through both jurisdiction-specific initiatives and a coordinated county-wide approach.

Goal 1: People & Community

Avoid or reduce the potential for life loss, injury, and economic damage to community members from hazard events.

Goal 2: Continuity of Services

Increase the ability of local government, agencies, special districts, and partner organizations to serve the community during and after hazard events.



Goal 3: Natural & Built Environment

Protect the County's unique character, scenic beauty, and values in the natural and built environment from being compromised by hazard events.

Goal 4: Lifeline Resilience

Identify and encourage mitigation activities that increase the disaster resilience of the community, institutions, private companies, and systems essential to a functioning County.

4.2 Translating Strategy to Action

As detailed in Section 2.3.4.3, the mitigation actions in this 2025 MJHMP are organized into FEMA's six broad categories, which provide a consistent framework for identifying, evaluating, and prioritizing hazard reduction efforts. These categories include Prevention (PRV), Property Protection (PPRO), Public Education and Awareness (PEA), Natural Resource Protection (NRP), Emergency Services (ES), and Structural Projects (SP). Together, they capture the full range of strategies available to reduce hazard risks in Santa Cruz County.

Proposed mitigation actions align with these categories, highlighting both the diversity of approaches and the emphasis on solutions that provide multiple community benefits. This framework ensures that limited resources are directed toward the actions with the greatest potential to reduce risk and strengthen long-term resilience.

Figure 4-1: Mitigation Concepts by Jurisdiction

Integrating Public Input

Public participation played a central role in shaping the Mitigation Action Plan by ensuring that the strategies and actions reflect the needs, concerns, and priorities of residents across Santa Cruz County. Through surveys, workshops, and stakeholder outreach, community members identified both the types of mitigation projects they value most and the barriers they face in taking action themselves.

Survey results show strong public demand for investments that improve safety, infrastructure resilience, and long-term community preparedness. The most frequently requested actions included upgrading bridges and roadways, creating safer evacuation corridors, expanding water storage and connectivity, and ensuring reliable backup power for emergency operations. Additional high priorities were improving stormwater and sewer systems, retrofitting critical facilities, and increasing access to public hazard and risk information. These findings directly informed the development of county-wide and jurisdiction-specific mitigation actions, ensuring that the final plan addresses the most urgent community needs.



Figure 4-2: Survey Results; Focus of Public Agency Mitigation Actions

At the same time, the survey highlighted key barriers that prevent residents from advancing mitigation on their own. The most significant challenge was a lack of funding, followed by a need for technical assistance, risks perceived as beyond individual control, and limited access to information about where to start. Recognizing these constraints, the Mitigation Action Plan emphasizes solutions that provide shared benefits at the community-scale, leverage outside funding sources, and include robust public education and outreach.

By integrating community input with technical risk assessment and planning team expertise, the Mitigation Action Plan prioritizes actions that not only reduce hazard exposure but also respond directly to the challenges residents experience. This approach ensures that mitigation is both technically sound and socially responsive, aligning limited resources with the areas of highest public concern and need.



Figure 4-3: Survey Results; Barriers to Reducing Property Risk

Action Prioritization

Mitigation actions in the 2025 MJHMP were prioritized using a scoring system that emphasizes risk reduction, equity, and collaboration. Each action was evaluated against four criteria. Hazard Risk (+0–2) assigns higher scores to actions that address hazards ranked as extreme, high, or medium in the jurisdiction's Risk Matrix, ensuring focus on the most pressing threats. Multi-Benefit Outcomes (+1) prioritize actions that provide ecological, social, and economic co-benefits while incorporating community and stakeholder perspectives. Equity Impact (+1) highlights actions that reduce disparities, improve conditions in disadvantaged neighborhoods, address the needs of vulnerable populations, and lower barriers to mitigation. Finally, Strategic Alignment (+1) gives preference to actions that are consistent with regional, local, and state plans and that foster collaboration among jurisdictions, non-profits, land trusts, and tribal partners. This framework ensures that selected actions not only reduce hazard risk but also advance equitable, multi-benefit, and regionally aligned resilience strategies.

1. **Hazard Risk (+0-2):** Actions that address high-priority hazards based on the jurisdiction's completed Risk Matrix (extreme, high, or medium).
2. **Multi-Benefit Outcomes (+1):** Actions that achieve multiple beneficial ecological, social, and economic outcomes, including public benefits.
3. **Equity Impact (+1):** Actions that help reduce disparities in access to opportunities, improve environmental health conditions for vulnerable populations, or reducing barriers of mitigation.
4. **Strategic Alignment (+1): :** Actions that are in alignment with regional, local, and state plans and programs, and demonstrate collaboration among planning partners.

Figure 4-4: Prioritization Criteria

4.3 County-Wide Mitigation Strategy

In recognizing that hazards do not distinguish jurisdictional boundaries and resource limitations, the Steering Group and HMPT determined that a coordinated, county-wide mitigation strategy was needed to address cross-cutting challenges. The County-Wide Mitigation Action Plan establishes a unified strategy for reducing risk across all participating jurisdictions. While each jurisdiction faces its own hazards and sets local priorities, many risks overlap and require county-wide coordination to address effectively. The mitigation strategy emphasizes actions that strengthen resilience across the entire county, build on local capabilities, and leverage regional collaboration for greater impact. This shared framework ensures that county-wide challenges are met with consistent, equitable, and coordinated solutions.

Figure 4-1 illustrates the county-wide mitigation concept, showing how the plan builds on the individual efforts and strengths of each participating jurisdiction to address shared hazard risks. The action plan was developed collaboratively by the county-wide Planning Team through the comprehensive planning process described in Section 2. The County-Wide Mitigation Action Plan is presented in Table 4-1.



Figure 4-5: County-Wide Mitigation Strategy Diagram

4.4 Mitigation Action Plan

The Mitigation Action Plan is the roadmap for reducing hazard risk and strengthening resilience across Santa Cruz County and all participating jurisdictions. It translates the county-wide goals, range of mitigation alternatives, and prioritization framework into a set of actionable steps designed to safeguard people, property, infrastructure, and natural systems.

The actions in the county-wide plan (Table 4-1), Santa Cruz County plan (Table 4-2), and those in Volume 2 annexes are the product of a structured process that combined data from the risk assessment, input from planning partners and stakeholders, and a prioritization framework designed to ensure accountability and transparency. Each action was evaluated against prioritization factors presented previously and accompanied by key details to guide implementation and accountability:

- **Timeline:** Short-term, medium-term, or long-term implementation schedule.
- **Responsibility:** The lead agency or department and supporting partners.
- **Cost/Benefit Review:** A qualitative review of relative costs and benefits:
    - Cost: Low (fundable under existing budget), Medium (requires budget adjustment or multi-year allocation), or High (requires new funding source such as grants or bonds).
    - Benefit: Low (difficult to quantify in short-term), Medium (provides long-term benefits or immediate property risk reduction), or High (provides immediate life-safety and property protection).

      Note: Actions with benefits equal to or greater than their costs are considered cost-beneficial.
- **Level of Readiness:** Actions were further categorized to reflect their stage of development:
    - Conceptual: The action addresses a known hazard but requires scoping or feasibility analysis.
    - Planning: The action has been defined and is undergoing design, permitting, or resource identification.
    - Implementation: The action is ready to proceed with identified resources, partnerships, and timeline.
- **Internal Funding Sources:** Local resources such as general funds, enterprise funds, or dedicated fees.
- **External Funding Sources:** State, federal, and private funding, including FEMA Hazard Mitigation Assistance programs and Cal OES grants.

Together, these elements ensure that the Mitigation Action Plan is not just a list of projects but a carefully prioritized and actionable strategy. By balancing readiness, cost-effectiveness, equity, and strategic alignment, the plan provides a clear pathway for jurisdictions to reduce risk while maximizing co-benefits and shared investment

Mitigation Action Identification

Each mitigation action in this MJHMP is assigned a unique identification number using alphanumeric characters that denote specific attributes, as illustrated in Figure 4-6. These attributes include the type of hazard being mitigated (e.g., WF for wildfire), an abbreviation for the responsible jurisdiction, and a number to facilitate easy reference and management.

In addition, the mitigation actions encompass both newly developed actions for this plan update and existing actions carried over from previous hazard mitigation plans that were yet to be completed or needed refinement. This is reflected in the identification information for each action as "new" or "existing."

Problem statements are similarly assigned a unique identification number, except that instead of beginning with "ma" for mitigation action, they begin with "ps" for problem statement. Problem statements for Santa Cruz County are found in the hazard profiles of the risk assessment in Volume 1 (Section 3.2), and statements for other participating jurisdictions are found in Volume 2.



Figure 4-6: Mitigation Action Number Key

Important Note: Recognizing that new needs and priorities may arise as a result of a disaster or other circumstances, the MJHMP partners reserve the right to support new and edit existing actions as necessary, so long as the actions conform to the overall goals of this plan.

PAGE INTENTIONALLY BLANK

Table 4-1: County-Wide Hazard Mitigation Action Plan

Hazard	Key Partners	Action ID	Action Title	Description	Selected FEMA Mitigation Alternative(s)	Priority
All Hazard	All Jurisdictions	**ma-AH-SCC-01**	County-Wide Hazard Mitigation Working Group	Develop an inter-jurisdictional and County inter-departmental hazard mitigation task force between OR3, CDI, GSD, Parks, AG to support collaboration for hazard mitigation planning, funding, and implementation through Measure Q, Prop 4, FEMA grants, and other state and federal grant sources.	PRV	Very High
All Hazard	Santa Cruz County, RCD, City of Scotts Valley, City of Watsonville, City of Capitola	**ma-AH-SCC-02**	Residential Hazard Mitigation Incentives	In collaboration with planning partners, explore cost-share models such as rebates, grants, CSA formation, and low-interest loans repaid through property tax bills (PACE-style financing) to reduce upfront costs and increase participation in hazard mitigation projects on private property / roads.	PPRO	Very High
All Hazard	All Jurisdictions	**ma-AH-SCC-04**	County-Wide Coordinated Outreach Strategy	In collaboration with MJHMP planning partners, coordinate a countywide outreach strategy to enhance public education and awareness of hazard risks and mitigation actions through consistent, aligned messaging. Efforts should leverage trusted voices and existing networks to reach diverse communities, using inclusive, multilingual, and accessible materials delivered across a variety of platforms. Develop a suite of ready-to-use outreach resources and tools that can be tailored to specific audiences and jurisdictions to promote sustained engagement and shared understanding of local hazards and mitigation opportunities.	PE&A	Very High
All Hazard	Santa Cruz County, City of Scotts Valley, City of Watsonville, City of Capitola	**ma-AH-SCC-05**	Establish Resilience Center Network	Identify and retrofit public agency and community-based organization (CBO)–owned facilities—such as libraries, Veterans Halls in Watsonville and Santa Cruz, the Davenport Resource Center, and other community centers—to serve as accessible, low-barrier resilience hubs. Upgrades may include backup power, HVAC and air filtration systems, ADA compliance improvements, and capacity to operate during heat, cold, smoke, wildfire, and other severe weather or hazard events, while supporting community outreach and emergency response operations.	ES, PE&A	High
All Hazard	Santa Cruz County, PV Water, Cabrillo College, Soquel Creek Water District, Scotts Valley Water District, City of Watsonville	**ma-AH-SCC-06**	Coordinated Catastrophic Water Supply Disruption Training & Exercise Program	Develop and implement a training and exercise program with county water districts to prepare for catastrophic loss of major water treatment facilities (e.g., due to fire/earthquake), with a focus on establishing Community Points of Distribution (CPODs) for safe drinking water, coordinating logistics, staffing, and communications during extended outages.	ES	Very High
All Hazard	All Jurisdictions	**ma-AH-SCC-07**	Communications System Improvements	Modernize and expand the County's public safety radio and communications system to improve interagency coordination, coverage in rural areas, and public notification capabilities.	ES, PRV	Very High
Drought	RCD, Santa Cruz County, Soquel Creek Water District, PV Water, Scotts Valley Water District	**ma-DR-RCD-04**	Multi-Benefit Water Resilience Projects	Plan, design, and implement multi-benefit land repurposing and water resilience projects.	SP, NRP	High
Drought	Santa Cruz County, PV Water, Soquel Creek Water District, Scotts Valley Water District	**ma-DR-SCC-04**	Enhanced County Water Resources Portfolio	In partnership with local water agencies, GSAs, and IRWM partners, support projects that expand and diversify the County's water resources portfolio including potable and non-potable recycled water projects, groundwater recharge and storage, conjunctive use and water transfer programs, stormwater infiltration and reuse.	NRP, PRV	High
Flood	RCD, Santa Cruz County, Cabrillo College, City of Capitola, City of Watsonville, Port District	**ma-FL-RCD-02**	Multi-Benefit Habitat Restoration	Expand multi-benefit floodplain, stream, and wetland restoration projects that reduce flood risk while restoring ecosystem function, particularly where prior land use changes have damaged natural infrastructure.	NRP, NSP	High

Hazard	Key Partners	Action ID	Action Title	Description	Selected FEMA Mitigation Alternative(s)	Priority
Flood	Santa Cruz County, City of Capitola, Cabrillo College, PV Water, Soquel Creek Water District, Port District, City of Scotts Valley, City of Watsonville	**ma-FL-SCC-02**	Expand Flood Hazard Forecasting, Data & Mapping	Develop, update, and refine flood models for key flashy / frequently flooding watersheds and tributaries, such as Corralitos Creek, to incorporate climate change scenarios and planned infrastructure projects, and with consideration of RLA mapping completed in this HMP update. Use updated models to inform mitigation investments, land use planning, and emergency preparedness.	ES, PE&A	High
Sea Level Rise	Santa Cruz County, City of Capitola, PV Water, Soquel Creek Water District, Port District, RCD	**ma-SLR-SCC-01**	Develop Community-Scale Coastal Adaptation Strategies	Develop community-scale adaptation strategies for Seacliff/Rio del Mar, Pleasure Point/East Cliff Drive, and other coastal neighborhoods vulnerable to sea level rise. Integrate findings from the County's Local Coastal Program (LCP) Update and Sea Level Rise Vulnerability Assessment to evaluate options such as managed retreat, nature-based solutions, shoreline restoration, and elevation of vulnerable infrastructure. Coordinate with local jurisdictions, community groups, and regional partners to guide future project design and investment priorities.	SP, PRV, NRP	High
Wildfire	Santa Cruz County, RCD, City of Capitola, City of Scotts Valley, Soquel Creek Water District, PV Water, City of Watsonville, Scotts Valley Water District, Cabrillo College	**ma-WF-SCC-05**	Collaborative Forest Health & Fuel Reduction Projects	Implement priority forest health, fuel reduction, and shaded fuel break projects on private lands and public-agency–owned parcels and watersheds through collaborative partnerships among local, regional, and state entities. These projects will advance shared forest health and wildfire risk reduction priorities identified in the Santa Cruz Mountains Regional Prioritization Plan (RPP) and will leverage cross-jurisdictional coordination, shared resources, and community engagement to achieve landscape-scale resilience outcomes.	PRV, PE&A, NRP	Very High

Table 4-2: Santa Cruz County Hazard Mitigation Action Plan

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
All Hazard	**ma-AH-SCC-01**	County-Wide Hazard Mitigation Working Group	Develop an inter-jurisdictional and County inter-departmental hazard mitigation task force between OR3, CDI, GSD, Parks, AG to support collaboration for hazard mitigation planning, funding, and implementation through Measure Q, Prop 4, FEMA grants, and other state and federal grant sources.	PRV	Ongoing	County OR3 (lead) + CDI (multiple divisions), GSD, Parks, and Agricultural Commissioner	Low	High	Staff time (limited)	N/A	Very High	ps-FL-SCC-05, ps-CC-SCC-01
All Hazard	**ma-AH-SCC-02**	Residential Hazard Mitigation Incentives	In collaboration with planning partners, explore cost-share models such as rebates, grants, CSA formation, and low-interest loans repaid through property tax bills (PACE-style financing) to reduce upfront costs and increase participation in hazard mitigation projects on private property / roads.	PPRO	Medium 3-5 Years	County OR3 (lead) + GSD, Environmental Planning, CDI - Planning, RCD, local jurisdictions, and CBOs	High	High	Staff time (limited)	FMA HMGP USDA CalOES / CAL FIRE programs bolstered by Prop 4, 3CE	Very High	ps-CS-SCC-02, ps-CC-SCC-01, ps-WF-SCC-02
All Hazard	**ma-AH-SCC-04**	County-Wide Coordinated Outreach Strategy	In collaboration with MJHMP planning partners, coordinate a countywide outreach strategy to enhance public education and awareness of hazard risks and mitigation actions through consistent, aligned messaging. Efforts should leverage trusted voices and existing networks to reach diverse communities, using inclusive, multilingual, and accessible materials delivered across a variety of platforms. Develop a suite of ready-to-use outreach resources and tools that can be tailored to specific audiences and jurisdictions to promote sustained engagement and shared understanding of local hazards and mitigation opportunities.	PE&A	Ongoing	County OR3 (lead) + Department PIO's, HSA - Public Health, Cities, water districts, Port, RCD, Cabrillo College, fire protection districts, libraries, COE/School Districts, CBO's (esp. Fire Safe Council, SCC LTRG)	Medium	High	Staff time (limited) General Fund via CIP (limited)	Measure Q California Fire Safe Council CalOES / Listos CAL FIRE HMGP	Very High	ps-CC-SCC-07, ps-CH-SCC-02,ps-CC-SCC-01, ps-WF-SCC-02, ps-WF-SCC-10, ps-WW-SCC-02
All Hazard	**ma-AH-SCC-05**	Establish Resilience Center Network	Identify and retrofit public agency and community-based organization (CBO)–owned facilities—such as libraries, Veterans Halls in Watsonville and Santa Cruz, the Davenport Resource Center, and other community centers—to serve as accessible, low-barrier resilience hubs. Upgrades may include backup power, HVAC and air filtration systems, ADA compliance improvements, and capacity to operate during heat, cold, smoke, wildfire, and other severe weather or hazard events, while supporting community outreach and emergency response operations.	ES, PE&A	Long 5-10 Years	County OR3 (planning) and GSD (implementation) + Facility owners/operators: Cities, Fairgrounds, libraries, schools, CBOs	High	High	Staff time (limited) General Fund via CIP (limited)	MOUs Measure Q HMGP Other State Grants (Prop 4), CDBG-DR	Very High	ps-AH-SCC-08, ps-EH-SCC-02, ps-AH-SCC-03, ps-AH-SCC-04, ps-CC-SCC-01, ps-EH-SCC-03, ps-EH-SCC-05, ps-SW-SCC-01, ps-WF-SCC-09, ps-WW-SCC-01
All Hazard	**ma-AH-SCC-08**	Road Network Mapping & System Integration	In coordination with RCD, CAL FIRE/County Fire, local FPD's, and local law enforcement identify and comprehensively map road systems across the county, including road type, capacity, ownership (public / private), and condition (e.g., surfacing, culverts), for integration into response data systems and into evacuation planning.	ES, PRV	Short 1-3 Years	County OR3 (lead) + ISD - GIS, CDI - Public Works / Roads, Sheriff, County Fire / CAL FIRE, local FPD's, RCD, CBO's (esp. Fire Safe Council, CERT)	Medium	High	Staff Time (limited)	Measure Q California Fire Safe Council CAL FIRE CalTrans	Very High	ps-EQ-SCC-07, ps-AH-SCC-07, ps-FL-SCC-02, ps-FL-SCC-06, ps-SF-RCD-02, ps-WF-SCC-06, ps-CC-SCC-01, ps-WF-SCC-04, ps-WW-SCC-02

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
All Hazard	**ma-AH-SCC-03**	Climate Action & Hazard Mitigation Outreach	Expand and diversify existing public outreach channels to broaden awareness of the County's Climate Action and Adaptation Plan (CAAP) and its links to hazard mitigation, including accessible web and social media content, dashboard tracking of objectives / performance metrics, and attendance at community events with partners.	PE&A	Short 1-3 Years	County OR3 (lead) + Department PIO's, ISD, Cities, regional climate collaboratives (RCPWG, MBCAAN), COE, UCSC, CSUBM, Cabrillo, CBO's	Medium	Medium	Staff time (limited)	Private organization grants UC / CSU resilience partnerships	High	ps-AH-SCC-08, ps-AH-SCC-04, ps-EH-SVL-04, ps-CC-SCC-01, ps-CC-SCC-06, ps-EH-SCC-03, ps-WF-SCC-02, ps-WF-SCC-10
All Hazard	**ma-AH-SCC-06**	Coordinated Catastrophic Water Supply Disruption Training & Exercise Program	Develop and implement a training and exercise program with county water districts to prepare for catastrophic loss of major water treatment facilities (e.g., due to fire/earthquake).	ES	Ongoing	County OR3 & HSA - Environmental Health (co-lead) + Water districts, small water system operators, fire protection districts, Cities, CalOES, HSA, CBO partners (esp. CERT, LTRG)	Low	Medium	Staff time	BAUASI EMPG SHSGP	High	ps-EQ-SCC-06, ps-EQ-SCC-07, ps-LQ-SCC-01, ps-AH-SCC-02, ps-DR-SCC-04, ps-SF-SCC-03, ps-SF-SCC-07, ps-TS-SCC-01, ps-WF-RCD-01, ps-CC-SCC-01
All Hazard	**ma-AH-SCC-07**	Communications System Improvements	Modernize and expand the County's public safety radio and communications system to improve interagency coordination, coverage in rural areas, and public notification capabilities.	ES, PRV	Short 1-3 Years	County CEO (lead) + ISD, Cities, Sheriff, local LE, Fire Protection Districts, EMS, Netcomm	High	High	Staff Time General Fund, via CIP	MOUs with partner agencies	High	ps-AH-SCC-01, ps-AH-SCC-05, ps-AH-SCC-06, ps-CS-SCC-01, ps-AH-SCC-07
All Hazard	**ma-AH-SCC-09**	Support VOAD & CBO Disaster Coordination	In partnership with the Long-Term Recovery Group (LTRG) and community-based organizations (CBOs), develop and implement procedures for coordinating Volunteer Organizations Active in Disaster (VOAD) within the County's emergency management framework. This includes establishing standard operating procedures (SOPs) for VOAD activation and integration into Emergency Operations Center (EOC) functions, offering regular trainings and exercises for VOAD and CBO partners, and development of recovery and donation management frameworks.		Short 1-3 Years	County OR3 (lead) + Long Term Recovery Group (LTRG) and RWG	Low	Medium	Staff Time	EMPG, SHSGP, Private Grants	High	ps-EQ-SCC-01, ps-CC-SCC-01, ps-SW-SCC-01, ps-WF-SCC-10, ps-WW-SCC-01, ps-WW-SCC-02
Climate Change	**ma-CC-SCC-01**	Regional Climate Project Working Group (RCPWG) Alignment	Support the Regional Climate Project Working Group in finalizing a long-term governance model and advancing priority regional climate adaptation and hazard mitigation projects.	NRP	Short 1-3 Years	County OR3 (participant / partner agency) + RCPWG stakeholders including Cities, water+ other special districts, regional/state agencies, and CBO's	Low	Medium	Staff Time General Fund (limited)	EPA DOT CalTrans Establishment of future JPA's / sustainable funding mechanisms	High	ps-CC-SCC-04, ps-CC-SCC-02, ps-CC-SCC-01
Climate Change	**ma-CC-SCC-02**	Shothole Borer Rapid Response & Management	In partnership with UCNAR, develop and implement a rapid response program for shothole borer infestations to expedite contracting to remove and safely process infested trees, particularly box elder along Zayante Creek and other riparian areas where dead or dying trees increase fire risk, contribute to downstream flood hazards, and threaten creek ecosystem health.	NRP, PRV	Short 1-3 Years	County AGC (lead) + OR3, HSA - Environmental Health, CDI-Planning, RCD, State Parks, UCNAR, USDA-NRCS, Santa Cruz Mountain Stewardship Network partners	Medium	Medium	Staff Time	USDA-NRCS UCNAR	High	ps-CC-SCC-07, ps-CC-SCC-06

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
Climate Change	**ma-CC-SCC-03**	Harmful Algal Bloom (HAB) Monitoring & Response	Expand monitoring and response for harmful algal blooms in reservoirs, lagoons, and lakes such as Pinto Lake. Activities include temperature and nutrient monitoring (e.g., shading, upstream nutrient management, point source control), in-lake treatments where feasible, and posting public advisories during HAB events.	NRP	Short 1-3 Years	County HSA - Environmental Health (lead) + County Parks, RCD, water districts, City of Watsonville, DWR	Medium	High	Staff time (limited if expanded) General Fund (limited, if expanded) Measure Q	DWR Coastal Conservancy	High	ps-CC-SCC-06, ps-CC-SCC-07
Coastal Erosion	**ma-CE-SCC-01**	Coastal Bluff & Access Adaptation	Develop and implement a phased adaptation program for transportation corridors and coastal access points in high-risk bluff areas. Use a mix of nature-based and, where necessary, structural measures—such as revegetation, drainage improvements, and living shorelines—to reduce bluff collapse risk and maintain safe, sustainable public access. Coordinate with Caltrans, State Parks, and coastal property owners to align with regional shoreline management priorities.	SP	Long 5-10 Years	County CDI - Planning (lead) + CDI - Sanitation, Stormwater Management + Flood Control; OR3, cities, CA State Parks, Coastal Commission	High	High	Staff time (limited)	Measure Q BRIC (if reinstated) Coastal Conservancy DOC Long-term finance strategies	High	ps-CE-SCC-01, ps-CH-SCC-02, ps-CS-SCC-01, ps-CS-SCC-02
Coastal Hazards	**ma-CH-SCC-01**	Enhanced Shoreline & Coastal Asset Protections	Conduct a feasibility study and phased implementation program to relocate, retrofit, elevate, or otherwise protect coastal assets and critical infrastructure—including stormwater and sewer systems, pump stations, and bluff-top facilities—to withstand projected storm surge, erosion, and sea level rise impacts. Integrate natural and engineered shoreline measures to enhance protection and maintain natural storm-buffering functions, consistent with the County's 2026 SLR Vulnerability Assessment.	NRP, SP	Long 5-10 Years	County CDI - Planning (lead) + CDI - Sanitation, Stormwater Management + Flood Control; OR3, cities, CA State Parks, Coastal Commission	High	High	Special Services Funding Sources (i.e., service fees, CSA, Measure D)	Measure Q Coastal Conservancy HMGP CDBG BRIC EPA DOC	High	ps-CH-CPT-01, ps-CH-SPD-01, ps-AH-SCC-06, ps-CC-SCC-01, ps-CC-SCC-02, ps-CC-SCC-03, ps-CC-SCC-05, ps-CE-SCC-01, ps-CH-SCC-02, ps-CS-SCC-01, ps-CS-SCC-02
Dam Failure	**ma-DF-SCC-01**	High-Risk Dam Training & Exercise	Coordinate with partners and participate in a multi-agency training and exercise focused on Newell Creek Dam to test the dam's Emergency Action Plan, communication protocols, and community preparedness.	ES, PE&A	Short 1-3 Years	County OR3 (coordination lead) + City of Santa Cruz (Water Department, Fire), DSOD, OR3, SLVWD, local FPD's, Sherriff, school and care facilities within inundation zone, CERT	Low	Medium	Staff Time (limited)	BAUASI EMPG / SHSGP	Medium	ps-DF-SCC-01, ps-DF-SCC-02, ps-DF-SCC-04
Dam Failure	**ma-DF-SCC-02**	Dam Failure Outreach & Evacuation Drills	Develop and share online inundation mapping and outreach/communications tools for residents and businesses in high-risk downstream zones (e.g., Felton, Lompico). Conduct periodic community-scale evacuation drills in partnership with schools, care facilities, CBOs, and local agencies, and integrate outcomes into response planning and warning systems.	PE&A, ES, PRV	Medium 3-5 Years	County OR3 (coordination lead) + City of Santa Cruz Water, local FPD's, schools, care facilities, CERT	Medium	Medium	Staff Time (limited)	BAUASI EMPG / SHSGP	Medium	ps-DF-SCC-04, ps-DF-SCC-03
Drought	**ma-DR-SCC-02**	Water Conservation Education & Outreach	In partnership with the RCD and local water agencies, provide education and outreach on water conservation practices for both residential/commercial and agricultural users.	PE&A	Ongoing	County HSA - Environmental Health and AGC + RCD, water districts, Cities, Farm Bureau, UCSC, Cabrillo, COE	Low	Medium	Staff time (limited if expanded)	UCNAR USDA - NRCS DOC	Medium	ps-DR-CPT-03, ps-DR-RCD-04, ps-DR-SCC-01, ps-DR-SCC-02

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
Drought	**ma-DR-SCC-01**	Drought Resilience for Small Water Systems	Support development of drought contingency plans, interconnection options, and capacity expansions for small and private water systems, especially in communities where wells increasingly go dry and in WUI zones where water supply deficits (e.g., tank shortfalls, dry hydrants) compound wildfire risk.	PRV, ES, SP	Medium 3-5 Years	County HSA - Environmental Health (lead) + OR3, County Parks, RCD, water districts, Cities, DWR	Low	Medium	Staff time General Fund (limited if expanded)	DWR DOC HMGP BRIC Prop 4 Measure Q	High	ps-DR-SCC-05, ps-DR-SCC-06, ps-AH-SCC-02, ps-CC-SCC-01, ps-CC-SCC-02, ps-DR-SCC-01, ps-DR-SCC-02
Drought	**ma-DR-SCC-03**	Watershed Monitoring & Drought Adaptation	Monitor and protect low-flow streams, temperature-sensitive ecosystems, fish habitat, and key aquifer recharge areas during extended droughts.	NRP, SP	Short 1-3 Years	County HSA - Environmental Health (lead) + GIS, County Parks, RCD, water districts, Cities, NOAA, DWR, CBO's	Medium	Medium	Staff Time General Fund (both limited if activities expanded beyond existing monitoring)	DWR DOC HMGP BRIC Prop 4 Measure Q	High	ps-DR-RCD-01, ps-CC-SCC-01, ps-CC-SCC-03, ps-CC-SCC-06, ps-DR-SCC-01, ps-DR-SCC-03, ps-DR-SCC-04
Drought	**ma-DR-SCC-04**	Enhanced County Water Resources Portfolio	In partnership with local water agencies, GSAs, and IRWM partners, support projects that expand and diversify the County's water resources portfolio including potable and non-potable recycled water projects, groundwater recharge and storage, conjunctive use and water transfer programs, stormwater infiltration and reuse.	NRP, PRV	Long 5-10 Years	County HSA- Environmental Health (lead collaboration through GSA's / IRWM) + Cities, water districts, RCD, OR3	High	High	Staff time (limited)	DWR DOC HMGP BRIC Prop 4 Measure Q	High	ps-DR-SCC-07, ps-CC-SCC-01, ps-CC-SCC-06, ps-DR-SCC-01, ps-DR-SCC-06
Earthquake	**ma-EQ-SCC-01**	Critical Facilities & Infrastructure Assessment & Hardening	Conduct structural assessments and phased hardening of vulnerable critical facilities (e.g., fire stations, shelters, 500 Westridge, Juvenile Hall) and aboveground water and wastewater infrastructure in liquefaction and fault rupture zones.	SP, PRV	Long 5-10 Years	County GSD, CDI - Building Official, CDI - Sanitation, SCCSD, ISD, County Fire, OR3	High	High	General Fund via CIP (limited)	HMGP BRIC	High	ps-EQ-SVL-05, ps-AH-SCC-06, ps-EQ-SCC-03, ps-EQ-SCC-04, ps-EQ-SCC-06, ps-EQ-SCC-07, ps-LQ-SCC-01
Earthquake	**ma-EQ-SCC-02**	Earthquake Outreach & Education	Launch an ongoing outreach and education campaign for homeowners, renters, and small businesses on earthquake preparedness and mitigation including both structural and non-structural retrofit options, as well as promotion of the Earthquake Brace + Bolt program.	PE&A	Short 1-3 Years	County OR3 (lead) + Department PIO's, Cities, CBO's	Low	Medium	Staff time (limited)	CalOES Listos, CARESTAR	High	ps-EQ-SVL-01, ps-EQ-WTS-02, ps-EQ-SCC-01, ps-EQ-SCC-02, ps-EQ-SCC-05, ps-LQ-SCC-01
Extreme Heat	**ma-EH-SCC-01**	Outdoor Worker Extreme Heat Protections	Coordinate with agricultural agencies and employers of outdoor workers to ensure extreme heat requirements are adhered to (e.g., shaded rest areas, hydration stations), provide support for enhanced heat mitigation, and educate workers on their rights and resources.	PE&A, PRV	Short 1-3 Years	County AGC (lead) + OR3, HSA - Public Health Emergency Preparedness, RCD, CBO's	Low	Medium	Staff time (limited)	CalOES Listos, CARESTAR	Medium	ps-EH-SCC-01, ps-EH-WTS-01, ps-EH-CPT-01, ps-EH-CPT-03, ps-EH-SCC-03, ps-EH-SCC-04, ps-EH-SCC-05, ps-EH-SVL-03, ps-CC-SCC-01

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
Flood	**ma-FL-SCC-01**	Flood Mitigation Assistance Program	Provide technical and financial assistance to homeowners, mobile home parks, small businesses, and farmers to relocate, elevate, or floodproof vulnerable structures in repetitive loss and other flood-prone areas. Explore cost-sharing mechanisms, incentives, and partnerships to maximize use of FEMA's Flood Mitigation Assistance (FMA) program and related state/federal funding sources.	PPRO	Medium 3-5 Years	County CDI - Floodplain Manager (lead) + OR3, CDI - Environmental Planning, CBO's (esp. SCC LTRG)	High	High	Staff time (limited)	FMA HMGP USDA-NRCS	High	ps-FL-SCC-09, ps-FL-SCC-01, ps-FL-SCC-02, ps-FL-SCC-03, ps-FL-SCC-09
Flood	**ma-FL-SCC-02**	Expand Flood Hazard Forecasting, Data & Mapping	Develop, update, and refine flood models for key flashy / frequently flooding watersheds and tributaries, such as Corralitos Creek, to incorporate climate change scenarios and planned infrastructure projects, and with consideration of RLA mapping completed in this HMP update. Use updated models to inform mitigation investments, land use planning, and emergency preparedness.	ES, PE&A	Short 1-3 Years	County CDI - Stormwater Management and Flood Control (lead) + OR3, ISD - GIS, PRFMA, USACE, NWS, PVWMA, DWR	Medium	High	General Fund (limited)	Measure Q DWR USACE	High	ps-FL-SCC-05, ps-FL-SCC-07, ps-FL-SCC-09, ps-LV-SCC-01
Flood	**ma-FL-SCC-03**	Improve Flood Warning Systems	Identify opportunities to improve storm monitoring tools and expand real-time river gage and flood detection and warning systems and develop MOU's with partner agencies for installation and maintenance costs.	ES, PE&A	Medium 3-5 Years	County CDI - Stormwater Management and Flood Control (lead) + OR3, ISD - GIS, NWS, Cities, PRFMA	Medium	Medium	General fund (limited if expanded)	Measure Q DWR MOUs UCSC partnerships	High	ps-FL-PVW-02, ps-AH-SCC-07, ps-FL-SCC-01
Flood	**ma-FL-SCC-04**	Paulsen Road Flood Resilience Project Implementation	Advance phased implementation of the Paulsen Road Multi-Benefit Flood Resilience and Connectivity Project, following assessment and design studies, to improve emergency access, restore watershed health, enhance floodplain resilience along the corridor.	SP, PPRO, NRP	Medium 3-5 Years	County CDI - Roads, CDI - Stormwater Management + Flood Control, County OR3, Parks, PRFMA, PVWMA, RCD, SC Fairgrounds, CBOs (i.e., Land Trust)	High	High	General Fund (limited) Staff Time (limited)	Measure Q BRIC DOC DWR Prop 4 HMGP CDBG-DR	High	ps-FL-RCD-02, ps-CC-SCC-05, ps-FL-SCC-01, ps-FL-SCC-04, ps-FL-SCC-06
Flood	**ma-FL-SCC-05**	Flood Risk & Mitigation Outreach	Deliver bi-annual outreach in flood-prone and vulnerable communities—through workshops, indigenous language accessible video, and partnership with trusted voices (e.g., CBO's, schools)—to build awareness of flood risks, mapping updates, mitigation options, and insurance, with emphasis on equitable access for Spanish- and Indigenous-language speakers.	PE&A	Short 1-3 Years	County OR3 (lead) + CDI (PIO), PRFMA, CBO's (esp. organizations serving South County), RCD, cities, school districts, UCSC, Cabrillo	Low	Medium	Staff time (limited)	Private organization grants (i.e, AT&T, PG&E) BAUASI EMPG/SHSGP	High	ps-FL-WTS-02, ps-FL-SCC-01, ps-FL-SCC-07, ps-FL-SCC-09
Flood	**ma-FL-SCC-06**	Sewer Infrastructure Flood Mitigation	Assess sewer pump stations and other wastewater infrastructure located in flood-prone areas for susceptibility and identify drainage improvements and other mitigation measures to improve resilience to floodwater inflow and infiltration. Implement highest-priority improvements identified.	PRV, SP	Medium 3-5 Years	County CDI (Sanitation / Stormwater Management + Flood Control / Roads / Planning), OR3, CA State Parks, Sanitation Districts	High	High	Service rate fees (limited)	BRIC HMGP Measure Q DWR	High	ps-FL-SCC-08, ps-FL-SVL-03, ps-AH-SCC-06, ps-CC-SCC-05
Flood	**ma-FL-SCC-07**	Enhanced Streamwood Management	Complete analyses and development of tools that inform siting of streamwood installation projects that would have the dual benefit of enhancing wildlife habitat and reducing flood-related risks to infrastructure and property.	PRV, NRP, SP	Medium 3-5 Years	County Environmental Health (lead) + CDI (Stormwater Management + Flood Control), RCD, CDFW, RWQCB, watershed groups	Medium	High	Staff time (limited)	Measure Q DWR DOC Prop 4	High	ps-FL-RCD-02, ps-CC-SCC-03

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
Flood	**ma-FL-SCC-08**	Channel Maintenance Program	Develop a channel maintenance program, including metrics to develop maintenance specification sheets for each County - maintained channel and complete a CEQA analysis.	PRV, NRP	Short 1-3 Years	County CDI - Roads / Stormwater Management + Flood Control, OR3, and Parks	Medium	Medium	Staff time (limited)	DWR DOC CalTrans Prop 4 Measure Q	High	ps-FL-RCD-01, ps-LV-SCC-01
Heavy Rain	**ma-HR-SCC-01**	Implement Stormwater BMPs	Identify low-lying areas on County-owned lands suitable for development of stormwater BMPs and implement measures to retain stormwater and reduce the risk of flooding in adjacent or downstream areas.	NRP, SP	Short 1-3 Years	County Parks, Environmental Health, OR3, CDI - Roads / Stormwater Management + Flood Control, RCD, Cities	Medium	Medium	Staff time (limited)	DWR DOC Prop 4 Measure Q	High	ps-HR-CPT-01, ps-HR-WTS-01, ps-HR-SCC-01
Sea Level Rise	**ma-SLR-SCC-01**	Develop Community-Scale Coastal Adaptation Strategies	Develop community-scale adaptation strategies for Seacliff/Rio del Mar, Pleasure Point/East Cliff Drive, and other coastal neighborhoods vulnerable to sea level rise. Integrate findings from the County's Local Coastal Program (LCP) Update and Sea Level Rise Vulnerability Assessment to evaluate options such as managed retreat, nature-based solutions, shoreline restoration, and elevation of vulnerable infrastructure. Coordinate with local jurisdictions, community groups, and regional partners to guide future project design and investment priorities.	SP, PRV, NRP	Long 5-10 Years	County CDI - Planning (lead) + CDI - Sanitation, Stormwater Management + Flood Control; OR3, cities, CA State Parks, Coastal Commission	High	High	Special Services Funding Sources (i.e., service fees, CSA, Measure D)	Measure Q Coastal Conservancy HMGP CDBG BRIC EPA DOC	High	ps-SLR-SCC-01, ps-CC-SCC-01, ps-CC-SCC-02, ps-CC-SCC-03, ps-CC-SCC-05, ps-CE-SCC-01, ps-CH-SCC-01, ps-CH-SCC-02, ps-CS-SCC-01
Sea Level Rise	**ma-SLR-SCC-02**	Lower Watsonville Slough SLR Resiliency	Support ongoing efforts to assess and address flood and sea level rise risks in the Lower Watsonville Slough and adjacent areas (including Reach 1 of the Pajaro River, Hwy 1 corridor, and Beach Road). The County's role will focus on technical studies, data sharing, and coordination to integrate with partner-led projects and ensure consistency across planning efforts.	ES	Medium 3-5 Years	County CDI (Stormwater / Roads) + PVWMA, City of Watsonville, PRFMA, State Parks, Pajaro Dunes Association, and local CSAs	High	High	Staff time (limited)	Measure Q, Coastal Conservancy USACE HMGP BRIC NOAA	High	ps-SLR-PVW-03, ps-CC-SCC-01, ps-CE-SCC-01
Sea Level Rise	**ma-SLR-SCC-03**	Coastal Sanitation Infrastructure Mitigation Alternatives Study	In coordination with State Parks / local agency partners, evaluate alternatives for armoring, relocation, or other protections for vulnerable coastal sanitation infrastructure at sites such as Rio del Mar, Las Olas / Seacliff, Hidden Beach, and the East Cliff Drive force main. Initial study will build on priorities identified in the County's 2026 SLR Vulnerability Assessment / LCP	SP, PRV	Medium 3-5 Years	County CDI - Sanitation (lead) + CDI - Planning, Stormwater + Flood Control, SCCSD, CA State Parks, cities, Coastal Commission	Medium	High	Special Services Funding Sources (i.e., service fees, CSA, Measure D)	Coastal Conservancy, Measure Q, Prop 4, HMGP, BRIC	High	ps-SLR-SCC-01, ps-CC-SCC-01, ps-CC-SCC-02, ps-CC-SCC-05, ps-CE-SCC-01, ps-CS-SCC-02
Severe Weather	**ma-SW-SCC-01**	Critical Facility Weatherproofing	Identify and implement priority safety, backup generation, and weatherization upgrades for critical County facilities and data storage centers.	SP	Medium 3-5 Years	County GSD, ISD, OR3	Low	Medium	Staff time (limited) General Fund via CIP (limited)	CDBG Prop 4 HMGP	Medium	ps-SW-SCC-02, ps-CC-SCC-05, ps-HW-SCC-01, ps-WW-SCC-02

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
Severe Weather	**ma-SW-SCC-02**	Expand Alert & Warning Systems	Expand public access to NOAA weather radios to ensure timely alerts in areas with limited cell coverage or high frequency of power outages. Partner with CBOs to distribute radios, provide training, and integrate their use into household and community preparedness. Ensure maintenance of the X-band radar is secured.	PRV, ES, PE&A	Long 5-10 Years	County OR3 (lead) + Cities, NWS, CBOs, schools, and local emergency partners	Medium	High	Staff time (limited)	BAUASI EMPG SHSGP HMGP	High	ps-SW-CBC-03, ps-SW-SCC-01, ps-SW-SVL-01, ps-HW-SCC-01, ps-SW-SCC-03, ps-WW-SCC-02
Slope Failure	**ma-SF-SCC-01**	Develop Drainage Structure Inventory & Prioritization Framework	Develop prioritization framework and upgrade aging stormwater conveyance systems / culverts using both nature-based and structural solutions where appropriate, to reduce slope failure potential.	NRP, PRV, ES	Short 1-3 Years	County CDI - Public Works (lead) + OR3, CDI - Roads, Planning, RTC, RCD	High	High	Staff time (limited)	HMGP Cal Trans Measure Q	High	ps-SF-SVL-04, ps-SF-SCC-04, ps-SF-SVL-02, ps-FL-SCC-06, ps-HR-SCC-01, ps-SF-SCC-01, ps-SF-SCC-02, ps-SF-SCC-03, ps-SF-SCC-07
Slope Failure	**ma-SF-SCC-02**	Landslide Risk & Mitigation Education Campaign	Partner with the RCD, FPD's, and trusted CBOs to educate residents in landslide-prone rural areas served by private roads or informal road associations on slope failure risks and mitigation options. Provide information on stabilization strategies, benefits/costs, and how forming a Community Service Area (CSAs) could support long-term slope and road maintenance. Prioritize outreach to one-way-in/one-way-out communities with vulnerable populations at higher evacuation risk.	PE&A	Short 1-3 Years	County OR3, CDI - Public Works, LAFCO, RCD, CBOs, HOAs / private road associations	Low	Medium	Staff time (limited)	NA - dependent on community interest in CSA formation	High	ps-SF-SCC-01,ps-CE-SCC-01, ps-SF-SCC-02, ps-SF-SCC-03, ps-SF-SCC-04, ps-SF-SCC-05, ps-SF-SCC-06, ps-SF-SCC-07
Tsunami	**ma-TS-SCC-01**	Tsunami Signage & Evacuation Drills	Install updated tsunami warning signage in maximum inundation zones, and regularly conduct outreach and community drills, especially in harbor and beachfront areas.	ES, PRV, PE&A	Short 1-3 Years	County OR3, CDI - Roads, ISD-GIS, Sheriff + FPDs, Port District, State Parks, cities, CERT, UCSC	Medium	Medium	Staff time	EMPG SHSGP BAUASI	Medium	ps-TS-SCC-01, ps-TS-SCC-02, ps-TS-SPD-04
Wildfire	**ma-WF-SCC-01**	Evacuation Route Fuel Management	Expand roadside shaded fuel breaks and maintain vertical/horizontal clearances along key County-maintained evacuation routes in high-risk WUI areas (high fire hazard / limited egress) with consideration for combined wildfire and high wind hazards that can block roads through downed trees, debris, or powerlines.	NRP, PPRO, PRV	Short 1-3 Years	County OR3, CDI - Roads, CDI - Environmental Planning, Fire Safe Council, Fire Districts	Medium	High	Staff time (limited)	HMGP BRIC CAL FIRE Prop 4 Measure Q	Very High	ps-WF-SCC-01, ps-WF-RCD-03, ps-WF-SCC-02, ps-CC-SCC-01, ps-DR-SCC-06, ps-WF-SCC-04, ps-WF-SCC-06, ps-WF-SCC-08
Wildfire	**ma-WF-SCC-02**	Mitigation Education, Inspection & Incentives Program	Through partnerships with fire districts, RCD, and the Fire Safe Council, expand free, no-obligation property inspections and offer incentives such as cost shares and low-interest loans to incentivize home hardening, improving access and address signage, and establishing defensible space in high-risk WUI zones.	PPRO, PE&A	Short 1-3 Years	County OR3, Fire Districts, RCD, Fire Safe Council	Medium	High	Staff time (limited)	HMGP BRIC CAL FIRE CalOES Prop 4 Measure Q	Very High	ps-WF-CBC-02, ps-CC-SCC-01, ps-WF-SCC-01, ps-WF-SCC-02, ps-WF-SCC-04, ps-WF-SCC-08
Wildfire	**ma-WF-SCC-03**	Community Chipping & Biomass Disposal Programs	Expand neighborhood chipping programs to increase coverage across at-risk neighborhoods and promote free or low-cost slash disposal opportunities.	NRP, PPRO, PE&A	Short 1-3 Years	County OR3, RCD, CDI - Solid Waste, Fire Districts, Fire Safe Council	Medium	High	General Fund (limited)	HMGP BRIC CAL FIRE CalOES Prop 4 Measure Q	Very High	ps-WF-SCC-07, ps-CC-SCC-01, ps-DR-SCC-06, ps-WF-SCC-01, ps-WF-SCC-02, ps-WF-SCC-04, ps-WF-SCC-08

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
Wildfire	**ma-WF-SCC-05**	Collaborative Forest Health & Fuel Reduction Projects	Implement priority forest health, fuel reduction, and shaded fuel break projects on private lands and public-agency–owned parcels and watersheds through collaborative partnerships among local, regional, and state entities. These projects will advance shared forest health and wildfire risk reduction priorities identified in the Santa Cruz Mountains Regional Prioritization Plan (RPP) and will leverage cross-jurisdictional coordination, shared resources, and community engagement to achieve landscape-scale resilience outcomes.	NRP, PRV, PE&A	Short 1-3 Years	County OR3 + RCD, water districts, CAL FIRE, FPDs, Fire Safe Council, Santa Cruz Mountain Stewardship Network	High	High	General Fund (limited) Staff time (limited)	HMGP BRIC DOC CAL FIRE CalOES Prop 4 Measure Q	Very High	ps-WF-RCD-02, ps-WF-SCC-09, ps-CC-SCC-01, ps-CC-SCC-03, ps-CC-SCC-04, ps-DR-SCC-06, ps-WF-SCC-01, ps-WF-SCC-03, ps-WF-SCC-04, ps-WF-SCC-08, ps-WF-SCC-10
Wildfire	**ma-WF-SCC-04**	Critical Facilities & Infrastructure Protections	Complete shaded fuel breaks, defensible space treatments, and hardening measures at critical facilities and infrastructure sites (including County as well as outside agency-owned properties for communications towers, corrections, power, sewer, water, stormwater, and solid waste.)	SP, NRP, ES	Short 1-3 Years	County GSD, OR3, Fire, Parks, and CDI (Sanitation) + CAL FIRE, utility providers	Medium	High	General Fund via CIP (limited)	HMGP BRIC CAL FIRE CalOES Prop 4 Measure Q	High	ps-WF-SCC-03, ps-CC-SCC-01, ps-CC-SCC-02, ps-CC-SCC-05, ps-DR-SCC-06
Wildfire	**ma-WF-SCC-06**	Post-Fire Watershed Health & Erosion Control Plan	In partnership with the RCD and NRCS, formalize a Countywide recovery plan for post-fire watershed protection including erosion control measures for private residences along steep slopes. Incorporate lessons learned and documentation from the CZU Fire recovery and establish protocols for long-term watershed health and resilience.	NRP, ES, PRV	Short 1-3 Years	County OR3, CDI (Environmental Planning), and Environmental Health + RCD, NRCS, Santa Cruz Mountain Stewardship Network	Medium	High	General Fund (limited) Staff time	CAL FIRE DOC Prop 4 Measure Q	High	ps-WF-SVL-02, ps-WF-SCC-05, ps-CC-SCC-01, ps-CC-SCC-03, ps-SF-SCC-06, ps-WF-SCC-01, ps-WF-SCC-08
Wildfire	**ma-WF-SCC-07**	Biomass Utilization & Air Curtain Burner Program	In coordination with the Santa Cruz Mountains Stewardship Network's regional biomass strategy, pursue permitting and acquisition of a Carbonator system to centralize processing of hazardous fuels and standing dead trees into biochar.	NRP	Short 1-3 Years	County OR3 and CDI (Environmental Planning / Solid Waste) + RCD, SCMSN, CAL FIRE, Fire Safe Councils	High	High	General Fund (limited)	CAL FIRE DOC Prop 4 Measure Q	High	ps-WF-SCC-08, ps-CC-SCC-01, ps-DR-SCC-06, ps-WF-SCC-01, ps-WF-SCC-09
Wildfire	**ma-WF-SCC-08**	Streamlining Sensitive Habitat Permitting	Develop streamlined permitting pathways and habitat-specific BMPs to support wildfire risk reduction projects in environmentally sensitive areas while maintaining ecological safeguards and watershed health.	NRP	Short 1-3 Years	County CDI - Environmental Planning (lead) + OR3, Parks, HSA - Environmental Health, County Fire / CAL FIRE, RCD, CDFW, RWQCB	Medium	Medium	Staff time (limited)	BRIC HMGP CAL FIRE DOC Prop 4 Measure Q	High	ps-WF-RCD-02, ps-WF-SCC-04, ps-WF-SCC-10, ps-CC-SCC-01, ps-CC-SCC-03, ps-WF-SCC-01
Wildfire	**ma-WF-SCC-09**	Strengthening WUI & Fire Safety Ordinances	Evaluate opportunities to strengthen local policies and ordinances in alignment with the state fire code to reduce wildfire risk in the wildland–urban interface (WUI). This may include assessing options for enhanced defensible space, vegetation management, and wildfire-resistant construction standards, developed through stakeholder engagement and coordination with local fire agencies.	NRP, PRV	Short 1-3 Years	County CDI - Planning (lead) + County Fire / CAL FIRE; FPD's, OR3, Fire Safe Councils	Medium	High	Staff time (limited)	CAL FIRE	High	ps-WF-SCC-07, ps-WF-SVL-03, ps-CC-SCC-01, ps-WF-SCC-01, ps-WF-SCC-04

4.5 Status of Previous Mitigation Actions

In 2021, Santa Cruz County adopted its previous FEMA-approved HMP. This 2025 MJHMP represents a comprehensive update from that previous plan, as discussed in Section 1.5. Table 4-3 provides status updates for the previous Santa Cruz County Mitigation Action Plan, from which many of the mitigation actions in Table 4-2 were sourced and revised. Status updates for the old action plans of other jurisdictions with previous HMPs are provided in the annexes of Volume 2.

Table 4-3: Status of 2021 Santa Cruz County Mitigation Actions

Action ID	Description	Status
A-1	Coordinate preparedness efforts with other agencies and cities within the county	Combined and revised into ma-AH-SCC-08, ma-CC-SCC-01, ma-DF-SCC-01, ma-EQ-SCC-01, ma-FL-SCC-02, ma-FL-SCC-03, ma-SF-SCC-02, ma-WF-SCC-01, ma-WF-SCC-03, ma-WF-SCC-04, ma-WF-SCC-05
A-2	Continue to enforce floodplain management regulations on all permit applications	Combined and revised into ma-FL-SCC-01
A-3	Continue to participate in the Community Rating System to improve floodplain management	Combined and revised into ma-FL-SCC-01
A-4	Reduce fire risk in urban/wildland interface (WUI) by advocating use of improved building materials and appropriate code enforcement, including defensible space and fuel reduction programs	Combined and revised into ma-WF-SCC-02, ma-WF-SCC-03, ma-WF-SCC-04, ma-WF-SCC-05
A-5	Promote land use planning which will reduce incidence of human caused wildfires especially in very high hazard areas	Combined and revised into ma-WF-SCC-02, ma-WF-SCC-05
A-6	Advocate for creation of secondary road access improvement	Combined and revised into ma-AH-SCC-08
A-7	Implement water conservation efforts to maximize the use of existing water resources	Revised into ma-DR-SCC-02
A-8	Support the development of additional water supplies	Combined and revised into ma-DR-SCC-04
A-9	Promote more effective use of groundwater storage through increased groundwater recharge and conjunctive use among agencies	Combined and revised into ma-DR-SCC-03, ma-DR-SCC-04
A-10	Continue to coordinate communication system upgrades with other agencies and cities, including evacuation management and operations, for homes and businesses within specific areas	Combined and revised into ma-FL-SCC-03
A-11	Promotion of built-in fire extinguishing systems and fire alarm systems	Combined and revised into ma-WF-SCC-02

Action ID	Description	Status
A-12	Continue to maintain cooperative fire protection and prevention agreements with other agencies	Combined and revised into ma-AH-SCC-08, ma-WF-SCC-01, ma-WF-SCC-04
A-13	Improve road signs and address marking to increase visibility and reduce response times	Combined and revised into ma-WF-SCC-02
A-14	Enhance support for interoperability communications system with local, state, and federal emergency services	Combined and revised into ma-FL-SCC-03
A-15	Continue to require that the County Geologist review development in areas of suspected landsliding and require engineering geology reports when landsliding is identified or suspected	Combined and revised into ma-SF-SCC-01, ma-SF-SCC-02
A-16	Continue to require that an engineering geologist and/or geotechnical engineer investigate the site of any proposed construction near landsliding and require mitigation of landslide hazards before issuing any building or grading permit	Combined and revised into ma-SF-SCC-02
A-17	Continue to require that an engineering geologist and a geotechnical engineer investigate any landslide damage to homes or roadways before repair of the landslide and reuse of the homes or roadways	Combined and revised into ma-SF-SCC-01
A-18	Continue to refine and improve our evacuation management plans and tools using Zonehaven	Combined and revised into ma-AH-SCC-08, ma-DF-SCC-01, ma-DF-SCC-02
A-19	Re-establish and support Community Organizations Assisting in Disaster (COAD)	Revised into ma-AH-SCC-09
A-20	Reduction of fire risk in the urban/wildland interface (WUI) through hazardous fuel reduction projects including but not limited to indigenous land use practices of controlled burns, hazardous fuel removal, other shaded fuel break burn strategies	Combined and revised into ma-WF-SCC-01, ma-WF-SCC-03, ma-WF-SCC-04, ma-WF-SCC-05
A-21	Support CZU Fire Recovery for survivors utilizing best practices for improving overall safety of rebuild	Combined and revised into ma-WF-SCC-01, ma-WF-SCC-02
A-22	Enhance our early warning, and rainfall monitoring capacity in the high debris flow risk areas of the County following the CZU fires of 2020	Combined and revised into ma-SF-SCC-01
A-23	Identify, monitor, and mitigate where feasible the hazards and risks associated with post fire debris flows	Combined and revised into ma-SF-SCC-01, ma-WF-SCC-06
A-24	Expand use and functionality of targeted shelters County Wide to serve as “All Hazard Resiliency Centers” which can serve as an all-hazard resource for community members in events including but not limited to: earthquakes, fires, floods, Public Safety Power Shut-off events, extreme weather events, poor air quality days. Building resiliency centers may include but is not limited to back-up power generation capacity, air filtration, air conditioning, kitchen facilities, shelter capacity	Combined and revised into ma-SW-SCC-01
B-1	Upgrade roadways, sewer, water, and other infrastructure to withstand seismic shaking	Combined and revised into ma-EQ-SCC-01

Action ID	Description	Status
B-2	Review and revise California Environmental quality Act (CEQA) Initial Study checklist to ensure storm water runoff is fully mitigated	Completed
B-3	Implement additional fire prevention programs through inspections and education	Combined and revised into ma-WF-SCC-02
B-4	Maintain adequate Fire Suppression and Prevention staffing levels to meet the needs of the county residents and development trends	Cancelled, operational focus; addressed through other planning efforts, replaced with actions that focus on mitigation
B-5	Update and revise the Geologic Hazards Ordinance	Completed
B-6	Pursue elevation of structures to raise them above the 100-year flood level	Combined and revised into ma-FL-SCC-01
B-7	Continue to enforce requirements for on-site retention of storm water runoff from impervious surfaces where feasible for all new development in the Groundwater Recharge Zone and the Water Supply Watershed Zone and throughout Santa Cruz County	Combined and revised into ma-SF-SCC-01, ma-SW-SCC-01
B-8	Evaluate the effectiveness of current policies and ordinances designed to limit storm water runoff and recommend revisions to improve the effectiveness of these policies	Combined and revised into ma-SF-SCC-01, ma-SW-SCC-01
B-9	Evaluate the effectiveness of current drainage plan requirements	Combined and revised into ma-SF-SCC-01, ma-SW-SCC-01
B-10	Implement the "Stormwater Facilities Master Plan" for Flood control Districts 5 & 6	Combined and revised into ma-SF-SCC-01
B-11	Continue to inspect and maintain drainage system infrastructure	Combined and revised into ma-SF-SCC-01
B-12	Develop public education materials on flood protection and mitigation by working collaboratively with community groups, non- governmental organizations, and the local media	Combined and revised into ma-FL-SCC-01, ma-FL-SCC-02, ma-FL-SCC-03
B-13	Regulate development in flood zones to optimize preservation of open space through the application of the Geologic Hazards Ordinance and Open Space Preservation policies	Combined and revised into ma-FL-SCC-02
B-14	Limit development and monitor conditions of development and grading permits near natural channels and wetlands to prevent sedimentation	Combined and revised into ma-SF-SCC-01, ma-SF-SCC-02
B-15	Promote drought planning by the 150 small water systems under county jurisdiction	Revised into ma-DR-SCC-01
B-16	Promote seismic safety upgrade of all emergency use and critical structures	Combined and revised into ma-EQ-SCC-01
B-17	Require all new and replacement critical structures be designed to standards of the California building Code and County Geologic Hazard Code	Combined and revised into ma-EQ-SCC-01

Action ID	Description	Status
B-18	Train appropriate plan check staff on seismic requirements for structures	Cancelled, ongoing baseline mitigation requirement
B-19	Encourage zoning in geologically constrained areas that reflect the nature and extent of the seismic hazard	Cancelled, mitigation achieved through Ch. 16 implementation
B-20	Implement the Pajaro River Flood Risk Management Project to reduce the probability and consequences of flooding in the City of Watsonville, the Town of Pajaro, and surrounding agricultural lands	Cancelled, ongoing responsibility of PRFMA
C-1	Management of early warning system	Combined and revised into ma-TS-SCC-01
C-2	Update tsunami maps	Combined and revised into ma-TS-SCC-01
C-3	Protect and preserve the coastline through permit review and continue to review coastal development for conformance with the County's Geologic Hazards ordinance	Cancelled, ongoing baseline mitigation requirement
C-4	Encourage the replacement of existing seawalls with shoreline protection structures which meet current engineering practice, integrate coastal access elements, and reduce their footprint impact on coastal resources	Combined and revised into ma-CE-SCC-01, ma-CH-SCC-01
C-5	Develop an event protocol with the State Division of Safety of Dams	Combined and revised into ma-DF-SCC-01, ma-DF-SCC-02
C-6	Continue to require soils reports as part of the building permit process	Cancelled, ongoing baseline mitigation requirement
C-7	Encourage investigation of tsunami threat to the county and update development regulations based upon the best available information	Combined and revised into ma-TS-SCC-01
C-8	Protect and preserve the coastline and infrastructure through restoration efforts	Combined and revised into ma-CE-SCC-01, ma-CH-SCC-01, ma-SLR-SCC-01
C-9	Update dam inundation maps	Combined and revised into ma-DF-SCC-01
C-10	Review dam evaluation files to determine the extent of potential dam failures	Combined and revised into ma-DF-SCC-01
C-11	Continue to enforce design criteria for areas of known expansive soils	Cancelled, ongoing baseline mitigation requirement
C-12	Adopt General Plan and County Code amendments to implement the Sustainable Santa Cruz County Plan to support higher density development along major transit corridors.	Completed
C-13	Plan for climate change	Combined and revised into ma-CC-SCC-01, ma-CH-SCC-01, ma-DR-SCC-03, ma-FL-SCC-02, ma-SLR-SCC-01

Action ID	Description	Status
C-14	Develop a forum for ongoing engagement with coastal private property owners and the California Coastal Commission to discuss frameworks for land use policies that respond to expected future losses	Combined and revised into ma-CC-SCC-01
C-15	Consider relocating coastal development away from areas that will be inundated to eliminate the risk of damage and the need for coastal protection	Combined and revised into ma-CH-SCC-01, ma-SLR-SCC-01
C-16	Consider limiting new engineered protection structures to infill in locations where the back beach is currently fixed	Combined and revised into ma-SLR-SCC-01
C-17	Consider a program to identify those areas where managed retreat should replace engineered protection structures, based on public benefit	Combined and revised into ma-CH-SCC-01, ma-SLR-SCC-01
C-18	Work with the engineering community to define a standard increment of additional height that should be added to the FEMA 100-year wave run up, storm surge, and flood levels when analyzing hazards in specific locations	Combined and revised into ma-SLR-SCC-01
C-19	In consultation with the California Coastal Commission, consider revising regulations that address rebuilding structures that are repeatedly damaged by SLR and coastal storms	Combined and revised into ma-CC-SCC-01, ma-SLR-SCC-01
C-20	Amend the Public Safety Element of the General Plan and revise implementing regulations to increase the efficacy of the damage prevention and flood protection aspects of the National Flood Insurance Program	Completed, pending Coastal Commission certification
C-21	Work with the County Office of Response, Recovery, and Resilience to refine FEMA flood hazard mapping to account for climate change, as maps are the basis for evacuation notification in the event of anticipated flooding and/or a tsunami	Combined and revised into ma-FL-SCC-02
C-22	Consider evaluating unprotected developed coastal bluff areas subject to future erosion, and develop plans and timeline for either armor placement, or retreat and relocation of existing public structures and/or infrastructure	Combined and revised into ma-CE-SCC-01, ma-CH-SCC-01, ma-SLR-SCC-01
C-23	Consider designing and siting all future County projects and infrastructure to account for sea level rise projections, considering projected life span of project	Combined and revised into ma-CH-SCC-01, ma-SLR-SCC-01
C-24	Consider securing federal grant funding for the following drainage improvements within the Rio Del Mar Esplanade necessary to protect against a 10-year storm	Combined and revised into ma-SF-SCC-01
C-25	Continue to improve wastewater collection system to reduce infiltration by groundwater or surface water	Combined and revised into ma-CH-SCC-01
C-26	Consider coordinating with the City of Santa Cruz on programs to minimize vulnerabilities at the Neary Lagoon plant	Combined and revised into ma-CH-SCC-01

PAGE INTENTIONALLY BLANK

Section 5. Works Cited

(2014). Retrieved from National Climate Assessment: https://nca2014.globalchange.gov/

85-560, U. G.-F. (1985). *Floods from Dam Failures.* Denver.

Association of Monterey Bay Area Governments. (2022). *Association of Monterey Bay Area Governments Scheduled for Adoption June 2022 .* Monterey: AMBAG.

Association of State Dam Safety Officials. (2024, Novmeber). *Dam Failures and Incidents*. Retrieved from https://damsafety.org/dam-failures

Beacon Economics. (2018). *Sonoma County Complex FIres: Housing and Fiscal Impact Report.* Santa Rosa, Cali.: Sonoma County Economic Development Board. Retrieved 0126 2020, from file:///C:/Users/Swing-Laptop/Downloads/Sonoma%20County%20Complex%20Fires%20Housing%20and%20Fiscal%20Impact%20Report%202018.pdf

Bole, A., Crimmins, A., Glass, G., Saha, S., Shimamoto, M. M., Trtanj, J., & White-Newsome, J. L. (2018). Chapter 14: Human Health. In D. C. Reidmiller (Ed.), *Impacts, Risks, and Adaptation in the United States: Fourth National Climate Assessment, Volume II.* Washington, DC, USA: U.S. Global Change Research Program. doi:10.7930/NCA4.2018

Cal. Air Resources Board. (2020). *Protecting Yourself from Wildfire Smoke.* CARB. Retrieved 04 07, 2020, from https://ww2.arb.ca.gov/protecting-yourself-wildfire-smoke

Cal. Dep't of Water Resources. (2015). *California's Most Significant Droughts: Comparing Historical and Recent Conditions*.

Cal-Adapt. (2018). *Annual Averages*. Retrieved from cal-adapt: https://cal-adapt.org/tools/annual-averages/#climatevar=tasmax&scenario=rcp45&lat=38.24&lng=-121.35&boundary=climregions&units=fahrenheit

(2021). *California Drought Contingency Plan.*

California Energy Comission. (2018). *Electricity Demand Changes and Grid Infrastructure Vulnerabilities in LA County by 2060: Policy Brief.* Retrieved from https://www.ioes.ucla.edu/wp-content/uploads/ElectricityDemandandGridVulnerabilityPolicyBrief.pdf

California Office of Environmental Health Hazard Assessment. (2019). *Heat Related Mortality and Morbidity.* Retrieved 04 02, 2021, from https://oehha.ca.gov/epic/impacts-biological-systems/heat-related-mortality-and-morbidity

CalOES. (2018). *California State Hazard Mitigation Plan.*

CalOES. (2025). *Dam Safety Planning*. Retrieved from Cal OES: https://www.caloes.ca.gov/office-of-the-director/operations/planning-preparedness-prevention/planning-preparedness/dam-safety-planning/

CDC. (2020, December 10). *Disparities in Deaths from COVID-19*. Retrieved from https://www.cdc.gov/coronavirus/2019-ncov/community/health-equity/racial-ethnic-disparities/disparities-deaths.html

CDC. (2021). *Extreme Heat.* Retrieved 04 01, 2021, from https://www.cdc.gov/disasters/extremeheat/index.html

Disasters Are Us. (n.d.). *Heat Wave*. Retrieved 05 08, 2020, from http://www.disastersrus.org/emtools/Heatwave/heatwave.htm

DWR. (2025). *California Water Plan*. Retrieved from California Department of Water Resources: https://water.ca.gov/Programs/California-Water-Plan

DWR. (2025). *Division of Safety of Dams*. Retrieved Jan. 30, 2020, from https://water.ca.gov/programs/all-programs/division-of-safety-of-dams

DWR. (2025). *Urban Water Management Plans*. Retrieved from California Department of Water Resources: https://water.ca.gov/Programs/Water-Use-And-Efficiency/Urban-Water-Use-Efficiency/Urban-Water-Management-Plans

Ebi, K., Balbus, J., Luber, G., Bole, A., Crimmins, A., Glass, G., . . . White-Newsome, J. (2018). Human Health. In D. Reidmiller, C. Avery, D. Easterling, K. Kunkel, K. Lewis, T. Maycock, & B. Stewart (Eds.), *Impacts, Risks, and Adaptation in the United States: Fourth National Climate Assessment, Volume II* (pp. 572-603). Washington, DC, USA: U.S. Global Change Research Program. doi:10.7930/NCA4.2018.CH14

EPA. (2021). *Learn About Environmental Justice.*

EPA. (2024, August 20). *Learn About Heat Islands*. Retrieved from https://www.epa.gov/heatislands/learn-about-heat-islands#_ftn1

Federal Highway Administration. (2013). *A Guide for Maintaining Pedestrian Facilities for Enhanced Safety.* Retrieved 04 02, 2021, from https://safety.fhwa.dot.gov/ped_bike/tools_solve/fhwasa13037/chap3.cfm

FEMA. (2024). *Disaster Declarations for States and Counties*. Retrieved from FEMA: https://www.fema.gov/tl/data-visualization/disaster-declarations-states-and-counties

Fothergill, A. M. (1999). Race, ethnicity and disasters in the United States: A review of the literature. Disasters. 23(2), 156-173.

Graham, B. a. (1988). Assessing the Threat to Life from Dam Failure. *Water Resources Bulletin, vol. 24, no. 6*.

HHS. (2020). *Access and Functional Needs*. (U. D. Services, Producer) Retrieved from Public Health Emergency: https://www.phe.gov/Preparedness/planning/abc/Pages/afn-guidance.aspx

Hoffman, J. S., Shandas, V., & Pendleton, N. (2020). The Effects of Historical Housing Policies on Resident Exposure to Intra-Urban Heat: A Study of 108 US Urban Areas. *Climate, 8*(1), 12-27. doi:https://doi.org/10.3390/cli8010012

Howell, J., & Elliot, J. R. (2019). Damages Done: The Longitudinal impacts of Natural Hazards on Wealth inequity in the United States. *Social Problems*, 448-467.

Hulley, G. C., Dousset, B., & Kahn, B. H. (2020, July). Rising Trends in Heatwave Metrics Across Southern California. *Earth's Future, 8*(7). doi:10.1029/2020EF001480

Krause, E., & Reeves, R. (2017, Sept 18). *Hurricans hit the poor the hardest.* Retrieved from Bookings Institute: https://www.brookings.edu/blog/social-mobility-memos/2017/09/18/hurricanes-hit-the-poor-the-hardest/

Lenhard, M. (2019, Nov. 26). How the California Wildfires are Impacting Tourism. *Skift.com*. Retrieved Jan. 26, 2020, from https://skift.com/2019/11/26/how-the-california-wildfires-are-impacting-tourism/

Levin, P., & Davies, I. (2019, Nov. 6). *Racial and Ethnic Minorities are More Vulnerable to Wildfires.* Retrieved Jan. 30, 2020, from The Conversation: http://theconversation.com/racial-and-ethnic-minorities-are-more-vulnerable-to-wildfires-106290

Makwana, N. (2019). *Disaster and its impact on mental health: A narrative review.* Retrieved 08 31, 2021, from https://www.ncbi.nlm.nih.gov/pmc/articles/PMC6857396/

Manconi, A. e. (2016). *Real-time detection, location, and characterization of Rockslides using broadband regional seismic networks.* Retrieved from https://agupubs.onlinelibrary.wiley.com/doi/pdf/10.1002/2016GL069572

Mandel, K. (2018, Aug. 21). *How Natural Disasters Widen the Wealth Gap Between Minority and White Communities.* Retrieved Jan. 30, 2020, from ThinkProgress.org: https://thinkprogress.org/wealth-gap-between-minority-and-white-communities-widens-after-natural-disasters-5108851f6b27/

National Advisory Council. (2020). *Novemeber 2020 Report to the FEMA Administrator.*

National Center for Disaster Preparedness. (2020). *Vulnerable Populations*. Retrieved 01 24, 2020, from https://ncdp.columbia.edu/research/vulnerable-populations/

National Center for Disaster Preparedness. (2020). *Vulnerable Populations*. Retrieved from https://ncdp.columbia.edu/research/vulnerable-populations/

National Institute of Building Sciences. (2019). *Natural Hazard Mitigation Saves: 2019 Report.* Retrieved 07 16, 2020, from https://www.nibs.org/page/mitigationsaves

National Weather Service. (2020). *Education*. Retrieved from https://www.weather.gov/

National Weather Service. (2022). *Wet Bulb Globe Temperature vs Heat Index*. Retrieved March 28, 2022, from Weather.gov: https://www.weather.gov/ict/WBGT

NIBS, 2. (2019, December 1). *National Hazard Mitigation Saves: 2019 Report*. Retrieved from National Institute of Building Sciences: https://www.nibs.org/projects/natural-hazard-mitigation-saves-2019-report

NIHHIS. (2021). *Extreme Heat - NIHHIS*. Retrieved March 7, 2022, from toolkit.climate.gov: https://toolkit.climate.gov/topics/human-health/extreme-heat

NOAA. (2023). *5 Unexpected Consequances of Extreme Heat*. Retrieved from NOAA Research: https://research.noaa.gov/5-unexpected-consequences-of-extreme-heat/

NOAA. (2025). *2024: An active year of U.S. billion-dollar weather and climate disasters*. Retrieved from Climate.gov: Science Information for a Climate-Smart Nation: https://www.climate.gov/news-features/blogs/beyond-data/2024-active-year-us-billion-dollar-weather-and-climate-disasters

NWS. (2023). *A parade of storms impact Bay Area*. Retrieved from National Weather Service: https://www.weather.gov/mtr/AtmosphericRivers_12_2022-01_2023

OCIA. (2015). *Drought Impacts to Critical Infrastructure.* U.S. Department of Homeland Security, Office of Cyber and Infrastructure Analysis. Retrieved from file:///C:/Users/Raini%20Ott/Downloads/Drought+Impacts+to+Critical+Infrastructure.pdf

Prevention, C. f. (n.d.). *Climate Change and Extrememe Heat Events.*

San Francisco Department of Emergency Management. (2019). *Communicable Diseases*. Retrieved from SF72: https://www.sf72.org/hazard/communicable-diseases

Santa Cruz County. (2024). *Housing Element of the General Plan.* Santa Cruz County.

Santa Cruz County. (2025). *Economic Contributions of Santa Cruz County Agriculture.* Office of the Agircultural Commissioner.

Santa Cruz County Regional Transportation Commission, 2. (2025). *Climate Adaptation Vulnerability Assessment (CAVA).* Santa Cruz County RTC.

Sarofim, M., Saha, S., Hawkins, M., Mills, D., Hess, J., Horton, J., . . . St. Julliana, A. (2016). Ch 2: Temperature-Related Death and Illness. In *The Impacts of Climate Change on Human Health in the United States: A Scientific Assessment* (pp. 43-68). Retrieved from https://health2016.globalchange.gov/low/ClimateHealth2016_02_Temperature_small.pdf

Shahir Masri et al. (2021). *Disproportionate Impacts of Wildfires among Elderly and Low-Income Communities in California from 2000–2020.*

Sherwin, B. (2019). *After the Storm: The Importance of Acknowledging Environmental Justice in Sustainable Development and Disaster Preparedness*.

State of California. (2018). *Sacramento Valley Regional Report; California's Forth Climate Change Assessment*.

State Water Board. (2018). *History of the Water Boards*. Retrieved from State Water Resources Control Board: https://www.waterboards.ca.gov/about_us/water_boards_structure/history.html

U.S. Dep't of Ag. (2017). *Hired Farm Labor, Workers and Payroll*. Retrieved 01 26, 2020, from USDA National Agricultural Statistics Service: https://www.nass.usda.gov/Quick_Stats/CDQT/chapter/2/table/7/state/CA/county/055/year/2017

UAF. (2015). *The Demise of Scotch Cap Lighthouse*. Retrieved from University of Alaska Fairbanks (UAF) Geophysical Institute: https://www.gi.alaska.edu/alaska-science-forum/demise-scotch-cap-lighthouse

Union of Concerned Scientists. (2018). *Heat Waves and Climate Change*. Retrieved from https://safety.fhwa.dot.gov/ped_bike/tools_solve/fhwasa13037/chap3.cfm

US Department of Energy. (2019). *Extreme Weather and Climate Vulnerabilities of the Electric Grid.* Retrieved 04 02, 2021, from https://www.energy.gov/sites/prod/files/2019/09/f67/Oak%20Ridge%20National%20Laboratory%20EIS%20Response.pdf

USGS. (2020). *Does human activity cause landslides?* Retrieved from https://www.usgs.gov/faqs/do-human-activities-cause-landslides?qt-news_science_products=0#qt-news_science_products

Visit Santa Cruz. (2019). *Santa Cruz County Facts, Stats, and FAQs*. Retrieved from Visit Santa Cruz: https://www.santacruz.org/press/facts-stats-faqs/

Water Education Foundation. (2020). *Oroville Dam: Aquapedia Background*. Retrieved Jan. 30, 2020, from Aquapedia: https://www.watereducation.org/aquapedia/oroville-dam

PAGE INTENTIONALLY BLANK

Appendix A. Analysis Methodology

SANTA CRUZ COUNTY
MULTI-JURISDICTIONAL
HAZARD MITIGATION PLAN

INTENTIONAL BLANK PAGE

A vulnerability assessment was conducted using Geographic Information Systems (GIS) for each of the priority hazards identified by the county-wide Hazard Mitigation Planning Team (HMPT). Several sources of data are necessary to conduct a vulnerability analysis. This appendix presents an outline of the data inputs, processing steps, and outputs used to create the vulnerability analysis results presented in the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). The analysis methodology is presented first, followed by an overview of the analysis data.

A.1. Natural Hazard Exposure

The natural hazard exposure analysis is an inventory of population, parcels, critical facilities, and other assets within each natural hazard area. As shown in Figure A- 1, the presence of a structure inside a natural hazard area (the flood zone in this example) qualifies that structure as exposed to the natural hazard.

Figure A- 1: Hazard Exposure

The total counts of parcels, people, facilities, and assets and the sum of values within the planning area which could be exposed to a hazard event are referred to as the “exposure” in this plan. A natural hazards overlay was developed to reflect the combination of many known natural hazard spatial footprints. The spatial overlay method enables summarization of building values, parcel counts, population exposure, and critical facility exposure within a hazard’s geographic extents (see C. Natural Hazard Exposure in Figure A-4). The input data is used to evaluate exposure for wildfire, flood, areas protected by levee, dam inundation, earthquake, liquefaction, faults of required investigation, landslide, SLR, and tsunami run-up.

A.1.1. Damage Estimation with HAZUS

FEMA’s HAZUS software was implemented to conduct a detailed loss estimation for flooding within the Special Flood Hazard Area (SFHA). HAZUS is a nationally applicable standardized methodology that contains models for estimating potential losses from earthquakes, floods, and hurricanes. HAZUS uses GIS technology to estimate physical, economic, and social impacts of disasters. For purposes of this planning effort, HAZUS was used to generate damage estimations due to possible flooding. The estimated damage and losses provided by the HAZUS Software provide the ability to understand possible widescale damage to

buildings and facilities. Figure A- 2provides a visual simplification of the HAZUS Software flood modeling parameters.



Figure A- 2: Flood Depth and Damage Curves

In the hypothetical geography shown in Figure A- 3, even though both structures are exposed to flooding, it is expected that the structure with a first-floor height below the depth-of-flooding will receive significantly more damage than the structure with a first-floor height above the expected water depth. Note that not all building data contains first-floor height, and first-floor height is an example of the type of field utilized by HAZUS in calculating damage estimates.



Figure A- 3: HAZUS Damage Estimations

Damage estimations are summarized by flood scenario and building occupancy type. Custom depth grids were modeled from county LiDAR data and the most up-to-date DFIRM at the time the analysis was run. HAZUS Inventory data were analyzed within HAZUS 7.0 against these depth grids at various return intervals.

HAZUS is a FEMA product with highly detailed documentation provided on the analysis steps and algorithms performed against the input data and associated scenarios in the process of obtaining loss estimates. The explanation in this appendix section is simplified. Refer to the full documentation and technical manuals from FEMA for greater explanation on HAZUS specifics.

A.1.2. Distinguishing Results: Natural Hazard Exposure Analysis vs HAZUS Results

Table and chart references throughout the hazard mitigation plan are explicitly called out for HAZUS results as "Damage Estimates". There are expected differences in the results between estimations of Natural Hazard overlays and HAZUS results. Snapshot tables and Natural Hazard Exposure sections do not contain HAZUS estimates.

A.2. Analysis Data: Population, Parcel Value & Assets

A.2.1. Population

Population input data for analyses consisted of 2023 ACS 5-Year Estimates for Census Block Groups. These were then processed through GIS modeling in order to break down the proportional population for smaller units of area in relation to natural hazards. Large bodies of water and parks were omitted from the weighted areas.

A.2.2. Parcels

County provided parcel geometry was joined with County Assessor data. Centroids were created to represent parcels at a single location. The centroid approach offered data integrity benefits over the use of address points due to multiple buildings occurring per parcel APN. Improved parcels were chosen for the parcels dataset by a query of building area and use-code descriptors. A replacement cost of $400 per square foot was used in place of assessed structure values. HAZUS occupany type categories and HAZUS based content multipliers were used to generally estimate content value based on a ration of replacement value.

Real Property Assets

For jurisdictions that supplied building specific tabular building data or insurance schedules, addresses were used to compile Real Property Asset data with valuations and structural data for analyses were possible. These assets were utilized in vulnerability exposure analysis. The tabular data were geocoded, and quality checked for building placement. This data, which is not exclusive to insurance or valuation rolls, is presented in the exposure analysis as "Real Property Assets". There may be some overlap with these infrastructure locations and other asset sources.

A.2.3. Critical Facilities & Infrastructure

Critical facilities and transportation/lifeline typically include hospitals, fire stations, police stations, storage of critical records, and similar facilities. These data came from a collection of sources, including but not limited to: county GIS, county and local jurisdiction insurance data, CDSS, CEC, FCC, HAZUS, USACE, NBI, FEMA, and National Park Service (NPS). All data sources have a level of accuracy acceptable for planning purposes.

Table A- 1 is a complete list of Critical Infrastructure data used in the analysis.

A.2.4. Natural Hazard Data

A.2.4.1. Earthquake Shaking

The CGS 2% chance/50-year probability map was used as a qualitative guide in selecting an earthquake epicenter-based ShakeMap scenario for analyses. The M7.1 N San Andreas; Santa Cruz Mountain earthquake scenario and ShakeMaps were used in this plan's analyses.

Intensity	Shaking	MMI	Description/Damage
I	Not Felt	0-1	Not felt except by a very few under especially favorable conditions.
II	Weak	1-2	Felt only by a few persons at rest, especially on upper floors of buildings.
III	Weak	2-3	Felt quite noticeably by persons indoors, especially on upper floors of buildings. Many people do not recognize it as an earthquake. Standing motor cars may rock slightly. Vibrations similar to the passing of a truck. Duration estimated.
IV	Light	3-4	Felt indoors by many, outdoors by few during the day. At night, some awakened. Dishes, windows, doors disturbed; walls make cracking sound. Sensation like heavy truck striking building. Standing motor cars rocked noticeably.
V	Moderate	4-5	Felt by nearly everyone; many awakened. Some dishes, windows broken. Unstable objects overturned. Pendulum clocks may stop.
VI	Strong	5-6	Felt by all, many frightened. Some heavy furniture moved; a few instances of fallen plaster. Damage slight.
VII	Very Strong	6-7	Damage negligible in buildings of good design and construction; slight to moderate in well-built ordinary structures; considerable damage in poorly built or badly designed structures; some chimneys broken.
VIII	Severe	7-8	Damage slight in specially designed structures; considerable damage in ordinary substantial buildings with partial collapse. Damage great in poorly built structures. Fall of chimneys, factory stacks, columns, monuments, walls. Heavy furniture overturned.

Intensity	Shaking	MMI	Description/Damage
IX	Violent	8-9	Damage considerable in specially designed structures; well-designed frame structures thrown out of plumb. Damage great in substantial buildings, with partial collapse. Buildings shifted off foundations.
X	Extreme	9-10	Some well-built wooden structures destroyed; most masonry and frame structures destroyed with foundations. Rails bent.

Source: USGS Scenario MMI Grid

A.2.4.2. Liquefaction Potential

Hazard	Native Class	Description
Low	Low	Soil potential for liquefaction. Based on "Geology and Liquefaction Potential of Quaternary Deposits in Santa Cruz County" 1975 W.R. Dupre.
Moderate	Moderate	
High	High	
Very High	Very High	

Source: County. W.R. Dupre 1975

A.2.4.3. Fault Zones of Required Investigation

Hazard	Native Class	Description
County Fault Zone	CFZ	County defined fault zones.
State Fault Zone	SFZ	State Fault Zones of Required Investigation - Regulatory areas around active faults with the potential for surface rupture.

Source: CGS and County Data

A.2.4.4. Sea Level Rise Inundation

Hazard	Native Class	Description
Sea Level Rise	50_w100	COSMOS v3.1 - 50cm Sea Level Rise modeled 100-YR Coastal Flood Event inundation boundary

Source: COSMOS v3.1

A.2.4.5. Tsunami Run-Up

Hazard	Description
Tsunami Run-up Area	County provided tsunamic run-up inundation area boundary

Source: County

A.2.4.6. Dam Failure Inundation

Dam inundation zone GIS data were provided by Cal DWR. These represent the estimated flood extent in the event of dam failure for individual dams.

Hazard	Description
Inundation Zone	Dam Inundation maps for the State of California are required by California Government Code Section 8589.5(b). DWR Dam Breach Inundation studies are used for inundation sourcing for dams with published inundation areas.

Source: Cal DWR

A.2.4.7. Flood Hazard Zones

The input parameters for HAZUS analysis of Flood exposure included depth grids created with the FEMA Flood Zone data for the 100-YR Flood Riverine as well as 100-YR Coastal zones within the DFIRM. 100-YR, Coastal, and 500-YR were scenarios used to analyze the exposure to inputs. The Coastal VE Zone is within the SFHA.

Hazard	Flood Zone	Description
100-YR Flood [SFHA]	Subtype: Floodway	A "Regulatory Floodway" means the channel of a river or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than a designated height. Communities must regulate development in these floodways to ensure that there are no increases in upstream flood elevations.
	SFHA outside Floodway	The land area covered by the floodwaters of the base flood is the Special Flood Hazard Area (SFHA) on NFIP maps. The SFHA is the area where the National Flood Insurance Program's (NFIP's) floodplain management regulations must be enforced and the area where the mandatory purchase of flood insurance applies.
100-YR Coastal Flood [SFHA]	VE	Coastal High-Hazard Area where wave action and fast-moving water have potential to cause high levels of damage during a base flood event. Part of the SFHA.
500-YR Flood [non-SFHA]	Subtype: 0.2% Annual Chance	Moderate risk areas within the 0.2-percent-annual-chance floodplain, areas of 1-percent-annual-chance flooding where average depths are less than 1 foot, areas of 1-percent-annual-chance flooding where the contributing drainage area is less than one square mile, and areas protected from the 1-percent-annual-chance flood by a levee. No BFEs or base flood depths are shown within these zones.

Source: FEMA DFIRM

A.2.4.8. USACE Best Available Mapping (BAM) Flood Awareness Zones

Hazard	Description
Awareness Zone	Awareness floodplains identify the 100-year flood hazard areas using approximate assessment procedures. These floodplains will be shown simply as flood-prone areas without specific depths and other flood hazard data.

Source: BAM USACE

A.2.4.9. Landslide Susceptibility

GIS layer with geographic boundaries defining the likelihood of deep-seated landslides. Underlying geology and slope angle are used in the creation of this layer by the California Geological Society. Low, Medium, and High landslide classes were chosen as summary classes for this plan.

Susceptibility	Native Class	Description
Low	**1-5**	These classes express the generalization that on very low slopes, landslide susceptibility is low even in weak materials, and that landslide susceptibility increases with slope and in weaker rocks.
Medium	**6-7**	Very high landslide susceptibility, classes VIII, IX, and X, includes moderate and steep slopes in hard rocks and weak rocks.
High	**8-10**	Very high landslide susceptibility, classes VIII, IX, and X, includes very steep slopes in hard rocks and moderate to very steep slopes in weak rocks.

Source: CGS Susceptibility to Deep-Seated Landslides in California

A.2.4.10. Wildfire Hazard Severity

A proprietary Dynamic Planning + Science composite GIS layer derived from wildland-urban interfaces, California Public Utilities Commission fire threat areas, and Fire Hazard Severity Zones (FHSZ).

Hazard	Native Class	Description
Moderate	**Moderate**	Classification of a zone as moderate, high or very high fire hazard is based on a combination of how a fire will behave and the probability of flames and embers threatening buildings. "This data represents Fire Hazard Severity Zones (FHSZ) in the State Responsibility Area (SRA), effective April 1st 2024, and recommended Fire Hazard Severity Zones in the Local Responsibility Area (LRA) from 2007-2011. It also represents Fire Hazard Severity Zones originally adopted in SRA that have since been reclassified as LRA." - California Department of Forestry and Fire Protection. Accessed June 2024. ***Additionally - The March 2025 unpublished LRA delineations were included in areas not covered by the April 2024 CAL FIRE data. Very little overlap occurs between these two datasets.**
High	**High**	
Very High	**Very High**	

Source: CAL FIRE April 2024 Authoritative layer and CAL FIRE unpublished March 2025 LRA layer.

A.2.4.11. Wind Classification

Wind Power Class	10 m (33 ft)		50 m (164 feet)[1]	
	Wind Power Density W/m²	Mean Speed[2] m/s (mph)	Wind Power Density W/m²	Mean Speed[2] m/s (mph)
1	≤ 100	4.4 (9.8)	≤ 200	5.6 (12.5)
2	100-150	5.1 (11.5)	200-300	6.4 (14.3)
3	150-200	5.6 (12.5)	300-400	7.0 (15.7)
4	200-250	6.0 (13.4)	400-500	7.5 (16.8)
5	250-300	6.4 (14.3)	500-600	8.0 (17.9)
6	300-400	7.0 (15.7)	600-800	8.8 (19.7)
7	>400	9.4 (21.1)	>800	11.9 (26.6)

Notes: [1]Vertical extrapolation of wind speed based on the 1/7 power law. [2]Mean wind speed is based on Rayleigh speed distribution of equivalent mean wind power density and is for standard sea-level conditions.

Source: NREL, 2007

A.2.5. Methodology Overview



Figure A- 4: Data Analysis Methodology

A.2.6. Data Dictionary

Table A- 1: GIS Data Dictionary

Dataset	Data Steward	Notes
Jurisdictional/Municipal Boundaries	County	County GIS. Port District and Cabrillo College digitized based on parcel boundaries
County Boundary	County	County GIS
High-Resolution Elevation Model	County	LiDAR
GNIS	USGS	For Placenames
Stream	NHD+	Cartographic Purposes
Water	NHD+	Cartographic Purposes
Building Outlines	Microsoft, OSM	County Provided
Parcel Geometry	County	County GIS
Parcel Roll	County	County Assessor's Office
AMR	County	American Medical Response-separate from other medical (queried out facilities)
Emergency Operations Center	County	Queried from County 'Facilities' GIS layer. Only including County-wide EOC in this layer
Fire Station	County	Queried from County 'Facilities' GIS layer. Includes associated assets from participating Jurisdiction provided GIS Data
Hospital	County	Queried from County 'Facilities' GIS layer
Law Enforcement	County	Queried from County 'Facilities' GIS layer. Includes associated assets from participating Jurisdiction provided GIS Data
Adult Care Facility	County	Queried Nursing Homes from County 'Facilities' layer
Cabrillo Campus Buildings	DPS	Digitized from the available online campus map
Capitola City Additional Response Assets	City	Uncategorized geolocated city assets. Law enforcement, fire stations, library, city hall were all incorporated with appropriate datasets from the county
Cell Tower	County	County Provided via email
Child Care Center	CDSS	Queried from County 'Facilities' GIS layer
City Hall	County, City, DPS	Combination of County GIS, City data, and digitizing
County Real Property Asset	County	From the County GIS "County Facilities" layer. May be some overlap
Dam	USACE NID, DWR	USACE NID
Healthcare Facility	County	Queried 'clinics' from County 'Facilities' GIS layer
Historic Building	NPS	Historical data from NPS as registered
Historic Site	NPS	Historical data from NPS as registered

Dataset	Data Steward	Notes
Library	County	Queried from County 'Facilities' GIS layer
Power Generation	CEC	Updated CEC data from 2023; 3rd party source data can be supplemented by local data per availability. Includes non-traditional power plants
PVWMA Asset Location	DPS	Digitized office location
Radio Sites	County	County Provided
Resource Conservation District	DPS	Digitized office location
School	County	County GIS School's data
Scotts Valley City Water Treatment	City	This water treatment facility was not in the SVWD provided data but was in the City's data
SqCWD Water Treatment	District	SCWD GIS Files
SVWD Administration	District	From SVWD GIS File "Asset Locations"
SVWD Water Treatment	District	From SVWD GIS
Watsonville Emergency Shelters	City	From City GIS Files. Other Watsonville assets were integrated from city GIS into appropriate layers (Ie Fire Stations)
Watsonville Water Treatment	City	From City GIS Files. Other Watsonville assets were integrated from city GIS into appropriate layers (Ie Fire Stations)
Mobile Home Park	CAHCD	From CAHCD Mobile Home Park Search
Drainage Yard	DPS	Digitized based on prior plan assets
Airport	DPS	Manually Digitized
Bridge NBI	NBI	County GIS Hub
Capitola City Misc	City	Geolocated assets from city provided table. Integrated categorically with other major layers such as fire stations, law enforcement, etc. These are assets with no categorical integration
Church	County	Queried From County GIS Data Hub "Facilities" layer
County Maintained Roads	County	County Maintained Roads' Layer, has overlap with Streets layer
Levee	FEMA	FEMA DFIRM Sourced
Maintained Channel	County	County GIS Hub
NG Pipeline	CEC	From CEC Legacy
NG Station	CEC	From CEC Legacy
Capitola Pump Station	Capitola	Digitized from notes
SqCWD Hydrant	SqCWD	Appended to initial dataset by request. Data provided via email
Watsonville Surface Water Intake	Watsonville	Appended to initial dataset by request. Data provided via email

Dataset	Data Steward	Notes
Watsonville Water Control Valve	Watsonville	Appended to initial dataset by request. Data provided via email
Watsonville Hydrant	Watsonville	Appended to initial dataset by request. Data provided via email
Watsonville Water System Valve	Watsonville	Appended to initial dataset by request. Data provided via email
Watsonville Pump	Watsonville	Appended to initial dataset by request. Data provided via email
Watsonville Water Main	Watsonville	Appended to initial dataset by request. Data provided via email
PVWMA Harkins Slough Pump Recharge	PVWMA	Appended to initial dataset by request. Data provided via email
PVWMA Harkins Slough Recovery Well Line	PVWMA	Appended to initial dataset by request. Data provided via email
PVWMA Struve Slough Pipeline	PVWMA	Appended to initial dataset by request. Data provided via email
PVWMA Fiber Comms Line	PVWMA	Appended to initial dataset by request. Data provided via email
PVWMA Water Supply Facility	PVWMA	Appended to initial dataset by request. Data provided via email
Stormwater Culvert	County	Appended to initial dataset by request. Data provided via email
Sanitation Pipe	County	Appended to initial dataset by request. Data provided via email
SCWD Treated Water Mains	County	City of Santa Cruz Water Mains
Central Water Main Lines	County	Central Wawter District Water Mains
Parks	County	From County GIS Hub "Existing Parks" layer
Port District Infrastructure	DPS	Manually Digitized
PVWMA Coastal Distribution	District	District provided GIS Data
PVWMA College Lake Pipeline Water	District	District provided GIS Data
PVWMA College Lake Project Water	District	District provided GIS Data
Railroad	County	From County GIS Hub "Railroads" layer
Streets	County	Using County GIS Streets layer in addition to (and with overlap) the county maintained roads layer
Scotts Valley City Community Centers	City	Geolocated assets from city provided table. Integrated categorically with other major layers such as fire stations, law enforcement, etc. These are those assests with no categorical integration
SqCWD Emergency Intertie	District	District provided GIS Data
SqCWD Main	District	District provided GIS Data
SqCWD Pressure Regulating Valve	District	District provided GIS Data
SqCWD Production Well	District	District provided GIS Data

Dataset	Data Steward	Notes
SqCWD Pump Station	District	District provided GIS Data
SqCWD SWIP Well	District	District provided GIS Data
SqCWD Tank	District	District provided GIS Data
Substation	CEC	From CEC 2018
SVWD Backflow Device	District	District provided GIS Data
SVWD Backflow Facility	District	District provided GIS Data
SVWD ControlValve	District	District provided GIS Data
SVWD Hydrant	District	District provided GIS Data
SVWD Lateral	District	District provided GIS Data
SVWD Main	District	District provided GIS Data
SVWD PRV	District	District provided GIS Data
SVWD Pump	District	District provided GIS Data
SVWD Tank	District	District provided GIS Data
SVWD Well	District	District provided GIS Data
Transit Facilities	County	From County GIS Data Hub "Facilities" layer. May change to TL
Transmission Line	CEC	From CEC 2024
Watsonville Unreinforced Masonry	City	From City GIS Files. Other Watsonville assets were integrated from city GIS into appropriate layers (Ie Fire Stations)
Geotracker CleanupSite	Geotracker	Geotracker cleanup sites active
HWTS Active Facility	DTSC	HWTS Active Facilities
Census Block	US Census Bureau	2020 Census
Census Block Group	US Census Bureau	2023 5YR ACS
Dam Inundation	DWR	DWR 2025
EQ Scenario	USGS, CISN	M7.1 N San Andreas; Santa Cruz Mountain
Flood Awareness Zones	BAM USACE	Awareness floodplains identify the 100-year flood hazard areas using approximate assessment procedures. These floodplains will be shown simply as flood-prone areas without specific depths and other flood hazard data
Flood Hazard	FEMA, County	FEMA most recent DFIRM including SHFA areas and 0.2% Annual Chance of Flooding. Includes Coastal Flooding within 100 Yr
Sea Level Rise	Cal-Adapt, USGS	COSMOS v3.1 - 50cm Sea Level Rise modeled 100-YR Coastal Flood Event inundation boundary
Landslide Susceptibility	CGS	CGS

Dataset	Data Steward	Notes
Liquefaction	County	County GIS Liquefaction layer, Low, Moderate, High, Very High. Based on "Geology and Liquefaction Potential of Quaternary Deposits in Santa Cruz County" 1975 W.R. Dupre
Tsunami Run-up	County	County GIS Tsunamic Runup Area Boundary
Wildfire Hazard Severity Zone	County	Classification of a zone as moderate, high or very high fire hazard is based on a combination of how a fire will behave and the probability of flames and embers threatening buildings. "This data represents Fire Hazard Severity Zones (FHSZ) in the State Responsibility Area (SRA), effective April 1st 2024, and recommended Fire Hazard Severity Zones in the Local Responsibility Area (LRA) from 2007-2011. It also represents Fire Hazard Severity Zones originally adopted in SRA that have since been reclassified as LRA." - California Department of Forestry and Fire Protection. Accessed June 2024. *Additionally - The March 2025 unpublished LRA delineations were included in areas not covered by the April 2024 CAL FIRE data. Very little overlap occurs between these two datasets
Expansive Soil	County	County Data Portal
EQ Fault Zones	County	State and County mapped
Fire Perimeter Calfire	NIFC	Cartographic Purposes
Fire Regime MFRI	USGS	https://www.landfire.gov/NationalProductDescriptions13.php
Repetitive Loss Areas	FEMA	FEMA/County Supported
Shake Potential	USGS, CISN	Used for EQ Scenario Selection and Cartographic/Thematic mapping purposes

PAGE INTENTIONALLY BLANK

Appendix B. Process Documentation

SANTA CRUZ COUNTY
MULTI-JURISDICTIONAL
HAZARD MITIGATION PLAN

INTENTIONAL BLANK PAGE

Planning Process Documentation Appendix

Table of Contents

Planning Committee Meeting Documentation B.1-1

Public Notice & Press Release Documentation B.2-1

Survey & Results Documentation B.3-1

Mitigation Strategy Prioritization Process Documentation B.4-1

Website Documentation B.5-1

Outreach Events B.6-1

Stakeholder Listening Sessions B.7-1

PAGE INTENTIONALLY BLANK

Planning Committee Meeting Documentation

Appendix B.1

PAGE INTENTIONALLY BLANK



Internal Kickoff Zoom

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

December Check In with Partner Jurisdictions

Date:	December 13, 2024	**Facilitator**:	Clare Peabody, County OR3
Time:	10:00am – 11:00am	**Location**:	Via Teams: Meeting Link

Participating Organizations

County of Santa Cruz	Soquel Creek Water District
City of Watsonville	Scotts Valley Water District
City of Capitola	Santa Cruz Port District
City of Santa Cruz	RCD of Santa Cruz County
City of Scotts Valley	Cabrillo College
Pajaro Valley Water Management Agency	Dynamic Planning + Science (Consultant)

Meeting Purpose:

- Provide an overview of the MJHMP planning process
- Introduce the consultant team (DP+S)
- Outline expectations, roles, and next steps for participating jurisdictions.

By the end of the meeting Partners will:

- Understand project background, objectives and timeline for 2025;
- Obtain clarity regarding staff time commitments and expectations for participation;
- Have been introduced to the consultant team Dynamic Planning + Science
- Feel informed and prepared to begin identifying Planning Committee membership

Agenda

ID	Time	Action Item
1	5 min	Welcome and Introductions **Result:** Partners understand the purpose of the meeting, expected outcomes, and meeting flow.
2	10 min	Project Background **Result:** Partners understand the project's purpose, funding source, and intended outcomes.
3	5 min	Consultant Team Intro with Dynamic Planning + Science **Result:** Partners know who the consultant team members are and understand their roles and responsibilities throughout the planning process.

ID	Time	Action Item

4	25 min	Expectations and Commitments
		• MJHMP Planning Process Timeline
		• Overview of Stakeholder Groups and Responsibilities
		  ○ Primary Representatives
		  ○ Planning Committee
		Result: Partners understand overall project timeline, expected roles, time commitments, and responsibilities as Planning Committee members or lead contacts.

5	10 min	Check Out / Next Steps **Result:** Partners

Action Commitments

Description	Assigned to	Target Date
Confirm formal participation and intent to develop a formal annex to the Santa Cruz County MJHMP; submit signed Letter of Intent (LOI) if not already completed.	All partners	January 3, 2024
Identify primary contacts for each participating jurisdiction	All partners	January 3, 2024
Designate staff too serve on Planning Committee	All partners	January 10, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan

Hazard Mitigation Planning Committee (HMPC) Meeting #1

Date: Monday, January 27th, 2025

Time: 9:00 a.m. – 11:00 a.m

Facilitator: Santa Cruz County Office of Response, Recovery & Resilience / DP+S

Location: Santa Cruz County Emergency Operations Center, 5200 Soquel Ave. OR Teams

Meeting Purpose: The first of four Planning Team meetings to develop the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP).

At the end of the meeting participants will:

- Possess the background knowledge necessary to meaningfully contribute to the MJHMP planning process.
- Understand the plan's purpose, goals, and how it supports FEMA grant eligibility.
- Be familiar with their roles and responsibilities as members of the Planning Team and the overall project timeline.
- Begin fostering collaboration across jurisdictions to ensure a comprehensive and actionable plan.

Agenda

ID	Time	Action Item	Key Decision/ Support Request
1	10 min	**Welcome and Introductions** **Result:** Partners understand meeting purpose and expected outcomes. Establish connections across different jurisdictions to strengthen collaboration.	
2	10 min	**Background and Mitigation 101** **Result:** Partners develop shared understanding of hazard mitigation principles and regulatory environment guiding HMP development	

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3	10 min	**The Planning Process / Project Schedule Overview**  **Result:** Clear expectations	
4	10 min	**HMA Funding Opportunities** **Result:** Partners are familiar with main categories of FEMA HMA funding (BRIC, FMA, HMGP) and their alignment with HMP goals.	
5	*10 min*	*Break*	
6		**2021 HMP Flip Through & What's Changed** **Result:**	Solicit feedback on mitigation success stories and recent disasters/ development trends/ changes in community priorities that will guide the new MJHMP
7		**Outreach Strategy Review** **Result:**	
8		**Next Steps** **Result:**	

Meeting Action *Commitments*

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Description	Assigned to	Target Date	Date Completed

PC 1 In Person Attenance

PC 1 In Person Attendance 2

Santa Cruz County Hazard Mitigation Plan 2025 Update

Planning Team Meeting #1
Monday, January 27th, 2025
9:00 A.M. – 11:00 P.M.

MITIGATE HAZARDS
www.mitigatehazards.com

PC 1 Powerpoint

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #1

County Emergency Operations Center, 5200 Soquel Ave

January 27, 2025, 9am - 11am

Name	Agency	Email	Phone
Courtney Lindberg	City of Watsonville	courtney.lindberg@watsonville.gov	
Nikki Bryant	City of Capitola	nbryant@ci.capitola.ca.us	
Chloe Woodmansee	City of Capitola	cwoodmansee@ci.capitola.ca.us	
Elizabeth Byrd	County of Santa Cruz	elizabeth.byrd@santacruzcountyca.gov	(831) 454-2437
Brian Lockwood	PV Water	lockwood@pvwater.org	722-9292
Taylor Bateman	Scotts Valley	tbateman@scottsvalley.gov	831-440-5633
Lun Wang	Santa Cruz Co. HSA	lun.wang@santacruzcountyca.gov	
GREG BENSON	EMS	GREGORY.BENSON@SANTACRUZCOUNTYCA.GOV	
TOTO VU-DUC	CITY OF WATSONVILLE	toto.vuduc@watsonville.gov	831 768 3187
CLARE PEABODY	COUNTY OES	clare.peabody@santacruzcountyca.gov	831 454 9584
DAVE REID	"	DAVID.REID@SANTACRUZCOUNTY.CA.GOV	

PC 1 Sign In_Part1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #1

County Emergency Operations Center, 5200 Soquel Ave
January 27, 2025, 9am - 11am

Name	Agency	Email	Phone
Jorge Melgoza	City of Capitola	jmelgoza@ci.capitola.ca.us	831-475-73[illegible]
MATT MACHADO	County of Santa Cruz		
Elizabeth Bypal	County of Santa Cruz	Elizabeth.bypal@santacruzcountyca.gov	(831) 454-4397
Jessica Kahn	City of Capitola	jkahn@ci.capitola.ca.us	8314757300
Luis Toledo	Cabrillo College	ltoledo@cabrillo.edu	831-212-8433
Skyler Murphy	Soquel Creek WD	SkylerM@soquelcreekwater.org	831-475-8501
NICK BALDRIGE	SCSO	NICHOLAS.BALDRIGE@SANTACRUZCOUNTYCA.GOV	
Shelley Flock	Soquel Creek WD	shelleyf@soquelcreekwater.org	831-588-7500
MATT ABERNATHY	RCD of Santa Cruz Co	MABERNATHY@RCDSANTACRUZ.org	
KATIE HERLIHY	City of Capitola	kherlihy@ci.capitola.ca.us	
Matt Orbach	City of Watsonville	matt.orbach@watsonville.gov	
Robin Woodman	City of Capitola	building-official@ci.capitola.ca.us	

PC 1 Sign In_Part2


SCC MJHMP - Hazard Mitigation Planning Committee Meeting # 1
31:21
Pop out
Chat
People
26
Raise
React
View
More
Camera
Mic
Share
Leave
Clare Peabody (Unverified)
Julie Charle...
DO
Raini Ott, D...
Jessica deG...
Matt Price (...
In this meeting (26)
David Rodriguez (Unverified)
Ethan Mobley, DP... (Unverified)
Holland MacLaurie (Unverified)
Jessica deGrassi (Unverified)
Joseph DeSante (Unverified)
Julie Charles - Cab... (Unverified)
Leah MacCarter (Unverified)
Marcus Mendiola (Unverified)
Matt Price (Unverified)
Nate Gillespie (Unverified)
Nick Calubaquib (Unverified)
Raini Ott, DP+S (Unverified)
Robert Tidmore (Unverified)
Sierra Ryan (Unverified)
Tiffany Wise-West (Unverified)
Tom Avila (Unverified)
Project Org Chart
Santa Cruz County PM Team
City of Scotts Valley
City of Santa Cruz
City of Capitola
City of Watsonville
Soquel Creek Water District
Scotts Valley Water District
Pajaro Valley Water Management Agency
Resource Conservation District of Santa Cruz County
Santa Cruz Port District
Cabrillo College
teams.microsoft.com is sharing your screen.
Stop sharing
Hide
SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN
Ethan Mobley, DP+S (Unverified)
Search
10:14 AM
1/27/2025

PC 1 Zoom

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Hazard Mitigation Planning Team (HMPT) Meeting #2

NOTE: In-person attendance required to participate in a small group exercise.

Date: Thursday, March 27, 2025
Time: 1:00 P.M. – 3:00 P.M.
Location: Santa Cruz County Emergency Operations Center (5200 Soquel Ave, Santa Cruz 95062)

Facilitator: Santa Cruz County Office of Response, Recovery & Resilience (OR3) and Dynamic Planning + Science (DP+S)

Meeting Purpose

To confirm the overarching goals of the MJHMP and to determine the realm of hazards and areas of concern across Santa Cruz County. At the end of the meeting participants will:

- Ensure all stakeholders have a baseline understanding of local hazards and current conditions.
- Ensure that all stakeholders are aligned on the overarching, county-wide goals of the plan, key findings, and next steps.
- Identify potential county-wide priority hazards, areas of concern, and mitigation strategies through a facilitated small group exercise.

Agenda

ID	Time	Action Item	Key Decision/ Support Request
1	5 min	**Welcome** **Result:** Overview of meeting goals and expected outcomes.	
2	5 min	**Key Takeaways from HMPT Meeting #1** **Result:** Recap of discussions and decisions made.	
3	25 min	**Risk and Vulnerability Overview** **Result:** Baseline understanding of the hazard vulnerability assessment process and preliminary results in preparation for first round of Breakout Sessions. a) Risk Assessment Process: Overview of the process, highlighting key findings so far.	Consensus on overarching plan goals.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

		b) Demographics and Vulnerable Populations: Overview of demographics and at-risk populations. c) Hazards Overview: Discuss top threats and local perceptions from stakeholder engagement. d) Interactive Risk Matrix: Introduction to risk matrix and exercise for first round of jurisdiction Breakout Sessions. e) Risk Assessment Mapping Platform (RAMP): Introduction to RAMP tool for hazard risk analysis. f) MJHMP Goals: Find consensus on the overarching county-wide goals for the plan.	
4	1 hr 20 min	**Small Group Exercise** **Result:** Scratching the surface of hazards and impacts across the county to begin to understand the people, property, and critical facilities and infrastructure at risk. Start to focus in on where and what type of mitigation is needed most. a) Station #1: Wildfire Hazard b) Station #2: Flooding and Inundation Hazards c) Station #3: Geologic and Earthquake Hazards d) Station #4: Drought and Extreme Weather Hazards *At each station, ask yourself: Within the areas affected by this hazard…* • *What lifelines or other community assets should we focus on?* • *What vulnerable populations are present?* • *Where should we focus mitigation efforts?* • *What specific types of mitigation efforts should we focus on?*	Start to identify priority county-wide hazards, areas of concern, and potential mitigation strategies.
5	5 min	**Closeout** a) Stakeholder Engagement: Upcoming events. b) Project Schedule Reminders: Individual jurisdiction Breakout Sessions in April and May, optional RAMP training sessions April 4 and 18, and HMPT Meeting #3 in early June. c) Questions: County and DP+S staff available for post-meeting questions.	

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Meeting Action Commitments

Description	Assigned to	Target Date	Date Completed

PC 2 In Person Attendance (1)

PC 2 In Person Attendance (2)

PC 2 In Person Attendance



PC 2 Map Poster w Comments 1



PC 2 Map Poster w Comments 2



PC 2 Map Poster w Comments 3

2025 MJHMP
DISTRICTS
declining 18+ under population
1 in 3 60+ by 2030
HOUSING REHAB
BUILDING ENVL-
55+ MOBILE HOME COMMUNITIES
ADULT MOBILE HOMES
HOTTER IN VALLEYS
Power out = water out for wells
Drought - Agriculture
Watsonville
Capitola
Bridges
Larry Storms
Tourists stay home
$
homeless populations vulnerable to heat
Businesses impacted from Waves + Sea Level Rise
Capitola Village
Cold water shock
CROP (RED) DOLLARS FROM DROUGHT
Conservation
Capitola gear also adaptable for heating/cooling chairs
State Parks - (closures + parking)
diversify water portfolios beyond conservation
Drought tolerant water supply
Pure Water Soquel
Soquel Creek
Sea Water Intrusion
Water Supply
Technically, PV Water is a Special District
Scotts Valley Water District
Pajaro Valley Water Management Agency
Resource Conservation District of Santa Cruz County
Santa Cruz Port District
Cabrillo College
Recharge Methazzle for Sea water intrusion & recharge
Fish species impacted by drought
Watsonville Cost of Living
PEOPLE IN FORESTED AREAS (Cabrillo)
EUCALYPTUS - EVERYWHERE - RATS IN WARD, FLOODING (OBSTRUCTION OF DITCHES)
20,000 people on wells
2,500 people on Small water systems
Storm Water Opp: For Water Supply
Sanitation pump stations @ Seacliff Beach, Hidden Beach - Pump Explanade All Vulnerable to Sea Level Rise
Privately owned utilities to harden their infrastructures
Major Transportation Corridors - Cliff Drive Village - Park Avenue on Bluff
Flooding in URBAN AREAS - 50 year old pipes beneath mobile home parks as live, one of capacity
Water supply levels
Saltwater intrusion
Plantation Homes
Use of recycled water for agriculture (upgraded thg chapter) Watsonville
Damage to traffic signals from failure
Trees (falling)
Roads in Hazard Areas
Changing climate impacts what crops can grow
Impacts to more tourists
Trees / Root Crops Occurs w/ wind
Agriculture Access Cabrillo
Co Fire
Schools closing post-winter storms - Safety - public + workers to coastal areas to observe extreme weather storms, etc
Farmers, crops heavily impacted in southern county (Pajaro Valley)
PV Water
Pajaro Valley is already operating at capacity, depleted on gw. Talks to find solutions
Post on water quality re: increased nitrates, algae, more treatments needed
Recharge
Assistance landscapers + Home Owners to adapt against changing climate
Changes to landscape and design
Need more water to irrigate
Water Supply
Groundwater recharge for drought resilience + Stormwater management
Hwy 1 Watsonville to SLO (very busy) - Coastal Hazard study maybe Watsonville and Coastal Access
Private Roads
Water Supply
Private Roads
Access Roads
Emergency Response
Private Roads
Access Roads
Emergency Response
Private Roads
Access Roads
Emergency Response

Santa Cruz County
Hazard Mitigation Plan 2025 Update

Hazard Mitigation Planning Team (HMPT) Meeting #2

Thursday, March 27, 2024

1:00 P.M. – 3:00 P.M.

MITIGATE HAZARDS

www.mitigatehazards.com

PC 2 Powerpoint

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #2

County Emergency Operations Center, 5200 Soquel Ave
March 27, 2025, 1:00 p.m. - 3:00 p.m.

Name	Agency	Email	Phone
TOTO VU-DUC	CITY OF WATSONVILLE	tho.vuduc@watsonville.gov	831-768-3187
Cristy Cassel	City of Watsonville	cristy.cassel@watsonville.gov	831.768-3166
Holland Maclaurie	Santa Cruz Harbor	hmaclaurie@santacruzharbor.org	
Patricia Zamora	Community bridges	patricia2@cbridges.org	
LAURA WHALEY	SC PUBLIC LIBRARIES	WHALEYL@SANTACRUZPL.ORG	831-331-0219
Julie Charles	Cabrillo Comm College	jcharle@cabrillo.edu	707.656.8501
Brian Gallagher	Cabrillo College	bgallagh@cabrillo.edu	
David Carlson	County of S.C.		
TOM AVILA	CITY OF WATS	tom.avila@watsonville.gov	
CAROLYN BURKE	CO. OF SC	carolyn.burke@santacruzcounty.gov	
Courtney Trask	UCSC	trask@ucsc.edu	831 459 4520
Chloe Woodmansee	Capitola	cwoodmansee@ci.capitola.ca.us	
Jessica Kahn	Capitola	jkahn@ci.capitola.ca.us	
Matt Kotila	Capitola	mkotila@ci.capitola.ca.us	831 475 7300 476-4227
Skyler Murphy	Soquel Creek Water	SkylerM@soquelcreekwater.org	831 475 8501
Matt Abernathy	RCDSCC	MABERNATHY@RCDSANTACRUZ.ORG	

PC 2 Sign In 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #2

County Emergency Operations Center, 5200 Soquel Ave
March 27, 2025, 1:00 p.m. - 3:00 p.m.

Name	Agency	Email	Phone
Charles Hanley	Watsonville	charles.hanley@watsonville.gov	831-768-3462
Erin Johnson	UC Santa Cruz	erinj@ucsc.edu	831-212-3234
Brian Lockwood	PV Water	Lockwood@pvwater.org	722-9292
Sierra Ryan	Santa Cruz County		
Taylor Bateman	City of S.V.	tbateman@scottsvalley.org	
Forrest Reuter	PRFMA	FORREST.REUTER@PREMA.ORG	
DAVID RODRIGUEZ	WATSONVILLE PD	david.rodriguez@watsonville.gov	
Elizabeth Byrd	County of Santa Cruz	elizabeth.byrd@santacruzcountyca.gov	831-588-9788
Amanda Gullings	OR3	amanda.gullings@santacruzcountyca.gov	
Jonathan Pick	Watsonville Water	jonathan@watsonvillewaterlaw.org	831-728 4106
Matt Orbach	City of Watsonville	matt.orbach@watsonville.gov	831-600-5469
Nate Gillespie	Scotts Valley Water District	ngillespie@svwd.org	(831)600-1903
David McNair	Scotts Valley Water District	dmcnair@svwd.org	831.600.1902
Antonella Gentile	Santa Cruz County DPW	antonella.gentile@santacruzcountyca.gov 831 454 2632	
DAVE REID	SCC OR3	—	—
Lisa Lurie	RCDSCC	llurie@rcdsantacruz.org	

PC 2 Sign In 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #2

County Emergency Operations Center, 5200 Soquel Ave
March 27, 2025, 1:00 p.m. - 3:00 p.m.

Name	Agency	Email	Phone
Lauren Moody	Fire Safe Santa Cruz County	lauren@firesafesantacruzcounty.org	541.968.0008
Katie Herlihy	City of Capitola	kherlihy@ci.capitola.ca.us	831-475-7300
Joelle Mehner	CalOES	joelle.mehner@caloes.ca.gov	(916) 926-9854
Justin Meek	City of Watsonville	justin.meek@watsonville.gov	768-3077

PC 2 Sign In 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #2

County Emergency Operations Center, 5200 Soquel Ave

March 27, 2025, 1:00 p.m. - 3:00 p.m.

Name	Agency	Email	Phone
Cameron McDonald	RCDSCC	cmcdonald@rcdsantacruz.org	(831)205-3766
Sam Filson	CAL FIRE/SANTACRUZCOFD	SAM.FILSON@FIRE.CA.GOV	831-278-1764
NICK BALDRIGE	SCSO	NICHOLAS.BALDRIGE@SANTACRUZCOUNTYCA.GOV	831-334-0006
Luis Toledo	Cabrillo College	lvtoledo@cabrillo.edu	831-212-8434
Courtney Lindberg	City of Watsonville	courtney.lindberg@watsonville.com	8053280944
Rob Tidmore	Santa Cruz County Parks	robert.tidmore@santacruzcountyca.gov	831-454-7947
MATT MACHADO	SANTA CRUZ COUNTY		
Carly Blanchard	City of Scotts Valley	cblanchard@scottsvalley.gov	831 222 0275
Angie Gruys	RCDSCC	agruys@rcdsantacruz.org	831.419.8710

PC 2 Sign In 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #2

County Emergency Operations Center, 5200 Soquel Ave

March 27, 2025, 1:00 p.m. - 3:00 p.m.

Name	Agency	Email	Phone
Denise Harris	Visit SCCo	dharris@santacruz.org	

PC 2 Sign In 5

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

7	5 min	**Prepare for Round 2 of Breakout Sessions** **Result:** Communicate objectives for second round of breakout meetings. Confirm outstanding action items and responsibilities.	Jurisdiction coordination on second round of breakout meetings.
8	5 min	**Closing Remarks and Next Steps** **Result:** Summary of key takeaways, next steps, and upcoming meeting details.	

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan

Hazard Mitigation Planning Team (HMPT) Meeting #3

Date: Monday, June 2, 2025

Time: 1:00 p.m. – 3:00 P.M.

Location: Zoom

Facilitator: Santa Cruz County Office of Response, Recovery & Resilience (OR3) / Dynamic Planning + Science (DP+S)

Join Zoom Meeting
https://us02web.zoom.us/j/89427240680?from=addon
Meeting ID: 894 2724 0680

Meeting Purpose: The third of four county-wide Planning Team meetings to advance the development of the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). This session is designed to build upon the outcomes of previous meetings, focusing on the refinement of hazard profiles, prioritization of mitigation actions, and alignment of strategies across jurisdictions to ensure comprehensive risk reduction and FEMA compliance.

At the end of the meeting participants will:

- **Understand and Have Consensus on County-Wide Hazard Priorities** based on the results of the first round of breakout meetings, public engagement so far, and updates to hazard risk assessments.
- **Align and Refine the County-Wide Mitigation Strategy** to address identified risks and community priorities and to ensure they are actionable, cost- and resource-effective, align with local capabilities and FEMA guidelines, and that they support inter-agency collaboration.
- **Understand Next Steps in Preparing for Round 2 of Breakout Sessions** including by responding to data needs and coordinating scheduling with DP+S, which will ensure all jurisdictions are equipped to finalize their mitigation strategies.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Agenda

ID	Time	Action Item	Key Decision/ Support Request
1	10 min	**Welcome and Introductions** **Result:** Opening remarks, overview of meeting objectives, and introduce new members if any. Review schedule and get our online polling up and going for participants	
2	10 min	**Breakout Session Recap and Discussion Themes** **Result:** Breakout meeting achievements, major themes from public and stakeholder engagement so far, and hazard risk assessment updates.	
3	20 min	**Refine Hazard Profiles** **Result:** Collaborative review and refinement of priority hazards for profiling based on breakout session findings and new data. Focus on removing hazards of low concern and adding new hazards of higher concern.	Find consensus on medium to extreme county-wide priority hazards to profile.
4	20 mins	**Align and Refine Mitigation Strategy Development Intro:** **Results:** Explore mitigation strategy development fundamentals, mitigation alternatives, principles of mitigation action plan development, and shifting policies from the federal administration.	Review Mitigation Alternatives Handout apply concepts to existing mitigation strategies
5	5 min Stretch Break	**Stretch break to get them legs moving!!!**	
6	50 mins.	**Align and Refine Mitigation Strategies Exercise** **Result:** Prioritized and refined county-wide mitigation actions through an exercise using interactive polling to rank priorities and compare public perceptions and community feedback to identify gaps for improvement. Identified strategies for enhanced inter-agency coordination and resource sharing.	Find consensus on county-wide mitigation action priority areas and projects, and identify opportunities for collaboration.



PC 3 Attendance (1)



PC 3 Attendance (2)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

PUBLIC EDUCATION & AWARENESS (PE&A)

Public education and awareness activities are used to **communicate risk and mitigation options** to residents, elected officials, business owners, potential property buyers, and visitors about hazardous areas, such as mitigation techniques they can use to protect themselves and their personal property.

EXAMPLES

- Community and neighborhood outreach
- Speaker series / demonstration events
- Hazard mapping
- Real estate disclosures
- Materials library
- School children educational programs
- Hazard expositions

NATURAL RESOURCE PROTECTION (NRP)

Natural resource protection activities reduce the impact of natural hazards by **preserving or restoring natural areas and their protective functions**. Such areas include floodplains, wetlands, steep slopes, and sand dunes. Parks, recreation, or conservation agencies and organizations often implement these protective measures.

EXAMPLES

- Floodplain protection
- Watershed management
- Vegetation management (e.g., fire resistant landscaping, fuel breaks, etc.)
- Erosion and sediment control
- Wetland and habitat preservation and restoration

EMERGENCY SERVICES (ES)

Although not typically considered a "mitigation" technique, emergency service measures do help minimize the impacts of a hazard event on people and property. These are actions taken to **support and improve emergency response** prior to, during, or after a hazard event.

EXAMPLES

- Warning systems
- Evacuation planning and improvement projects
- Sandbag staging for flood protection
- Installing temporary shutters on buildings for wind protection
- Damage assessment planning and management

STRUCTURAL PROJECTS (SP)

Structural mitigation projects are intended to lessen the impacts of a natural disaster event by **modifying the hazard's natural progression through construction**. They are usually designed by engineers and managed or maintained by facilities, operational, or public works staff.

EXAMPLES

- Stormwater diversions / detention / retention infrastructure
- Utility or road hardening
- Seismic retrofits
- Enhanced public infrastructure design standards

PC 3 Mitigation Alternatives Handout (1)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Mitigation Alternatives

County-Wide Planning Team Meeting #3

In an effort to **narrow mitigation alternatives** for inclusion in the Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP), we will use FEMA's six broad categories of mitigation alternatives to guide the development of the mitigation strategy. Each FEMA category is shown below and subsequently described in more detail. Please review each of the category descriptions and bulleted examples provided.

For more information and ideas about mitigation strategies and alternatives to consider, see FEMA's Mitigation Action Portfolio[1] and Mitigation Ideas[2].

FEMA MITIGATION ALTERNATIVES

PRV	PPRO	PE&A	NRP	ES	SP
Prevention	Property Protection	Public Education & Awareness	Natural Resource Protection	Emergency Services	Structural Projects

PREVENTION (PRV)

Preventative activities are intended **to keep hazard problems from getting worse** and are typically administered through government programs or regulatory actions that influence the way land is developed and buildings are constructed. They are particularly effective in **reducing a community's future vulnerability**, especially in areas where development has not occurred or capital improvements have not been substantial.

EXAMPLES
- Planning and zoning ordinances
- Building codes
- Open space preservation
- Floodplain regulations
- Stormwater management regulations
- Drainage system maintenance
- Capital improvements programming
- Riverine / fault zone setbacks

PROPERTY PROTECTION (PPRO)

Property protection measures involve the **modification of existing buildings and structures** to help them better withstand the forces of a hazard or to remove the structures from hazardous locations.

EXAMPLES
- Building elevation
- Critical facilities protection
- Retrofitting (e.g., wind proofing, flood proofing, seismic design techniques, etc.)
- Safe rooms, shutters, shatter-resistant glass
- Insurance

[1] https://www.fema.gov/sites/default/files/2020-08/fema_mitigation-action-portfolio-support-document_08-01-2020_0.pdf
[2] https://www.fema.gov/sites/default/files/2020-06/fema-mitigation-ideas_02-13-2013.pdf

PC 3 Mitigation Alternatives Handout (2)

PC 4 Mitigation Activity

PC 4 Photo 1

CITIES
STATION ASSIGNMENTS
Extreme Temperatures, & Drought) – Clare
Hazards & Severe Weather Hazards) – Ethan
ake & Slope Failure Hazards) – Chris
lure and Flood) - Raini
WATSONVILLE
FIRE

PC 4 Photo 2

PC 4 Photo 3

PC 4 Photo 4

PC 4 Photo 5



PC 4 Presentation

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING DETAILS & AGENDA

Hazard Mitigation Planning Team (HMPT) Meeting #4

Date: Monday, August 4, 2025
Time: 2:00 - 4:30 P.M.
Location: In-Person at Santa Cruz County Emergency Operations Center (5200 Soquel Ave, Santa Cruz)

Facilitator: Santa Cruz County Office of Response, Recovery & Resilience (OR3) / Dynamic Planning + Science (DP+S)

Meeting Purpose

The fourth county-wide Planning Team meeting for the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) focuses on refining the mitigation strategy and advancing regional collaboration to ensure its success. This session builds upon the foundational work of prior large group and breakout meetings to align jurisdiction-specific and inter-jurisdictional mitigation efforts within a scalable framework, and to ensure consistency with FEMA requirements.

At the end of the meeting participants will:

- **Understand Multi-Jurisdictional Capabilities** in implementing the county-wide mitigation strategy to support regional collaboration through review of local capabilities across planning, technical, fiscal, and outreach domains to highlight both shared strengths and unique resources.
- **Coordinate Mitigation Action Development** for inter-agency collaboration to successfully address widespread hazard problems through review of draft actions that are both scalable across jurisdictions and tailored to local needs, aligned with SMARTIE criteria to ensure effectiveness, equity, and strategic use of resources.
- **Have Consensus on a County-Wide Mitigation Strategy** that resource-effectively addresses cross-cutting problems in alignment with multi-jurisdictional capabilities via enhanced inter-agency collaboration.

This read-ahead packet for Meeting #4 will facilitate a structured review of local capabilities to support an integrated assessment. It will also support engagement among participants in the evaluation and development of a coordinated, county-wide mitigation strategy using a facilitated exercise, ensuring alignment with local needs, community priorities, and inter-jurisdictional capabilities.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #4

County Emergency Operations Center, 5200 Soquel Ave

August 4, 2025, 2-4:30pm

Name	Agency	Email	Phone
Cameron McDonald	RCD SCC	cmcdonald@rcdsantacruz.org	(253) 225-4653
Chloe W.	Capitola	cwoodman@ci.capitola.ca.us	
DAVID SANFORD	COUNTY	agc0020@agdept.com	831-763-4080

PC 4 Sign Ins (1)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #4

County Emergency Operations Center, 5200 Soquel Ave

August 4, 2025, 2-4:30pm

Name	Agency	Email	Phone
Leslie Rios	City of Watsonville	Leslie.rios@watsonville.gov	768-3172
Toto Vu-duc	City of Watsonville	Toto.vuduc@watsonville.gov	768-3187
Holland Maclaurin	Port District	hmaclaurin@santacruzharbor.org	831-713-8608
LAURA WHALEY	SCPL	WHALEYL@SANTACRUZPL.ORG	831-427-7760
Sierra Ryan	County		
JED WILSON	CALFIRE/CO FIRE	jed.wilson@fire.ca.gov	831.254.1700
SAM FILSON	CALFIRE/CO FIRE	SAM.FILSON@FIRE.CA.GOV	831.278 1754
Angie Guys	RCD	aguys@rcdsantacruz.org	
Mary Martin	PV Water	Mmartin@pvwater.org	
Peyton Higgs	County	Phiggs@csumb.edu	619-980-6081
Luis Toledo	Cabrillo College	ltoledo@Cabrillo.edu	831-212-8434
Skyler Murphy	Soquel Creek Water	Skylerm@Soquelcreekwater.org	831 475-8501
RICH CASALE	USDA-NRCS	richard.casale@usda.gov	831-359.1297
Carolyn Burke	County CDI	carolyn.burke@santacruzcountyca.gov	

PC 4 Sign Ins (2)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2025 SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN

Planning Committee Meeting #4

County Emergency Operations Center, 5200 Soquel Ave

August 4, 2025, 2-4:30pm

Name	Agency	Email	Phone
TOM AVILA	WTS FIRE	tom.avila@watsonville.gov	
Lisa Lurie	RCD	llurie@rcdsantacruz.org	
Leah MacCarter	CDI	leah.maccarter@santacruzcounty.ca.gov	

PC 4 Sign Ins (3)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Cabrillo College Breakout Meeting #1

Date: Tuesday, May 13, 2025
Time: 9:00 – 11:00 A.M.
Location: Zoom
Meeting ID: 889 3398 8451

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to Cabrillo College, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	No decision or support requested
2	20 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

Cabrillo College BO 1 Agenda 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	**20 min**	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	**5 min**	**Next Steps and Closeout** a) Upcoming events, HMPT Meeting #3, and Cabrillo College Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.



Cabrillo College BO 1 Photo

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan

Cabrillo College Breakout Meeting #1 | MEETING NOTES

Date: Tuesday, May 13, 2025
Time: 9:00 A.M. – 11:00 A.M.
Location: Zoom

Quick recap

The Dynamic Planning + Science (DPS) and Cabrillo College teams discussed campus emergency response capabilities, hazard risks, and mitigation planning. Topics included wildfire, flooding, earthquake vulnerabilities, hazard prioritization, defensible space, and critical infrastructure resilience. The session also previewed upcoming steps in the hazard mitigation planning process, including virtual meetings, breakout sessions, and document development.

Summary

The meeting began with introductions from the DPS and Cabrillo College teams. Ethan Mobley of DPS then provided a brief overview of the planning process conducted so far and the purpose and goals of the breakout meeting, which includes reviewing historical hazards, current risks, and conducting an interactive risk matrix exercise. Julie, the Director of Federal and State Emergency Grants, and Luis, the Assistant Director of Facilities and Maintenance, shared their roles and expressed interest in identifying gaps and areas of weakness in their emergency response plans. The meeting aimed to discuss the college's facilities, expansion plans, and emergency response strategies.

Interactive Risk Matrix and Hazard Mitigation Plan

The group then participated in an interactive risk matrix exercise, led by Ethan, to identify and prioritize hazards based on local conditions. Ethan reviewed the timeline for plan development, including a full stakeholder meeting scheduled for June 2, refinement of mitigation actions in June and July, and the public release of the draft plan in October. He explained that with a FEMA-approved plan, the college would be eligible to apply directly to Cal OES for funding.

Cabrillo College Student Distribution and Resilience

Luis shared student distribution data using a graduation dashboard, which showed a strong presence in Santa Cruz and Watsonville, along with out-of-region students from places like San Jose, Texas, and Mexico. Julie added that around 40% of courses are delivered online,

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

using synchronous, asynchronous, and hybrid models. The group discussed how these dynamics affect hazard exposure and operational continuity. Luis thought that AT&T provides internet service at both campuses, and Ethan noted the importance of connectivity in ensuring resilience. Ethan emphasizes the importance of understanding the college's unique footprint and vulnerabilities to hazards like flooding and wildfire, particularly for the Aptos campus.

Flood Risk and Infrastructure Discussion

The team discussed flood risks at the Watsonville campus, particularly the vulnerability of backup generators, parking areas, and buildings located within the 100-year floodplain. Julie recalled that the 2023 storms caused significant flooding and damage to a storage warehouse. Luis raised concerns about sewer laterals being affected by leaning trees and wind events, with the group concluding that both flood and wind damage represent major infrastructure risks.

Earthquake Risks and Mitigation Strategies

In terms of earthquake preparedness, Luis shared that the maintenance team has braced furniture and shelving to reduce risk. However, no comprehensive structural assessment has been performed. Ethan recommended hiring a seismic engineer to evaluate older buildings and described how building codes have evolved through benchmark years following major quakes. Julie noted that the previous hazard mitigation plan contained a per-building hazard ranking that could be updated for the current plan. Ethan explains the concept of benchmark years in building codes, which are updated after major earthquakes to improve seismic safety standards.

Cabrillo College Wildfire and Water Management

The conversation shifted to wildfire and drought. Ethan emphasized the need for defensible space, particularly in areas near Porter Creek and the wildland interface. Luis described ongoing work with Cal Fire to clear vegetation around the gulch and the Porter Creek area at the intersection with Perimeter Road. and mentioned water sourcing for the campus, including wells in Porter Gulch and backup supply from Soquel Creek Irrigation District. The team explored the idea of enhancing energy reliability at critical facilities, such as the wells, through mobile generators or a microgrid. The presence of three separate power meters on campus could help facilitate such a project.

Cabrillo College BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Cabrillo College Risk Assessment Prioritization

The group also discussed how to prioritize hazards for the final risk assessment. Ethan guided the team through evaluating each hazard's probability and potential impact, focusing on flooding, wildfire, extreme weather, drought, slope failure, and earthquakes. The team agreed that flooding, wildfire, and extreme weather are the most immediate concerns. The conversation also addressed the college's role as a shelter facility and how regional hazards might affect students, particularly those commuting from areas throughout Santa Cruz County.

Cabrillo College Hazard Mitigation Planning

The team discusses the prioritization of hazards for Cabrillo College, with wildfire, flooding, and extreme weather identified as the main focus areas. They review enrollment data to understand the geographic distribution of students and staff. Ethan outlines the upcoming steps in the planning process, including virtual meetings, breakout sessions on mitigation, and document production. The team is reminded to continue promoting the public survey and to keep their board of trustees informed about the hazard mitigation planning efforts.

Next steps

DPS Team Action Items

- Update hazard rankings and prioritization based on new risk assessment discussion
- Evaluate potential microgrid implementation at the three power demarcation points on campus
- Evaluate defensible space improvements around campus wellheads to reduce wildfire risk

SCC Team Action Items

- Luis: Send DPS team the detailed building construction data including year built, construction materials, and roofing types for all campus buildings
- Luis: Obtain flood insurance information from the Insurance Director for Cabrillo College buildings
- Luis: Investigate if AT&T is the sole internet provider for both Aptos and Watsonville campuses
- Luis: Send GIS data/mapping of campus buildings to Brian

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Luis/Brian: Document any earthquake mitigation measures taken since the 2020 Dewberry hazard assessment and provide DPS with information
- Julie: Provide accurate student enrollment data and trends, including geographic distribution of students
- Julie: Get records from marketing team about the hazard mitigation plan public survey distribution to students/campus
- Luis/Julie: Keep the college President informed about the hazard mitigation planning efforts
- Facilities Team: Assess the undersized French drain between Trafton and Union Street for potential upgrade project
- Facilities Team: Document current wildfire mitigation practices and defensible space maintenance procedures and provide DPS with information

Cabrillo College BO 1 Summary 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

City of Capitola Breakout Meeting #1

Date: Monday, May 12, 2025
Time: 3:00 – 5:00 P.M.
Location: Zoom
Meeting ID: 885 1437 1550

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Raini Ott

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to the City of Capitola, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the MJHMP update.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	
2	15 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.
4	30 min	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.

Capitola BO 1 Agenda 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

5	**5 min**	**Next Steps and Closeout** a) Upcoming events, HMPT Meeting #3, and Capitola Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.



Capitola BO 1 Risk Matrix Screenshot

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Summary for City of Capitola Breakout Meeting #1

Monday, May 12, 2025, 3:00-5:00 PM

City of Capitola Breakout Meeting #1 focused on hazard mitigation planning with discussions on various natural disasters that have occurred or could occur and their potential impacts on critical infrastructure and the community. Santa Cruz County (SCC) staff and the consultant team from Dynamic Planning + Science (DPS) introduced their roles and tools, guiding the Capitola team through the planning process and demonstrating how to use the Risk Assessment Mapping Platform (RAMP) for operational planning and response. Through an interactive exercise, the group identified priority hazards for the city, including high wind, winter storm, coastal erosion, flood, and earthquake hazards, and discussed potential mitigation actions and funding opportunities for future disaster prevention and recovery efforts. The importance of community outreach and engagement as part of the planning process was also emphasized.

Next Steps

Capitola Team Action Items

- Email any additional data to DPS
- Jessica: Provide details on unpaid claims from 2023 and 2024 storms. Follow up on FHWA funding status for infrastructure projects
- Jamie: Share population projections from separate project.
- Chloe and Nikki: Coordinate with DPS team to integrate hazard mitigation outreach with the city table at Twilight Concert Series (or Makers Market?)

SCC Team Action Items

- Support additional outreach events at Capitola concerts with evacuation planning and emergency preparedness materials

DPS Team Action Items

- Update mitigation plan to mostly focus on high wind, winter storm, coastal erosion, flood, and earthquake hazards
- Review and refine Capitola's mitigation actions, focusing on such issues as Stockton Bridge, City Hall, and Cliff Drive vulnerabilities; coastal erosion concerns for the western bluff area at city limits; analyzing drainage and coastal flooding in the village; and studying Noble Gulch drainage
- Update hazard analysis to include combined impacts of multiple hazards on the same facilities
- Add missing critical infrastructure to GIS mapping, where appropriate, including pump stations, Brisbane Peary Bridge, Stockton Bridge, other bridge infrastructure, and city corporation yard

Capitola BO 1 Summary1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Include Capitola Wharf Resiliency Project and Stockton Avenue Bridge Replacement Project in mitigation planning
- Coordinate with Capitola staff for public outreach events during the first week of August and prepare engagement materials

Meeting Summary

To start the meeting, the team from DPS introduced themselves and discussed their roles in the planning process. They also discussed the importance of the breakout meeting for the Capitola team to get detailed information and ensure their jurisdictional annex is well-planned. The group discussed the need for collaboration and challenges of the current funding environment, and reviewed local hazards and conditions through interactive discussions.

General Hazard Concerns and Mitigation Planning

In the meeting, the group discussed the hazards and risks associated with natural disasters affecting the City of Capitola, including high wind, winter storm, coastal erosion, flood, earthquake, and tsunami hazards. They also discussed the importance of understanding the demographics and vulnerabilities of the affected areas, the need for a shared understanding of the hazards and risks that takes public perception into account, and the importance of evaluating the capabilities and resources of the community in developing an actionable mitigation plan.

The discussion covered the increasing frequency and duration of certain hazard events, including drought, its impacts on water supply, and saltwater intrusion. The city's water supplies were highlighted, and an update was provided on the Soquel Pure Water project, which is nearing completion. The discussion touched on the city's exposure to strong to severe shaking, with a particular focus on liquefaction and its impact on critical infrastructure and facilities. Landslide risk was also a focus, noting that many of the city's critical facilities are located in areas with 30% or greater slopes. The group covered flood and coastal hazards, including the city's high exposure to tsunami, with a particular emphasis on coastal erosion and cliff failure issues.

Risk Assessment Discussion with RAMP Tool

The DPS team demonstrated how to use the RAMP tool for mitigation and operational planning, guiding the group through the tool's features, including the ability to filter by area, hazard, population, and critical facility type.

Using RAMP, the group focused in on areas of concern, particularly flooding around the police station, fire station, and City Hall. The group expressed concerns about the risk of flooding and the ability to react in emergencies. A potential mitigation strategy was suggested to further study flood risks that are not currently captured by FEMA flood insurance maps, including identifying critical facilities that may not be represented.

Capitola BO 1 Summary2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Updating GIS Data for Critical Facilities

GIS and other data gaps were identified and the group agreed to follow up to ensure all appropriate critical facilities, such as the pump station and the Brisbane Peary Bridge, are included in the vulnerability assessment. They also discussed the importance of identifying combined hazards across the community. With flooding and sea level rise hazards being most evident, the group determined that the risks associated with wildfire and geologic hazards could be better spelled out. The group examined the new responsibility areas mapping for wildfire hazard zones in and around the city and the potential for increased compliance requirements in the future.

City Infrastructure and Funding

The city's previous hazard mitigation plan identified the big risks well, but there is more work to do in strategic mitigation planning and the group discussed how to identify where resources should be concentrated for risk reduction in the current funding environment. The group identified Stockton Bridge, City Hall, the police station Cliff Drive, and the Noble Gulch pipe complex as high-risk areas that need more attention in mitigation planning and emergency response funding. The DPS team explained the process of allocating funds for risk mitigation and the importance of identifying who owns the infrastructure.

Priority Hazards

The group discussed the changing nature of hazards and their impacts on the community, highlighting various hazards such as coastal erosion, sea level rise, tsunami, slope failure, high wind events, earthquakes, wildfires, and floods. It was agreed that coastal erosion and sea level rise are highly likely to occur, while tsunamis and wildfires are less likely. They also discussed the potential impact of these hazards on critical infrastructure and the community, the need for a more detailed risk assessment, and the importance of focusing on the most likely and impactful hazards. By the end of the discussion, the group agreed to focus on specific hazards of greatest concern, prioritizing coastal storms, high wind, coastal erosion, flood, and earthquake in the mitigation strategy.

Public Outreach

The group ended the meeting with discussion of public outreach efforts to gather the community's perceptions on these issues and planned to work together to engage people at community events and gatherings in August.

Capitola BO 1 Summary3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Pajaro Valley Water Management Agency (PVWMA) Breakout Meeting #1

Date: Friday, April 25, 2025
Time: 09:00 A.M. – 11:00 A.M.
Location: Zoom
Meeting ID: 897 9584 1972
Passcode: 227158

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Christopher Velasco

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to PVWMA, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	No decision or support requested
2	20 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

PVWMA BO 1 Agenda 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	**20 min**	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	**5 min**	**Next Steps and Closeout** a) Upcoming events and PVWMA Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.

SANTA CRUZ COUNTY | HAZARD MITIGATION PLAN

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Meeting Summary for PV Water Breakout Session #1
Friday, April 25, 2025, 9am-11am

The team from Dynamic Planning + Science, Pajaro Valley Water Management Agency (PV Water) and other organizations discussed the mitigation planning process for the Santa Cruz County MJHMP, focusing on historical hazards, risk assessments, and potential impacts on their water system and infrastructure. They also discussed the challenges of maintaining the agricultural economy, the impact of population growth on water demand, and the importance of considering the demographics of their service area in grant writing processes. The team also discussed the need for more detailed information about their infrastructure, the challenges of power outages, and the potential effects of various hazards on their operations.

Next steps

- Casey:
  - Review and send comprehensive GIS data of PV Water's infrastructure points including wells, Harkin Slough location, pump stations, and other critical facilities to the DP+S team
  - Send shapefile of all water line turnouts to the DP+S team
  - Provide point locations for the new College Lake infrastructure project to the DP+S team
  - Send coordinates for the future Watsonville Slough project location to the DP+S team

- PV Water Team:
  - Provide data points for specific infrastructure footprint areas, including center points of critical locations
  - Send updated infrastructure asset list for facilities in Monterey County, including the 23 miles of pipeline (for RAMP).
  - Review and provide input on draft mitigation plan expected in late summer.
  - Review and provide input on draft mitigation actions during June-July meetings

- DP+S Team:
  - Focus the PV Water Annex on infrastructure west of Highway 1 and critical facilities in flood-prone areas.

PVWMA BO 1 Summary_Part1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

  - Include discussion of levee certification and needs around the water recycling facility in the mitigation plan as it is not covered under the US ACOE project (Possible Problem Statement).
  - Coordinate with PV Water and Watsonville for joint outreach efforts at the Strawberry Festival
  - Keep the public survey open until August for continued community input
  - Prepare draft mitigation plan for review by August
  - Submit final plan to Cal OES by end of October
  - Review and verify infrastructure points within landslide hazard zones, particularly around Harkin Slough Pump station (add to RAMP).

- Shinehah/Operations Team:
  - Define what electrical upgrades would need to take place in order to enable generator connections at the recycled water facility (Possible Mitigation Action)

- Marcus:
  - Share findings from the Water Resilience Planning workshops with the hazard mitigation planning team
  - Send RAMP tool link and password to the Water Resilience Planning team
  - Provide outreach materials for the Strawberry Festival on August 30th

- Brian Lockwood:
  - Attend the large group meeting on June 2nd to report on Watsonville and PV Water related issues
  - Have Rincon review shared hazard mitigation planning materials and contact Ethan's team with any questions

Summary

In the meeting, Ethan, the owner of Dynamic Planning + Science, introduced the team and discussed their role in creating a mitigation plan for Santa Cruz County. Clare, with OR3, expressed her interest in supporting the watershed resilience effort. Brian Lockwood, the General Manager of Pajaro Valley Water Management Agency, shared his excitement about the project. Casey Musil, the Associate Hydrologist, and Marcus Mendiola, the Water Conservation and Outreach Specialist, introduced themselves and their roles in the agency. Chris, a Senior Planner, shared his research on the agency's efforts to mitigate seawater intrusion. Brian Greer, the co-owner and GIS lead, offered his assistance with

PVWMA BO 1 Summary_Part2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

data feedback. The team discussed their roles and expressed their enthusiasm for the project.

Santa Cruz Mitigation Planning Process

Ethan led a meeting discussing the mitigation planning process for the Santa Cruz project. The team reviewed historical hazards in the area and current risk assessments. They also planned to conduct an interactive risk matrix exercise and discuss next steps, upcoming public outreach events, and data needs. The team emphasized the importance of understanding the mitigation process, the planning documents, and how to access funding. They also discussed the need to avoid and reduce the potential for loss of life and injury from natural hazards. The team also discussed the importance of understanding each hazard, including vulnerable populations, and how it relates to the agency's growth and expansion.

Agricultural Economy and Water Challenges

In the meeting, Brian Lockwood discussed the agricultural economy and the challenges of maintaining it while stopping seawater intrusion and reducing groundwater overdraft. He also mentioned the sustainability indicators defined by the Department of Water Resources. Ethan asked about the impact of population growth on the reclaimed water supply and the agricultural community. Brian explained that they treat wastewater to tertiary standards and sell it to growers, reducing their need for groundwater pumping. Marcus added that the value of crops has increased despite a slight decline in irrigated acreage. Clare asked about the water demands of specialty crops, and Brian explained that they have higher water demands than apples. The team also discussed the impact of city expansion on water demand and the importance of considering the demographics of their service area in grant writing processes. Chris asked about maps of protected farmlands, and Brian confirmed that they analyze this on a case-by-case basis. The conversation ended with a discussion of declared disasters in Santa Cruz County since 1953, including earthquakes and Covid.

Flood Hazards and Infrastructure Mapping Discussion

In the meeting, Chris discussed the flood hazards in the service area, noting that their data doesn't extend into Monterey County. Clare raised a question about how water districts extend beyond county boundaries and how flood impacts are captured in the plan. Ethan explained that they've done one-off mapping for areas without available data and are willing to augment with additional mapping. Marcus expressed concern about the accuracy of FEMA's 100-year and 500-year floodplains, noting that recent flood events have not been quantified as 100-year events. Clare suggested that updating hydrologic mapping could be

PVWMA BO 1 Summary_Part3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

a *Mitigation Action*. The team discussed the need for more detailed information about PV Water's infrastructure, including pipelines, treatment plants, and wells, to better understand their flood risk.

Power Outages in Flood Mitigation

The team discussed the challenges of power outages in their area, particularly in the west of Highway 1. They noted that power outages were frequent and often caused by accidents or storms. The team also discussed the need for backup power at their pump stations and the potential for microgrids to provide independent power. The most critical facility is thioer water recycling plant that is subject to frequent shutoffs. They also discussed the importance of considering power outages in their flood mitigation plans.

Water Treatment Plant Infrastructure Risks

The team discussed the critical sites and infrastructure of their water treatment plant. They identified the most prone areas to outages and discussed the potential impacts of sea level rise and landslides. The team also discussed the challenges of managing water during droughts and the effects of increased agricultural groundwater usage. They acknowledged the interconnectedness of their operations with the city of Watsonville and the importance of resilience in their systems. The team also discussed the potential risks of earthquakes and the need for infrastructure resilience.

Risk Assessment and Hazard Prioritization

Ethan led a discussion on risk assessment and hazard prioritization for PV Water. The team focused on the probability and impact of various hazards, such as flooding, sea level rise, wildfires, and earthquakes. They agreed to concentrate on hazards with high likelihood and critical impact, such as sea level rise and drought. The team also discussed the potential effects of these hazards on their water system and infrastructure. The conversation ended with a plan to profile these hazards and provide related mitigation actions in their annex. The team also stressed the symbiotic relationship between PV Water and Watsonville, specifically if the City's wastewater stops flowing due to a natural disaster it would negatively effect their ability to deliver recycled water to farmers who would then pull more groundwater leading to greater seawater intrusion into the aquifer and increased soil salinity – putting the highly valued local Ag industry at risk.

Hazard Mitigation Plan Coordination Meeting

Ethan discussed the upcoming meetings and survey for the hazard mitigation plan. He emphasized the need for public outreach and suggested coordinating with Watsonville and TV Water for the Strawberry Festival. Clare suggested sharing findings from the watershed

PVWMA BO 1 Summary_Part4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

scale resilience planning effort to inform the hazard mitigation plan. Marcus agreed to provide collateral for the festival and suggested coordinating with Ethan's team. The team also discussed the need for cross-coordination between the hazard mitigation plan and the watershed scale resilience planning effort.

PVWMA BO 1 Summary_Part5

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Resource Conservation District of Santa Cruz County (RCD) Breakout Meeting #1

Date: Thursday, May 1, 2025
Time: 09:00 A.M. – 11:00 A.M.
Location: Zoom
Meeting ID: 847 0172 7912
Passcode: 666237

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Christopher Velasco

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to RCD, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	No decision or support requested
2	20 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

RCD BO 1 Agenda 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	**20 min**	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	**5 min**	**Next Steps and Closeout** a) Upcoming events and RCD Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.



RCD BO 1 Screenshot

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Resource Conservation District of Santa Cruz County Breakout Session #1
May 1st, 2025, 9a-11a

Meeting Recap

The meeting brought together the Dynamic Planning +Science (DPS) team and the Resource Conservation District (RCD) team to discuss hazard mitigation and resiliency planning for Santa Cruz County. They explored various hazards affecting the region, including wildfires, floods, droughts, and coastal erosion, and discussed strategies for risk assessment, mitigation, and community engagement. The team emphasized the importance of collaboration between jurisdictions, understanding unique local characteristics, and integrating natural resource management into disaster preparedness efforts.

Next Steps

Lisa:

- Send the Healthy Land, Healthy Economies report and Regional Conservation Investment Strategy data to the DP+S team for incorporation into the hazard mitigation plan
- Share the countywide stormwater assessment data conducted with Dr. Andy Fisher regarding stormwater collection and infiltration potential
- Put together internal discussion about different mapping perspectives and data needs for hazard visualization in collaboration with the DPS team.
- Put together internal discussion about different mapping perspectives and data needs for hazard visualization
- : Share annual reports, strategic plan, and LAFCO 5-year service review documents with the planning team
- Follow up with fire chiefs to collect their priority projects for the regional priority plan and arrange subsequent vetting meetings

Clare:

- Follow up with CDI and roads crew regarding the culvert assessment dashboard data sharing and potential integration with RCD's needs
- Incorporate building age distribution data from census into the plan to show seismic safety requirements timeline

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Coordinate with RCD to organize a local breakout meeting focused on wildfire mitigation that includes Fire Safe Council and fire districts

RCD Team:

- Identify and provide key watershed areas where they are conducting floodplain restoration work to DP+S for mapping
- Share watershed planning data and floodplain restoration priority areas for Scott Creek, San Vicente Creek, and Waddell Creek areas
- Provide data on agricultural drought resilience work for inclusion in the hazard mitigation plan
- Check with Rich regarding historical earthquake response experience and potential residual impacts
- Review and provide input on hazard profiles focusing on flood, slope failure, wildfire, drought, and sea level rise
- Work with DPS team on RAMP system to include private road and bridge ownership information for CSA designation
- Review draft annex in September timeframe and provide feedback
- : Conduct second review of annex in October during public review period
- Add hazard mitigation plan survey link to RCD website and create social media posts to promote it
- Consider how to use Measure Q funds as potential local match for future hazard mitigation grant opportunities

DP+S Team:

- Create watershed-based maps for RCD's jurisdictional annex that integrate multiple hazards
- Review chat information for additional data provided during the meeting
- Draft the initial jurisdictional annex for RCD's review and feedback

Matt:

- Provide criteria used for evaluating individual forest health and wildfire resiliency projects to the planning team

Angie:

RCD BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Document San Lorenzo River watershed concentration of soil erosion issues for hazard analysis

Summary:

The meeting began with introductions from the DPS team and the RCD team. The DPS consists of Ethan Mobley, Chris Velasco, Brian, Cory, and Cameron, while the RCD team includes, Angie Gris, Matt Abernathy, and Lisa Lurie. Clare Peabody works for the County of Santa Cruz at OR3. The meeting aimed to discuss the plan for hazard mitigation and resiliency, with a focus on the RCD's unique perspective on the matter. The RCD team expressed their interest in disaster risk reduction and the intersection of farming with hazard protection. The DPS team shared their experience in emergency management and their interest in the RCD's work. The conversation ended with the DPS team preparing to present their plan.

Jurisdictional Collaboration and Risk Assessment

DP+S discussed the importance of the county's planning effort and the role of participating jurisdictions. They emphasized the need for each jurisdiction to function independently but collaborate when necessary. DP+S also highlighted the need for understanding the unique capabilities and focus areas of each jurisdiction. They mentioned the importance of public outreach and the need for a dynamic approach to grant writing. DP+S also discussed the risk assessment process, the importance of understanding each hazard, and the need for augmenting data with perceptions. They mentioned the need for a dialogue on how to describe the RCD in an anecdotal format versus a data format.

Organizational Growth and Community Needs

Lisa discussed the growth trajectory of the organization over the past 5 to 8 years, with a doubling of the budget and an increase in staffing. She highlighted the expansion of various program areas, including stewardship, agriculture, water conservation, watershed management, habitat restoration, and wildfire resilience. Angie and Cameron were invited to share their perspectives on changing demographics and needs in the community. Angie asked about the integration of water supply and drought into the program categories, and suggested considering

RCD BO 1 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

the impact of human activities like land use and land use change on community vulnerabilities.

Disasters and Affordable Housing

The team discussed the challenges of natural disasters, particularly in relation to droughts and erosion control systems. They also touched on the issue of affordable housing being built in flood-prone areas and the impact on lower-resourced farmers. The conversation then shifted to the importance of understanding growth trends in the Wui and how they interact with housing crises and risk pressures. The team also discussed the need to incorporate cost benefits of natural resources into FEMA's cost-benefit equation. They emphasized the importance of considering vulnerable populations in grant applications and the need to prioritize hazards such as fires, severe storms, and flooding. The team also discussed the need to integrate this plan into their current day practice and the importance of understanding the tools available to them.

Natural Disasters and Community Resilience

In the meeting, Clare and DP+S discussed the frequency of natural disasters and their impact on the community. They highlighted the recent atmospheric storms and the ongoing drought, emphasizing the need for resilience and mitigation strategies. Clare also mentioned the need to connect these disasters to stream health and water quality. DP+S shared his personal connection to the ocean and the impact of algae blooms on the local fishing industry. The team also discussed the importance of understanding the frequencies of occurrences in their region. Cameron expressed interest in the Risk Assessment Mapping Platform (RAMP) and its potential to identify key areas for focus. DP+S demonstrated the RAMP system, which shows the FEMA floodplain areas and lists storm runoff infrastructure damage and water contamination. The team discussed the need to separate out the ownership of roads in the RAMP system. Angie brought up the issue of private roads and their access to FEMA funds, suggesting the need for a County Service Agreement. The conversation ended with the team agreeing on the importance of understanding the institutional knowledge and the need for resilience and mitigation strategies.

RCD BO 1 Summary 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Culverts: Rebuilding After Disasters and Funding

The team discussed the challenges faced in rebuilding culverts after natural disasters. They noted that while there were studies identifying undersized culverts, the incentives were to rebuild them in kind rather than bigger. This led to issues with culverts being rebuilt at the same size, which then plugged. The team also discussed the difficulty of accessing federal funding for private landowners and the need for local funding sources. They also touched on the need for watershed planning and the importance of floodplain restoration for multi-benefits. The team agreed to focus on these areas in their future discussions.

Stormwater

The team discussed the importance of understanding the unique character and scenic beauty of Santa Cruz County, which attracts visitors. They also discussed the need for a countywide assessment to identify areas with high stormwater collection and infiltration potential for managed aquifer recharge projects. The team also discussed the ongoing culvert assessment and the potential for borrowing data from this assessment for their own internal use. They also discussed the need for a focus on the map, aligning with the RCD, and understanding how they ranked the culverts.

Hazard Resilience

The team discussed various hazards affecting Santa Cruz County, including landslides, earthquakes, and wildfires. They highlighted the importance of infrastructure resilience and the need for mitigation strategies. The team also discussed the potential impact of these hazards on critical infrastructure, such as water treatment facilities, pipelines, and communication systems. They emphasized the importance of preparedness and awareness, including earthquake kits and home improvements. The team also discussed the challenges of debris management post-fire and the potential risks to water quality. The conversation ended with a discussion on the need for a comprehensive plan to address these hazards and ensure the county's resilience.

RCD BO 1 Summary 5

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Wildfire Resilience and Defensible Space

The team discussed the importance of wildfire mitigation and defensible space in Santa Cruz County. They highlighted the need for a collaborative approach, involving the Fire Safe Council and the Regional Conservation District (RCD), to address the issue. The RCD is leading a regional priority plan focused on forest health and wildfire resiliency projects. They also discussed the need to educate the community on wildfire prevention and the importance of private landowners taking action. The team also touched on the issue of septic systems being vulnerable to wildfires and the need for landscape resiliency. They agreed to continue their partnership with the Fire Safe Council and to engage with fire districts in the planning process. The team also discussed the importance of addressing coastal erosion and drought hazards in the region.

Natural Hazards and Defensible Space

In the meeting, DP+S led a discussion on the probability and impact of various hazards, such as coastal storms, wildfires, and floods. The team decided to focus on the Big 3: wildfire, flooding, and drought. They also discussed the potential impacts of these hazards on critical infrastructure and the environment. The team agreed to revisit the categorization of these hazards in the future. Additionally, they discussed the potential impacts of sea level rise and soil hazards, and decided to keep them in the risk matrix. The team also discussed the potential impacts of dam failure and decided to keep it in the risk matrix.

Hazards and Mitigation Strategies Discussed

In the meeting, the team discussed the potential hazards and their impact on their area. They agreed to focus on flood, slope failure, wildfire, drought, and sea level rise, as these hazards have a higher frequency and occurrence. They also discussed the need for more risk information and anecdotal information for their annex. The team decided to meet again on June 2nd to discuss mitigation actions and strategies. They also discussed the importance of using their tool, the RAMP tool, for grant funding opportunities. The team also discussed the potential use of Measure Q funds as a local match for federal funding.

RCD BO 1 Summary 6

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Santa Cruz County Breakout Meeting #1

Date: Wednesday, May 7, 2025
Time: 9:00 – 11:00 A.M.
Location: Zoom
Meeting ID: 844 3845 1796

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Raini Ott

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to the County, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	No decision or support requested
2	20 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	**20 min**	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	**5 min**	**Next Steps and Closeout** a) Upcoming events, HMPT Meeting #3, and County Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.



SCC BO 1 Risk Matrix Screenshot

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Meeting Summary for Santa Cruz County Breakout Session #1

Wednesday, May 7, 2025, 9:00-11:00 AM

The Dynamic Planning + Science (DPS) team and Santa Cruz County (SCC) planning team met to discuss the ongoing hazard mitigation planning process, focusing on identifying priority hazards that the plan should address such as floods, wildfires, droughts, earthquakes, tsunamis, coastal storms, high winds, coastal erosion, landslides, expansive soils, dam and levee failures, and climate change. The discussion covered the probabilities and impacts of various hazards affecting the planning area and explored specific mitigation needs and potential strategies. The teams also discussed the progress and next steps of the project, including the upcoming meeting on June 2 and the importance of involving the public in their work.

Next Steps

DPS Team Action Items

- Obtain and integrate sanitary and stormwater systems GIS data (e.g., pump stations) into the mapping platform for risk assessment
- Work with Leah, Claire, and Dave offline on the repetitive loss analysis refinement
- For the June 2 large group meeting, present refined hazard prioritization matrix to larger group for consensus
- Map and assess critical water infrastructure in high fire risk areas, particularly for Graham Hill Treatment Plant and Loch Lomond Reservoir
- Differentiate between county-maintained roads and private roads in the hazard analysis data
- Integrate CZU post-wildfire debris flow hazard areas data into the risk assessment
- Connect with Chief Sampson regarding burn scar regrowth characteristics and associated wildfire risks
- Incorporate into the plan considerations for planning and mitigation activity partnerships with Firewise communities
- Incorporate into the plan enhanced coordination opportunities among large parcel owners for fire management
- Review and potentially remove expansive soils hazard profile based on assessment of past mitigation actions
- Add hazard profile for winter storms/high wind events
- Update coastal hazards definition to include coastal wave attack/coastal storm events

SCC Team Action Items

- Email any additional data to DPS
- Leah: Follow up with FEMA Region 9 to obtain and finalize repetitive loss information
- Dave Sanford: Provide 2023 flood agricultural loss data to DPS

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Carolyn Burke: Share spreadsheet containing flood control projects in Zone 7A area with DPS; connect Brian Creedy with Alex Krebs to provide sanitation and stormwater infrastructure data layers; share the draft master plan for Zone 5 which lists storm water infrastructure projects; look into County Service Areas data and provide a list if not available in GIS format
- Sierra Ryan: Send offline information about problematic streamwood areas and tree recruitment locations to the consulting team; provide mapped data of water systems and the parcels they serve
- Dave Carlson: Review and integrate transportation network vulnerability data from climate adaptation assessment into the landslide hazard analysis

Meeting Summary

The meeting began with introductions from the DPS and SCC teams, as well as from representatives of AT&T that attended. Ethan Mobley of DPS then provided a brief overview of the planning process conducted so far and the purpose and goals of the breakout meeting, which includes reviewing historical hazards, current risks, and conducting an interactive risk matrix exercise.

Santa Cruz County Hazard Mitigation Planning

In the meeting, the teams discussed the ongoing multi-jurisdictional hazard mitigation planning process for Santa Cruz County. They reviewed the nine-month project timeline and the importance of the breakout meetings to gather critical information. The teams also discussed the mitigation planning process, which involves assessing the impact of hazards, describing the problems, assessing existing resources, setting goals and objectives, and developing mitigation actions. They emphasized the need to increase awareness of the hazard mitigation plan and to encourage mitigation activities. The teams also discussed the role of the county's jurisdictional assessment team, which includes attending breakout meetings, educating themselves on mitigation, amplifying outreach efforts, and assisting in data collection. The plan to embed a repetitive loss analysis in the plan was communicated, and the importance of coordination with FEMA region 9 was noted.

Addressing County Hazards & Vulnerabilities

In the meeting, DPS discussed the importance of understanding and addressing various hazards in the county, including high winds, tsunamis, droughts, floods, coastal storms, wildfires, earthquakes, climate change, landslides, dam failures, expansive soils, and coastal erosion. They emphasized the need to understand the frequency and severity of these hazards, as well as the demographics and vulnerabilities of the affected populations and the county assets at risk. The team also discussed the importance of local perceptions and the need for a shared understanding of hazards. To guide the discussion, DPS used the Risk Assessment Mapping Platform (RAMP) to visualize these hazards. During the discussion, the need to address climate change and the importance of local knowledge in successful mitigation planning were

SCC BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

emphasized. The teams also highlighted the need for better communication and notification systems, particularly in the context of earthquakes and dam failures, however unlikely.

Flood Protection in South County

The teams discussed the need for better flood protection in the South County area, particularly in the Lakes region. They identified the Pajaro and Salsipuedes levee systems as a potential solution but noted that it may not protect all areas. The teams also discussed the need for more hydrological monitoring in the Lakes area to fully understand the flood dynamics. They mentioned the creation of the Pajaro Regional Flood Management Agency and the challenges of funding for flood management projects. There was additional discussion on the need for better evacuation planning and the importance of considering the impact of flooding on agricultural land. They agreed to gather more data on flood-prone areas and to work on a regional planning approach to deal with flooding in these areas.

Wildfire Risk & Mitigation Strategies

The teams discussed wildfire risk and mitigation strategies, focusing on areas with high population density and fire risk. They considered the impact of regrowth patterns in burn scars and the need for coordinated management of large parcels of land. The teams also discussed landslide risk, with a focus on post-wildfire debris flow and the need for better data on private water systems. They agreed to update the hazard mitigation plan to include new data and to differentiate between county-maintained roads and private roads.

Hazards & Impacts on Facilities

In the meeting, the teams discussed the probabilities and impacts of various hazards in the planning area. They focused on identifying priority hazards that the plan should address such as floods, wildfires, droughts, earthquakes, tsunamis, coastal storms, high winds, coastal erosion, landslides, dam and levee failures, and climate change. The team agreed that wildfire, flooding, and high wind events are highly likely to occur, while coastal erosion and sea level rise are also likely. They also discussed the potential impact of these hazards on critical facilities and infrastructure. The team decided to prioritize these hazards in their plan and adjust the plan accordingly. They also discussed the potential impact of drought and its relation to other hazards. The team agreed to revisit the issue of expansive soils after reviewing previous mitigation efforts and currently regulatory requirements.

Project Progress & Public Involvement

At the end of the meeting, the teams discussed the progress of the project, including the upcoming county-wide planning team meeting on June 2 and the need for refinements. They also discussed the importance of involving the public in hazard mitigation planning and implementation work and the need to make adjustments based on community feedback. Attendees were encouraged to share the online public survey. The teams also discussed data-sharing needs and issues to follow up with offline.

SCC BO 1 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

City of Scotts Valley Breakout Meeting #1

Date: Tuesday, May 27, 2025
Time: 9:00 – 11:00 A.M.
Location: Zoom
Meeting ID: 813 9533 3752

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Raini Ott

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to the City of Scotts Valley, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the MJHMP update.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	
2	15 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past plans c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.
4	30 min	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.

Scotts Valley BO 1 Agenda 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

5	**5 min**	**Next Steps and Closeout** a) Upcoming events, HMPT Meeting #3, and Scotts Valley Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Summary for City of Scotts Valley Breakout Meeting #1

Tuesday, May 27, 2025, 9:00-11:00 AM

City of Scotts Valley Breakout Meeting #1 focused on hazard mitigation planning with discussions covering various natural hazards, risk assessments, and potential mitigation strategies. Santa Cruz County (SCC) staff and the consultant team from Dynamic Planning + Science (DPS) introduced their roles and guided the Scotts Valley team through the planning process. Participants reviewed demographic data, survey results, and preliminary hazard assessments, using tools like the Risk Assessment Mapping Platform (RAMP) to analyze and prioritize risks. The group also addressed emergency access routes, infrastructure concerns, and upcoming tasks related to public outreach and coordination for the county-wide planning team. Through an interactive exercise, the group identified priority hazards for the city, including earthquake, wildfire, slope failure, and drought, with hazards such as high wind, flood, and high heat being identified as additional concerns.

Next Steps

Scotts Valley Team Action Items

- Carly to follow up with Brian regarding transportation assets and storm drain data for RAMP and to consider scheduling a brief city council update on the hazard mitigation planning process.
- All team members to continue promoting the online public survey through August.

SCC Team Action Items

- Support additional outreach events as needed

DPS Team Action Items

- Focus mitigation strategy primarily on earthquake, wildfire, slope failure, and drought hazards.
- Draft problem statements for the next breakout meeting.
- Coordinate with Scotts Valley team on public outreach events in early August, potentially including National Night Out.

Meeting Summary

The meeting served as an introduction to hazard mitigation planning and focusing on identifying the City of Scotts Valley's hazard risks and local priorities. The group discussed the importance of collaboration and data management, with DPS highlighting risk assessment tools and outstanding infrastructure data needs. The team reviewed demographic data, public survey results, and preliminary hazard assessments, with wildfire, high winds, and earthquakes emerging as top concerns. The group worked to identify potential projects based on priority

Scotts Valley BO 1 Summary 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

hazards which could be supported by inclusion in the mitigation plan. Participants were encouraged to share local knowledge and perspectives to refine the risk assessment and inform future mitigation strategies.

Scotts Valley Natural Hazards Assessment

The group discussed various natural hazards affecting Scotts Valley, including flood risks from Carbonera Creek and its tributaries, drought concerns, and wildfire threats. They noted that while water supply was not a top priority for local water districts, recycled water systems and wastewater treatment were important considerations for the city. The discussion highlighted the need to address older non-conforming development and improve evacuation routes, as well as the challenge of providing adequate water for new housing developments. The team also reviewed earthquake and landslide risks, particularly in areas with alluvial soils and steep slopes.

Risk Assessment Mapping Platform Review

The team discussed the Risk Assessment Mapping Platform (RAMP) and its functionality, with DPS providing instructions on how to access and navigate the tool. They explored various hazard layers, including earthquake, wildfire, and flood scenarios, and discussed the need to update infrastructure data, particularly for wastewater facilities and pump stations. SCC staff suggested using the tool for benefit-cost analyses of flood mitigation projects. The group agreed to focus on specific areas of concern and help identify missing infrastructure data, including the locations of several pump and lift stations.

Emergency Access and Evacuation

The group discussed potential emergency access routes and mitigation efforts for areas with limited egress, particularly in neighborhoods near Granite Creek and Ladado open space. They explored the possibility of using non-vehicular methods for emergency personnel access and identified areas with infiltration issues at the wastewater treatment plant. Additionally, they discussed erosion hotspots and slope stabilization projects, including one sponsored by USDA for a creek outside city limits. The importance of maintaining open corridors through Mount Herman and Granite Creek during evacuations was highlighted. The group reviewed key facilities including the Sky Park emergency staging area, community centers, and healthcare facilities, noting that during the CZU fire, 100,000 people had to evacuate through Mount Herman.

Private Property Restoration Challenges

The group discussed challenges with managing restoration projects on private property, particularly regarding funding, land ownership, and landowner resistance. It was explained that the city had to manage and fund two restoration projects on private property, with hopes for FEMA reimbursement. The group discussed the complexities of privately maintained roads and

Scotts Valley BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

the difficulties in providing assistance or managing large-scale projects in areas with fragmented ownership.

Priority Hazards

The group used a risk matrix to evaluate and prioritize hazards based on probability and impact. The group discussed several potential hazards, including wildfire, earthquake, slope failure, flood, high heat, high winds, and drought. They agreed that earthquake was the highest concern, noting it could have catastrophic impacts on the wastewater plant. High heat impacts were primarily a concern for vulnerable populations, but it was highlighted that local cooling centers like the senior center and library are available during events. The group also considered the impact of drought on water storage and recreational facilities. They concluded that drought was likely to occur and have a high impact, though the exact effects on water production and recreational areas were unclear. The team decided to prioritize earthquake, wildfire, slope failure, and drought in their mitigation strategy, as these were the most disruptive events.

Upcoming Meetings and Community Outreach

DPS discussed upcoming events and tasks related to the county-wide planning team meeting scheduled for June 2 followed by decision maker briefings. Raini also highlighted plans for public outreach events in early August, including a potential National Night Out event in the city, and encouraged the Scotts Valley team to suggest alternative or additional community events. The importance of coordinating these efforts and spreading the word about the online survey, which will run through August, was emphasized.

Scotts Valley BO 1 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Santa Cruz Port District Breakout Meeting #1

Date: Wednesday, April 9, 2025
Time: 10:00 A.M. – 12:00 P.M.
Location: Zoom

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to Santa Cruz Port District, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	
2	20 min	**Overview of Mitigation Planning Process** Result: Recap of progress thus Far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	20 min	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	5 min	**Next Steps and Closeout** a) Upcoming events and SCPD Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.



SCPD BO 1 Risk Matrix Screenshot

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Meeting summary for Santa Cruz County Multi-Jurisdiction Hazard Mitigation Plan Santa Cruz Port District Break Out Meeting #1 (04/09/2025)

Quick recap

The meeting focused on hazard mitigation planning for the Santa Cruz Port District, discussing various risks such as flooding, sea level rise, and earthquakes, as well as their potential impacts on the diverse harbor community. Participants prioritized natural hazards using a risk matrix and explored potential mitigation strategies, with flooding and coastal storms identified as the highest priority. The jurisdictional assessment team also addressed vulnerable populations, particularly liveaboard residents, and discussed plans for gathering public input on mitigation priorities through surveys and newsletters.

Summary

Updated Meeting Agenda and Attendees

In the meeting, DP+S discussed an updated agenda for a meeting, which was initially sent out with incorrect details. They confirmed that the correct agenda was sent out the previous day. The meeting then proceeded with the attendees, including Holland, Blake, and Carl, who were present. The meeting was recorded for internal purposes and to keep a record of the project's progress.

Port District Hazard Mitigation Planning

The meeting focuses on the hazard mitigation planning process for the port district. Dave expresses excitement about the port's participation and the potential for federal grant funding to mitigate hazards. DP+S explained that as part of a multi-jurisdictional plan, the port can now apply for grants independently. The meeting aims to document the port's specific risks and vulnerabilities, develop a shared understanding of local hazards, evaluate capabilities, and identify areas of concern and potential mitigation actions. DP+S

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

also highlights the importance of considering vulnerable populations like liveaboards in the planning process.

Santa Cruz Harbor User Demographics

The Santa Cruz harbor has a diverse mix of users, including recreational boaters, commercial fishermen, live-aboards, and educational programs. Holland explained that while the number of slips has remained constant, the harbor attracts a wide range of demographics. Blake added that the harbor serves everyone from wealthy boat owners to those nearly homeless, as well as youth programs and scientific researchers. The harbor recently completed an economic impact study, which will be presented in May to the District Board, though Holland notes it provides conservative numbers due to the timing of the study. Live-aboards make up about 8% of the harbor's occupants, with recreational boats forming the majority and the commercial fishing fleet having shrunk in recent years.

Flood Hazards and Sea Level Rise

The discussion focuses on flood hazards and sea level rise affecting the Santa Cruz Harbor. Blake and Holland describe recent experiences with flooding, including inundation of electrical transformers, flooding of buildings over water, and concerns about dock pilings being overtopped. They mention erosion issues and the destruction of docks from recent storm events. The group discusses potential mitigation measures like temporary sea walls, extending jetties, and strategies to soften wave currents inside the harbor. They also highlight the importance of addressing sedimentation and shoaling to maintain the harbor as a safe refuge. The conversation touched on seismic risks, particularly liquefaction, and the need to upgrade infrastructure. Holland mentions plans to replace and raise the aging West seawall to address sea level rise and flooding, though funding remains a challenge for the estimated $17-20 million project.

Drought's Economic Impact on Fisheries

Blake and Holland discussed the economic impact of drought on their fisheries, particularly the salmon fishing industry. Blake explained that droughts lead to diminished salmon reproduction, affecting their life cycle and resulting in closures. Holland added that the economic impact is significant, with annual income from salmon fishing being around $600,000.

Emergency Communications

The group also discussed the challenges of emergency communication during disasters, as they are not in charge of sending out alerts and are at the mercy of larger emergency

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

operations. They also touched on the issue of disaster fatigue and amnesia, where people forget about past disasters and become less concerned.

Prioritizing Natural Hazards at the Port

The group discusses and prioritizes natural hazards affecting the port using a risk matrix. They focus on six main hazards: sea level rise, tsunami, earthquake, drought, coastal erosion, and flooding/coastal storms. Flooding/coastal storms are identified as the highest priority, being highly likely and having a significant impact. The group notes that mitigation efforts for flooding and surge events would also help address tsunami and sea level rise risks. Earthquakes are considered likely with critical impact, while drought is deemed possible with minor effects. The exercise helps guide future mitigation efforts, with a focus on addressing multiple hazards through related infrastructure improvements.

Port's Vulnerable Populations and Mitigation Strategies

The group discusses the port's vulnerable populations, particularly focusing on liveaboard residents. Blake estimates that 55-60% of liveaboards are elderly, with about 20% of those having functional needs. Of the remaining population, around 40% may have mental health or substance abuse issues. Holland mentioned that the HMP survey will be distributed through social media and their spring newsletter. The team discusses upcoming meetings and action items, including sharing economic impact and seawall studies, and completing a capabilities assessment for the port district.

Next steps

Port Staff Action Items

- Send the seawall study with engineering results and associated costs
- Send economic impact study to DP+S
- Develop replacement Cost Data per linear foot of dock and piers. Provide slip count data and dock infrastructure values/estimates
- Distribute and promote the hazard mitigation survey through social media and spring newsletter.
- Compile and send list of shelf-ready projects in queue for disaster recovery / mitigation.
- Attend the RAMP tool training on the 18th

SCPD BO 1 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Port Staff Mitigation Think Ahead Items

- Consider implementing Venice-style temporary/semi-permanent sea walls for flood protection. Or other items discussed regarding wave run up.
- Consider strategies to protect vulnerable liveaboard populations during tsunami and storm surge events
- Consider seismic upgrades to address liquefaction risks to port infrastructure
- Continue monitoring and maintaining the compromised seawall in the Southwest Harbor area until replacement project can be implemented
- Consider shoaling and sedimentation concerns into as part of coastal storm hazard mitigation.
- Review and document infrastructure vulnerabilities, particularly focusing on electrical transformers, restroom facilities, and pilings
- Think about how we can improve the emergency communication system for harbor residents and boat owners during hazard events.
- Continue coordination with Brian Garcia to develop threshold criteria for surge events to implement mitigation measures for early warning communications.

DP+S Staff Action Items

- Holland & Cory: Work offline on the assessment of capabilities for special districts
- Create a one-off map showing dock infrastructure for hazard mitigation planning
- Follow up with Dave (OR3) regarding the peer data scope limitations

SCPD BO 1 Summary 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Soquel Creek Water District Breakout Meeting #1

Date: Thursday, April 10, 2025
Time: 9:00 A.M. – 11:00 A.M.
Location: Zoom

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Cory Schreiner

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to Soquel Creek Water District, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	
2	20 min	**Overview of Mitigation Planning Process** Result: Recap of progress thus Far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	20 min	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	5 min	**Next Steps and Closeout** a) Upcoming events and SqCWD Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.

SANTA CRUZ COUNTY | HAZARD MITIGATION PLAN



SCWD BO 1 Risk Matrix Screenshot

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan

Soquel Creek Water District Breakout Meeting #1 | MEETING NOTES

Date: Thursday, April 10, 2025
Time: 9:00 A.M. – 11:00 A.M.
Location: Zoom

Quick recap

The Soquel Creek Water District Breakout Meeting #1 focusing on reviewing and prioritizing risks to their infrastructure from various hazards including flooding, earthquakes, wildfires, and coastal erosion. The team discussed vulnerabilities in their water system, potential mitigation strategies, and the need for improved data and risk assessments. They ultimately prioritized wildfire and earthquake risks for high priority mitigation efforts, while also considering the impacts of drought, flooding, sea level rise, coastal erosion, and tsunami on their infrastructure and operations.

Summary

Updated Meeting Agenda and Attendees

During the meeting, the team discusses the Soquel Creek Water District's participation in a multi-jurisdictional hazard mitigation planning process. Ethan, the project manager, explains the purpose and benefits of the plan, including eligibility for FEMA funding. The meeting focuses on reviewing hazards affecting the district's infrastructure, prioritizing risks, and identifying potential mitigation actions. Ethan emphasizes the importance of the district's input in assessing vulnerabilities and reviewing draft documents later in the process.

Flood Damage to Soquel Creek

The team discusses recent flooding events and their impact on Soquel Creek Water District's infrastructure. Connor reports that the most significant damage occurred on North Main Street in Soquel, where flooding blocked a culvert and bridge structure. As the water overtopped and washed out the area, it took a main water line with it. This incident, which involved Bates Creek, made the front page of the LA Times. The discussion also touches on using GIS tools to analyze flood risk and exposure of critical infrastructure within the district's boundaries.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Infrastructure Vulnerabilities and Risk Assessment

The team discussed the vulnerabilities in their infrastructure, particularly in relation to flood hazards and land slope failures. They identified areas that were not adequately protected and discussed potential mitigation strategies. The team also discussed the need for a more detailed risk and resilience assessment, which would be updated annually. There was a discussion about the accuracy of their GIS data, with some discrepancies noted. The team agreed to work on improving the data and identifying specific problem areas for further analysis.

Flood Risks to Water Infrastructure

The team discusses flood risks to water infrastructure, focusing on production wells in floodplains and coastal areas. They identify a standby well with potential flood protection measures and discuss vulnerabilities where water lines intersect with county culverts. The team discussed the possibility to overlay county culvert assessment data with their infrastructure to prioritize mitigation projects. They also consider coastal flooding risks, including sea level rise and tsunami inundation, and discuss potential mitigation actions for protecting hydrants on beaches and addressing sand deposition issues affecting valve access. The planning team has been developing this risk assessment tool since 2016 and is working on a tight timeline to complete the hazard mitigation plan before October.

Infrastructure Hazards and Mitigation Projects

The team discussed various hazards affecting their infrastructure, including coastal bluff erosion, landslide risk, and earthquake hazards. They examined the risk of erosion and landslide in specific areas, such as Capitola and Soquel Creek. The team also discussed the potential impact of sea level rise on coastal areas. They identified areas of concern, such as water tanks that have not been retrofitted and are prone to sloughing after an earthquake. The team agreed to continue monitoring these areas and to focus on mitigation projects.

Pipeline Infrastructure and Liquefaction Concerns

Ethan and Taj discussed the infrastructure of their organization, focusing on the use of PVC and HDPE for their pipelines. They also discussed the potential for liquefaction in their lifelines, with a particular concern for a pump station in a high liquefaction zone. Nicholas added that they have interties with other organizations, including Santa Cruz and Central Water District, which could be beneficial in emergency situations. Clare suggested that they should consider scenario planning for catastrophic events, such as a major earthquake, to ensure resiliency in their infrastructure.

SCWD BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Wildfire Risk and Infrastructure Concerns

During the meeting, Ethan discussed the high wildfire risk areas and the concerns raised by the public after the Southern California events. He acknowledged that fire hydrants are meant for structure fires, not wildfires. Taj expressed concerns about the risk of wildfires in the Santa Cruz hills and the need for defensible space around water tanks and critical infrastructure. Nicholas mentioned a study on the Larkin Valley tank surrounded by eucalyptus trees and the potential for grant money to remove the eucalyptus. Taj suggested adding fire department connections at the tanks for easier access. Clare discussed the importance of data sharing between central fire and Soquel Creek. The team also discussed the Larkin Valley area and the need for awareness of critical infrastructure within high wildfire severity zones.

Risk Assessment and Hazard Prioritization

Ethan led a discussion on risk assessment and hazard prioritization for the district. He proposed using a simple risk matrix tool to guide the process, focusing on probability and impact. They focus on eight main hazards: wildfire, slope failure, sea level rise, tsunami, earthquake, drought, coastal erosion, and flooding/coastal storms. They agreed that all these hazards could have some impact on the district, either directly or indirectly. The team also discussed the district's groundwater supply and its plans for a recycled water facility.

Prioritizing Hazards in Water Infrastructure

The group discusses and prioritizes various hazards affecting their water infrastructure. They identify sea level rise, tsunami, coastal erosion, flooding, slope failure, earthquake, drought, and wildfire as potential risks. After evaluating the likelihood and impact of each hazard, they decide to focus their mitigation efforts primarily on wildfire and earthquakes, which they consider the most critical and likely to occur. Drought and flooding are given secondary priority, followed by sea level rise and coastal erosion. The group notes that their Pure Water Soquel Project has already helped mitigate some drought-related risks.

Planning Process and Production Discussion

Ethan and Skyler discussed the progress of their planning process and production, with a focus on surveying and social media promotion. They planned to continue their surveys and social media promotion, and to report out on commonalities and differences in their larger group setting. They also discussed the importance of mitigation strategies and the need for a static document. Ethan emphasized the usefulness of their online tools for other

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

grant purposes and promised to make the meeting materials and recordings available on their website. Skyler agreed to email Brian to flush out the data for wells and hydrants.

Next steps

SqCWD Staff Action Items

- Review and verify the accuracy of 45 production wells shown in the mapping system, particularly their status
- Send hydrant data to the project team for coastal hazard analysis
- Send list of vulnerable infrastructure locations to the project team
- Investigate the incorrect production well data point shown in Aptos Creek area
- Work with outreach team to document and provide details of how the hazard mitigation survey was distributed to the community
- Attend RAMP tool training on April 18th
- Attend June 2nd group meeting to discuss commonalities and differences in hazard mitigation approaches

SqCWD Staff Mitigation Think Ahead Items

- Complete seismic retrofit of remaining water tank next winter
- Revaluate tanks for sloshing susceptibility under new requirements
- Continue clearing defensible space around water infrastructure facilities
- Complete the study for potential eucalyptus removal around Larkin Valley tank

DP+S Staff Action Items

- Focus mitigation strategies primarily on wildfire and earthquake hazards, followed by drought/flood, and then sea level rise/coastal issues
- Create mitigation action plan for protecting hydrants on beaches from debris damage
- Incorporate county culvert assessment data into hazard analysis when available
- Brian to coordinate updating GIS data for active wells and hydrants in the RAMP tool

SCWD BO 1 Summary 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

Scotts Valley Water District Breakout Meeting #1

Date: Thursday, April 3, 2025
Time: 9:00 A.M. – 11:00 A.M.
Location: Zoom

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Cory Schreiner

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to Scotts Valley Water District, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	
2	20 min	**Overview of Mitigation Planning Process** Result: Recap of progress thus Far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	20 min	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	5 min	**Next Steps and Closeout** a) Upcoming events and SVWD Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.



SVWD BO 1 Risk Matrix Screenshot

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan

Scotts Valley Water District Breakout Meeting #1 | MEETING NOTES

Date: Thursday, April 3, 2025
Time: 9:00 A.M. – 11:00 A.M.
Location: Zoom

The meeting focused on potential risks and hazards affecting SVWD's water infrastructure, with particular attention to areas vulnerable to landslides, flooding, and wildfire. Discussions highlighted the need for further geotechnical assessments, infrastructure improvements, and consideration of underrepresented and vulnerable communities. The team also reviewed the current hazard risk assessment and explored the use of the new interactive mapping tool, RAMP. The session concluded with an overview of the planning roadmap and next steps in the mitigation process.

Meeting Summary of Topics

Introduction

The meeting opened with introductions and an overview of the meeting format, which was designed to gather input for the County's Hazard Mitigation Plan. The facilitation team introduced the consulting group and outlined the agenda, which included an overview of mitigation planning process, review of historical hazards and current risk, interactive risk matrix exercise, and RAMP demonstration. The importance of collaborative input was emphasized, and attendees were informed that all materials presented are available on the project website.

Company Operations and Resource Discussion

The meeting featured an in-depth discussion of the company's structure, resources, and operations within its jurisdiction. Led by Ethan Mobley, the team—including Cory Schreiner, Brian Greer, and Raini Ott—outlined their roles and shared insights into their experiences and challenges, particularly in relation to county stakeholders and available resources. The session concluded with introductions and a brief overview of the organization's operational framework..

Fire Prevention and Hazard Mitigation

During the meeting, D. McNair and DP+S shared their experiences and roles in fire prevention and management. D. McNair expressed interest in bringing in a facilitator to

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

support a future meeting with local elected officials focused on fire prevention strategies. The discussion also covered challenges related to maintaining adequate water pressure and flow rates in rural areas. The session concluded with an introduction to the hazard mitigation planning process, highlighting the importance of assessing natural hazards, building a shared understanding of local risks, and identifying actionable mitigation strategies. The team emphasized the need to align the mitigation plan with the district's capabilities and available resources.

Liquefaction, Flood, and Landslide Hazards Discussed

The team discussed the potential impacts of liquefaction within the district, focusing on population exposure and contributing factors such as soil type and groundwater levels. They also examined flood hazards, emphasizing the vulnerability of critical infrastructure within flood zones. A total of 41 critical infrastructure points and 3.1 miles of infrastructure were identified within the floodplain. In addition, the team reviewed landslide risks and noted the location of multiple treatment plants situated within flood-prone areas.

Water Infrastructure Risk and Mitigation

The team reviewed risks and hazards impacting their water infrastructure, with a focus on areas vulnerable to landslides and flooding. They referenced a recent landslide incident that impacted one of the storage reservoirs, underscoring the need for additional geotechnical assessments. The discussion also explored opportunities to secure funding for infrastructure improvements and hazard mitigation, emphasizing the long-term financial and operational benefits. Key sites—including the Glenwood and Bethany tanks—were identified as areas of concern, and the team agreed to continue monitoring these locations while pursuing strategies to reduce future risk.

Water District Infrastructure and Risks

The group reviewed key infrastructure components within the water district, with particular attention to the Montefiore Booster Station, which is currently supported by an aging backup generator in need of replacement. They also discussed seismic risks, noting that the entire district falls within an area of very strong shaking potential in the event of a magnitude 7.1 earthquake. Attention then turned to the district's water lines—primarily asbestos concrete—and the potential seismic vulnerabilities of vaults and related facilities. D. McNair highlighted that the McDorsa Tank, one of the older storage tanks, lacks seismic restraints and may require retrofitting. The discussion concluded with a transition to the topic of wildfire hazards.

SVWD BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Scotts Valley Water District Wildfire Hazard

The Scotts Valley Water District is actively addressing wildfire risks by enhancing its fire hydrant database and coordinating maintenance efforts with the local fire district. Efforts are concentrated in two high-risk zones with limited water storage: the Northridge zone, which relies on a 50,000-gallon redwood tank, and Via Fontenay, which has a 30,000-gallon redwood tank. The district is planning hydraulic analysis and engineering evaluations to explore options for increasing storage capacity and improving water distribution in these areas. In addition, they are maintaining defensible space around district facilities, though challenges remain with vegetation on neighboring properties. The discussion also acknowledged the limited effectiveness of hydrants during wildfire events and emphasized the need for broader, community-wide fire prevention strategies.

Scotts Valley Water District Risk Assessment

During the meeting, the team reviewed the risk assessment for a range of hazards, including drought, flooding, slope failure and soil instability, wildfire, earthquakes and climate change. After discussion, they agreed to prioritize earthquake, wildfire and slope failure as the primary hazards for the Scotts Valley Water District. The potential impacts of drought were also highlighted, particularly in relation to water restrictions and the possible need for a drought surcharge. The team committed to focusing on these key hazards and developing targeted mitigation strategies. They also emphasized the importance of promoting the community survey and upcoming outreach events. The group plans to report back to the larger planning team in June, followed by a second breakout session to further refine mitigation actions.

SVWD BO 1 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)

City of Watsonville Breakout Meeting #1

Date: Thursday, April 24, 2025
Time: 10:00 A.M. – 12:00 P.M.
Location: Zoom
Meeting ID: 865 9185 4345
Passcode: 584035

Facilitator(s): Dynamic Planning + Science (DP+S), Ethan Mobley & Christopher Velasco

Meeting Purpose

To support the development of the Santa Cruz County MJHMP by reviewing local hazard histories specific to the City of Watsonville, assessing jurisdiction-specific capabilities, and initiating the risk prioritization process. At the end of the breakout meeting, participants will:

- Have a shared understanding of past hazard impacts and current risks within their jurisdiction.
- Begin to evaluate local capabilities and resources for hazard mitigation.
- Have prioritized hazards through a collaborative risk matrix exercise.
- Begin identifying relevant mitigation actions and assess progress on previous strategies.
- Confirm next steps for contributing to the updated MJHMP.

Agenda

ID	Time	Action Item	Key Decision / Support Request
1	5 min	**Welcome and Introductions** Result: Overview of meeting goals, structure, and expected outcomes.	No decision or support requested
2	20 min	**Overview of the Mitigation Planning Process** Result: Recap of progress thus far and HMPT Meetings #1 and #2, FEMA planning requirements, and how local input informs the MJHMP.	Confirm alignment on planning purpose and process.
3	60 min	**Review of Historical Hazards and Current Risk** Result: Establish baseline understanding of hazard trends, exposure, and recent disaster impacts. a) Local hazard history and impacts b) Hazard profiles and trends from past HMPs and CAVA c) Current risks and top hazards for the jurisdiction	Validate key hazards affecting each jurisdiction.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

4	**20 min**	**Interactive Risk Matrix Exercise** Result: Collaborative assessment of hazard likelihood and consequence to inform prioritization.	Reach consensus on top-priority hazards for the jurisdiction.
5	**5 min**	**Next Steps and Closeout** a) Upcoming events and City of Watsonville Breakout Meeting #2 b) Data requests and outreach support, survey promotion c) Questions and open discussion	Confirm upcoming tasks and needed follow-up.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Meeting Summary for City of Watsonville Breakout Session #1
Thursday, April 24, 2025, 10am-12pm

The Dynamic Planning + Science (DPS) team and the Watsonville city team discussed the importance of updating the hazard mitigation plan every five years to address new priorities and perspectives, with a focus on Watsonville's specific hazards, capabilities, and resources. They also discussed the challenges of securing funding for the levee system, the need for more data, including water infrastructure, to improve their plans, and the potential impact of levee replacement on flood maps. The team agreed to prioritize hazards for Watsonville using a risk matrix exercise and outlined the upcoming series of meetings and public outreach events for the hazard mitigation plan.

Next steps

- **DPS Team**:
  - Schedule a separate RAMP training session focused on Watsonville and South County staff
  - Update RAMP to include Watsonville's water infrastructure once received
  - Review Watsonville's General Plan and Environmental Justice documents to incorporate future growth areas and vulnerabilities in the hazard mitigation plan
  - Include narrative about Watsonville's service relationship with North Monterey County communities in the hazard mitigation plan
  - Refine and align mitigation actions with Watsonville's current capabilities and priorities in the next planning phase
  - Ask Brian Lockwood: To provide information about water quality and flooding risks related to Watsonville Slough being used as a drinking water source
  - Support outreach events in August including Strawberry Festival and National Night Out with Spanish language materials

- **Charles/GIS Team**: Provide water infrastructure data (bridges) and distribution lines to DPS team for inclusion in RAMP tool
- **Courtney/Public Works**: Coordinate with Caltrans on the $7 million repair project for Main Street/152 sidewalk near Knob Hill shopping center
- **Public Works Team**: Provide bridge infrastructure data to Ethan, particularly for city-owned bridges not currently showing in the National Bridge Inventory

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- **Planning Team**:
  - Review the new Local Responsibility Area map and assess implications for infrastructure in relation to the safety element requirements
  - Update map illustrations in the annex to include wider coverage area extending north to Corralitos filter plant and west to the landfill
  - Prepare Spanish language materials and translation support for public outreach events
  - Create simplified, public-friendly version of hazard maps showing homes and surrounding hazards for August events
  - Prepare collateral materials and messaging for smaller local events

- **Water Department Team**:
  - Provide drought impact data from 2015-2017 and 2023 periods, including information about wellhead conditions and water levels
  - Consider mitigation strategies for critical facilities located in flood-prone areas
  - Verify and update the list of 8 unreinforced masonry buildings in Watsonville

- **City Engineering Team**: Review and consider updating city standards for water pipe materials, particularly evaluating HDPE or PVC options instead of ductile iron

Summary

The meeting begins with introductions from the Dynamic Planning + Science (DPS) team, led by Ethan Mobley, and the Watsonville city team, including Toto Vuduc, Courtney, Tamara Vides, Nick Calubaquib, and David Rodriguez. Ethan explains that they are working on a multi-hazard jurisdiction plan for Santa Cruz County, with Watsonville being part of this larger effort. The group discusses the importance of updating the hazard mitigation plan every five years to address new priorities and perspectives. Ethan outlines the agenda for the meeting, which includes reviewing historical hazards, current risks, and conducting an interactive risk matrix exercise. The team agrees to adjust the agenda to accommodate Tamara's limited time and focus on discussing Watsonville's local priorities for hazard planning.

Watsonville BO 1 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Watsonville Mitigation Planning Process Overview

Ethan explains the mitigation planning process, emphasizing the need to assess Watsonville's specific hazards, capabilities, and resources. He outlines the timeline for developing the plan, aiming for a draft by October. The team discusses demographic data, with Tamara and Justin noting that recent census data significantly undercounts Watsonville's population due to anti-immigrant campaigns. Justin provides insights on population trends and growth projections from the general plan. The group also examines vulnerability across the county and discusses how to prioritize mitigation actions for Watsonville's more vulnerable populations. Ethan presents data on hazard frequency and severity, as well as survey results on local perceptions of hazards, highlighting differences between Watsonville and the broader county.

Watsonville Flood Hazard and Mitigation

In the meeting, Ethan and Chris discussed the flood hazard in Watsonville, focusing on the 2023 floods and the multi-jurisdictional efforts to mitigate them. They highlighted the potential for water contamination and infrastructure damage, particularly to the wastewater treatment plant. They also discussed the use of the Risk Assessment Mapping Platform (RAMP) to identify critical facilities in the 100-year floodplain. Tamara emphasized the importance of recognizing the elderly population in the affected areas, as they require different mobilization strategies. The team also discussed the potential for population changes in the riverine areas.

Flood Hazards in Watsonville

The group discusses flood hazards in Watsonville, focusing on vulnerable populations and critical areas. They identify an elderly population near the Pajaro River who may have difficulty evacuating and protecting their property. A *senior village area* is highlighted on the map. The discussion also covers localized flooding issues not connected to levee overtopping, including a recent incident involving Coralitos Creek. Matt points out that disadvantaged communities are located in flood-prone areas, particularly in the downtown and industrial zones. Justin mentions that most of Watsonville qualifies as disadvantaged according to their environmental justice assessment, with only a few pockets of higher income areas.

Watsonville BO 1 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Securing Funding for Levee System

The team discussed the challenges of securing funding for the levee system that would protect the wastewater treatment plant. They highlighted the issue of property values and the prioritization of flood improvements along the Pajaro River system. The team also discussed potential growth areas and the need for flood mitigation measures. They identified the area between East Lake and Wagner as a potential growth area. The team also discussed the need for more data, including water infrastructure, to improve their plans. They also discussed the importance of critical infrastructure points and the need to filter data down to the FEMA flood plains.

Floodplain Management Ordinance Expansion Discussion

The team discussed the need to include more facilities in the floodplain management ordinance, such as the municipal services center and City Hall. They also discussed the challenges of evacuating residents during flooding events, particularly in the community of Pajaro. The team agreed to include more information about the vulnerability of North Monterey County populations in their plan. They also discussed the use of the Watsonville slough as a drinking water source and the potential risks associated with it. The team also discussed the need for more information about water infrastructure and supply issues related to flooding and erosion, especially in the sloughs.

Flood Challenges and Emergency Shelter Options

Ethan, David, and Toto discussed the challenges of evacuating the police department and community during floods. They considered relocating or flood-proofing the police station, which would require significant resources and time. They also discussed the potential impact of levee replacement on flood maps and the need for proper levee maintenance. Nick added that the city's emergency shelters are limited, with only a few viable options, and that the fairgrounds are the best-suited facility despite transportation issues. The team agreed to explore options for emergency shelters that are suitable for all types of hazards.

Watsonville Infrastructure and Hazard Mitigation

The team discussed the landslide and earthquake hazards in Watsonville, focusing on the infrastructure and potential damage to critical facilities. They also discussed the unreinforced masonry buildings and the need for mitigation actions. The team discussed the water infrastructure, including the use of HDPE pipes, and the need for regular maintenance and inspection. They also discussed the wildfire hazard and the need for evacuation routes and debris management. The team agreed to review the critical

Watsonville BO 1 Summary 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

infrastructure facilities in high or moderate fire zones and to consider additional areas that may be included in the revised mapping effort.

Watsonville Hazard Risk Matrix Discussion

The group discusses prioritizing hazards for Watsonville using a risk matrix exercise. They assess the probability and impact of various hazards, focusing on flooding, levee failure, earthquakes, soil hazards, wildfires, drought, and climate change. Flooding and levee failure are considered highly likely with potentially critical impacts. Earthquakes are deemed likely with critical impacts. Soil hazards and wildfires are rated as possible with limited impacts. Drought is considered likely but with minor impacts due to adequate water supply. Climate change is discussed as a multiplier that affects other hazards. The group agrees to focus on these prioritized hazards in their mitigation planning efforts.

Hazard Mitigation Plan Outreach Strategy

Ethan outlines the upcoming series of meetings and public outreach events for the hazard mitigation plan. He proposes tabling at South County events like the Strawberry Festival and National Night Out in August to conduct surveys and provide resources. Justin suggests additional local events for outreach. The team discusses the need for Spanish translation and simplified materials for public engagement. They also mention conducting one-on-one interviews with community partners. Action items include potentially scheduling a RAMP training session, getting water infrastructure data into RAMP, and adjusting map views to include key infrastructure areas.

Watsonville BO 1 Summary 5



Cabrillo College BO 2 Photo



Cabrillo College BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE



In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3

SECTION 2. Capabilities Assessment 4

SECTION 3. Problem Statements 7

SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
    a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
    b. Are any concerns not reflected in at least one statement, either specifically or generally?
    c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
    d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional HMP
Pajaro Valley Water Management Agency (PVWMA), Breakout #2 Meeting Recap
Meeting Date: July 16th, 2025, from 10AM-12PM

Summary

Breakout #2 meeting focused on developing a multi-jurisdictional hazard mitigation plan for the college, discussing various risks and mitigation strategies. Participants reviewed existing plans, assessed capabilities, and identified problem areas, with particular emphasis on wildfire, flooding, seismic risks, and infrastructure concerns. The group also discussed improving emergency alert systems, website hazard information, and building safety protocols, while planning for a board presentation and setting deadlines for document reviews.

Next steps

(Director, Federal/ State Emergency Grants):

- Contact Kristen Fabos regarding earthquake alert system management and implementation
- Contact Red in IT department to the status of the PA system implementation
- Write to the webmaster about updating the emergency webpage to include links to OR3 website
- Draft and send email to request 10-minute presentation time slot for the board meeting

Luis (Assistant Director, Facilities):

- Send the complete hazard mitigation plan document to the team
- Work with Cal Fire to coordinate the eucalyptus tree removal project and establish a maintenance plan
- Send the building construction dates list to Dynamic Planning + Science team for their database
- Submit presentation materials to the meeting scheduler before August 4th
- Identify which mitigation actions need collaboration from other jurisdictions for August 4th county-wide meeting

DP+S Team:

- Edit and consolidate the mitigation actions table and send back to the team by end of week
- Develop static maps for the final product due August 28th

Cabrillo College Team:

- Review and provide feedback on mitigation tables, problem statements, and capabilities assessment by September 2nd
- Review the full administrative draft package distributed on August 28th within two weeks
- Prepare for Board of Trustees presentation on August 4th in Watsonville Building C, Room 107

CabrilloCollege BO 2 Summary_1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

College Hazard Mitigation Plan Update

The group discusses the college's participation in a multi-jurisdictional hazard mitigation plan, which will replace their standalone plan. DP+S Staff explained that this approach will reduce costs and allow the college to pursue grants independently. Luis mentions a hazard communications plan that Brian has been working on, which is separate from the mitigation plan. The team reviews the previous mitigation plan created by Dewberry, which Luis (Cabrillo College) locates and offers to share. DP+S Staff emphasize that this meeting is a working session to review and refine the plan's content.

College Hazard Mitigation Plan Development

The meeting focuses on developing mitigation actions for the college's hazard mitigation plan. DP+S Staff outlined the process, which includes assessing capabilities, identifying problem areas, evaluating mitigation alternatives, and refining the plan. They emphasize the importance of presenting to the Board of Trustees in August or September, with DP+S Staff offering to attend the August 4th meeting to assist. The team discusses the sources used for the capabilities assessment, including various college documents and plans. DP+S Staff stressed the need for consensus on the mitigation strategy and encourages identifying areas where collaboration with other entities might be necessary.

College Hazard Risk Analysis Review

DP+S Staff presented a risk matrix analysis of hazards affecting colleges, focusing on wildfire, flooding, drought, severe weather, earthquake, and slope failure. They discussed how hazard impacts, victims, and threats need to be characterized to improve resiliency. Julie (Cabrillo College) made edits to Attachment B of the Hazard Mitigation Plan, which DP+S Staff will review. The group agreed to continue their discussion in a shared Word file, with Julie sending her edits via email.

Streamlining Federal Grant Processes

DP+S Staff and Julie (Cabrillo College) discussed changes to a document, including color coding for certain entries. They clarified that Julie manages cross-college grants, including facility-related projects, and works with grant writers and the president to pursue opportunities. Julie (Cabrillo College) noted that federal grants, particularly FEMA grants, are challenging to obtain. DP+S Staff mentioned the need for streamlining federal grant processes and reducing red tape, citing an example of difficulties faced by another organization in obtaining funding.

Emergency Alert System Integration Discussion

The group discussed emergency alert systems, noting that while they receive tsunami alerts through RAVE, though they haven't received geological hazard warnings. They explored the possibility of integrating a PA system with earthquake alerts from the USGS system, with Luis (Cabrillo College) indicating that their IT department had been working on this, but the status was unknown. Julie (Cabrillo College) mentioned that Cabrillo College could issue bonds for projects, though their last two bond efforts were rejected by voters, and they face budget challenges.

CabrilloCollege BO 2 Summary_2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Website Hazard Information Improvements

The group discussed the need to improve the website's hazard information, with DP+S Staff suggesting linking to external resources like OR3 and Santa Cruz.gov rather than duplicating content. Julie (Cabrillo College) noted that hazard-related information is currently dispersed across the site, and Cory mentioned an existing safety and emergency page. They agreed to relink to OR3 for hazard information and potentially include the hazard mitigation plan, though Julie expressed uncertainty about its sensitivity. The discussion concluded with plans to refine the website's structure, focusing on key components like problem statements and capabilities.

Campus Flood Mitigation Planning

The group discussed flood damage and drainage issues at the Watsonville and Aptos campuses. Julie mentioned past flooding from a stream during storms in 2023, while Luis (Cabrillo College) described French drain installations and flood mitigation efforts. They discussed the location of a pump station near the Watsonville campus and the planned student housing construction. The conversation touched on the need for better documentation of flood risks and drainage facilities in their records.

Campus Building Safety Assessment

The group discussed building safety and maintenance protocols at the campus, including biannual inspections by Keenan and Associates and annual fire inspections. Luis (Cabrillo College) confirmed that the oldest building on campus, Cessna House, was built in 1910, with Watsonville Building B constructed in 1936. The discussion revealed that while some buildings had been retrofitted, there was a need to identify which structures required seismic mitigation, and Luis agreed to provide a detailed list of building construction dates to help with this assessment.

Campus Risk Mitigation Strategies

The group discussed various risk mitigation actions for the campus, focusing on flooding, seismic risks, and slope stability. Luis (Cabrillo College) explained that the campus has three water meters, with two serving the main campus and one for traffic signals and wells. They discussed the need for flood emergency response planning and the potential for elevating or flood-proofing buildings, though the Corps of Engineers' levee project may reduce flood risk. The team also reviewed ongoing maintenance activities, including hazardous tree removal, storm drain cleaning, and slope stabilization efforts, while considering the integration of hazard planning into the campus master plan.

Campus Safety and Infrastructure Planning

The group discussed campus safety and infrastructure concerns, focusing on wildland management and power backup systems. Luis (Cabrillo College) explained that while the campus owns some land, much of it is inaccessible for thinning due to steep terrain and creek areas requiring permits. They discussed plans for Cal Fire to thin eucalyptus trees along access roads, and Luis (Cabrillo College) noted that critical facilities have emergency generators for servers and emergency lighting, though the campus is gradually moving to cloud-based systems for increased reliability. The group also touched on water

CabrilloCollege BO 2 Summary_3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

resilience, with Luis (Cabrillo College) mentioning plans to measure campus wells within the next year or two and having a municipal water source as a backup.

Campus Wildfire Risk Management Plan

The group discussed wildfire risks and vegetation management around campus, with DP+S Staff highlighting concerns about defensible space and prevailing winds. Luis(Cabrillo College) noted community opposition against tree removal, while Julie and Luis (both Cabrillo College) confirmed no major fire incidents but acknowledged nearby fire department access. They agreed to review mitigation plans, with DP+S Staff planning to consolidate actions and address wildfire, extreme weather, and backup power as top priorities. The team scheduled a board presentation for August 4th in Watsonville and set deadlines for document reviews, with Julie (Cabrillo College) confirming her availability.

CabrilloCollege BO 2 Summary_4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE



In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3
SECTION 2. Capabilities Assessment 4
SECTION 3. Problem Statements 7
SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

Capitola BO 2 Read Ahead 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
    a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
    b. Are any concerns not reflected in at least one statement, either specifically or generally?
    c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
    d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Summary for City of Capitola Breakout Meeting #2

Monday, May 12, 2025, 3:00-5:00 PM

City of Capitola Breakout Meeting #2 focused on developing the mitigation strategy, including reviewing the city's draft capabilities assessment, hazard problem statements, and mitigation actions. The team from Dynamic Planning + Science (DP+S) led the discussion with the city team about updating various sections of their hazard mitigation plan, including regarding slope failure, drought, wildfire, and climate adaptation strategies. They reviewed and revised problem statements and mitigation actions, emphasizing collaboration with other agencies and focusing on high-risk areas. The group also addressed administrative matters, including upcoming deadlines, outreach events, and the timeline for completing the MJHMP planning process.

Next Steps

Capitola Team Action Items

- Identify collaboration opportunities with the county, RCD, and other jurisdictions for the next planning team meeting on August 4.
- Review and provide comments on Mitigation Strategy, including Capabilities Assessment, Problem Statements, and Mitigation Actions (Read-Ahead Attachments B, C, and D) by September 2.
- Review and provide comments on the administrative draft of the plan at the end of August/early September.

DP+S Team Action Items

- Update problem statements and mitigation actions based on the discussion and resend for city review.

Meeting Summary

The teams discussed updating problem statements and mitigation actions for slope failure to focus on non-coastal areas, including risk assessment and potential monitor installation. They also reviewed drought-related actions, such as water conservation incentives and education programs, noting that these would likely be led by other agencies with city participation. Fuel management and hillside access route improvements were discussed as components of wildfire mitigation. DP+S proposed deleting any actions that are no longer relevant, and the teams agreed that for many public outreach and education programs, particularly those related to drought and wildfire, collaboration with other lead agencies like the county, RCD, water providers, and fire districts would be beneficial.

Wildfire Mitigation & Evacuation Planning

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

The group discussed vegetation management in high-risk areas, particularly between Park Avenue and the Cliffwood Heights neighborhood. They identified a eucalyptus grove as a concern and identified property ownership along Park Avenue. DP+S suggested removing ladder fuels and potentially replacing eucalyptus trees, noting they are invasive species despite their aesthetic appeal. The group discussed including Park Avenue as a critical evacuation route in the problem statements, along with Cliff Drive. DP+S mentioned an upcoming memo regarding safety element updates and unfunded mandates, specifically referencing Assembly Bill 747 which requires analysis of evacuation routes in hazard mitigation plans.

Extreme Heat Mitigation

They then reviewed home weatherization incentives, noting that energy efficiency improvements support would be through 3CE rather than PG&E. The city team suggested making information available at the front counter and on the city website instead of conducting active outreach. The discussion also touched on urban forest management plans and cooling centers, with the group agreeing that it would be more appropriate to include cooling center activities in the county's plan rather than the city's.

Climate Action Adaptation

The teams discussed updates to the city's climate action and adaptation plans. They decided to remove a proposed climate resilience scorecard action, as it may be redundant with existing monitoring efforts. The city team noted that their adaptation planning process will likely take about 5 years to complete. The group emphasizes the importance of including equity considerations in adaptation decision-making.

Conclusion

DP+S reminded the city team of upcoming outreach events, including the Capitola Makers Market on August 3, and the last county-wide planning team meeting on August 4. DP+S also communicated the deadline of September 2 for reviewing and commenting on the draft mitigation strategy and that the administrative draft review is scheduled for late August to early September.

Capitola BO 2 Summary 2



PVWMA BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE



In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3

SECTION 2. Capabilities Assessment 4

SECTION 3. Problem Statements 7

SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
   a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
   b. Are any concerns not reflected in at least one statement, either specifically or generally?
   c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
   d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional HMP
Pajaro Valley Water Management Agency (PVWMA), Breakout #2 Meeting Recap
Meeting Date: July 18th, 2025, from 9AM-11AM

Summary

The meeting focused on developing and refining a five-year implementation plan for hazard mitigation, with discussions covering various natural threats to water infrastructure, including wildfires, floods, earthquakes, and sea level rise. The group assessed current capabilities, identified gaps in existing safety plans, and explored potential mitigation strategies for different hazards, emphasizing the importance of proactive measures and alignment with risk assessments. The team also discussed staff roles, grant management, and agreed on next steps, including reviewing and commenting on a packet by September 2nd, 2025 and participating in a collaborative exercise on August 4th, 2025 (Countywide Meeting) to further discuss mitigation actions and opportunities for collaboration.

Next steps

PVWMA Team:

- Review and provide feedback on the mitigation strategy document by September 2nd
- Review and refine problem statements for each hazard type in the read-ahead packet
- Review and validate the proposed mitigation actions for each identified hazard
- Explore collaboration on Shell Road Pump Station improvements and road elevation project
- Develop memorandum of agreement with RCD for post-wildfire soil retention and erosion control
- Collaborate with the County on public education campaign regarding well contamination during floods
- Evaluate flood-proofing options for Supplemental Wells 1 and 2 which are at risk of flooding Prepare discussion points about collaboration opportunities for the August 4th meeting

Brian Lockwood, PVWMA Director:

- Calculate and provide staff hourly rates to Claire for grant tracking purposes

Brian, Director and Casey, Associate Hydrologist:

- Evaluate and confirm the number of facility sites requiring defensible space management

Marcus, Finance and Administrative Services Manager:

- Attend the next public meeting on August 4th as Brian's representative

DP+S Team:

- Create a non-public web application for tracking mitigation actions and progress
- Revise and deliver the updated read-ahead packet to PV Water by early next week
- Remove PV Water acronym references from the capabilities assessment document to make it more general

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Update the wildfire mitigation action timeline from 2028 to 2027

Five-Year Implementation Plan Review

The meeting focused on reviewing and refining planning documents for a five-year implementation plan. Brian (PVWMA) reported that he had presented a draft to his board, who were prepared for the public review process. DP+S Staff explained that the current working session was an opportunity to edit the material over the next six weeks, with the final document due in approximately 6 weeks. The group discussed the status of FEMA funding, noting recent news articles about potential changes to FEMA's structure, though DP+S Staff confirmed that FEMA remains active with significant disaster funding.

Hazard Mitigation Strategy Development

The meeting focuses on developing a mitigation strategy for a hazard mitigation plan. DP+S Staff explained the process, which includes assessing capabilities, defining problem statements, and evaluating mitigation alternatives. They emphasize the importance of tailoring strategies to the agency's specific mission and resources. The timeline for the plan development is discussed, with an administrative draft due in August and public review in September-October. Brian (PVMWA) inquiries about potential public meetings after the plan's release. The capabilities assessment and mitigation action development process are outlined, with a focus on being specific and measurable while balancing public consumption and operational details.

Pajaro Valley Hazards Assessment

DP+S Staff presented a streamlined set of 10 hazards for PVWMA, excluding dam failure and slope failure as they are not significant threats. They discussed the potential impacts of climate change on natural hazards. Brian (PVWMA) mentioned that Standard & Poor's requested an analysis of the district's resilience against wildfire, particularly in light of recent fires. DP+S Staff emphasized that PVWMA's plan can be streamlined under the larger county-wide plan, focusing on specific hazards relevant to their operations. They also introduced the concept of problem statements for each hazard, considering impacts on infrastructure, government operations, and vulnerable communities.

Wildfire and Flood Water Impacts

The group discussed the impacts of wildfires and floods on water infrastructure and supply. Brian (PVWMA) emphasized that while wildfire impacts to their water supply facilities were minimal, however, the main concern was for domestic well users in wildfire zones. They discussed potential mitigation measures, including electrical improvements to facilities to enable generator use during power outages. The entire group also explored the risks of floodwater contamination to wells and aquifers, with Brian (PVWMA) sharing an example of recent flooding that contaminated wells in Monterey County. They agreed that well destruction programs could be a useful mitigation strategy, though this would likely be a county-level responsibility with PVWMA as a collaborator.

PVWMA BO 2 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Water Infrastructure Natural Threats

The entire group discussed various natural threats to water infrastructure, including increased frequency of flood and drought events, as well as earthquake risks. Casey (PVWMA) and Shinehah (Operations & Maintenance Manager, PVWMA) provided details on their water system, noting that most of it is underground cement mortar line and steel pipe, with about 25% being HDPE, and that the recycled water facility could be a critical point of failure if it goes down. PVWMA staff mentioned that College Lake project would be operational next year and would be impacted by reduced rainfall and drought conditions. DP+S Staff concluded by discussing the need to redeliver and edit the presentation, with a due date of September 2nd.

Saltwater Intrusion Mitigation Project

The group discussed the impacts of sea level rise on water quality, with Brian (PVWMA) explaining how saltwater intrusion affects groundwater and surface water systems. They explored potential mitigation strategies, including a new diversion facility further upstream on Struve Slough, which is at 100% design and pending environmental permits. Casey (PVWMA) suggested modifying existing infrastructure and increasing downstream capacity to reduce the impact of saltwater flow. The project is estimated to cost around $50 million and is expected to be constructed by 2027, with WIFIA funding covering about 50% of the construction costs.

Safety and Resilience Strategy Review

The group discussed capabilities assessment and strategy development, focusing on various safety and resilience plans. They identified gaps in existing fire, seismic, and flood response plans, while noting ongoing work on the Pajaro River watershed resilience plan with $2 million in funding. The entire group agreed to simplify the capabilities document by removing specific references to PVWMA and making descriptions more concise, with Brian (PVWMA) highlighting their GIS and data capabilities despite not having a dedicated position for it.

Staff Roles and Grant Management

The meeting discussed staff roles and responsibilities, with Brian (PVWMA) highlighting Casey (PVWMA) as the dedicated GIS person and Marcus (PVWMA) as the Water Conservation and Outreach Specialist. They discussed grant management, with DP+S Staff explaining their tracking system using AppSheet and noting that the project has accumulated $30,000 in in-kind labor. The conversation then shifted to mitigation actions, where DP+S Staff outlined various categories including prevention, property protection, public education, natural resource protection, and emergency services, emphasizing the need for equity-oriented, fundable actions that align with risk assessments and are feasible within the jurisdiction.

Remote Facility Defensible Space Planning

The group discussed defensible space requirements at remote facilities, agreeing to focus on key sites like the pump station and infiltration basin, with Brian noting they had recently started working with

PVWMA BO 2 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Watsonville Wetlands Watch for vegetation management. They reviewed post-fire runoff reduction projects, with Casey (PVWMA) suggesting these could be appropriate given the episodic nature of wildfires, though DP+S Staff emphasized the need to move from reactive to proactive mitigation measures. The discussion concluded with considerations for flood mitigation, where they identified two wells as potential vulnerable points, though most infrastructure was built above the 100-year floodplain, and explored the possibility of collaborative public education campaigns with the county regarding well contamination risks during floods.

Flood Risk Assessment for Wells

The team discussed flood risks to several wells in the area, particularly Supplemental Wells 1 and 2 which are located near the river and in flood zones. Brian (PVWMA) explained that while there is funding for levee improvements up to Highway 1, there are concerns about the timeline and reliability of these projects. The group agreed to consider flood-proofing measures for the wells, with Brian (PVWMA) noting that during heavy rain events, some wells are currently inaccessible due to flooding.

Water Management and Safety Challenges

The group discussed various water management challenges, including flood protection, well protection, seismic safety, and sea level rise impacts. Brian (PVWMA) clarified that well protection is primarily the responsibility of the regional flood management agency, while flood protection projects would not safeguard certain wells. They also discussed ongoing efforts to manage drought, recharge projects, and mitigate seawater intrusion, with Casey (PVWMA) highlighting the importance of emergency power supply for water service during earthquakes. The team agreed to review and provide comments on a packet by September 2nd. DP+S Staff mentioned plans for a collaborative exercise on August 4th to discuss mitigation actions and opportunities for collaboration.

PVWMA BO 2 Summary 4



RCD BO 2 Photo



RCD BO 2 Read Ahead_Part1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE



In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3

SECTION 2. Capabilities Assessment 4

SECTION 3. Problem Statements 7

SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
   a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
   b. Are any concerns not reflected in at least one statement, either specifically or generally?
   c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
   d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-jurisdictional HMP
Resource Conservation District of Santa Cruz County (RCD), Breakout #2 Meeting Recap
Meeting Date: July 17th, 2024 from 12PM-2PM

Summary:

The meeting focused on developing and refining hazard mitigation strategies for the Resource Conservation District, with discussions covering various natural hazards including wildfires, floods, and landslides across Santa Cruz County. The team reviewed specific mitigation actions and capabilities assessments, while addressing concerns about coastal hazards, dam failure risks, and flood mapping impacts on agriculture. The group established key deadlines for document submissions and public review, with plans to meet again in August to further discuss implementation strategies and collaboration opportunities across jurisdictions.

Next steps

RCD:

- (Lisa) Prepare presentation for August 13th Board meeting regarding hazard mitigation decision-making briefing
- (Lisa/RCD Team) Meet with Rich and DP+S team on August 4th morning to review mitigation actions
- (Lisa) Share edited Word document with team's consolidated comments regarding problem statements and capabilities assessment
- (Lisa) Revise sea level rise impact statement to reflect compound effects on upstream flooding and groundwater supply
- (Lisa/RCD Team) Review and provide feedback on the updated mitigation actions document by September 2nd
- (Lisa and Team) Review and edit the culvert program description to clearly define RCD's role versus county responsibilities before August 4th meeting
- (RCD Team) Update capabilities assessment to reflect current and future mitigation activities specific to RCD operations
- (RCD Team) Review Admin draft starting August 28th
- (RCD Team) Review and provide feedback on culvert study from the county regarding priorities and criteria
- (Lisa and Team) Revise the bluff stabilization action item to focus on integrating techniques into coastal restoration projects

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- (Lisa and Team) Update implementation targets for mitigation actions based on funding status
- (RCD Team) Revise slope failure mitigation actions to focus on stream bank stabilization and agricultural erosion control
- (RCD Team) Define specific physical projects within existing programs for better progress measurement
- (RCD Team) Participate in public outreach events at Strawberry Festival and Capitola Makers Mark
- (RCD Team) Continue sharing the public survey for hazard mitigation input
- (Cameron/Matt) Support hazard stations at the August 4th meeting as subject matter experts
- (Lisa) Consider inviting OES representatives to give presentation at the Board meeting

DP+S

- Plan to Cal OES for review by October 31st
- Prepare and release public review draft by September 29th
- Update the problem statements to focus on people/landowners being helped rather than RCD assets
- Revise and refine mitigation actions to include both current capabilities and aspirational goals

DP+S and RCD

- Schedule a side meeting with Chris to review mitigation actions in detail before August 4th

Problem Statements and Mitigation Actions

The meeting began with a casual conversation about weather conditions, particularly focusing on monsoons and wildfires in different regions. Chris mentioned working on problem statements and mitigation actions with a group, while Corey provided insights into how they review and refine these statements. The meeting then transitioned to include more participants, with Ethan and others joining to discuss ongoing work and updates.

RCD Hazard Mitigation Strategy Review

The meeting focuses on reviewing and developing the hazard mitigation strategy for the Resource Conservation District (RCD). DP+S explains they are in the process of writing profiles and developing problem statements, mitigation alternatives, and capabilities assessments. They emphasize the importance of RCD's input on their capabilities and mitigation priorities. Lisa confirms they will review the decision-making briefing materials for their board. The group discusses upcoming public outreach events and key dates for the draft review process. DP+S stresses the need to define problem statements, assess capabilities, and develop specific, measurable mitigation actions tailored to RCD's operations and mission.

RCD BO 2 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

County Hazard Profile Planning Meeting

DP+S presented a consolidated list of 10 hazards to be profiled in the county plan, including wildfire, flood, earthquake, severe weather, coastal hazards, landslides, and climate change. They explained that soil hazards were removed and incorporated into slope failure, while sea level rise will be addressed under climate change. Lisa expressed concern about the reclassification of coastal hazards, noting ongoing studies focused on evaluating coastal hazards at river mouths. The group discussed the need to consider ecological restoration in coastal hazard planning.

Dam Risk Assessment Review

The team discussed dam failure risks, with Lisa and Angie noting that while Loch Lomond is the only major dam in Santa Cruz, they are more focused on removing smaller dams that pose fishery hazards and localized flooding risks. They identified that the current risk matrix might need refinement, particularly regarding the placement of road stabilization measures which were incorrectly categorized. The team agreed to review the dam failure section further, with Angie and Lisa planning to discuss culvert infrastructure and its classification in relation to flooding and soil erosion risks offline.

Santa Cruz Flood Risk Assessment

The group discussed flood risk areas in Santa Cruz County, identifying vulnerable communities and agricultural producers. They identified the Pajaro, San Lorenzo, and lower lying areas as having higher population risks, while Scott Creek, San Vicente Creek, and Waddell Creek were noted as having fewer residents but important ecological functions. Cameron highlighted that socially disadvantaged farmers experience higher flood impacts and have less ability to recover. The discussion also touched on restoration projects in the lower Pajaro and Watsonville sloughs, which serve multiple purposes including flood risk mitigation and habitat protection.

Culvert Maintenance and Storm Planning

The group discussed changes in culvert sizing and maintenance due to intensified storms, with Angie noting that operations haven't changed significantly but future planning now considers debris and fire risks. They reviewed a county culvert study examining sizing, condition, and potential failures, particularly in post-fire areas where undersized culverts have caused issues. The team agreed to focus on RCD-specific priorities for their document revisions, with Lisa making redline changes around watershed priorities, while Cameron and others highlighted the importance of education and proper implementation of BMPs, noting problems with incorrect post-storm mitigation efforts by unqualified contractors.

Flood and Landslide Impact Assessment

The group discussed flood maps and their impact on agriculture, particularly in the Pajaro area where Cameron noted significant flooding in 2023 affecting prime farmland. They explored the frequency of FEMA flood map updates, which typically occur every 10-20 years, and Brian mentioned he was working on depth grids from a 2017 update. The conversation then shifted to landslides and slope failures in the

RCD BO 2 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz Mountains, with Angie highlighting that rural communities face disproportionate impacts, including loss of life and access to private roads, while Lisa suggested revising the threat statement for RCD O.2 to include local geologic conditions and changes in land use such as deforestation and increased impermeable surfaces.

Impact Statement Structure and Priorities

The team discussed how to structure their impact statement, deciding to use a Word document for tracking changes while presenting updates in PowerPoint format. They clarified that while environmental impacts should be included, the term "victims" should specifically refer to human casualties as defined by FEMA, though they acknowledged the complexity of quantifying impacts on both human and ecological systems. The group agreed to organize the impact statement by prioritizing major challenges like flooding and slope failure, with climate change impacts to be incorporated into each hazard profile rather than having a separate standalone section.

Wildfire Impact on Water Infrastructure

The group discussed the impacts of wildfires on water infrastructure and natural ecosystems, emphasizing that uncontrolled high-severity fires primarily affect forest health and watershed resilience rather than specific mitigation projects. They clarified that water infrastructure is primarily designed for structural fires, not large-scale wildfires, and that the recovery period for water access can be lengthy when infrastructure is damaged. The team agreed to refine their documentation to better reflect these distinctions and the role of RCD projects in managing fire risks through controlled measures like shaded fuel breaks.

Climate Change Impacts on Agriculture

The group discussed climate change impacts on agriculture, water supplies, and forest health. They highlighted how droughts, sea level rise, and coastal erosion threaten water resources and agricultural productivity, particularly affecting socially disadvantaged and smaller growers. The team agreed to research additional threats to forest health and coastal hazards.

Culvert Retrofit Strategy Discussion

DP+S and Lisa discussed the refinement and alignment of mitigation strategies, focusing on specific, fundable, and equity-oriented actions tied to risk assessments. They explored the potential for a rural culvert retrofit program, with Lisa highlighting the need for collaboration with the county and the importance of focusing on compromised or undersized culverts with resource concerns. Angie raised questions about implementation, including the roles of the RCD and county, and the possibility of competing or collaborating on grant applications. The group agreed to discuss these issues further in the next meeting on August 4th, emphasizing the need for clear roles and priorities.

Road and Coastal Stabilization Programs

The group discussed various programs related to road stabilization, culverts, and coastal erosion, focusing on future implementation and collaboration opportunities. Lisa suggested aligning slope failure

RCD BO 2 Summary 4

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

efforts with stream bank stabilization and agricultural erosion control, while DP+S emphasized the importance of specifying physical projects within programs for better progress tracking. Cameron mentioned plant recommendations and runoff control, and Angie inquired about FEMA grant eligibility for private lands, which DP+S explained involves complex requirements and is best managed through larger, consolidated projects. The team also discussed the need to tie programs to natural hazards rather than the end-of-life cycle of infrastructure.

Hazard Mitigation Plan Development Timeline

The team discussed the development of a mitigation action plan, focusing on balancing aspirational goals with concrete commitments. DP+S explained that while detailed implementation metrics would be hidden from public view, the plan needs to be flexible and updateable, with a focus on collaboration across jurisdictions. The team agreed to submit an updated draft by September 2nd, with a public review scheduled for September 29th, and final submission to Cal OES by October 31st. A key upcoming event was identified as August 4th, where the team will meet at the strawberry festival and conduct a workshop session to review hazard mitigation actions and identify areas needing collaboration.



SCC BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE

In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:



- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3
SECTION 2. Capabilities Assessment 4
SECTION 3. Problem Statements 7
SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
   a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
   b. Are any concerns not reflected in at least one statement, either specifically or generally?
   c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
   d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-jurisdictional HMP
County of Santa Cruz, Breakout #2 Meeting Recap
Meeting Date: July 30th, 2025 from 2PM-4:30PM

Summary

The County Planning Team, DPS staff, and various agency partners met to review draft materials for the Multi-Jurisdictional Hazard Mitigation Plan (MJHMP), including the capabilities assessment, problem statements (Attachment C), and initial mitigation action options. The discussion focused heavily on refining hazard-specific problem statements using the impact-victim-threat framework and aligning them with realistic mitigation strategies. Participants were encouraged to provide redlines and feedback to improve relevance and jurisdictional accuracy. The group emphasized prioritizing a smaller, more actionable set of mitigation actions and preparing for the August 4 countywide meeting and the forthcoming administrative draft.

Next Steps

County Staff / Planning Team:

- Provide comments on problem statements and mitigation actions by September
- Submit feedback on Attachment C (Problem Statements) with particular attention to wildfire, flood, and earthquake sections
- Review capabilities assessment offline with Claire's help to finalize staffing and organizational entries
- Identify cross-jurisdictional needs (e.g., Scotts Valley, Soquel, etc.) and collaborative opportunities to flag during the August 4 meeting
- Collect any missing infrastructure or road data (e.g., private roads, water/sewer, communications)
- Refine outreach language around vulnerable populations (limited-English, elderly, renters)
- Submit redlines for PowerPoint / mitigation alternatives by early August

DP+S Team:

- Update Attachment C based on redline edits and comments provided during and after the meeting
- Incorporate new problem statements for:
- Private road access, road condition data gaps, and fire apparatus access
- Define small private utility and wastewater operators as *Victims*
- Make All-Hazard section communications infrastructure vulnerability (including alert systems and transmission towers)
- Seismic vulnerabilities to critical infrastructure (especially water and shelter facilities)
- Post-disaster rebuilding challenges tied to code compliance and state fire recovery standards
- Draft updated statements for aging population and limited-English speakers in wildfire areas
- Prepare updated problem statement matrix (SharePoint editable version) for circulation
- Bring mitigation strategies and draft implementation roles to August 4 meeting

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Meeting Objectives and Framing

This session focused on three assignments: Capabilities Assessment, Problem Statements (Attachment C), and Mitigation Actions. Emphasis was placed on refining problem statements using existing data and prior plans. Reminder that the Mitigation Plan is a living document, and statements may evolve across cycles. Hazard Problem Statements (Attachment C): focus on impact, victim, and threat structure with each problem statement aims to lead to a SMARTIE mitigation action. Participants discussed redlining directly in PowerPoint or using SharePoint documents.

Wildfire

Issues raised include fire apparatus access on private roads, lack of turnaround space, and washout-prone crossings. Attention was paid to unmanaged regrowth in burn scars and fragmented land ownership complicate treatment. It was noted that small utilities (e.g., mutual water companies) are especially vulnerable to wildfires while there exists an alert and warning system limitations for rural communities lacking cellular service.

Flood / Pajaro River System

Flooding remains a top priority hazard for the County. Discussion emphasized impacts to wastewater treatment, vulnerable populations in floodplain, and the port/fishing economies. There was clarification for the responsibilities of the County for rural-area flood risk with respect to PRFMA.

Earthquake

Earthquake seen as highest consequence hazard due to systemic infrastructure impacts as Santa Cruz County has limited infrastructure connecting it to the greater region. There was a point brought up to distinguish between county-owned buildings, private and public utility systems. A need for softer language around unverified seismic vulnerability (“may require retrofit” vs “are in need”) for buildings built before benchmark building code years.

Addition of Select Problem Statements

Problem Statements are needed for the following:

- Critical water system disruptions
- Bridges and evacuation routes
- Jail and essential services evaluations
- Communications systems’ vulnerability (including outdated radio networks)
- Climate Change / Extreme Temperatures
- Small utilities and aging populations disproportionately impacted
- Barriers to rebuilding (e.g., state fire code recovery requirements) noted

Recommendation to revise language around vulnerable populations to reflect factual demographic patterns, not generalizations.

SCC BO 2 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Risk Prioritization & Mitigation Strategy

The team reviewed countywide risk matrix; identified wildfire, coastal hazards, flood, and sea level rise as top-tier risks. There was discussion on metrics used to prioritize (based on likelihood and impact; gut check from Breakout #1) and an emphasis on streamlining actions to avoid overloading implementation in the future. There was also a proposal to group hazards under *All-Hazards* where applicable to reduce plan bloat

Outreach & Timeline Reminders

- Homework due: September 2
- Admin Draft target: August 28
- With two weeks for internal review before submission to Cal OES
- Community outreach events: Strawberry Festival, Maker's Market in Capitola,National Night Out
- Next countywide meeting: August 4, 2–4 PM
- Cal OES review expected in Fall; FEMA adoption review to follow
- Final decision-maker briefings tentatively scheduled for December
- Board adoption targeted for March 2026

SCC BO 2 Summary 3



Scotts Valley BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE



In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3

SECTION 2. Capabilities Assessment 4

SECTION 3. Problem Statements 7

SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
    a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
    b. Are any concerns not reflected in at least one statement, either specifically or generally?
    c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
    d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-Jurisdictional HMP
City of Scotts Vallet, Breakout #2 Meeting Recap
Meeting Date: July 21, 2025 from 9AM-11AM

Summary

Raini led a meeting to discuss project updates and review a read-ahead packet with the team, offering support for those who hadn't completed the homework. The group worked on developing a mitigation strategy for the City of Scotts Valley, including reviewing capabilities assessments and discussing hazard problems, risk matrices, and potential mitigation actions. The team reviewed various aspects of the hazard mitigation plan, including problem statements, impacts on vulnerable populations, and potential collaboration opportunities between different agencies, with an upcoming meeting scheduled to discuss interagency collaboration and the September 2nd deadline approaching.

Scotts Valley Mitigation Strategy Development

Raini led a work session to discuss the development of the mitigation strategy, focusing on the city of Scotts Valley's capabilities assessment and hazard problems. The group reviewed the project timeline, including upcoming decision maker briefings, outreach events, and an administrative draft review. They discussed the process of defining problems, evaluating alternatives, and developing mitigation actions that align with SMARTIE principles. The team agreed to review the capabilities assessment materials and provide feedback, with Raini offering support for any questions or follow-up discussions.

Scotts Valley Hazard Planning Review

The team reviewed a capabilities assessment for the city of Scotts Valley's hazard mitigation planning, noting several areas for improvement including water management planning and staffing. Raini clarified that while Scotts Valley is a participating jurisdiction in the multi-jurisdictional plan, other local agencies like Central Fire and Santa Cruz have separate standalone plans. The team discussed feedback submission procedures, with Rodolfo identified as the new public works director and lead contact for the plan, and Erin confirmed that questions should be directed to Raini.

Countywide Risk Matrix Presentation

Raini presented a risk matrix organizing countywide priority hazards, explaining how different types of hazards are categorized and prioritized based on likelihood and impact. The group discussed the organization of hazards into categories like flood, extreme temperatures, severe weather, coastal hazards, and climate change, with specific focus on high and extreme priority levels. Jeremy and others confirmed the matrix was acceptable, and Raini explained the methodology used to determine hazard ratings, which considers probability of occurrence and potential impact. The conversation ended with a brief discussion about attendance and participation in previous meetings.

Hazard Problem Statements Review

The team reviewed hazard problem statements for earthquake, wildfire, and slope failure, with Raini explaining the impact, victim, and threat components for each. Jeremy confirmed no issues with the

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

earthquake statements, while Erin requested to review wildfire details further and suggested adding emergency access hindrance to slope failure. DP+S emphasized that problem statements are not final and can be modified during the administrative review process.

Climate Disparities and Infrastructure Vulnerabilities

Raini discussed the impacts of drought, flooding, severe weather, and extreme temperatures on the city, highlighting how these events disproportionately affect low-income households, renters, and mobile home residents. She emphasized the need for updated flood hazard mapping and stormwater capacity assessments, as well as improved vegetation management and utility hardening to reduce vulnerability to high wind events. Raini also noted that climate change is amplifying these natural hazards and increasing their frequency and intensity, particularly affecting elderly residents and those with limited mobility.

FEMA Hazard Mitigation Planning Discussion

Raini presented FEMA's six categories of hazard mitigation activities and discussed potential draft actions for Scotts Vallet priority hazards, including earthquake and wildfire. She emphasized the importance of local, regional, and state funding sources, as well as strengthening clarity, feasibility, and equity in planning. Raini outlined review criteria for the mitigation strategies, including whether actions are clearly defined, address priority hazards, are eligible for funding, benefit underserved populations, and can be implemented within current capacity. She also highlighted the need for collaboration opportunities with regional agencies to achieve broader benefits across the county.

Wildfire Mitigation Plan Collaboration

DP+S and Raini discussed wildfire mitigation actions and shared that the detailed implementation plan might not be included in the final document due to jurisdictional concerns. Erin was informed about a web app for reviewing plans and was offered a sample of a completed hazard mitigation plan from another agency. They also discussed the collaboration opportunities between the Fire Protection district and the city in the hazard mitigation plan, noting that the Fire Protection district cannot be the fiscal agent but can participate in the effort. Erin mentioned ongoing work with fire code amendments at the county level, and Raini highlighted various mitigation strategies for slope failures, drought, and climate resilience.

Interagency Collaboration and Road Data

The team discussed an upcoming August 4th meeting to identify interagency collaboration opportunities, with Erin confirming her attendance and agreeing to check with other fire districts for representation. Raini emphasized that the meeting would focus on collaborative efforts and highlighted the need for better communication regarding private roads and road data across the county. The team was reminded that their mitigation strategy homework, consisting of three attachments, is due on September 2nd, with an administrative draft review scheduled for late August to mid-September.

Scotts Valley BO 2 Summary 2



SCPD BO 2 Photo



SCPD BO 2 Read Ahead Packet 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column placeholder for SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE

In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:



- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.

2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.
3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County
Jurisdictional Breakout Meeting Series #2
Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3
SECTION 2. Capabilities Assessment 5
SECTION 3. Problem Statements 8
SECTION 4. Mitigation Actions 10

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda
B. Draft Capabilities Assessment
C. Draft Problem Statements
D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
    a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
    b. Are any concerns not reflected in at least one statement, either specifically or generally?
    c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
    d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Problem Statement Format

The Problem Statements are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), the AOC, and the problem description.

	A	B	C	D	E
1	**Hazard**	**Problem ID (Existing / New)**	**Area of Concern**	**Description**	**VALIDATION FIELD (Retain, Revise, Delete)**

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

Port District MJHMP Breakout Meeting #2

Tuesday July 15, 11:00 - 11:30 AM

Quick recap

The meeting focused on reviewing the Murray Street Bridge project's seismic retrofitting and discussing regional collaboration needs, including potential funding sources and improved interagency notification processes. The group evaluated the port's emergency preparedness capabilities, including their stormwater management, response procedures, and infrastructure challenges such as sedimentation and a significant sinkhole. The discussion concluded with plans for infrastructure improvements, including resilient dock retrofits and tsunami preparedness measures, while addressing challenges around access restrictions during hazardous conditions and the need for emergency backup power systems.

Next steps

- Port District: Develop and implement coastal hazard mitigation strategy, including wave run-up, surge, and coastal erosion measures
- Port District: Continue engineering and implementation of seawall replacement project with higher elevation specifications
- Port District: Continue phased implementation of steel piling replacements with HDP sleeves based on available funding
- Port District: Develop formal surge event response protocols and documentation for harbor users
- Port District: Consolidate and improve hazard communication strategies for both tsunami and storm surge events
- Blake: Work with engineering firm to complete wave modeling study for dock and infrastructure improvements
- Holland: Include hazard mitigation plan update in the written report for the upcoming commission meeting on the 22nd and send the report to DP+S
- Port District: Review and provide feedback on the hazard mitigation planning documents sent by DP+S by September 2nd
- Port District: Prepare key mitigation actions requiring regional collaboration to present at the August 4th meeting

SCPD BO 2 Summary 1

- Port District: Consider installation of permanent backup generator system for critical port facilities
- Port District: Assess and retrofit port buildings for earthquake resilience
- Port District: Continue collaboration with National Weather Service for storm surge forecasting and early warning
- Port District: Re-establish partnership with Arana Gulch Watershed Alliance to address sedimentation issues
- Holland: Send materials about dredging operations and sediment management to DP+S
- DP+S: Consolidate and update the mitigation actions document and send the updated Word version to Holland and Blake
- Port District: Document and track king tide water levels and flooding impacts across harbor facilities for sea level rise monitoring
- Holland & Blake: Prepare to discuss watershed management and emergency response coordination at the August 4th EOC meeting
- Holland/Blake: Review Admin draft document when released on August 28th
- All: Attend follow-up meeting on the 4th at EOC from 1-3 PM
- All: Review public release document by September 29th

Summary

Murray Street Bridge Retrofit Planning

The group discussed the Murray Street Bridge project, which is closed for three years for seismic retrofitting and upgrades. They reviewed a mitigation plan document and PowerPoint presentation, with a deadline of September 2nd for feedback. The discussion focused on identifying regional collaboration needs and potential funding sources, particularly for FEMA hazard mitigation funding. Holland emphasized the importance of improved interagency notification processes for quick-onset disasters. The team reviewed their capabilities matrix, which assesses planning, administrative, and fiscal capabilities, and discussed the need to complete the plan by October due to Watsonville's plan expiration.

Port Emergency Preparedness Review

SCPD BO 2 Summary 2

The meeting focused on reviewing the port's emergency preparedness and capabilities. Holland and Blake discussed their existing emergency response procedures, including a recent tsunami tabletop exercise involving county and city agencies. They confirmed having a stormwater pollution prevention program but lack formal engineering and public outreach capabilities. The port relies on rate increases and financing for major projects, with limited grant writing experience. DP+S noted that while the port has adequate operational funding, they would need to consider outreach and education capabilities for future mitigation planning.

Coastal Hazards Classification and Mitigation

The group discussed hazard classification and agreed to consolidate coastal hazards into a single category that includes wave run-up, surge, erosion, and tsunami, while separating flooding concerns. They clarified that the Port District experiences primarily coastal storm-related flooding rather than tributary flooding, and agreed to revise the terminology to reflect this distinction. The discussion focused on how to properly categorize and mitigate these hazards, with particular attention to impacts on infrastructure, victims (including harbor staff and residents), and increasing threat levels due to more frequent extreme weather events.

Port Sedimentation and Winter Operations

The discussion focused on the impact of storms and sedimentation on a port's operations, particularly during the winter crab fishing season. Blake explained that heavy rainfall from the San Lorenzo River and other tributaries brings sediment and debris into the port, making it difficult for large crab boats and other vessels to operate. Holland noted that the port requires annual dredging from November to April to manage the increased sedimentation, which has led to more frequent and costly dredging operations. The group also discussed how these issues affect commercial fisheries and other marine-related businesses in the area.

Port Infrastructure and Sinkhole Repair

The group discussed infrastructure challenges at a port, including a significant sinkhole caused by water movement that has impacted parking and launch ramps. Blake explained that while the sinkhole was likely caused by gradual sea water intrusion, recent storms exacerbated the issue. They also discussed ongoing engineering work to strengthen and replace docks, with plans to consider aluminum frame docks instead of concrete due to lateral pressure concerns. The conversation concluded with a discussion about potential sea wall or gate systems to reduce surge effects, though Blake expressed skepticism about the feasibility of a movable port wall.

Ports' Mitigation Strategy Refinement

DP+S discussed refining the ports' mitigation strategy, focusing on specific, measurable, and fundable actions tied to risk assessments. They emphasized the importance of equity-oriented actions and collaboration opportunities, particularly for vulnerable populations in marinas. Blake shared that the harbor currently lacks formal written protocols for surge event responses but relies on informal communication and weather forecasts. They decided to keep this action in the strategy, noting that while initial planning is mostly internal, additional support from OR3 might be needed during actual events.

Resilient Dock Retrofit Progress Update

The team discussed the progress and planning of a resilient dock and gangway retrofit project, which involves replacing pilings with corrosion-resistant materials and conducting wave modeling to assess harbor dynamics. Blake explained that steel pilings with HDP sleeves are being used, and engineering work is ongoing with a subcontracted firm focusing on wave modeling. Holland noted that while the project is further out than initially thought, they are making progress with the sea wall construction, and the team agreed to take victory laps for completed work while acknowledging that further engineering and design work will follow.

Dock Access and Sediment Management

The group discussed challenges with restricting access to docks during hazardous conditions, noting that despite extreme hazards, it's difficult to keep people away, even with law enforcement. They explored the idea of consolidating outreach efforts and considered implementing a sign system similar to forest fire danger ratings. The discussion also covered the port's sediment management strategy, where Holland explained that their current dredging operations are a bypass operation that places sediment back into the littoral cell to benefit down-coast beaches, though they are limited by regulatory permits in what they can do with the material.

Tsunami Preparedness and Signage Updates

The group discussed tsunami preparedness and signage in the area. They noted that new tsunami signs are being installed based on worst-case scenario studies, though sirens are not currently in place. Holland mentioned that the county and city rely on county interpretations for tsunami alerts. The conversation also covered debris management and sedimentation issues in the harbor, with Holland mentioning a previous partnership with the Orana Gulch Watershed Alliance that had since lapsed. They agreed to discuss these topics further at an upcoming meeting on August 4th.

SCPD BO 2 Summary 4

Port Backup Power Planning Meeting

DP+S discussed emergency backup power needs with Blake and Holland, noting their current small-scale backup systems and the need for a permanent generator solution. They explored potential impacts of drought on the port's fishing and tourism economy, though concluded this wasn't within their program's scope. The group agreed to keep climate change and sea level rise concerns in the plan, with Blake mentioning observed flooding in dock areas. DP+S outlined the next steps including an administrative draft review on August 28th and public release by September 29th, with a follow-up meeting scheduled for the 4th at the EOC.

SCPD BO 2 Summary 5



SCWD BO 2 Photo



SCWD BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE

In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.

2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.
3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3

SECTION 2. Capabilities Assessment 4

SECTION 3. Problem Statements 7

SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
   a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
   b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
   c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration

Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
    a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
    b. Are any concerns not reflected in at least one statement, either specifically or generally?
    c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
    d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Problem Statement Format

The Problem Statements are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), the AOC, and the problem description.

	A	B	C	D	E
1	Hazard	Problem ID (Existing / New)	Area of Concern	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim
Who is (most) impacted?

Example Statement
Older adults and people with mobility limitations lack adequate evacuation support.

Impact
What are the direct and indirect impacts of hazard events?

Example Statement
Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat
What local conditions create location-specific risk?

Example Statement
FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column placeholder for SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-jurisdictional HMP
Soquel Creek Water District, Breakout #2 Meeting Recap
Meeting Date: July 22nd, 2025 from 3PM-5PM

Summary

The team discussed the mitigation planning process, focusing on developing strategies for water infrastructure vulnerabilities and natural hazards affecting the district. They reviewed problem statements, capabilities, and potential mitigation actions, emphasizing the importance of coordinated efforts and prioritizing high-risk areas. The group also addressed legal considerations, reputational risks, and collaboration opportunities with neighboring agencies, while planning for upcoming meetings and deadlines in the mitigation plan development process.

Next steps

Soquel Creek Water District Team:

- Soquel Creek Water District Team: Present hazard mitigation plan update to Board of Directors on August 19th
- Skylar: Consolidate team's comments and feedback on the mitigation plan attachments and send to Ethan before August 4th
- Review and provide feedback on mitigation actions in Attachment D, particularly regarding priorities and collaboration opportunities
- Review and provide comments on problem statements and mitigation actions by September 2nd
- Attend the county breakout meeting on August 30th to discuss comments and mitigation actions
- Skylar: Send GPS data for Pure Water Soquel treatment facilities to include these points in the mapping tool
- Skylar: Identify and prepare mitigation actions that require collaboration with other agencies to present at the August 4th meeting
- Review and verify if slope failure was included in previous EPA vulnerability assessments
- Taj: Review and note vulnerable bridges with pipeline crossings for inclusion as mitigation actions
- Assess and validate the proposed implementation dates for mitigation actions in the draft plan
- Submit final homework and comments by September 2nd for admin draft review

DPS Team:

- Update mitigation actions database based on the team's feedback after September 2nd
- Send the PowerPoint presentation to Skylar for team review and comments
- Send the legal memo regarding governmental immunity and risk protection to the team
- Revise and clean up the mitigation actions document based on meeting discussion

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Revise and clean up the problem statements and mitigation actions document based on meeting discussion

Soquel Creek Water District Mitigation Planning and Timeline Review

The team discussed the mitigation planning process, with Ethan explaining they are in Phase 3 and working to develop a mitigation strategy. The group reviewed upcoming activities including a presentation to the board on August 19th, and Ethan outlined a tight timeline with key dates including September 2nd for team review, September 29th for public review, and October 31st for submission to Cal OES. Ethan emphasized that while jurisdictions can pursue grants independently, coordinated applications would be competitive, and explained that the county will disperse planning grant funds among jurisdictions.

Water District Risk Assessment Review

Ethan led a discussion on the assessment of problem statements, capabilities, and mitigation actions for a water district. He emphasized the importance of reviewing regulatory environments, fiscal capabilities, and educational outreach efforts. The team identified earthquake and fire as the district's primary hazards, with sea level rise and coastal erosion as secondary concerns. Ethan explained their approach to characterizing these hazards, focusing on impact, victims, and threats, and outlined their process for developing specific, measurable mitigation actions aligned with the district's capabilities. Ethan invited feedback from the group to refine the problem statements and mitigation strategies.

Water Infrastructure Emergency Preparedness

The group discussed water infrastructure vulnerabilities and emergency preparedness, focusing on fire hydrants, generators, and EV charging stations. Melanie highlighted the importance of backup power at pump stations and vehicle accessibility during emergencies, while Taj mentioned the need for coordination with Central Fire to improve response times. The discussion also touched on the city's wastewater treatment plant and purified water facilities, which are not considered critical for immediate water distribution but play a role in drought mitigation. The group agreed to further address these issues in an upcoming exercise on August 4th, considering whether the county or water district should take the lead on providing essential infrastructure like EV charging stations.

Natural Hazards in Water Infrastructure

The group discussed various natural hazards affecting water infrastructure, including flooding, earthquakes, and coastal erosion. They reviewed maps showing liquefaction risk areas and identified vulnerable facilities, such as production wells and water tanks. The team also discussed the need to consider vulnerable populations, particularly low-income residents, in disaster planning. They agreed to update the hazard assessment tool with additional data, including the location of water treatment

SCWD BO 2 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

facilities. The group planned to review potential mitigation actions and prioritize them for future implementation.

Mitigation Strategies Review and Planning

The team discussed the review and consolidation of problem statements and mitigation actions, with Skylar confirming they would collect and consolidate comments into SharePoint documents before the August 28 deadline. Ethan emphasized the importance of focusing on actionable, measurable mitigation strategies that align with high and medium priority hazards, particularly for water infrastructure and wildfire protection. The group agreed to review and prioritize mitigation actions, with Taj suggesting potential collaboration opportunities with neighboring water agencies and Central Fire District for mutual aid and training exercises.

Infrastructure Planning, Draft Planning, and Legal Protections

Ethan discussed plans for an upcoming meeting on August 4th, emphasizing the need to present draft information as a collaborative opportunity rather than finalized plans. He explained they would use a visual exercise involving hexagons to identify connections between mitigation actions and encourage inter-agency collaboration. Melanie raised concerns about including potentially unfeasible items that could create liability issues, prompting Ethan to clarify that the items were intended as draft concepts for discussion rather than firm commitments.

Ethan discussed legal protections for capital improvement plans and shared a 10-page memo with the team. He emphasized the importance of detailed planning and provided examples of vulnerabilities in various infrastructure plans. The group reviewed several action items, including updating flood and sea level rise vulnerability mapping, improving access to infrastructure on the beach, and integrating slope failure risk into planning documents. They also discussed collaboration opportunities with other departments and the need to review existing floodplain data and infrastructure planning.

Mitigation Plan Draft Review

Ethan presented a draft mitigation plan for review, explaining that while it meets the current budget constraints for the multi-jurisdictional environment, Skylar will have the opportunity to make edits before the August 4th meeting. The group discussed a new funding mechanism related to the Palisade fires, noting that while Melanie's jurisdiction isn't yet eligible due to pending plan status, they can still apply with a "pending" designation. Ethan committed to delivering the working draft to Skylar and mentioned that the plan will be included in a larger packet for the upcoming board meeting on September 2nd, with tables to be completed based on homework by August 28th.

SCWD BO 2 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Water District Interdependencies Map Review

Ethan and David discussed the development of a map showing water districts and their interdependencies, with a focus on recycled water usage for landscape purposes. David shared that his agency operates a tertiary treatment plant and distributes recycled water to parks, schools, and commercial areas. The group also touched on emergency preparedness plans and past consulting work, including a problematic facilities master plan. Ethan suggested preparing a brief overview for David's board meeting to explain the county-wide effort and upcoming public review process.

Hazard Mitigation Plan Legal Review

Ethan discussed reputational risks and legal implications of creating a hazard mitigation plan, emphasizing that while the document demonstrates due diligence, it's important to balance transparency with avoiding overly specific commitments. He explained that government entities typically have immunity from lawsuits related to infrastructure failures, and suggested sharing the memo with attorneys before legal review. The group discussed coordinating with neighboring cities like Santa Cruz on their existing plans, as Soquel Creek Water District currently lacks a comprehensive hazard mitigation document.

SCWD BO 2 Summary 4



SVWD BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE

In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.

2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.
3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3
SECTION 2. Capabilities Assessment 4
SECTION 3. Problem Statements 7
SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda

B. Draft Capabilities Assessment

C. Draft Problem Statements

D. Draft Mitigation Actions

SVWD BO 2 Read Ahead 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
   a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
   b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
   c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration

Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
    a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
    b. Are any concerns not reflected in at least one statement, either specifically or generally?
    c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
    d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Problem Statement Format

The Problem Statements are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), the AOC, and the problem description.

	A	B	C	D	E
1	Hazard	Problem ID (Existing / New)	Area of Concern	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim
Who is (most) impacted?

Example Statement
Older adults and people with mobility limitations lack adequate evacuation support.

Impact
What are the direct and indirect impacts of hazard events?

Example Statement
Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat
What local conditions create location-specific risk?

Example Statement
FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.
4. Provide feedback to the Consultant Team before or during the breakout meeting, or within one week following.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column placeholder for SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-jurisdictional HMP
Scotts Valley Water District, Breakout #2 Meeting Recap
Meeting Date: July 15th, 2024 from 1PM-3PM

Summary

The Dynamic Planning + Science (DPS) team reviewed document production work and source materials, including hazard information and administrative documents. The team then focused on reviewing and developing mitigation planning processes, discussing various hazards and infrastructure vulnerabilities while emphasizing the need for specific problem statements and measurable actions. The group explored water infrastructure challenges, including flood and seismic risks, and discussed potential improvements and regional collaborations, with particular attention to emergency preparedness and interdependent water systems. The group agreed on next steps for their mitigation strategy document, including individual review assignments and upcoming community outreach events, with a target completion date in early September.

Next steps

Scotts Valley Water District Team:

- Submit final homework and comments by September 2nd for admin draft review
- Prepare priority hazards and collaboration opportunities for August 4th countywide meeting
- Review and provide comments on remaining mitigation actions by first week of August
- Review Admin draft during the 2-week period in late August/early September
- Follow up with FEMA regarding funding for Glenwood Tank slope repair engineering and design
- Complete design and engineering plans for Glenwood Tank slope stabilization
- Verify if Sequoia Tank has earthquake restraints installed
- Evaluate tank replacement program for Villa Fontana and Northridge redwood tanks based on wildfire hazard risk
- Review water supply assessment for Town City project considering the remaining 45 acre-feet buffer in groundwater allocation
- Complete hydrant inspection, photography, and maintenance program for all hydrants by 2025
- Continue vegetation management and brush removal around tank sites and pump stations, including canopy reduction
- Continue collaboration with City of Santa Cruz regarding intertie usage for groundwater aquifer management during wet year
- Work with City of Scotts Valley on potential encroachment permit fee forgiveness for infrastructure projects
- Work with Fire District to update and align hydrant database and numbering system
- Hire interns/volunteers to conduct hydrant painting and maintenance work this summer

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

DPS Team:

- Revise and clean up the mitigation actions document based on meeting discussion
- Organize a social media push for plan review
- Look into possibility of developing a map showing water districts, interties, and water source dependencies
- Prepare a 5-minute presentation for the Water District Board about the hazard mitigation plan
- Revise and clean up the problem statements and mitigation actions document based on meeting discussion

Scotts Valley Water District Hazard Mitigation Plan Review

The team discussed the progress and next steps of the mitigation planning process, emphasizing the importance of aligning problem statements with capabilities assessments. They outlined upcoming events and resources available to participants, including a decision-maker briefing and access to the project website. The team also highlighted the ongoing development of the mitigation plan, including annexes and volumes, and stressed the importance of reviewing and certifying the capabilities assessment over the next 6 weeks

Hazards Mitigation Strategy Development

The group discussed the development of mitigation actions for various hazards, focusing on wildfire, earthquake, slope failure, and coastal hazards. They emphasized the need to define specific, measurable, and attainable problem statements for each hazard to enhance resilience. Ethan highlighted the importance of prioritizing high-impact hazards and consolidating existing plans to improve accountability. He also mentioned the need to consider the impact on critical infrastructure, vulnerable populations, and the intensifying frequency of certain hazards. Ethan invited feedback from the group to refine the problem statements and mitigation strategies.

Flood Resilience for Water Systems

The group discussed flood resilience concerns, particularly regarding the El Pueblo treatment plant, which is located in a 100-year flood zone. David confirmed they have two other treatment plants as backups, plus emergency interconnections with neighboring water agencies including San Lorenzo Valley Water District and Santa Cruz Water Department. Ethan noted that while elevated tanks are generally safe during flooding, pump stations in lower areas could be impacted, though Nate confirmed there are workarounds to bypass affected tanks. The discussion revealed that while 3.1 miles of water infrastructure and 41 critical assets are located in flood zones, the district lacks a formal flood resilience plan or detailed engineering studies for these sites.

SVWD BO 2 Summary 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Infrastructure Flood Risk Assessment

The team reviewed infrastructure assets and discussed flood risk concerns, with Ethan explaining that fire hydrants and water meters were not critical as they typically have bottom closures and are above ground. After examining the 41 identified assets, including PRVs and control valves, David confirmed there was minimal risk of flooding affecting these facilities, as they have workarounds and the impact would be low. The team agreed to adjust the risk assessment accordingly and decided to remove flood mitigation actions from their plan, though they noted earthquake risk would require different considerations.

Water Tank Seismic Vulnerability Assessment

The team discussed seismic vulnerabilities of water storage tanks, identifying that MacDorsa, Bethany, Sequoia, Mount Roberta, and Villa Fontana tanks require engineered evaluation and potential retrofitting due to structural vulnerabilities. They confirmed that Glenwood and Southwood tanks have earthquake restraints, while Sequoia's status needs verification. The group also addressed concerns about the Booster Station's aging generator, though David clarified it's well-maintained and a backup generator is available. David noted that ~60% of their system uses AC pipe, which performed poorly in the 1989 earthquake, and mentioned ongoing engineering work at Glenwood Tank to address slope stability issues, with potential FEMA funding.

Northridge Water Infrastructure Challenges

The group discussed water infrastructure challenges in Northridge, focusing on undersized redwood tanks installed in 2001 that are susceptible to burning. They explored drought impacts on groundwater resources, with David explaining that while drought doesn't directly affect the small tanks, it impacts groundwater levels and requires monitoring through the Santa Margarita Groundwater Agency. The discussion also covered potential water supply solutions, including an intertie with the City of Santa Cruz for surface water during wet years, and noted that while Paradise requires fire-resistant landscaping after fires, Northridge currently doesn't have similar requirements.

Water Infrastructure and Maintenance Planning

The group discussed infrastructure improvements and mitigation actions for water systems, focusing on fire hydrant maintenance, critical zone storage, and asset hardening. David and Nate reported ongoing efforts to upgrade and maintain fire hydrants, including recent database alignment with the fire district and plans for comprehensive inspections and maintenance. They identified potential collaboration opportunities with the city of Scotts Valley for encroachment permit fees and discussed the need for regional support on slope stabilization and drought mitigation efforts. Ethan emphasized the importance

SVWD BO 2 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

of preparing mitigation actions for the August meeting and encouraged the team to identify areas needing collaborative regional support.

Water District Interdependencies Map Review

Ethan and David discussed the development of a map showing water districts and their interdependencies, with a focus on recycled water usage for landscape purposes. David shared that his agency operates a tertiary treatment plant and distributes recycled water to parks, schools, and commercial areas. The group also touched on emergency preparedness plans and past consulting work, including a problematic facilities master plan. Ethan suggested preparing a brief overview for David's board meeting to explain the county-wide effort and upcoming public review process.

SVWD BO 2 Summary 4



Watsonville BO 2 Photo



Watsonville BO 2 Read Ahead 1

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Although you are welcome to make edits in any of these columns in Attachment D with tracked changes enabled, there is also a dedicated column for validating that the action is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SMARTIE



In developing Mitigation Actions, the principles of SMARTIE are used to ensure the hazard mitigation strategy is realistic and actionable. A Mitigation Action that meets these principles is:

- **Specific:** Clearly defined project scope and goals.
- **Measurable:** Outcomes and milestones can be tracked.
- **Attainable:** Designed to align with the agency's capabilities or those of partners.
- **Relevant:** Tied directly to risks identified in the plan.
- **Timely or Time-Bound:** Includes deadlines for completion.
- **Inclusive:** Intentionally involves or benefit diverse populations.
- **Equity Minded:** Prioritizes resources toward communities with greater risk or fewer adaptive capacities.

Mitigation Alternatives

Once hazard problems are defined (Problem Statements) and local resources and capabilities are accounted for (Capabilities Assessment), a range of mitigation solutions are identified that could be used to address concerns. These mitigation alternatives are evaluated for their associated costs and benefits to pinpoint which actions provide the greatest risk reduction using available resources and should be made part of the final mitigation strategy. The Consultant Team has drafted many Mitigation Actions to consider, including refined actions from the previous mitigation plan, as applicable, and new alternative actions. FEMA's six broad mitigation categories, listed below, provide the framework for identifying and evaluating potential mitigation actions.

- **Prevention (PRV):** Measures aimed at avoiding or minimizing hazard impacts through regulations and planning.
- **Property Protection (PPRO):** Actions to safeguard individual properties from hazard damage.
- **Public Education and Awareness (PE&A):** Efforts to inform and engage the public about hazard risks and mitigation strategies.
- **Natural Resource Protection (NRP):** Strategies that preserve, restore, or manage natural systems to reduce hazard impacts.
- **Emergency Services (ES):** Actions to enhance preparedness and response capabilities before, during, and after hazard events.
- **Structural Projects (SP):** Construction-based efforts designed to reduce hazard impacts.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

FEMA's six mitigation alternatives are summarized here for ease of reference. See the Mitigation Alternatives Handout from Planning Team Meeting #3 for additional guidance.

Prevention (PRV)	Planning / Zoning ordinances Stormwater and Drainage Management
Property Protection (PPRO)	Retrofitting (e.g., flood proofing, seismic) Buy Outs and Elevations
Public Education (PE&A)	Demonstration / Outreach Events Residential Mitigation Assistance
Natural Resource Protection (NRP)	Natural Floodplain Management Vegetation Management
Emergency Services (ES)	Warning Systems Evacuation Routes Analysis
Structural Projects (SP)	Stormwater Detention /Retention Utility Hardening

Mitigation Case Studies

In support of the drafted Mitigation Actions in Attachment D, below are several case studies of successful mitigation projects for high-priority hazards within Santa Cruz County. These case studies are provided as ideas for different potential projects and as examples of what kinds of mitigation activities have been funded in the past. Additional case studies and ideas are found in FEMA's Mitigation Action Portfolio and Mitigation Ideas publications.

Wildfire

1. **Implementing Fuel Breaks and Defensible Space in Butte County, California:** The Butte County Fire Safe Council established strategic fuel breaks and promoted defensible space around properties. This initiative involved clearing vegetation along roadways and around communities to create buffer zones, thereby reducing wildfire intensity near residential areas. The council collaborated with local residents to educate them on maintaining defensible space, significantly enhancing community resilience to wildfires.
2. **Enhancing Wildfire Mitigation through Ecosystem Protection in Berkeley, California:** The Claremont Canyon Conservancy collaborated with local agencies to remove eucalyptus trees and reforest with native species like coastal redwoods, enhancing wildfire resilience. This approach ensured that mitigation efforts were environmentally sustainable and supported the preservation of native species.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

3. **Community-Wide Comprehensive Wildfire Mitigation Program in Ventura, California:** The City of Ventura developed a Climate Action and Resilience Plan (CARP) in response to the 2017 Thomas Fire. This comprehensive plan guides day-to-day decision-making and serves as a long-term vision for the city as the climate changes. Key components of the plan include home-hardening programs, nature-based solutions, and community engagement strategies to enhance wildfire resilience.

Earthquake

1. **Seismic Vulnerability Retrofits in Berkeley, California:** In 2018, the City of Berkeley received a $1.2 million Hazard Mitigation Grant Program (HMGP) grant from FEMA to create a grant program for building owners to retrofit seismically vulnerable buildings to better withstand earthquake impacts. The program provides grants, paid out as reimbursements, for upgrades for certain types of commercial and multi-family residential buildings (including buildings with nonductile concrete, tilt-up, soft story, and unreinforced masonry) for up to 75% of design costs and up to 40% of construction costs. The program is designed to encourage property owners to be proactive, rather than reactive, in implementing seismic retrofits by offering direct compensation for a large percentage of total costs incurred to the building owner.

Slope Failure / Coastal Erosion

1. **Portuguese Bend Landslide Mitigation in Rancho Palos Verdes, California:** The City of Rancho Palos Verdes faced ongoing challenges due to the Portuguese Bend Landslide, affecting residential areas and infrastructure. In 2023, FEMA awarded a $23 million grant to the city for the Portuguese Mud/Landslide Community Infrastructure Resilience Project. The project focused on enhancing existing groundwater extraction systems and installing new subsurface water extraction systems to stabilize the landslide area, thereby protecting homes and infrastructure from further damage.
2. **Managed Retreat in Newtok, Alaska:** Progressive shoreline erosion along the Ninglick River, combined with permafrost degradation and seasonal storm flooding, began to seriously threaten the very land on Nelson Island that the Village of Newtok sits on. Erosion studies done for the Village found no permanent/cost-effective solution that would allow the village to remain in its current location. Therefore, in 2006, the Village formed a planning group to initiate the process of relocating to higher ground. The new site, called Mertarvik, is nine miles upriver from Newtok and infrastructure construction was completed in 2014. In lieu of building brand new housing, the Village decided to retrofit old military barracks from Joint Base Elmendorf-Richardson in Anchorage to serve as housing.

Flood / Coastal Storm

1. **Community Flood Risk Reduction in Galena, Alaska:** In 2013, flooding from the Yukon River inundated over 90% of Galena, Alaska, forcing evacuations and devastating infrastructure. In response, FEMA's Hazard Mitigation Grant Program (HMGP) and the State of Alaska launched a flood risk reduction and relocation initiative. Homes were elevated or moved to higher ground, while critical infrastructure like the power plant and school was reinforced. Flood-resistant housing incorporated structural retrofits, including reinforced foundations, flood vents, and improved drainage. A community-wide risk strategy was developed in partnership with FEMA and state agencies, integrating climate adaptation and long-term resilience. These efforts significantly reduced future flood risks and improved community safety.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

2. **Stormwater Infrastructure Upgrades in Taylorsville, North Carolina:** The town of Taylorsville, North Carolina, implemented nature-based and environmentally friendly flood mitigation improvements. The project included upgrading pumps and control panels at sewer pump stations, elevating electrical equipment, and fortifying exposed sewer pipes with natural materials.

High Wind

1. **Undergrounding Power Lines to Enhance Reliability in Corvallis, Oregon:** In Corvallis, Consumers Power Inc. (CPI) collaborated with local partners to relocate a problematic section of its 12,470-volt feeder line serving a healthcare complex, including Good Samaritan Hospital, from overhead to underground. This mitigation project, completed in 2003 with assistance from FEMA's Hazard Mitigation Grant Program (HMGP), significantly reduced power outages caused by winter storms, thereby enhancing the reliability of electrical service to critical facilities.

Drought

1. **Nature-Based Drought Mitigation in Shafter, California:** The City of Shafter implemented a nature-based solution to enhance groundwater recharge and mitigate drought risks. In partnership with local water districts, the city regraded approximately 200 acres into water storage and recharge basins, replenishing the Kern Groundwater Basin. This project helped secure water supplies for a primarily agriculture-based community, which relies entirely on groundwater for residential use.
2. **Aquifer Storage and Recovery in Salinas, Puerto Rico:** The municipality of Salinas developed an aquifer storage and recovery (ASR) strategy to ensure long-term water security during severe droughts. This project involved storing excess water in natural aquifers during periods of abundance for use during droughts, providing a reliable water source for the community.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County

Jurisdictional Breakout Meeting Series #2

Read-Ahead Packet

CONTENTS

SECTION 1. Meeting Purpose & Overview 3
SECTION 2. Capabilities Assessment 4
SECTION 3. Problem Statements 7
SECTION 4. Mitigation Actions 9

ATTACHMENTS

A. Breakout Meeting #2 Details & Agenda
B. Draft Capabilities Assessment
C. Draft Problem Statements
D. Draft Mitigation Actions

Watsonville BO 2 Read Ahead 2

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 1. MEETING PURPOSE & OVERVIEW

Jurisdictional Breakout Meeting Series #2

Breakout Meeting Series #2 is part of Phase 3, *Develop the Mitigation Strategy*, which is the most important phase of developing the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). These breakout meetings focus on taking all the information we've previously gathered, discussed, and analyzed, and using it to build an actionable mitigation strategy that addresses the highest priority hazard problems and greatest areas of concern; aligns with community feedback and jurisdictional capabilities; and considers opportunities for multi-jurisdictional collaboration.

See Attachment A for jurisdiction-specific breakout meeting details, including date, time, location, and agenda. Each breakout meeting will include group discussion on these components, which are detailed in this read-ahead packet to facilitate that dialog.

At the end of Breakout Meeting #2 for each jurisdiction, participants will:

- **Understand and Have Consensus on Jurisdictional Capabilities** in implementing their unique mitigation strategy to address jurisdiction-specific problems and support regional collaboration (see SECTION 2 and Attachment B).

- **Understand and Have Consensus on Jurisdictional Problem Statements** which describe the area(s) of concern (victim, impact, or threat) for high-priority hazards and specific risks that were identified through the risk assessment process, community feedback, and prioritization exercise from Breakout Meeting #1 (see SECTION 3 and Attachment C).

- **Understand and Have Consensus on Jurisdictional Mitigation Actions** that align with local capabilities, community-driven priorities, and FEMA guidelines; address specific problem statements; follow the SMARTIE guidelines and are cost- and resource-effective; and support inter-agency collaboration (see SECTION 4 and Attachment D).

Please return all comments to the Consultant Team by Tuesday, September 2, 2025

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 2. CAPABILITIES ASSESSMENT

Attachment B contains a jurisdiction-specific Capabilities Assessment that was drafted by the Consultant Team and your jurisdiction's lead contact. There are two types of Capabilities Assessment, depending on the type of jurisdiction: Municipal and Special District. Each looks at planning, regulatory, administrative, technical, fiscal, and education and outreach capabilities.

Instructions for Capabilities Assessment Review

1. Review Attachment B prior to the scheduled breakout meeting. In reviewing your assessment, consider the following:
    a. Are all types of capabilities captured for your jurisdiction? Are any missing? Are there any unique capabilities that should be added to the list?
    b. Are all the currently employed capabilities identified accurately? Does any information need to be updated?
    c. In the "HMP Integration" columns, are the status, current mitigation usage, and future usage opportunity correctly captured for that capability?
2. In reviewing and editing in Attachment B, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Capabilities Assessment Format

The Capabilities Assessment is formatted into a table with columns identifying the capability category or type of resource and the status of the capability in hazard mitigation planning. A heading and subheading introduce each category of capabilities above the list of general types (e.g., Planning and Regulatory, Construction and Future Development Regulations).

	A	B	C	D	E
1		HMP Integration			
2	Resources for Hazard Risk Reduction	Status	Current Mitigation Use	Future Opportunity	VALIDATION FIELD (Notes / Links / Corrections)
3	Planning and Regulatory Capabilities				
4	Construction and Future Development Regulations				

There is also a dedicated column for validating that the capability and its status are accurate, or for noting needed revisions or any additional helpful details, such as web links to more information about the resource. Only the validation field column should be edited.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Hazard Mitigation Planning Integration Status

Each assessment lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present in the first place and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

HMP Integration		
Status	Current Mitigation Use	Future Opportunity
Status: Currently in use or present. **Current Use:** Used widely for mitigation. **Future Opportunity:** Opportunity to expand and integrate.		
Status: (Sort of) Seldomly used or limited presence. **Current Use:** Limited use in mitigation planning. **Future Opportunity:** Limited opportunity to expand and integrate.		
Status: (No) Not present or available. **Current Use:** Not used in mitigation planning. **Future Opportunity:** No opportunity to expand or integrate.		

Municipal Capabilities Assessments

Municipal Capabilities Assessments provide an overview of a municipality's capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a municipality within each major category are provided below.

Planning and Regulatory	▪ General plans, CIPs, EOPs, CWPPs, growth management plans, and hazard-specific plans ▪ Building and development codes ▪ Zoning and subdivision regulations ▪ Floodplain and other hazard-specific ordinances ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, building, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Utility and service fees ▪ Levy taxes and special tax bonds ▪ CDBG grants and CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Local citizen or community-based hazard groups, CERTs, and Fire Safe Councils ▪ Regular public safety or preparedness events ▪ Hazard planning desk and technical assistance

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Special District Capabilities Assessments

Special District Capabilities Assessments provide an overview of a special district's unique capabilities, as authorized by federal and state law. Although this is not an exhaustive list, examples of capabilities that might be applicable to a special district within each major category are provided below.

Planning and Regulatory	▪ CIPs, CWPPs, emergency response plans, and hazard-specific plans ▪ Stormwater management and seismic safety programs
Administrative and Technical	▪ Planning, facilities, engineering, and information systems staff ▪ Dedicated emergency management, grant management, and public outreach staff ▪ GIS and data analysis ▪ Emergency warning systems and services
Fiscal	▪ Service fees ▪ Levy taxes and special tax bonds ▪ CIP funding ▪ Withheld spending in hazard-prone areas
Education and Outreach	▪ Dedicated webpages, social media accounts, and newsletters ▪ Partnerships with RCDs, Fire Safe Councils, or other hazard-focused organizations ▪ Regular public safety or preparedness events

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 3. PROBLEM STATEMENTS

Attachment C contains jurisdiction-specific Problem Statements that were drafted by the Consultant Team based on all the information previously gathered and discussed. These statements describe problems associated with different hazards in the community and unique conditions that need to be mitigated to reduce risk. They also describe which Area of Concern (AOC), in terms of victim, impact, and threat, is most relevant to the statement.

Instructions for Problem Statement Review

1. Review Attachment C prior to the scheduled breakout meeting. In reviewing your statements, consider the following:
   a. Do the statements capture your jurisdiction-specific concerns about priority hazards?
   b. Are any concerns not reflected in at least one statement, either specifically or generally?
   c. For each statement, is it in the correct hazard group and does it align with the correct AOC?
   d. For each statement, does it clearly and concisely describe what the concern is?
2. In reviewing and editing in Attachment C, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Problem Statement Format

The Problem Statements are sorted by hazard and formatted into a table with columns identifying the hazard, the AOC, a unique identification number and if it is existing or new (as applicable), and the problem description.

Wildfire

Hazard	Area of Concern	Problem ID (Existing/New)	Description	VALIDATION FIELD (Retain, Revise, Delete)

Although you are welcome to make edits in any of these columns in Attachment C with tracked changes enabled, there is also a dedicated column for validating that the statement is relevant and should be retained, or for noting any needed revisions, including deletion if not relevant.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Interpreting Areas of Concern (AOCs)

Areas of concern describe how hazards impact different aspects of a community and set the stage for identifying mitigation actions that reduce risk by changing the victims, impacts, or threats of different hazards. Each problem statement in Attachment C identifies which type of hazard problem (i.e., AOC) it concerns the most.

Victim

Who is (most) impacted?

Example Statement

Older adults and people with mobility limitations lack adequate evacuation support.

Impact

What are the direct and indirect impacts of hazard events?

Example Statement

Aging assets such as culverts decrease stormwater conveyance capacity and increase road vulnerability during heavy rain events.

Threat

What local conditions create location-specific risk?

Example Statement

FEMA floodplain maps do not reflect localized or future flood conditions, limiting the ability to plan for or fund effective mitigation.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

SECTION 4. MITIGATION ACTIONS

Attachment D contains jurisdiction-specific Mitigation Actions that were drafted by the Consultant Team based on all the information previously gathered and discussed, including the previous mitigation plan, if applicable; the Capabilities Assessment in Attachment B; and the drafted Problem Statements in Attachment C. Mitigation Actions describe what your jurisdiction plans to do to address one or multiple Problem Statements utilizing the resources available, including those identified in the Capabilities Assessment.

Instructions for Mitigation Action Review

1. Review Attachment D prior to the scheduled breakout meeting. In reviewing your actions, consider the following:
    a. If applicable, are any of the existing actions from the previous mitigation plan completed or that should be cancelled because they are no longer relevant?
    b. Does each action address at least one Problem Statement? Are any actions missing that are needed to address high-priority issues?
    c. Are there any actions that are unnecessary, or that don't address a Problem Statement?
    d. Do the actions follow SMARTIE guidelines and are they matched to your jurisdiction's capabilities? Are there any actions completely out of reach for implementation, even if funding was secured?
    e. Are there opportunities to collaborate with local and regional partners on any of the actions for more efficient or effective implementation?
2. In reviewing and editing in Attachment D, make sure tracked changes is enabled.
3. Note any information that needs to be updated (missing, not relevant, etc.). You can make these notes in the attachment or a separate document, verbally during the breakout meeting, or in the body of an email to the Consultant Team.

Background Information

Mitigation Action Format

The Mitigation Actions are formatted into a table with columns identifying the hazard, a unique identification number and if it is existing or new (as applicable), a short title for the action, the action description, the type of mitigation alternative it is, its implementation priority, and the Problem Statements it aims to address. In addition, there is a column for defining SMARTIE principles that will be assigned to the action once it is validated, to include, for example, actionable objectives, responsible parties, and timelines in the final strategy. For now, the SMARTIE column contains preliminary information.

	A	B	C	D	E	F	G	H	I
1	Hazard	Action ID (Existing / New)	Action Title	Description	SMARTIE IMPLEMENTATION	Selected FEMA Mitigation Alternative(s)	Priority	Problems Addressed	VALIDATION FIELD (Completed, Cancel, Retain, Revise)

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Santa Cruz County Multi-jurisdictional HMP
City of Watsonville, Breakout #2 Meeting Recap
Meeting Date: July 14th, 2024 from 1PM-3PM

Summary

The Dynamic Planning + Science (DPS) team reviewed key hazard mitigation related documents for City of Watsonville, focusing on capabilities assessment, problem statements, and community outreach planning. They discussed various hazard profiles and vulnerabilities, including fire prevention, flood risks, and high heat concerns, while examining jurisdictional limitations and coordination between city and county resources. The group agreed on next steps for their mitigation strategy document, including individual review assignments and upcoming community outreach events, with a target completion date in early September.

Next steps

City of Watsonville Team:

- Submit final homework and comments by September 2nd for admin draft review
- Prepare priority hazards and collaboration opportunities for August 4th countywide meeting
- Review and provide comments on remaining mitigation actions by first week of August
- Review Admin draft during the 2-week period in late August/early September
- Update flood mitigation action to separate wastewater treatment plant flood-proofing from other facilities
- (Joseph)Research and verify the current count and status of unreinforced masonry buildings in Watsonville
- (Justin)Provide additional details about police station relocation possibilities from Downtown Specific Plan
- (Justin/Building Team) Revise seismic retrofit program goals and timeline to be more realistic and feasible
- (Charles) Review the mapping components for the hazard mitigation plan
- (Leslie) Review and adjust green infrastructure goals to target 10 new features by 2030
- (Toto)Collect and consolidate all team members' comments on the capabilities assessment document and send to DP+S team
- (Toto)Schedule a 45-minute follow-up meeting to discuss remaining mitigation actions

DPS Team:

- Update the capabilities assessment to reflect Justin's suggested reordering of planning and regulatory items
- Revise problem statements to consistently refer to the Pajaro River system throughout the document
- Remove references to agricultural workers from heat-related hazards in Watsonville's specific plan and move to county-level documentation

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

- Update the earthquake problem statement EQ-05 to include highways in the infrastructure impact list
- Pull out Watsonville-specific public survey results regarding priority hazards
- (Rainy) Send PowerPoint file to Toto with marker indicating where the group left off

Watsonville Hazard Mitigation Plan Review

The team discussed the Read Ahead packet for Watsonville's hazard mitigation plan, focusing on capabilities assessment and problem statements. They reviewed the schedule for upcoming community outreach events and administrative draft review. The group examined the capabilities assessment document, with Justin suggesting a reordering of planning and regulatory sections. Tom mentioned Watsonville's ISO rating of 2 and discussed the evolving nature of ISO ratings in the insurance industry. The team agreed to collect comments on the capabilities assessment through a shared document, with Toto offering to serve as the central coordinator.

Fire Prevention and Emergency Roles

The group discussed fire prevention and emergency management roles, with Tom explaining that while the fire department handles plan reviews through consultants, they don't have staff to conduct fire mitigation activities which fall under public works. Tom and Toto clarified that the fire department is not the main coordinator of emergency services, as the city manager and Ronel's office handle that role, though they may participate in county EOC functions through a liaison. Ethan noted that he had analyzed wildfire-related code requirements and would share the triggering events with Joseph, who confirmed they have a roof rating requirement but needed to verify its scope.

Floodplain Administrator Role Clarification

The team discussed the floodplain administrator role, clarifying that while the building official typically fills this position, the city manager's designee, who is engineering staff, currently holds the role. They reviewed education and outreach capabilities, noting that while Christy's team handles compliance and messaging, some programming remains decentralized. The group agreed to develop an implementation plan for the hazard mitigation effort, with a focus on coordinating between the city and county resources, and planned to discuss this further at the August 4th meeting.

Watsonville Hazard Prioritization Discussion

The group discussed hazard profiles, focusing on Watsonville's priority hazards and their prioritization from medium to extreme risk. They agreed to include high heat as a sub-hazard under climate change, though there was some debate about its frequency and impact. Ethan provided the National Weather Service's definition of high heat, which the group used to assess its likelihood in Watsonville. While some participants felt high heat was unlikely to occur, Tom suggested re-evaluating the definitions of "unlikely" and "possible" based on ISO standards. The group agreed to further consider this perspective.

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

Watsonville Hazard Assessment Review

The group discussed hazard assessments and problem statements for Watsonville, focusing on high heat concerns and flood risks. They reviewed public survey feedback about hazards, with high heat emerging as a significant concern for both residents and agricultural workers. Ethan and Raini agreed to analyze Watsonville-specific data, while Chris emphasized the importance of distinguishing between city responsibilities and those outside their jurisdiction. The team also discussed slope failure issues and reviewed problem statements categorized by impact, victim, and threat, with flood being identified as Watsonville's top priority hazard.

Addressing Vulnerabilities in Pajaro Watershed

The group discussed how to address vulnerabilities of unhoused populations and agricultural workers in the Pajaro River watershed. They agreed to modify the language around unhoused populations to focus on elderly residents and others in the area, while including all residents in the description of flood risks. The team also decided to keep a problem statement about extreme heat impacts on agricultural workers, recognizing the employment disruptions caused by weather events. Ethan mentioned similar economic impacts affecting the port due to fishing and drought conditions.

Watsonville's Jurisdiction and Natural Disasters

The team discussed Watsonville's jurisdictional limitations, particularly regarding heat-related issues for farm workers, agreeing that such concerns fall under county rather than city responsibility. They aligned on making the language consistent throughout the document when referring to watershed or river systems, whether using specific creek names or referring to the broader network. The discussion also covered earthquake impacts, with Tom highlighting how Highway 1 was completely cut off during the 1989 earthquake within city limits, while the 2023 levee breach affected the highway system in the county area.

URM Inventory Assessment in Watsonville

The meeting discussed the lack of a formal program to inventory and evaluate unreinforced masonry buildings (URM) in Watsonville, with Joseph agreeing to research the issue further. Matt found an existing URM list from 2012-2013 containing 8 buildings, though most of these were not downtown. The group acknowledged that while some older masonry buildings may have been destroyed in the 1989 earthquake, there could still be unreinforced structures that need evaluation and potential seismic retrofitting.

Agricultural Workers in Disaster Planning

The group discussed how to address agricultural workers' needs in their disaster planning, with Tom and Ethan agreeing that city residents affected by employment disruptions should be included, even if the events occur outside city boundaries. They explored the compounding effects of climate change, particularly the sequence of water and wind events, and discussed the need to factor in these complex interactions in their mitigation planning. Justin suggested expanding the slope failure section to include

Watsonville BO 2 Summary 3

SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

neighborhoods along slough systems and clarified that the rural and fringe area residents refer to those in unincorporated Santa Cruz County served by city utilities.

Flood Mitigation and Justice Planning

The team discussed flood mitigation actions and environmental justice elements in their general plan update. Justin explained that while they had previously worked on an environmental justice element in 2020, they are now incorporating relevant topics into the draft 2050 general plan update. Raini presented six FEMA-prescribed mitigation alternatives and emphasized the importance of considering regional collaboration opportunities with partner agencies for meeting on August 4th. The group agreed to use the same format for the upcoming large group meeting as their first packet, focusing on identifying highest priority hazards and potential collaborative opportunities.

Flood-Proofing Infrastructure Planning

The group discussed flood-proofing measures for various facilities, including the wastewater treatment plant, police station, and emergency shelters. Justin suggested exploring options for relocating the police station to a higher ground during its planned rebuild, while Ethan emphasized the importance of demonstrating a clear nexus between the hazard and the building's lifecycle for funding purposes. The team agreed to update the action items and send the final Excel version to Toto, with Raini offering to share the PowerPoint file for further reference.

Watsonville Seismic Retrofit Strategy

The group discussed seismic retrofitting goals for Watsonville, with Joseph cautioning that mandatory retrofit programs could be expensive and lead to building demolitions, suggesting instead to focus on incentivized programs. Toto proposed revising the goal from specific building numbers to a percentage of prioritized at-risk sites, while Ethan suggested focusing on residential structures first. Justin highlighted collaboration opportunities with Caltrans regarding roads and bridges outside city jurisdiction, and Ethan proposed creating a committee to share California Building Code amendments and compare notes with other cities' retrofit programs.

Mitigation Strategy Document Review Plan

The team discussed next steps for their mitigation strategy document. Toto suggested sending Raini the PowerPoint file with comments up to slide 27, allowing time for individual review and comments by early August, followed by a brief final meeting to address the remaining slides. The group agreed to this approach, with Tom and others preferring individual assignments while acknowledging the value of a collective review. Raini reminded them of upcoming community outreach events, a county-wide group meeting, and a decision maker briefing, with the homework due September 2nd and an admin draft review scheduled for late August or early September.

Watsonville BO 2 Summary 4

PAGE INTENTIONALLY BLANK

Public Notice & Press Release Documentation

Appendix B.2

PAGE INTENTIONALLY BLANK

Fw: Spring Updates

From: Santa Cruz County Office of Response, Recovery & Resilience <or3staff@santacruzcountyca.gov>
Sent: Tuesday, March 11, 2025 7:59:58 PM
To: Clare Peabody <Clare.Peabody@santacruzcountyca.gov>
Subject: Spring Updates

****CAUTION:**This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.****

View this email in your browser

SANTA CRUZ COUNTY OFFICE OF RESPONSE, RECOVERY & RESILIENCE

Important ReCoverCA Program Announcement

The California Department of Housing and Community Development has announced that applications for its 2020 and 2021 ReCoverCA Housing Programs will close on April 15, 2025.

ReCoverCA's 2020 Owner-Occupied Rehabilitation and Reconstruction (OOR) and 2021 Single-Family Reconstruction (SFR) Programs offer eligible single-family homeowners grants of up to $500,000 to rebuild homes damaged or destroyed in qualifying 2020 and 2021 disasters.

If you were a resident of Santa Cruz County in 2020, you could be eligible. Additional information, including eligibility guidelines and resources to help complete the application, are available on the ReCoverCA website: www.hcd.ca.gov/grants-and-funding/recoverca.

RESOURCE CONSERVATION DISTRICT OF SANTA CRUZ COUNTY

RCD Spring Chipping Program

Registration begins for all eligible Santa Cruz County residents on April 1st and runs through April 30th. Members of FireWise Communities may sign up a week early, starting March 25.

This program offers no-cost chipping to eligible Santa Cruz County residents for material in the defensible space zone. Sign up for program alerts and learn more here.

Multi-Jurisdictional Hazard Mitigation Plan Development Underway

📢 **Have your say!** Fill out the community survey to provide feedback on hazard risks and mitigation priorities: Survey Link https://mitigatehazards.com/santacruzmjhmp/

Santa Cruz County is developing a **Multi-Jurisdictional Hazard Mitigation Plan (MJHMP)** to enhance community resilience against natural disasters. Funded by a FEMA grant and led by the **Office of Response, Recovery, and Resilience**, this collaborative effort includes nine participating jurisdictions, such as the cities of **Scotts Valley, Capitola, and Watsonville**, along with several local water districts and agencies. The plan identifies local natural hazards, assesses their potential impacts, and outlines strategies to **reduce long-term risks** to infrastructure, property, and the environment.

Updating the MJHMP every five years is essential for maintaining eligibility for **federal Hazard Mitigation Assistance (HMA) grants**, which support proactive disaster prevention efforts. Community input is a vital part of this process—residents can help shape the plan by sharing their experiences and concerns.

Fill out the community survey to provide feedback on hazard risks and mitigation priorities: Survey Link https://mitigatehazards.com/santacruzmjhmp/

For more information, visit the project website: mitigatehazards.com.

OR3 Spring Updates

Share your concerns about fires and other hazards!

Santa Cruz County is conducting a Hazard Mitigation Survey. Make your voice heard.
English.
Español.
***Hazard mitigation** is the use of sustained, long-term actions to reduce the loss of life, personal injury, and property damage that can result from a natural disaster.*

Survey Advertisement on Regeneración Partner Website-Newsletter 4-2-25

Nextdoor HMP Posting



SCCo Facebook Posting



SCCo Instagram Posting



SCCo X Posting Spanish



SCCo X Posting

Survey Advertisement on Scotts Valley Facebook 4-10-25

Outlook

Santa Cruz County MJHMP - March Steering Committee Update and SURVEY LAUNCH!

From Clare Peabody <Clare.Peabody@santacruzcountyca.gov>

Date Mon 3/3/2025 9:41 AM

To David Reid <David.Reid@santacruzcountyca.gov>; Toto VuDuc <toto.vuduc@watsonville.gov>; Courtney Lindberg <courtney.lindberg@watsonville.gov>; Kahn, Jessica <jkahn@ci.capitola.ca.us>; Herlihy, Katie (kherlihy@ci.capitola.ca.us) <kherlihy@ci.capitola.ca.us>; Carly Blanchard <cblanchard@scottsvalley.gov>; Taylor Bateman <tbateman@scottsvalley.gov>; Skyler Murphy <skylerm@soquelcreekwater.org>; Soquel Water Shelley Flock <shelleyf@soquelcreekwater.org>; David McNair <DMcNair@svwd.org>; Nate Gillespie <ngillespie@svwd.org>; Lisa Lurie <llurie@rcdsantacruz.org>; Brian Lockwood <lockwood@pvwater.org>; maclaurie@santacruzharbor.org <maclaurie@santacruzharbor.org>; Luis Toledo <lutoledo@cabrillo.edu>; Julia Charles <jucharle@cabrillo.edu>

Cc Jason Hoppin <Jason.Hoppin@santacruzcountyca.gov>; Ethan E. Mobley <ethan@dynamicplanning.co>; Brian Greer <Brian@dynamicplanning.co>

Hello Santa Cruz County MJHMP Steering Committee,

I hope this finds you well! Thank you for your attendance at Planning Committee Meeting # 1 last month and for your engagement in the planning process so far. I want to provide a quick update on where we are in the MJHMP process and what's coming next. As **Steering Committee representatives**, you are the leads for your jurisdictions and the liaison to our consultant team. If you need a recap on Meeting # 1, you can find all materials on the project website:

Stakeholder Resources
Password: SantaCruz2025

Schedule Update

- **March 27:** Planning Committee Meeting #2 (In person @ EOC) / *TOPIC: Hazard Mapping & Community Vulnerabilities*
- **April – May** (following Meeting # 2): Round 1 of **jurisdiction-specific breakout sessions**
- **Early June** (tent. June 2): Planning Committee Meeting # 3 (Location TBD) - / *TOPIC: Mitigation Strategy Development*
- **June–July:** Second round of **breakout sessions** to refine strategies for each jurisdiction
- **Late July** (tent. July 31): Planning Committee Meeting # 4 - Final plan review
- **October 2025:** Final draft plan submission to CalOES/FEMA

Survey Launch & Media Kit

We are ready to launch the **public survey** to gather input on community hazard concerns. We have prepared press releases and social media materials to promote survey participation in both English and Spanish. Please help distribute these within your networks. Custom branded media graphics for each jurisdiction have been developed and can be downloaded here: **Santa Cruz Survey Media Kit Download** Also feel free to re-share the County's posts across social platforms (coming early this week!).

Next Steps: Breakout Sessions and Ongoing Outreach

- Here is the point at which I hand off to the DP+S team! Our consultant team will be reaching out to each of you next week directly to coordinate the **press release** for the public survey; as well as schedule a **breakout session** following PC2 specific to your jurisdiction.

Survey HMP Participant Blast_Part1

- Additionally, over the next few months we will be identifying **outreach opportunities** at public events such as Farmers' Markets, resource fairs, etc. to share more information about the plan, share preparedness/mitigation resources, and promote the survey to the wider community. Have an idea for a standalone public event / workshop? Have an event on the calendar and want to promote the HMP or get some OR3 representation? Reach out to me directly and let's coordinate!

Thank you all, and let me know if you have any questions. Looking forward to seeing you all at Planning Committee Meeting # 2 next month, March 27th at the EOC.

Sincerely,
Clare

Clare Peabody | Emergency Services Analyst (she/her)
SANTA CRUZ COUNTY OFFICE OF
RESPONSE, RECOVERY & RESILIENCE
clare.peabody@santacruzcountyca.gov
831.588-9584 (cell)
Website

Survey HMP Participant Blast_Part2

Press Release

Santa Cruz County staff and key stakeholders are updating the current Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). The goal of the planning effort is to revisit natural hazard information and update the 2021 plan to account for changes in population and occurrences of natural disasters in the planning area. This effort is two-fold; it assists in reduction of repetitive damages to community infrastructure and the county will maintain eligibility for grants under Federal Emergency Management Agency's (FEMA) Hazard Mitigation Assistance program.

The county's hazard mitigation plan provides a formal explanation of prevalent hazards within the county and how hazards may affect communities differently. Most importantly, the mitigation strategy presented in the plan responds to the known vulnerabilities within each community and provides prescriptions or actions to achieve the greatest reduction of natural hazard risk. The result of this planning effort could save lives, reduce injury and property damage, and protect the environment in the event of a natural hazard within the county.

The planning effort includes analysis of natural hazards within unincorporated county areas and the incorporated City of Scotts Valley, City of Santa Cruz, City of Capitola, and City of Watsonville. Also assisting in the planning effort are the special districts Soquel Creek Water District, Scotts Valley Water District, Pajaro Valley Water Management Agency, Resource Conservation District of Santa Cruz County, Santa Cruz Port District, and Cabrillo College which are incremental in their knowledge and capacity of managing local water and other natural resources.

Over the coming months the county stakeholders will finalize newly developed mitigation action strategies based upon stakeholder and public consensus.

For more information on the planning effort or the survey please visit
https://mitigatehazards.com/santacruzmjhmp/

Press Release SCC HMP_Part1

Social Media Post

☀️ **Your Voice Matters, Santa Cruz County!** ☀️

We're updating the Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) to better prepare our communities for natural disasters. This plan helps save lives, protect property, and reduce damage from future hazards.

📢 We need YOUR input! Share your thoughts to shape strategies that make a difference in your community. Whether you live in Santa Cruz, Scotts Valley, Capitola, Watsonville, or an unincorporated area, your feedback is essential.

🔗 **Take the survey now**: https://mitigatehazards.com/santacruzmjhmp/

Together, we can build a safer, more resilient Santa Cruz County! 💪 🌎

#SantaCruzCounty #HazardMitigation #CommunitySafety #PublicInput #FEMA #DisasterPreparedness

Sample Image, use provided PR_Survey_Information.jpg

Press Release SCC HMP_Part2

PR_Survey_Information_Social Image Spanish (1)

PR Survey Information Social Image Spanish

WHAT IS MITIGATION?

Hazard mitigation *means reducing risks from disasters—before they happen.* From home repairs to public infrastructure upgrades, mitigation means protecting people, property, and our way of life.

WHY IT MATTERS

Santa Cruz County is unique in its geography, history, and exposure to **many different types of hazards.** Our mitigation strategies must address:

Tsunami • Wildfire • Flooding
Coastal Erosion • Landslides
Earthquake • Drought
Extreme Heat • High Winds
Coastal Storms

WHO'S RESPONSIBLE?

- **Public agencies** handle large-scale projects—like road upgrades, drainage improvements, vegetation management, and slope stabilization.
- **Property owners & renters** can take steps to protect their homes and land—such as retrofitting, buying insurance, or clearing brush.

WHAT'S A HAZARD MITIGATION PLAN (HMP)?

The **HMP** is Santa Cruz County's roadmap for reducing disaster risk, which gets updated every 5 years. The County is currently updating the HMP in partnership with local cities / agencies, and we want to hear your concerns and priorities when it comes to mitigation.

➜ Take the survey to inform the plan!

HMP SURVEY LINK

SANTA CRUZ COUNTY OFFICE OF RESPONSE, RECOVERY & RESILIENCE

Participating Jurisdictions

City of Scotts Valley
City of Capitola
City of Watsonville
Scotts Valley Water District
Soquel Creek Water District
Pajaro Valley Water Management Agency (PVWMA)
Santa Cruz Port District
Resource Conservation District (RCD) of Santa Cruz County
Cabrillo College

What is Mitigation Handout 1

What is Mitigation Handout 2

We Need Your Input for Local Hazard Mitigation!

Santa Cruz County is unique in its geography, history, and exposure to many different types of hazards including **Tsunamis, Wildfires, Flooding, Coastal Erosion, Landslides Earthquake, Drought, Extreme Heat, High Winds and Coastal Storms.**

The **Hazard Mitigation Plan (HMP)** is Santa Cruz County's roadmap for reducing disaster risk, which gets updated every 5 years. The County is currently updating the HMP in partnership with local cities and agencies like the RCD, and we want to hear your concerns and priorities when it comes to mitigation.

The RCDs conservation work and hazard mitigation/preparedness assistance are intimately connected through our recognition that **healthy ecosystems can reduce the impact of natural disasters and enhance community resilience.** We are part of a multi-jurisdictional collaborative process across the County working to develop a comprehensive mitigation plan that serves all or our residents and the natural resources that support us. Your voice is an integral part of the process.

Please click HERE now **to take the survey** and help inform the plan. For more information about the planning process, go here.

RCD Newsletter

PAGE INTENTIONALLY BLANK

Survey & Results Documentation

Appendix B.3

PAGE INTENTIONALLY BLANK

Survey Form English



Survey Form Spanish

Total Surveys **455**















Survey Results A



Survey Results Long B

Mitigation Strategy Prioritization Process Documentation

Appendix B.4

PAGE INTENTIONALLY BLANK

HMPT4-19

CITIES
STATION ASSIGNMENTS
Extreme Temperatures, & Drought) – Clare
Hazards & Severe Weather Hazards) – Ethan
ake & Slope Failure Hazards) – Chris
lure and Flood) - Raini
WATSONVILLE
FIRE

HMPT4-21

Wildfire
How to Participate?
Write: One mitigation action per hexagon. Focus on actions where:
Multiple jurisdictions must act together
Shared resources are needed (e.g., funding, data, equipment)
One jurisdiction leads but needs support from others
Evacuation Route Fuel Management
Outreach Support
Website Support
Rural Wildfire Readiness Program
Outreach Program Development
SANTA CRUZ COUNTY
HAZARD MITIGATION PLAN

HMPT4-5



HMPT4-6

Website Documentation

Appendix B.5

PAGE INTENTIONALLY BLANK



Executive Summary



Get Involved



Stakeholder Resources



Success Stories


RAMP
MITIGATE HAZARDS
Population
Property
Critical Infrastructure
Help
Jurisdiction
Unincorporated County
City of Watsonville
City of Santa Cruz
City of Scotts Valley
City of Capitola
Cabrillo College
Resource Conservation District
Santa Cruz Port District
Soquel Creek Water District
Scotts Valley Water District
Pajaro Valley Water Management Agency
Selected Population
131,149
Vulnerability Data
Population Risk Filters
M7.1 N. San Andreas
Santa Cruz Mtn
Sea Level Rise
Tsunamic Runup Area
FEMA Flood Hazard
BAM 100yr Awareness Zones
Expansive Soils
Liquefaction
Fault Zone of Required Investigation
Dam Inundation Risk
Wildfire Risk
Landslide Risk
Map Hazard Layers
Weighted Population
1.0k
2.5m
88.0
2.5m
Hazard Layer
M7.1 N. San Andreas Santa Cruz Mtn Earthquake Scenario
Sea Level Rise
Tsunamic Runup Area
FEMA Flood Hazard
BAM 100yr Awareness Zone
Expansive Soils
Potential for Liquifaction
Fault Zones
Dam Inundation
Wildfire
Landslide
Base Map
Campbell
Saratoga
Los Gatos
Morgan Hill
San Martin
Scotts Valley
Santa Cruz
Capitola
Watsonville
Aromas
Leaflet | © OpenStreetMap contributors, © CARTO

RAMP

PAGE INTENTIONALLY BLANK

Outreach Events

Appendix B.6

PAGE INTENTIONALLY BLANK

FireSafe SANTA CRUZ COUNTY

A FREE COMMUNITY EVENT

WILDFIRE RESILIENCY FAIR CORRALITOS

SAT JUN 28

35 BROWNS VALLEY RD, CORRALITOS, CA 95076
CORRALITOS COMMUNITY CENTER

4:00PM-6:00PM

The Corralitos Wildfire Resiliency Fair is a community-focused event hosted by the Fire Safe Council of Santa Cruz County to empower residents with actionable knowledge on wildfire safety. Attendees will hear directly from CAL FIRE, Firewise leaders, United Policyholders, and local home ignition zone assessors on how to better protect homes and neighborhoods from wildfire threats.

CAL FIRE — California Department of Forestry & Fire Protection — Since 1885

United Policyholders — Empowering the Insured

NFPA | FIREWISE USA® — Residents Reducing Wildfire Risks

Santa Cruz County CERT — Community Emergency Response Team

RESOURCE CONSERVATION DISTRICT OF SANTA CRUZ COUNTY

Corralitos Wildfire Resiliency Fair Flier

Watsonville Community Bike Rides

Paseo En Bicicleta Por Watsonville

COMMUNITY WILDFIRE PREPARDNESS WORKSHOP

JOIN US TO DISCUSS LOCAL RESPONSIBILITY AREA HAZZARD MAPS, BUILDING CODE AND LAND USE REQUIREMENTS, WATER SYSTEMS AND HYDRANTS, AND CALIFORNIA FAIR INSURANCE PLAN Q&A.

TUESDAY, MARCH 18th

6:00-7:30 PM

SCOTTS VALLEY COMMUNITY CENTER

360 KINGS VILLAGE RD, SCOTTS VALLEY

Community Wildfire Event

FireSafe SANTA CRUZ COUNTY

A FREE COMMUNITY EVENT

WILDFIRE RESILIENCY FAIR CORRALITOS

SAT JUN 28

35 BROWNS VALLEY RD, CORRALITOS, CA 95076
CORRALITOS COMMUNITY CENTER

4:00PM-6:00PM

The Corralitos Wildfire Resiliency Fair is a community-focused event hosted by the Fire Safe Council of Santa Cruz County to empower residents with actionable knowledge on wildfire safety. Attendees will hear directly from CAL FIRE, Firewise leaders, United Policyholders, and local home ignition zone assessors on how to better protect homes and neighborhoods from wildfire threats.

CAL FIRE SINCE 1885 · United Policyholders Empowering the Insured · NFPA FIREWISE USA Residents Reducing Wildfire Risks · SANTA CRUZ COUNTY CERT COMMUNITY EMERGENCY RESPONSE TEAM · RESOURCE CONSERVATION DISTRICT OF SANTA CRUZ COUNTY

Corralitos Wildfire Resiliency Fair



Community Wildfire Event

Cultivating Communities Fair (1)

Cultivating Communities Fair (2)

Capitola City Council Presentation

no temas al fuego

SANTA CRUZ
INTEGRATED REGIONAL WATER MANAGEMENT

REGIONAL WATER MANAGEMENT GROUP MEETING

March 24 (Monday), 2025 from 10 - noon
Hybrid Meeting
In person: Community Foundation Santa Cruz County
Attendance in person is encouraged
7807 Soquel Drive, Aptos, CA 95003

Remote participation: via Zoom
https://us06web.zoom.us/j/2746136931?pwd=CbcGmkYIU1P1bruW9eVQSX18wq9qPE.1&omn=84211095226
Meeting ID: 274 613 6931
Passcode: RWMG

Dial-in Option +1 669 444 9171 US
Meeting ID: 274 613 6931 Passcode: 851062

AGENDA

1. Welcome & Introductions

2. Update on Measure Q Water and Wildlife Protection
   - General Update: *Rebecca Hurley, Santa Cruz County Parks*
   - Updates from Cities, County, Partners that will receive funds: *Round robin/open forum*
     www.santacruzcountyca.gov/MeasureQ.aspx

3. Forest Health and Wildfire Resiliency Regional Collaboration – Regional Project Prioritization
   Matt Abernathy and Lisa Lurie, Resource Conservation District Santa Cruz County

4. Open Forum – Opportunities for updates from agencies and organizations

Scotts Valley Wildfire Event

Watsonville Earth Day 1

Watsonville Earth Day 2



Wildfire Preparedness Event Flyer 1

Wildfire Preparedness Event Flyer 2

Pajaro Valley Water Management Agency

English

PAY ONLINE CONSTRUCTION UPDATES

Director Agendas & Minutes

Board Agendas and Minutes

Meetings are held at the Watsonville City Council Chambers, 275 Main Street, 4th Floor, Watsonville, CA 95076. Meetings typically occur the third Wednesday of the month at a 7:00PM start time. For copies of previous agendas or minutes please contact our office. Ordinances can be found under Resources and References. The Rules of Order for all Board Meetings.

PV Water may be able to accomodate online attendance for members of the public during meetings this will be the link: https://www.gotomeet.me/PVWater/board-of-directors If GoToMeeting is being used you call also call in at 1-877-309-2073 Access Code: 347-473-301#

*Meeting dates and location are tentative and subject to change.

2025 DOCS 2024 DOCS 2023 DOCS 2022 DOCS 2021 DOCS

ORDINANCES

2025 Docs

Date	Agenda Packets	Minutes
January 15, 2025	Agenda; Agenda Packet Presentations: CLP Update; FY24 Audit Adopted Resolution: 2025-01, Amending Administration & Finance Committee Bylaws	Minutes

Date	Agenda Packets	Minutes
July 16, 2025	Agenda; Agenda Packet Presentations: SCC MJHMP Update	
August 20, 2025		
September 17, 2025		
October 15, 2025		
November 19, 2025		
December 17, 2025		

Last updated on September 12, 2023.

Contact PV Water

Pajaro Valley Water Management Agency

36 Brennan St.
Watsonville, CA 95076

1 (831) 722-9292

Info@PVWater.org

View Our Staff Directory

Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan 2025 Update

Pajaro Valley Water Management Agency Board of Directors Meeting

July 16, 2025

MITIGATE HAZARDS
www.mitigatehazards.com

PVWMA Board Meeting Slide

SANTA CRUZ COUNTY OFFICE OF RESPONSE, RECOVERY & RESILIENCE

EMERGENCY MANAGEMENT COUNCIL

When: May 15, 2025, 1-3pm

Where: EOC, 5200 Soquel Ave., Santa Cruz

AGENDA

1. **Call to Order/Instructions for participation**
2. **Roll Call (*Emergency Management Council Appointed Members, Districts 1-5*)**
3. **Changes to the Agenda**
4. **Approval of Minutes** *(Attachment A)*
5. **Old Business –** Can EMC operate as a Hybrid Meeting?
6. **New Business**
7. **Informational Reports**
   - 7.1 Fire Safe Council – Lauren Moody
   - 7.2 OR3 – Multi-jurisdiction Hazard Mitigation Plan update, Federal Grants update
   - 7.3 City of Scotts Valley – Jason Rutherford
   - 7.4 City Of Santa Cruz – Robert Oatey/Meredith Albert
   - 7.5 City of Capitola – Leo Moreno
   - 7.6 City of Watsonville – Tom Avila
   - 7.7 County Office of Education – Rishi Lal
   - 7.8 Santa Cruz County Sheriff – Dan Freitas/Nicholas Baldrige
   - 7.9 County Fire – Jed Wilson
   - 7.10 Central Fire – Nigel Miller
8. **Non-Governmental Organizations**
   - 8.1 CERT Council – Amanda Gullings
   - 8.2 CERT Auxiliary – John Collins/Mary Edmond
   - 8.3 Medical Reserve Corp – Jessie Bola/ Greg Benson
   - 8.4 Amateur Radio Emergency Service (ARES) – John Gerhardt
   - 8.5 American Red Cross – Patsy Gasca

SANTA CRUZ COUNTY OFFICE OF
RESPONSE, RECOVERY & RESILIENCE

8.6 Watsonville Emergency Airlift Command Team (WEACT) – Tom Hail

8.7 UC Santa Cruz – Stephan Edgar/Vanessa Ackerman

9. **OR3 Grant Updates**

9.1 FY 2022 State Homeland Security Grant Program (SHSGP) – OPEN, closing 5/30/25

9.2 FY 2023 State Homeland Security Grant Program (SHSGP) – OPEN

9.3 FY 2024 State Homeland Security Grant Program (SHSGP) – Final Scope Pending Approval

9.4 FY 2025 State Homeland Security Grant Program (SHSGP) – Projects submitted for consideration

9.5 FY 23 Emergency Management Performance Grant (EMPG) – Closing 6/30/25

9.6 FY 24 Emergency Management Performance Grant (EMPG) – Approved

9.7 California Fire Safe Council – County Coordinator Grant ROUND 2 – Submitted

9.8 FEMA Building Resilient Infrastructure & Community Grant – Beginning Scope Development, Environmental permit scope development

10. **Announcements**

11. **Adjourn**

Emergency Management Council Agenda 2

Emergency Management Council Slides



RAMP Training Session 1



RAMP Training Session 2



RAMP Training Session 3



RAMP Training Session 4

Watsonville Strawberry Festival 1

Watsonville Strawberry Festival 2

Watsonville Strawberry Festival 3

Capitola Makers Market 1

Capitola Makers Market 2

Capitola Makers Market 3

Capitola Makers Market (4)

PAGE INTENTIONALLY BLANK

Stakeholder Listening Sessions

Appendix B.7

PAGE INTENTIONALLY BLANK

SECTION 1. STAKEHOLDER LISTENING SESSIONS

This section provides a summary of the major themes identified through a series of eight stakeholder listening sessions. In addition to information gathered through other public and stakeholder engagement efforts, these themes were used in refining and aligning the mitigation strategy with community needs and priorities.

Themes from Stakeholder Listening Sessions	
Fire Safe Council	▪ **Top Concerns:** Evacuation road vulnerability; vegetation overgrowth and forest management; landslides; underserved, elderly, and farm worker populations ▪ **Lessons Learned:** Road and culvert failures expose infrastructure fragility; importance of inter-agency coordination ▪ **Successful Projects:** Firewise mentoring and support; fuel breaks; home hardening assessments; collaborative work with agencies ▪ **Barriers:** Lack of education/incentives; insufficient maintenance plans; gaps in coordination and treatment areas ▪ **Other Notes:** Emphasize large-scale, holistic planning and increasing visibility/education around mitigation
Zayante Fire Protection District	▪ **Top Concerns:** Lack of sustained mitigation funding; nonconforming development in high-hazard areas; evacuation route vulnerability; storm damage; emergency communication failures ▪ **Lessons Learned:** Integration issues with CAL FIRE post-CZU; need for extended fire response; value of Firewise programs; administrative support needed for disaster recovery ▪ **Successful Projects:** Firewise efforts; fuel reduction (limited); remote-access fire vehicles ▪ **Barriers:** Inadequate funding; bureaucratic delays; staffing shortages; community fatigue ▪ **Other Notes:** Suggested scalable staffing ("surge specialties"); highlighted dispatch communication overhaul needs
CAL FIRE	▪ **Top Concerns:** Wildfire suppression; unregulated development; public water vulnerability; inadequate access ▪ **Lessons Learned:** Evacuation communication gaps during CZU; debris removal inadequacies ▪ **Successful Projects:** Fuel breaks and vegetation management on public lands; some success with small landowner coordination ▪ **Barriers:** Regulatory hurdles (CEQA, endangered species); maintenance funding gaps; local government leniency on rebuilding ▪ **Other Notes:** Emphasized enforcing land use codes; better development permitting; and managed retreat

keholder Listening Sessions Summary 1

Themes from Stakeholder Listening Sessions	
Pajaro Regional Flood Management Agency	▪ **Top Concerns:** Flood risk in Pajaro/Watsonville; aging and vulnerable levees; farmworker vulnerability; community trust and outreach ▪ **Lessons Learned:** Importance of coordination and legislative support ▪ **Successful Projects:** Pajaro River Levee project; legislative CEQA exemptions; regional partnerships; upstream mitigation efforts ▪ **Barriers:** Political and administrative changes; staff capacity; inter-agency coordination; jurisdictional boundary challenges; language barriers ▪ **Other Notes:** Building public trust and culturally competent outreach is central; PRFMA will be doing its own HMP
San Lorenzo Valley Water District	▪ **Top Concerns:** Wildfire; earthquakes; climate change; drought; infrastructure vulnerability; cybersecurity ▪ **Lessons Learned:** CZU fire caused infrastructure failure and contamination; emphasized infrastructure hardening ▪ **Successful Projects:** Fuel clearance; fireproofing sites (CalOES-funded); conservation planning ▪ **Barriers:** Capacity limitations; administrative burdens of grants; reliance on costly contractors ▪ **Other Notes:** Cybersecurity and endangered species are emerging mitigation issues
Encompass Community Services	▪ **Top Concerns:** Flooding; power outages; evacuation complications for vulnerable groups ▪ **Lessons Learned:** Communication and readiness has improved but still challenged by housing constraints ▪ **Successful Projects:** Shelter coordination; levee improvements; engagement strategies for unhoused populations ▪ **Barriers:** Outreach resource limitations; HUD housing coordination issues ▪ **Other Notes:** Advocates for human-centered mitigation; addressing root causes like housing insecurity
Community Bridges	▪ **Top Concerns:** Wildfire; flooding; inadequate communication infrastructure; delayed emergency response ▪ **Lessons Learned:** Plain-language alerts; need for county-wide communication uniformity; trust in local messengers ▪ **Successful Projects:** Local radio alerts; door-to-door evacuation outreach ▪ **Barriers:** Limited staffing; reliance on neighboring counties; poor access roads; infrastructure gaps ▪ **Other Notes:** Emphasized transit and shelter coordination for vulnerable residents

Themes from Stakeholder Listening Sessions	
USDA Natural Resources Conservation Service	▪ **Top Concerns:** Complacency and unpreparedness among residents; substandard slope stabilization, drainage, and erosion control measures; mixed messages from authorities; access routes and lack of defensible space; critical need for early warning systems and community-level planning ▪ **Lessons Learned:** Past storms (e.g., 1982) highlight need for public education; incentives and outreach more effective than mandates; "one size fits all" approaches don't work; poorly designed or temporary fixes often create more hazards; disasters offer opportunities to educate residents and rebuild better ▪ **Successful Projects:** "Erosion Control Month" campaigns in 1980s; winter preparedness clinics, floodplain outreach, and Local Assistance Centers; wildfire preparedness outreach; collaborative programs with RCD, OES, and NRCS ▪ **Barriers:** Complex, expensive, and delayed permitting processes discourage compliance; homeowners often lack awareness or underestimate risks; county and agency practices sometimes model poor responses; funding limitations and lack of consistent incentives; poor maintenance of mitigation measures undermines resilience ▪ **Other Notes:** Community-scale planning and drills are essential; neighborhood-level Firewise programs and coordination with HOAs can build resilience; mitigation practices should not trade one hazard for another; monitoring and maintenance are critical for all mitigation projects

keholder Listening Sessions Summary 3

PAGE INTENTIONALLY BLANK

SECTION 3

MUNICIPAL ANNEX

City of Watsonville

SANTA CRUZ COUNTY
MULTI-JURISDICTIONAL
HAZARD MITIGATION PLAN

INTENTIONAL BLANK PAGE

Santa Cruz County

2025 Multi-Jurisdictional Hazard Mitigation Plan

Volume 2, Section 3: City of Watsonville (WTS)

Municipal Annex

Adoption Record ..... **vi**

Section 3. City of Watsonville **3-1**

3.1 Scope & Purpose 3-1

3.2 Jurisdictional Setting 3-1

3.2.1 Geography & Climate 3-2

3.2.2 Historical Overview 3-2

3.2.3 Demographics & Vulnerable Populations 3-5

3.2.4 Economy 3-20

3.2.5 Growth Trends & Future Development 3-20

3.3 Planning Process 3-24

3.3.1 Public Input & Draft Review 3-27

3.4 What's New 3-27

3.4.1 Mitigation Activities 3-27

3.4.2 Mitigation Successes 3-28

3.5 Risk Assessment 3-30

3.5.1 Hazard Screening & Prioritization 3-30

3.5.2 Vulnerability to Specific Hazards 3-33

3.5.3 Planning for Hazards & Growth 3-53

3.5.4 Hazard Problem Statements 3-57

3.6 Mitigation Strategy 3-62

3.6.1 Aligning the Action Plan 3-62

3.6.2 Capabilities & Opportunities Assessment 3-66

3.6.3 City of Watsonville Mitigation Action Plan 3-73

3.6.4 Status of Previous Mitigation Actions 3-77

List of Figures

Figure 3-1: City of Watsonville Sphere of Influence 3-3
Figure 3-2 City of Watsonville Average Annual Precipitation Map 3-4
Figure 3-3: City of Watsonville - Median Household Income Map 3-8
Figure 3-4: City of Watsonville - Poverty Status Map 3-9
Figure 3-5: City of Watsonville - Occupied Housing Units Map 3-10
Figure 3-6: City of Watsonville - Economically Dependent Age Groups Map 3-13
Figure 3-7: City of Watsonville - Disabled Elderly Population Map 3-14
Figure 3-8: City of Watsonville - Race and Ethnicity Predominance Map 3-16
Figure 3-9: City of Watsonville - Percentage of Spanish-Speaking Population Map 3-17
Figure 3-10: City of Watsonville Social Vulnerability Index Map 3-19
Figure 3-11: Areas of Growth Identified from the 2050 General Plan 3-23
Figure 3-12: City of Watsonville - Risk Assessment Matrix 3-32
Figure 3-13 City of Watsonville - Wildfire Risk Exposure Map 3-35
Figure 3-14: City of Watsonville - FEMA Flood Risk Exposure 3-37
Figure 3-15: Pajaro River Levee System Source; Santa Cruz County 3-39
Figure 3-16: Exposure Summary – City of Watsonville Earthquake Risk (M7.1 San Andreas Shaking) 3-44
Figure 3-17: Exposure Summary – City of Watsonville Liquefaction Risk 3-45
Figure 3-18 City of Watsonville - Landslide Risk Exposure Map 3-48
Figure 3-19: Drought Severity Timeline 2000-2024 3-51
Figure 3-20: Mitigation Action Number Key 3-73

List of Tables

Table 3-1: Population and Housing Summary 3-5
Table 3-2: Household Income and Poverty Levels 3-6
Table 3-3: Owner- and Renter Occupied Households 3-7
Table 3-4: Economically Dependent Age Groups 3-11
Table 3-5: Watsonville Non-Institutionalized Disabled Population 3-12
Table 3-6: County-Wide Household Languages 3-15
Table 3-7: Population and Household Size 3-21
Table 3-8: City of Watsonville Planning Committee and Steering Group Members 3-24
Table 3-9: City of Watsonville Planning Team Meetings 3-26
Table 3-11: City Document Review Crosswalk 3-31
Table 3-12: City of Watsonville - National Flood Insurance Program Information 3-42
Table 3-13: Drought Classifications and Impacts 3-50
Table 3-14: City of Watsonville Problem Statements 3-57
Table 3-16: City of Watsonville Capabilities Assessment 3-68
Table 3-17: City of Watsonville Mitigation Action Plan 3-75

Adoption Record

To comply with the Federal Disaster Mitigation Act of 2000 (DMA 2000), the City of Watsonville has officially adopted this 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan, including Volume 1 in its entirety as well as this Volume 2 Municiple annex. The adoption of the MJHMP recognizes the city's commitment to reducing the impacts of natural hazards within its jurisdiction and across Santa Cruz County.

A copy of the city's adoption record is provided on the following pages. Adoption records for all jurisdictions are summarized in Volume 1, Table ES-1.

ADOPTION RECORD TO BE INSERTED UPON COMPLETION.

Section 3. City of Watsonville

3.1 Scope & Purpose

This annex details the elements specific to the City of Watsonville in the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP). This annex is not intended to be a standalone document but appends to and supplements the information contained in the umbrella plan document (Volume 1). As such, all sections of the umbrella plan, including the planning process and other procedural requirements apply to and were met by the City of Watsonville. This annex provides additional information specific to the City of Watsonville, with a focus on providing additional details on the planning process, risk assessment, and mitigation strategy for this jurisdiction.

City of Watsonville Points of Contact

Primary

Courtney Lindberg, Public Works Director
Public Works Department
City of Watsonville
250 Main Street
Watsonville, CA 95076
Telephone: (831) 768-3050
Email: courtney.lindberg@watsonville.gov

Alternate

Leslie Rios, Environmental Project Manager
Public Works Department
City of Watsonville
250 Main Street
Watsonville, CA 95076
Telephone: (831) 768-3050
Email: Leslie.rios@watsonville.gov

3.2 Jurisdictional Setting

The City of Watsonville is located in southern Santa Cruz County in Central California in the Pajaro Valley. Watsonville is 80 miles southeast of San Francisco. Located on the north bank of the Pajaro River, Watsonville is the center of Santa Cruz County's agricultural industry.

The City of Watsonville encompasses approximately 6.7 square miles, with an average elevation of 29 feet above sea level. While Watsonville continues to advance in urban planning, housing, transportation, and flood resilience, population growth is trending downward. City of Watsonville's location within Santa Cruz County and the State of California are shown in Figure 3-1.

- Date of Incorporation: March 30, 1868
- Current Population: 50,669 (United States Census Bureau, 2016-2021)
- Population Growth: The city has experienced a population decrease of -2.3% between 2013 and 2023 (United States Census Bureau, 2016-2021)

3.2.1 Geography & Climate

The City of Watsonville is situated in a low-lying river valley approximately three miles inland from the Pacific Ocean. Figure 3-1 illustrates its regional context within southern Santa Cruz County. The city's landscape is largely defined by alluvial deposits originating from surrounding hills and mountains, resulting in fertile soils that have historically supported its robust agricultural economy, particularly the cultivation of berries.

Soil composition varies across the city, with loam dominating the inland areas and sandy loam prevalent closer to the coast. Watsonville's topography is generally flat, with an average elevation of approximately 29 feet above sea level.

The city experiences a Mediterranean climate, characterized by warm to hot, dry summers and mild, wet winters. Average summer high temperatures can reach into the mid-90s°F, while winter lows occasionally drop into the upper 20s°F. Precipitation is concentrated between November and March, with minimal rainfall in the summer months. Snowfall is extremely rare due to the city's low elevation. Figure 3-2 presents the average annual precipitation data.

Prevailing winds are generally mild, but during summer evenings, onshore flow from the Pacific Ocean brings cooler marine air inland. These climatic and geographic conditions contribute to Watsonville's highly productive agricultural landscape but also present natural hazard risks, including flooding from the Pajaro River, periodic drought, and wildfire threats in surrounding upland areas.

3.2.2 Historical Overview

Watsonville was incorporated on March 30, 1868, and has since grown into the largest city in the Pajaro Valley, shaped by its agricultural economy and steady waves of residential development. The city's historic downtown reflects its 19th-century origins, with early civic and commercial buildings that continue to anchor the urban core.

Much of Watsonville's housing stock was constructed during the post–World War II era, when population growth and economic expansion spurred suburban-style development across the city. According to the City's Housing Element, about 45 percent of Watsonville's housing units are now more than 30 years old, reflecting their construction during the 1950s through the 1970s. These older homes, while integral to the city's neighborhoods and heritage, present ongoing challenges related to seismic safety, energy efficiency, and long-term maintenance (City of Watsonville Housing Element, 2015-2023).

Newer subdivisions, many built during the 1980s and 1990s, expanded the city's footprint, while more recent growth has emphasized infill housing, redevelopment of underutilized properties, and farmland preservation. This blend of historic downtown structures, mid-century neighborhoods, and newer developments defines Watsonville's built environment today, reflecting both the city's agricultural roots and its evolving role as a regional hub. (City of Watsonville General Plan, 2005)*;* (City of Watsonville Housing Element, 2015-2023).



Figure 3-1: City of Watsonville Sphere of Influence



Average Annual Precipitation (1991-2020, Inches)
City of Watsonville
*Data sources: PRISM 30-Year Normals 1991-2020.

18 – 25	25 – 35	35 – 45	45 – 50	50 – 64

INCHES

Figure 3-2 City of Watsonville Average Annual Precipitation Map

3.2.3 Demographics & Vulnerable Populations

This section describes the demographic characteristics of the City of Watsonville to guide hazard mitigation planning efforts. Natural disasters affect communities both physically and socially, with demographic composition playing a central role in determining how impacts are distributed, particularly among vulnerable groups facing greater challenges in preparedness, response, and recovery. Understanding the area's social and economic landscape also helps assess potential social costs from infrastructure damage, including housing, industry, public facilities, essential services, and transportation.

Exploring local demographic data may help to identify groups and geographic areas with specific vulnerability to hazard events. In the context of all-hazards preparedness and response planning, at-risk individuals (often used interchangeably with "vulnerable populations") are defined federally as "children, pregnant women, senior citizens, and other individuals who have access or functional needs in the event of a public health emergency." (42 U.S.C. § 2802(b)(4)(B) (2019)) These populations may include, but are not limited to, individuals who are economically disadvantaged, living with disabilities, dependent on caregivers, from historically marginalized communities, have limited English proficiency or are non-English speaking, lack access to transportation, are experiencing homelessness, or have chronic medical conditions.

Certain populations face greater risk following a natural hazard event due to age, economic mobility, physical disability, geographic location, or a combination of factors. Vulnerability in the face of a hazard event is not a fixed characteristic; the same individual may be at risk for some hazards but not at risk for others. Planning for vulnerable populations in the context of hazard mitigation can help communities to prioritize limited resources where they will be the most effective. Refer to Volume 1, Section 1.4.3, for a more in-depth discussion of planning for vulnerable populations, at-risk individuals with access and functional needs, and environmental justice.

The total population, total number of households, and average household size of the City of Watsonville are presented in Table 3-1, compared to the other municipalities and Santa Cruz County. The city is the second largest of all the incorporated municipalities and has the highest average household size.

Table 3-1: Population and Housing Summary

Jurisdiction	Total Population	Total Households	Average Household Size
City of Watsonville	**51,968**	**15,792**	**3.24**
Santa Cruz County	266,021	106,635	2.36

Source: ACS 5-Year, 2018-2023

3.2.3.1 Income & Housing

Economic mobility is one of the most important predictors of natural hazard vulnerability. Low-income residents are more likely to occupy housing which is inadequately maintained or otherwise poorly built to withstand extreme events. For example, mobile or modular homes are more susceptible to damage in earthquakes and floods than other types of residences and are less likely to contain A/C units to cope with high heat events. In urban areas, low-income residents are more likely to occupy older homes and apartment complexes with unreinforced masonry, which is particularly susceptible to seismic damage.

Low-income households and communities face disproportionate financial burden from costs associated with disaster preparedness, response, and recovery. Disasters create unexpected expenses which may serve as "tipping points" for families and individuals living on the edge of poverty or homelessness. Recovery costs may be higher for those without resources to conduct hazard mitigation activities ahead of time. Families and individuals who lack access to transportation may be unable to evacuate ahead of an emergency. (Krause & Reeves, 2017)

Low-income residents and renters are also less likely to purchase insurance, meaning that those with the most to lose during an event are also the least prepared to deal with potential losses. Major hurricane events in recent history such as Harvey, Irma, and Katrina all demonstrate that low-income and/or historically marginalized communities face increased vulnerability to hazard events and struggle the most to recover.

Median household income in the City of Watsonville was $74,785, with an overall poverty rate of 15.1%. By comparison, median income and poverty rates for Santa Cruz County were $109,266 and 11.2%, respectively. (see Table 3-2) Median income and poverty rates are also shown on the block group level in Figure 3-3 and Figure 3-4.

Table 3-2: Household Income and Poverty Levels

Jurisdiction	Median Income	Poverty Rate
City of Watsonville	**$74,785**	**15.1%**
Santa Cruz County (Total)	$109,266	11.2%

Source: ACS 5-Year, 2018-2023

Renters are also more vulnerable to natural hazards, as they are less likely to take out property insurance and the decision to make major structural improvements typically lies with the property owner. Federal disaster recovery services can exacerbate inequality between renters and homeowners; payout amounts are significantly higher for homeowners applying through FEMA's Individual Assistance (IA) program; from 1999 to 2013 U.S. homeowners saw their wealth increase with local hazard damages, whereas renters' wealth decreased. (Howell, Junia; Elliot, James, 2019)

Approximately 56% of occupied housing units in City of Watsonville are renters, compared to 40% for Santa Cruz County as a whole; refer to Table 3-3. Hence, Watsonville has a much higher percentage of renter occupied dwelling units than Santa Cruz County has a whole. Figure 3-5 depicts housing occupancy in Watsonville.

Table 3-3: Owner- and Renter Occupied Households

Jurisdiction	# Occupied Housing Units	# Renter Occupied	% Renter Occupied	# Owner Occupied	% Owner Occupied
City of Watsonville	**15,267**	**8,610**	**56.4%**	**6,657**	**43.6%**
Santa Cruz County	96,873	38,771	40.0%	58,102	60.0%

Source: ACS 5-Year, 2018-2023



Figure 3-3: City of Watsonville - Median Household Income Map



ACS Poverty Status

City of Watsonville

*Data sources: ESRI Demographics Service, ACS.

Percent of Population Whose Annual Income is Below Poverty

> 24%

< 1%

No Value

Figure 3-4: City of Watsonville - Poverty Status Map



Figure 3-5: City of Watsonville - Occupied Housing Units Map

3.2.3.2 Dependent & Elderly Disabled Populations

Age is a significant factor in assessing vulnerability to natural hazards. Both older adults and children are considered dependent populations due to their reliance on caregivers for safety, mobility, and support during emergency events. These populations face heightened risks during disasters such as floods, wildfires, and earthquakes, particularly when compounding factors such as poverty, disability, or social isolation are present.

In the City of Watsonville, approximately 30.6% of households include at least one individual over the age of 65, and 4.2% of all households are comprised of seniors living alone. Among senior households, 5.3% live below the poverty line (Table 3-4). Seniors who live alone often face greater challenges in emergency situations, including difficulties with evacuation, limited access to real-time alerts due to digital literacy or lack of internet access, and chronic health conditions that require special care. These factors make seniors, especially those who are low-income or socially isolated, among the most vulnerable in a disaster context. Critical facilities such as assisted living centers require advanced coordination for evacuation and continuity of care and are therefore prioritized in emergency response plans.

Children are another key dependent population. In Watsonville, 42.1% of households include individuals under 18, with 12.9% of these households headed by a single caregiver (Table 3-4). Children rely entirely on caregivers for transportation, shelter, and decision-making during emergencies. The disruption of school systems, childcare, and social services during disasters can have significant emotional, developmental, and educational impacts on youth. Additionally, families with limited economic means or single caregivers may struggle to maintain access to necessary resources and recovery support.

Figure 3-6 highlights areas of the city with elevated concentrations of economically depend age groups.

Table 3-4: Economically Dependent Age Groups

Jurisdiction	% Households 65+	% Households 65+ Living Alone	% Households 65+ in Poverty	% Households <18	% Households <18 w Single Caregiver
City of Watsonville	**30.6%**	**4.2%**	**5.3%**	**42.1%**	**12.9%**
Santa Cruz County	33.4%	7.9%	2.7%	24.8%	6.0%

Source: ACS 5-Year, 2018-2023

Elderly populations face increased risks during disaster events due to age-related health conditions, mobility limitations, and potential social isolation. In Watsonville, approximately 11.8% of the non-institutionalized population lives with a disability, a slightly higher rate than the countywide average of 11.1% (Table 3-5).

Table 3-5: Watsonville Non-Institutionalized Disabled Population

Jurisdiction	# Persons w Disability	% Persons w Disability
City of Watsonville	**6,109**	**11.8%**
Santa Cruz County	29,557	11.1%

Source: ACS 5-Year, 2018-2023

Among those with access and functional needs, elderly individuals with disabilities represent a highly vulnerable subpopulation when it comes to disaster preparedness, response, and recovery. This group includes seniors living with physical or cognitive impairments such as hearing or vision loss, reduced mobility, reliance on assistive medical devices, neurodivergence, or chronic health conditions that may be exacerbated by hazard events (e.g., exposure to wildfire smoke or extreme heat).

Figure 3-7 illustrates the distribution of elderly individuals (age 65+) with disabilities across the City of Watsonville. The data show notable concentrations—exceeding 47% of the elderly population—in several distinct neighborhoods, primarily located in the northern, eastern, and southeastern portions of the city. These include areas around East Lake Avenue, Green Valley Road, Airport Boulevard, and Freedom Boulevard, as well as pockets near the Pajaro River.

The combination of advanced age and disability can present significant challenges not only during emergency response but also in implementing hazard mitigation measures. Elderly individuals with disabilities may face physical, financial, or logistical barriers to undertaking activities such as seismic retrofitting, anchoring fuel tanks, installing foundation bracing, or implementing residential flood-proofing techniques. Many live in older housing stock that is more vulnerable to earthquake damage or repetitive flooding and may lack the resources or support networks needed to complete mitigation upgrades.



Figure 3-6: City of Watsonville - Economically Dependent Age Groups Map



Figure 3-7: City of Watsonville - Disabled Elderly Population Map

3.2.3.3 Race, Ethnicity & Language

Natural disasters compound racial disparities; non-white individuals and communities receive less recovery aid from FEMA than their white counterparts, even where the amount of damage is the same. (Howell, Junia; Elliott, James R., 2019) (National Advisory Council, 2020) These disparities are evidence of the complicated relationship between disaster recovery and overlapping social vulnerabilities including race, income, language, and health. Black and Latinx residents are more likely to be low income and renters, conditions which create barriers to navigating FEMA's Individual Assistance programs. Communities with more non-white residents may have lower tax revenue and property values, which means less investment in mitigation and rebuilding efforts before and after an emergency.

Figure 3-8 depicts the racial and ethnic composition of the City of Watsonville. According to ACS data, nearly all census tracts within the city boundaries identify Hispanic or Latino as the predominant racial or ethnic group. This demographic pattern reflects Watsonville's long-standing role as a cultural and economic hub for Latino communities in the Pajaro Valley, many of whom are employed in agriculture, food processing, and other essential industries.

The strong concentration of Hispanic and Latino populations has important implications for hazard mitigation planning. Language access, cultural relevance of outreach materials, and partnerships with trusted community-based organizations are essential to ensure effective communication of preparedness information, emergency alerts, and recovery resources. Tailoring hazard mitigation and resilience strategies to reflect Watsonville's demographic reality will help reduce disparities in disaster outcomes and ensure equitable access to mitigation programs.

Residents with limited English proficiency (LEP) face heightened barriers to understanding emergency alerts, accessing preparedness resources, and navigating post-disaster recovery programs. In Watsonville, nearly 49% of households speak Spanish and 15% report limited English proficiency, rates significantly higher than the county average (Table 3-6). Figure 3-9 shows where Spanish-speaking populations are concentrated in Watsonville.

Many LEP residents are renters or frontline workers living in high-risk areas, making it critical to provide translated preparedness materials, culturally competent outreach, and tailored emergency alerts. Partnering with trusted community organizations can enhance outreach effectiveness and help ensure equitable access to mitigation resources and life-safety information.

Table 3-6: County-Wide Household Languages

Jurisdiction	# Spanish Speaking Households	% Spanish Speaking Households	# Limited English Households	% Limited English Households	# Other Language Households
City of Watsonville	**7,719**	**48.9%**	**2,363**	**15.0%**	**0**
Santa Cruz County (Total)	18,325	17.2%	3,354	3.1%	90

Source: ACS 5-Year, 2018-2023



Figure 3-8: City of Watsonville - Race and Ethnicity Predominance Map



ACS Language Spoken

City of Watsonville

*Data sources: ESRI Demographics Service, ACS.

Percent of Population (5+) Who Speak Spanish at Home

> 33%

< 1%

No Value

Figure 3-9: City of Watsonville - Percentage of Spanish-Speaking Population Map

3.2.3.4 Social Vulnerability Index (SVI)

The CDC Social Vulnerability Index (SVI) provides important insight into the geographic and demographic factors that shape Watsonville's resilience to disasters. As described in Volume 1, Section 1.4.3.6, the SVI is a composite measure developed by the CDC that identifies communities more likely to require additional support before, during, and after an emergency. The index incorporates four key dimensions: socioeconomic status, household composition and disability, minority status and language, and housing and transportation access, producing scores that range from 0 (lowest vulnerability) to 1 (highest vulnerability).

Figure 3-10 shows that Watsonville ranks among the areas of highest vulnerability in Santa Cruz County, with many census tracts scoring between 0.50 and 1.00. This reflects the city's demographic and socioeconomic profile, which includes large populations of agricultural workers, renters, Spanish-speaking households, and lower-income families. In addition, a significant share of residents are seniors, children, or individuals with disabilities, further elevating vulnerability scores.

These conditions highlight how disaster preparedness, hazard mitigation, and recovery can be more challenging in Watsonville than in other parts of the county. Language barriers, limited access to transportation, and economic constraints can delay evacuation, reduce access to hazard insurance, and create barriers to implementing home retrofits or floodproofing measures.

The presence of elevated social vulnerability in Watsonville underscores the importance of equity-focused hazard mitigation strategies. Tailored outreach in multiple languages, partnerships with trusted community organizations, and targeted funding support for housing retrofits, flood protection, and seismic strengthening are critical steps to ensure that Watsonville residents, particularly those in high vulnerability neighborhoods, have the resources and support needed to reduce disaster risk.



Figure 3-10: City of Watsonville Social Vulnerability Index Map

3.2.4 Economy

Watsonville serves as the economic heart of the Pajaro Valley, with a local economy that is both agriculture-based and globally connected. The region is renowned for its fertile soils and temperate climate, which have made agriculture the city's economic backbone for more than a century. Today, Watsonville remains a national leader in berry and vegetable production, with strawberries, apples, fresh flowers, broccoli, cauliflower, and artichokes among the most significant crops grown in the valley.

In addition to farming, Watsonville has built a strong food-processing and distribution sector. The city's processors freeze and ship more fruits and vegetables than any other single area in the United States, and more than $280 million is invested annually in shipping fresh and processed products worldwide. This makes Watsonville a critical link in the national and international food supply chain.

Beyond agriculture, Watsonville hosts major employers in manufacturing, construction, and distribution. Companies headquartered in the city include Driscoll's Strawberries, Martinelli's, California Giant, Monterey Mushrooms, Graniterock, Granite Construction, West Marine, Vendwize, and Fox Racing Shox, all of which reflect the city's economic diversity. Together, these industries contribute to Watsonville's role as both a regional employment center and a hub of agricultural innovation.

Watsonville's economic profile has direct implications for hazard resilience. Agriculture and food processing are highly sensitive to disruptions caused by flooding, earthquakes, and climate-related hazards. Damage to fields, cold storage facilities, or transportation networks could have cascading impacts beyond the local economy, affecting regional food security and supply chains. Similarly, many of the city's essential industries rely on a large workforce of agricultural and service-sector employees, many of whom face economic vulnerabilities that can compound disaster impacts.

For this reason, hazard mitigation planning in Watsonville must prioritize the protection of critical economic infrastructure, workforce housing, and transportation corridors, ensuring that both local livelihoods and regional supply chains remain resilient in the face of future hazards.

3.2.5 Growth Trends & Future Development

The City of Watsonville had an estimated population of 51,968 in 2023, which is approximately 20% of the total population of Santa Cruz County. Between 2013 and 2019, Watsonville's population grew from 51,544 to 53,800, an increase of 4%. It then declined by nearly 2,000 people in the span of four years to 51,968 in 2023, almost wiping out all the growth between 2013 and 2019. Watsonville has ample room to grow both within the existing city limits and through annexation, and it would be expected the population would resume an upward trend.

Although recent demographic shifts indicate a downturn in population growth and development, they also highlight the need to recalibrate hazard mitigation strategies to reflect changing conditions. Reduced growth may alleviate immediate pressure on infrastructure and resource demand, yet it can also lead to challenges such as diminished funding for hazard mitigation initiatives or delayed upgrades to aging

infrastructure. Aligning development plans with hazard mitigation objectives becomes even more critical in this context. Proactive planning is essential to ensure that the city remains resilient, addressing potential vulnerabilities and maintaining readiness to respond to natural hazards despite slowing growth.

Population density and household composition can provide critical insights into the assumed location of risk within a community. In 2023, Watsonville had 15,792 total households, with an average household size of 3.24 individuals per household. This figure is the highest in Santa Cruz County and well above the Countywide average of 2.36. Such metrics suggest that the city may have a higher prevalence of multi-generational or family units as compared to senior or single-occupant households. Areas with higher population densities or distinctive household structures are often more susceptible to hazards like flooding, fire, or evacuation challenges, given the concentration of people and infrastructure. Consequently, mitigation strategies tailored for these demographics, including enhanced sheltering solutions and evacuation procedures, are essential. Although the City of Watsonville has taken significant mitigation steps since the prior MJHMP, ongoing efforts in this annex focus on addressing these vulnerabilities and refining strategies to counter persistent risks stemming from past development and residual hazard exposures.

Table 3-7: Population and Household Size

Jurisdiction	Population	Households	Avg. Household Size
Santa Cruz County	266,021	106,635	2.36
City of Watsonville	51,968	15,792	3.24

Source: 2016-2021 ACS 5-Year Estimates

Long Range Growth

The City of Watsonville is preparing for significant residential and commercial growth through its 2050 General Plan. The accompanying Environmental Impact Report projects the addition of up to 5,980 new housing units and approximately 1.7 million square feet of non-residential development. Much of this growth will occur as infill along East Lake Avenue, Freedom Boulevard, and Downtown Watsonville, where the recently adopted Downtown Specific Plan encourages mixed-use development and increased density.

Growth is also anticipated beyond current city limits in areas such as Buena Vista, Atkinson Lane, Area C, and the Highway 1 Gateway (See Figure 3-11), which together represent major opportunities for new homeownership and commercial development. However, these sites require annexation or approval through citywide referendums before large-scale development can proceed.

This projected growth carries important implications for hazard mitigation planning. First, expanded residential and commercial development will place additional demands on infrastructure while also increasing exposure to flood, seismic, and wildfire hazards, particularly in newly developed or annexed areas. Second, as development extends into outlying neighborhoods, equitable access to evacuation routes, emergency services, and mitigation funding will be essential to protect vulnerable populations. Finally, Watsonville has a unique opportunity to ensure that infill and new construction are designed with resilience in mind. This includes adopting elevated construction in flood-prone areas, incorporating green infrastructure to reduce stormwater impacts, and requiring seismic retrofitting or advanced building practices to better withstand future earthquakes.



Legend

- City Limit
- County Boundary
- Sphere of Influence (SOI)
- Existing Urban Limit Line (ULL)
- Proposed Urban Limit Line (ULL)
- Downtown Infill
- Station Area Infill
- Corridor Infill
- New Growth Area within ULL
- New Growth Area outside ULL
- Main Runway Airport Safety Zones 1-5
- Crosswind Runway Airport Safety Zones 1-5
- Proposed Passenger Rail Line and Station

Figure 3-11: Areas of Growth Identified from the 2050 General Plan

3.3 Planning Process

The City of Watsonville followed the planning process detailed in Volume 1, Section 2, including participating in the county-wide Hazard Mitigation Planning Team (HMPT) and formulating their own internal planning team to support the broader planning process.

The city's representatives in the Steering Group led stakeholder and public engagement efforts alongside the Consultant Team, with assistance from the county-wide HMPT and their internal planning team. This engagement process is described in Volume 1. Specifically, for the City of Watsonville, this included postings to the city website and social media, outreach events, and public presentations, as documented in Appendix B. Examples of Key Stakeholders engaged by Santa Cruz County on behalf of the city with relevance to the development of Watsonville's mitigation strategy include the USDA and other federal agencies; DWR and other state agencies; the City of Santa Cruz and other neighboring jurisdictions; community-based organizations such as Community Bridges and Watsonville Wetlands Watch; utility providers like AT&T and Pajaro Valley Water Management Agency; UC Santa Cruz and other academia; and local businesses.

All Key Stakeholders that participated in the planning process are listed in Volume 1, Section 2. The city's internal planning participants, their positions, and how they participated in the planning process are shown in Table 3-8.

Table 3-8: City of Watsonville Planning Committee and Steering Group Members

Stakeholder	Title	Department	CRS Expertise	Description of Involvement
Courtney Lindberg	Public Works Director	Public Works		Lead Point-of-Contact
Leslie Rios	Environmental Project Manager	Public Works		Alternate Point-of-Contact
Toto Vu-Duc	Environmental Project Manager	Public Works		Alternate Point-of-Contact
Charles Hanley	GIS Coordinator	Innovation and Technology		HMPT #2
Christopher Gregorio	Assistant Engineer / CRS Coordination	Public Works		HMPT #1, BO#2
Cristy Cassel	Conservation Outreach Program Manager	Public Works		HMPT #2
Danielle Green	Assistant Director of Public Works	Public Works		HMPT #1,#2; BO#1
David Rodriguez	Assistant Police Chief	Police		HMPT #2, BO#2
Joseph DeSante	Chief Building Official	Community Development		HMPT #1, BO#2.5
Justin Meek	Interim Community Development Director	Community Development		HMPT #2,#3. All Breakouts

Stakeholder	Title	Department	CRS Expertise	Description of Involvement
Matt Orbach	Assistant Community Development Director	Community Development		HMPT #1,#2; BO#1
Michelle Pulido	Public Information Officer	Police		HMPT #1,#2; BO#1
Nancy Porto	Community Outreach Coordinator	Public Works		Outreach Assistant
Nick Culabaquib	Deputy City Manager	City Manager's Office		HMPT #1; BO#1
Raunel Zavala	Senior Administrative Analyst			Kick-Off Meeting
Tamara Vides	City Manager	City Manager's Office		BO#1
Tom Avila	Division Chief – Operations	Fire		HMPT #1,#2;#3,#4; BO#1, BO#2,

The City of Watsonville participated in a comprehensive hazard mitigation planning process as part of the 2025 Santa Cruz County MJHMP update. This included a series of breakout meetings that engaged the city's planning team, which included key city personnel and stakeholders in evaluating hazards, identifying local vulnerabilities, and prioritizing mitigation strategies.

The kickoff meeting held on January 27, 2025, launched the planning process by introducing the project scope and clarifying the roles of the Steering Group and participating jurisdictional teams. In the months that followed, a series of structured meetings addressed foundational elements of the plan, including a review of key changes since the previous plan, an overview of hazard mitigation principles, and exercises to prioritize local hazards.

On Thursday, April 24, 2025, the City of Watsonville convened its first breakout session to advance local hazard mitigation planning efforts. The meeting reinforced Watsonville's role within the broader multi-jurisdictional framework and emphasized the importance of sustained participation from city departments and regional partners. Participants discussed recent and potential natural disasters, with particular focus on their impacts to critical infrastructure and community resilience. The session highlighted the increasing frequency and severity of hazard events and the vital role of proactive planning in reducing risk. Newly released hazard data were reviewed, and concerns were raised regarding inaccuracies in the updated CAL FIRE wildfire hazard maps, underscoring the need for reliable data and stronger coordination with state agencies to improve local risk modeling.

Building on this initial meeting, Watsonville city staff worked closely with the county-wide HMPT to review historical hazard impacts, assess ongoing development trends, and evaluate the city's capabilities and gaps in risk reduction. The breakout session included the development of a localized risk matrix to prioritize the hazards affecting the city, tailored to Watsonville's unique geography and built environment, and laid the foundation for identifying hazard-specific problem statements and mitigation actions.

July 14, 2025, Breakout Meeting shifted toward reviewing local capabilities and defining specific areas of concern, which informed the drafting of problem statements. Teams worked collaboratively to refine mitigation alternatives, align actions with FEMA guidelines, and develop a shortlist of priority mitigation actions and inter-jurisdictional collaboration opportunities.

These efforts built upon the county-wide meetings held between January 2025 and August 2025, which introduced the MJHMP update process, defined the roles of the Steering Group and county planning committee, and outlined the timeline and deliverables for each participating jurisdiction.

Throughout this planning process, the City of Watsonville has remained focused on aligning its goals with FEMA standards, maintaining eligibility for federal mitigation funding, and incorporating updated risk data into planning and policy documents. These localized efforts are documented in this annex as well as in Volume 1, Appendix B of the 2025 MJHMP. Table 3-9 shows meeting records for the City of Watsonville Planning Team. Steering Group and county-wide HMPT meetings are documented in Volume 1, Section 2.

Table 3-9: City of Watsonville Planning Team Meetings

Meeting & Date	Agenda / Topics	Goals / Key Inputs
County-Wide Steering Group and HMPT Meetings #1 & #2 January 27, 2025 – March 27, 2025		
WTS Planning Team Breakout Meeting #1 April 24, 2025	▪ Community engagement progress and results ▪ Risk assessment and community vulnerability ▪ Demographics and vulnerable populations ▪ Overview of jurisdiction-specific hazard risks and exposure ▪ Introduction to Risk Assessment Mapping Platform (RAMP) ▪ Jurisdiction-specific hazard risk ranking exercise	▪ Consensus on jurisdiction-specific priority hazards ▪ Identify capabilities and potential mitigation actions ▪ Community engagement volunteers
County-Wide HMPT Meeting #3 June 2, 2025		
WTS Planning Team Breakout Meeting #2 July 14, 2025	▪ Review capabilities assessment ▪ Review areas of concern and define problem statements ▪ Principles of effective mitigation strategies and actions, and mitigation alternatives ▪ Refine and align jurisdiction-specific mitigation actions exercise	▪ Consensus on jurisdiction-specific capabilities ▪ Consensus on jurisdiction-specific areas of concern ▪ Consensus on priority mitigation actions and collaboration opportunities ▪ Community engagement volunteers
County-Wide HMPT Meeting #4 August 4, 2025		

3.3.1 Public Input & Draft Review

As detailed in Volume 1, Section 2, the draft plan was available for public review and comment from September 29 to October 20, 2025. Public comments received during that time were similar to those gathered throughout the public engagement process, including the need for more equity in the distribution of mitigation activities and funding and the need for enhanced cooperation among jurisdictions, utility providers, and state agencies. These comments were incorporated into the city's mitigation strategy, as appropriate; although, most were already addressed by the Mitigation Action Plan which was based on previous public input.

Public and stakeholder input was gathered and incorporated throughout the plan development process, before the public review period, such as from the online public survey (see Volume 1, Section 2.1.2 and Appendix B, for details). During the review period, jurisdictional staff and stakeholders that participated in the plan development also reviewed the public draft and provided comments on minor corrections and revisions, which were addressed in the final plan.

3.4 What's New

This section provides an overview of hazard mitigation planning efforts for the planning area and highlights the updates made in the 2025 MJHMP. The City of Watsonville previously maintained its own standalone Local Hazard Mitigation Plan, which guided resilience planning and hazard mitigation actions at the city level. For the first time, Watsonville is now participating in the countywide MJHMP process. This integration reflects the City's ongoing commitment to regional resilience and acknowledges that many hazards such as flooding, severe storms, drought, and earthquakes cross jurisdictional boundaries.

Through participation in the MJHMP, Watsonville has identified its highest priority hazards, developed hazard specific problem statements, and proposed actionable strategies to reduce risks. By aligning with countywide partners and leveraging regional resources, Watsonville has strengthened its capacity to prepare for, withstand, and recover from disasters while continuing to protect its unique coastal community character.

3.4.1 Mitigation Activities

The city has successfully implemented several initiatives aimed at addressing identified vulnerabilities. These accomplishments are highlighted in this section and have directly contributed to reducing risks from hazards such as flooding, all hazards, and severe weather. These completed projects showcase Watsonville's ability to effectively plan, fund, and execute measures that protect its residents and infrastructure.

In addition, Watsonville has systematically reviewed and adjusted its mitigation actions, exemplifying adherence to FEMA's Planning Policy Guide principles and emphasizing the importance of dynamic and

adaptive mitigation planning. By fostering partnerships, leveraging funding opportunities, and prioritizing equity in implementation, the city aligns with best practices to build resilience against natural disasters. This ongoing effort is a testament to the city's commitment to the principles of risk-informed decision-making, equitable resource allocation, and integration with broader regional and state hazard mitigation objectives.

Adjustments to Previous Mitigation Actions

A significant portion of the city's mitigation efforts remain ongoing or in the pipeline. These actions, ranging from infrastructure upgrades to community outreach initiatives, represent the city's proactive approach to addressing hazards as resources become available.

Recognizing constraints such as limited funding and shifting priorities, the city has reevaluated certain initiatives, leading to their reprioritization or canceling of mitigation actions. Factors such as feasibility, cost-effectiveness, and emerging risks informed these decisions, ensuring alignment with the city's updated hazard mitigation goals. Adjustments to previous mitigation actions are documented as part of the City of Watsonville's Mitigation Action Plan in Table 3-15, and more specific status updates are provided in Table 3-16.

3.4.2 Mitigation Successes

Watsonville General Plan 2050

The City of Watsonville General Plan was last comprehensively updated in 1994. The city initiated a comprehensive update in 2023 and the updated plan, Watsonville General Plan 2050, is expected to be adopted by Fall 2025. The update includes an update to the Safety Element to reference the Santa Cruz Multi-Jurisdiction Hazard Mitigation Plan. Watsonville General Plan 2050 anticipates new growth occurring in undeveloped portions of Atkinson Lane and Manabe/Burgstrom. Watsonville General Plan 2050 also will address changes to State Law that apply to General Plans.

Watsonville 2030 Climate Action & Adaption Plan

The Watsonville City Council adopted the Watsonville 2030 Climate Action & Adaption Plan in July 2021. The plan sets in motion a suite of programs that are designed to reduce the community's greenhouse gas emissions to 80% lower than levels in 1990 by 2030, meeting a State-mandated legal target. The plan provides a roadmap to reduce the community's greenhouse gas emissions, combat the impacts of climate change, and explore carbon sequestration and habitat restoration.

Infrastructure Projects

The City of Watsonville is undertaking a number of infrastructure projects. These projects include the Water Main Replacement Project, Roache Well & Pump Station, Freedom/Green Valley Water & Sewer Improvements, Hames Reservoir Interior Coating & Connection Modifications, and Sydney & Jehl Avenue Sewer, Storm, & Water Improvements. These projects can assist the City of Watsonville at improving resiliency to extreme temperatures, drought, and climate change.

3.5 Risk Assessment

This section focuses on profiling hazards specific to the City of Watsonville and assessing their vulnerability independent of the broader county-wide planning area, which has been evaluated in Section 3 of Volume 1. The hazard profiles in Volume 1 discuss overall impacts to the planning area and describe relevant plans, policies, and regulations; past events; location; frequency and probability of future occurrences; severity and extent; warning time; secondary hazards; and climate change impacts. For more information on risk assessment methodologies, see Volume 1, Appendix A.

This section includes a tailored vulnerability assessment, analyzing assets at risk such as population, property, and critical facilities and infrastructure unique to the city, and information on city-specific differences in hazard vulnerability across the planning area. It also identifies total city assets at risk, including people, property, and critical facilities and infrastructure within the city. In addition, this section presents growth and development trends for the community, offering insights into vulnerabilities and risks that represent the broader context of assets at risk.

3.5.1 Hazard Screening & Prioritization

Members of the Planning Team from each participating jurisdiction came together to collaboratively decide which hazards would be included in the MJHMP and which would be excluded. The hazard screening and prioritization process integrated historic data, local knowledge, and consensus opinions to create a risk assessment matrix for the county as well as for each participating jurisdiction. These matrices indicate the priority of each profiled hazard. Details about this process, the results of the discussion, and in-depth profiles for county-wide hazards can be found in Volume 1, Section 3.

The City of Watsonville's internal planning group used the same hazard identification and prioritization process as the county-wide Planning Team. They reviewed previously prepared hazard mitigation plans and other relevant documents to determine the realm of natural hazards that have the potential to affect the city. Table 3-10 provides a crosswalk of hazards identified in the City of Watsonville's Geneal Plan, the 2021 Santa Cruz County MJHMP, and the 2023 State of California HMP. The crosswalk was used to develop a preliminary hazards list, providing a framework for the group to evaluate which hazards were truly relevant to the City of Watsonville and which ones were not.

The internal planning group then ranked hazards based on their probability of affecting City of Watsonville and potential impacts on the community. Figure 3-12 displays the results of the hazard risk ranking exercise that was performed. After reviewing the capabilities of the city, the Planning Team decided to profile Coastal Erosion, Sea-level Rise, Earthquake, Wildfire, Flood, Drought, High Winds, Winter Storms, Tsunami, and Slope Failure. All hazards have been profiled in Volume 1 of this document. The purpose of this annex is to specifically address the city's vulnerability to specifically identified hazards.

Table 3-10: City Document Review Crosswalk

Hazard	City of Watsonville General Plan 2005*	Santa Cruz County LHMP 2021	2023 California State HMP
Agricultural Pests			■
Avalanche			■
Climate Change		■	■
Dam Failure	■	■	■
Drought	■	■	■
Earthquake	■	■	■
Extreme Heat		■	■
Extreme Weather		■	■
Flood	■	■	■
Hazardous Materials	■		■
Human-Caused	■		■
Insects			■
Landslide		■	■
Levee Failure			■
Pandemic Disease			■
Sea Level Rise			■
Terrorism / Tech			■
Tsunami			■
Volcanic			■
Wildfire	■	■	■

**May Include additional elements such as safety element.*

Risk Assessment Matrix Definitions

PROBABILITY RATING

The likelihood of a hazard event occurring within a time period?

PROBABILITY

Highly Likely	**Highly likely** - 100% annual probability. Or Likely to occur every year in your lifetime.
Likely	**Likely** - between 10 & 100% annual probability. Or will occur several times in your lifetime.
Possible	**Possible** - between 1 & 10% annual probability. Or Likely to occur some time in your lifetime.
Unlikely	**Unlikely** - less than 1% annual probability. Or unlikely but possible to occur in your lifetime.

IMPACT RATING

In terms of injuries, damage, or death, would you anticipate impacts to be minor, limited, critical, or catastrophic when a significant hazard event occurs? The impact could be in terms of one hazard event (flooding from a culvert failure) or a large-scale event (multiple rivers flooding) in the same jurisdictional boundary.

IMPACT

Minor	Limited	Critical	Catastrophic

Minor - very few injuries, if any. Only minor property damage & minimal disruption on quality of life. Temporary shutdown of critical facilities.

Limited - minor injuries only. Approx. 10% or less of property in disaster footprint damaged or destroyed. Complete shutdown of critical facilities for more than one day.

Critical - multiple deaths/injuries possible. Between 25% and 50% of property in disaster footprint is damaged or destroyed. Complete shutdown of critical facilities for more than one week.

Catastrophic - high number of deaths/injuries possible. More than 50% of property in affected area damaged or destroyed. Complete shutdown of critical facilities for 30 days or more.

To concentrate resources, the jurisdictional planning team will focus on "High" and "Extreme" risk hazards. These hazards have the higher probability and greater impact as it relates to the jurisdictions planning area.

Hazard definitions are included in **Vol. 1** of this plan. Some hazards are discussed as subset hazards— e.g., "Dam Failure" within the "Flood" hazard profile. If a hazard is not present on the risk matrix or are grey in color, the jurisdictional planning team felt the hazard had a minimal footprint within their planning area and was not ranked.

Hazard Information / Legend:

CLIMATE CHANGE

Climate Change impacts will be addressed at the end of each hazard section and as a stand alone section for each jurisdiction.
For County and Municipal governments you will be required to address climate change impacts in the Safety Element of your General Plan. Climate change may change the frequency, duration and intensity of hazards listed above.

City of Watsonville Risk Matrix



Figure 3-12: City of Watsonville - Risk Assessment Matrix

3.5.2 Vulnerability to Specific Hazards

Assessing vulnerabilities exposes the unique characteristics of individual hazards and begins the process of narrowing down which areas within the city are vulnerable to specific hazard events. The vulnerability assessment considered unique local knowledge of hazards and impacts and a GIS overlaying method for examining such vulnerabilities in more depth. Using these methods, the city's planning group estimated vulnerable populations, properties, and assets, and potential losses, primarily to flood hazards. In addition, the exposure of city assets to drought, geological, earthquake, wildfire and slope failure were also considered.

Many of the hazard profiles include a snapshot map and damage estimation tables that illustrate the city's vulnerabilities to those specific hazards. These maps assisted the planning group in understanding the hazard exposure of populations, parcels, and critical facilities and infrastructure. Each snapshot map contains an exposure summary that displays the percentage of the population, the improvement and content value of parcels, and the amount of critical infrastructure that is exposed. For hazards without geospatial extents, such as drought and extreme weather, narratives are provided instead of exposure maps and tables.

Based on the hazard prioritization exercise, this vulnerability assessment focuses on eight hazards for the City of Watsonville, some of which encompass subhazards such as Levee Failure, Liquefaction, and Heavy Rain.

Wildfire
SECTION 3.5.2.1

Flood
SECTION 3.5.2.2

Earthquake
SECTION 3.5.2.3

Severe Weather
SECTION 3.5.2.4

Slope Failure
SECTION 3.5.2.5

Drought
SECTION 3.5.2.6

Extreme Heat
SECTION 3.5.2.7

Climate Change
SECTION 3.5.2.8

3.5.2.1 Wildfire Hazard

Watsonville is located in a river valley, with its urban edges extending into areas of grasslands, foothills, and wildland vegetation that create localized wildfire risk. While most of the city is urbanized and at low wildfire risk, Figure 3-13 shows that the northwest portion of Watsonville lies within CAL FIRE–designated moderate to high wildfire hazard zones. These areas coincide with the wildland-urban interface (WUI), where residential neighborhoods are located adjacent to flammable vegetation.

Exposure within city limits is relatively limited: only 18 residents and 2 parcels fall within mapped wildfire hazard zones. However, approximately 21 transportation and lifeline assets (2% of the citywide total) are also located in these zones, highlighting risks to local road access and emergency response. While structural exposure is modest, wildfire can still have disproportionate impacts on vulnerable populations and critical systems.

Watsonville residents living near the WUI, especially seniors, limited-English speakers, and other dependent populations, face evacuation challenges due to limited road access, lack of route redundancy, and barriers to emergency communication. Multiple critical facilities, including emergency shelters, water infrastructure, and hazardous materials storage sites, are also located in wildfire-prone areas, where fire-related damage or service interruption could result in cascading impacts.

Although wildfire has historically been a lower priority hazard compared to flooding and earthquakes, climate change is expected to increase wildfire risk across the region. Hotter and drier conditions, combined with fuel accumulation and the expansion of development into flammable landscapes, are heightening the city's exposure. Even localized fire events near the city's perimeter could disrupt transportation corridors, threaten utilities, or require rapid evacuations of at-risk populations.

For Watsonville, wildfire risk management should focus on protecting vulnerable populations at the WUI, hardening critical facilities, maintaining defensible space, and strengthening evacuation planning and communication systems. Continued collaboration with CAL FIRE, Santa Cruz County Fire, and neighboring jurisdictions will be essential to reducing wildfire risk along Watsonville's edges while ensuring equitable protection for the city's most at-risk residents.



Figure 3-13 City of Watsonville - Wildfire Risk Exposure Map

3.5.2.2 Flood Hazard

Flooding is one of the most significant hazards facing the City of Watsonville, posing risks to residents, businesses, critical infrastructure, and the local economy. The city's location along the Pajaro River and its tributaries, combined with flat low-lying topography and extensive development within the floodplain, has resulted in a long history of damaging flood events. In addition to riverine flooding, Watsonville is also vulnerable to localized stormwater flooding and levee failures, threats that are expected to worsen with climate change and sea level rise.

Location & Extent

The city's location at the confluence of the Pajaro River Basin and the Watsonville Slough watershed places much of the community at high risk of inundation. The eastern and downtown neighborhoods drain into the Pajaro River and its tributaries, Salsipuedes Creek and Corralitos Creek, while the central and western areas drain into the Watsonville Slough system, including Harkins, Struve, and West Struve Sloughs. These waterways, combined with Watsonville's flat topography and aging levee infrastructure, create multiple pathways for flooding.

Flooding in Watsonville can occur in several ways. In some neighborhoods, inadequate interior drainage results in shallow urban flooding, typically less than three feet in depth. More severe events occur when the Pajaro River or Salsipuedes Creek levees are overtopped or fail, a scenario that the U.S. Army Corps of Engineers has indicated is likely during a 100-year storm event. Overflow of Corralitos Creek upstream of the levees presents another chronic concern, particularly in the eastern half of the city, where floodwaters cannot re-enter the channel once overtopped. FEMA Flood Insurance Rate Maps (FIRMs) designate much of Watsonville as Special Flood Hazard Areas (SFHAs), classified as Zones A, AO, AH, and AE, with additional risk represented by shaded Zone X (0.2% annual chance flood).

Historical Flooding

Watsonville has a long history of damaging flood events. The 1955 and 1958 Pajaro River floods remain the largest on record, producing discharges of 24,000 and 23,500 cubic feet per second at the Chittenden gauge. Both events caused widespread inundation, with recurrence intervals of roughly 25 years. More recent floods in 1995 and 1998 also resulted in extensive property and infrastructure damage due to levee overtopping and failures. These events underscore the chronic nature of Watsonville's flood risk and the vulnerabilities that persist today.

Flood Risk Exposure

FEMA Flood Risk Exposure mapping (Figure 3-14) highlights the scale of Watsonville's exposure. Approximately 11,470 residents, about 22% of the city's population, and 2,084 parcels (20% of total) lie within the FEMA 100-year and 500-year flood hazard zones. The total improvement value at risk is estimated at $1.92 billion, with an additional $1.72 billion in contents value. Critical facilities are also threatened, including three essential facilities (43% of citywide total), 50 hazardous material sites (30%), and more than 1,500 transportation and lifeline assets (81%), reflecting the potential for community-wide disruption during a major flood.



Figure 3-14: City of Watsonville - FEMA Flood Risk Exposure

Social Vulnerability & At-Risk Populations

Flood impacts are disproportionately borne by Watsonville's most vulnerable residents. Elderly individuals living near the Pajaro River face mobility challenges during evacuation, while low-income and Spanish-speaking households in downtown and industrial flood zones may lack access to warnings, insurance, and recovery programs. These barriers increase the likelihood of prolonged displacement and financial hardship after a disaster.

Critical Facilities & Infrastructure Risks

Key city facilities, including the wastewater treatment plant and police station, are within the 1% annual chance floodplain. Flooding also disrupts stormwater systems and roadways in downtown and east Watsonville, causing business closures and limiting emergency access. The Watsonville Slough system faces contamination risk during flood events, threatening a critical backup water supply for drought periods.

Chronic Threats & Climate Change

Watsonville faces chronic flood risk from the Pajaro River and nearby creeks, made worse by aging levees and more intense storms linked to climate change. Ongoing urbanization has increased impervious surfaces, contributing to greater stormwater runoff and more frequent localized flooding. In addition, FEMA's flood maps are outdated and do not adequately account for sea level rise, sedimentation, or storm surge interaction with local sloughs, leading to an underestimation of future exposure

3.5.2.2.1 Levee Failure

Levee failure is a significant subhazard of riverine flooding in Watsonville, with the Pajaro River levee system representing one of the city's most critical sources of flood risk. Levees are designed to protect low-lying areas by containing river flows within a defined channel during high-water events. While they reduce the frequency of flooding, they do not eliminate risk. Levee failure can occur through overtopping during extreme storms, erosion of embankments, seepage beneath or through the levee structure, or collapse caused by prolonged saturation or foundation instability.

The Pajaro River levee system, constructed in the late 1940s, provides flood protection to Watsonville, the unincorporated community of Pajaro in Monterey County, and surrounding agricultural lands. However, the levees are widely recognized as under-designed for current hydrologic conditions and have a documented history of failures, including during the March 2023 atmospheric river event, when a major breach inundated large portions of Pajaro and prompted mass evacuations in both Monterey and Santa Cruz Counties. By contrast, the San Lorenzo River levee system in Santa Cruz has been upgraded in recent decades, but the Pajaro River levees remain vulnerable despite ongoing efforts such as the Pajaro River Flood Risk Management Project.

A levee breach poses a particularly severe hazard because the sudden release of impounded water can produce deeper, faster-moving floods than natural overbank events, leaving little time for evacuation. In

Watsonville, levee failure would threaten residential neighborhoods, critical infrastructure, major roadways, and agricultural areas, with consequences including property loss, prolonged service disruptions, contamination of water supplies, and risks to human safety. Factors that increase the likelihood of levee failure in Watsonville include:

- Extreme storm events exceeding the design capacity of the Pajaro River levees.
- Deferred maintenance, including erosion, vegetation, or burrowing animals that weaken structural integrity.
- Prolonged high flows, leading to seepage or internal erosion (piping).
- Seismic activity, which could compromise levee stability.
- Climate change, with more intense rainfall events increasing hydraulic stress on the levee system.

Given the central role of the Pajaro River levees in protecting Watsonville, levee failure remains one of the city's most acute and consequential flood hazards.

Figure 3-15: Pajaro River Levee System Source: Santa Cruz County

Implications for Hazard Mitigation

Flooding remains Watsonville's highest-impact hazard, threatening residents, infrastructure, and critical services. The Pajaro River Flood Risk Management Project is an essential regional investment to address levee deficiencies and reduce long-term flood exposure. At the local level, Watsonville must also prioritize:

- Upgrading stormwater infrastructure to reduce urban flooding.
- Floodproofing and elevating critical facilities to maintain essential services.
- Updating hazard maps to incorporate climate change and sea level rise.
- Equitable outreach and engagement, ensuring elderly, low-income, and Spanish-speaking populations receive accessible preparedness resources.

By combining structural investments with equity-focused strategies, Watsonville can reduce both the physical and social impacts of future floods, enhancing long-term resilience for the entire community.

Growth & Flood Hazard Overlap in Watsonville

Future growth in Watsonville is expected to occur through a mix of downtown infill, station area development, and expansion into designated growth areas at the city's edges. While these areas align with the city's long-term goals for compact, transit-oriented development, a closer look at flood hazard exposure reveals that many of these sites overlap with FEMA-designated floodplains and areas historically vulnerable to levee overtopping and stormwater flooding.

The Downtown Infill and Station Area are central to Watsonville's growth strategy, but they are also among the areas of highest flood exposure. FEMA flood maps show that much of the downtown core lies within the 100-year and 500-year floodplains of Struve Slough and Corralitos Creek, exposing future housing and commercial development to recurrent flooding. Without targeted floodproofing and stormwater infrastructure improvements, these projects could increase the concentration of vulnerable populations in high-risk areas.

Similarly, the Highway 1 Gateway growth area lies adjacent to the Harkins and Struve Sloughs, both identified on FEMA maps as subject to flooding. This means that new residential or commercial development here will likely face shallow flooding hazards and water quality concerns, especially during major storm events when slough systems overtop.

In the northeast, Area C (Atkinson Lane) overlaps with flood zones associated with Corralitos and Salsipuedes Creeks. Historical accounts and hydrologic studies note that floodwaters from Corralitos Creek, once overtopped, cannot easily re-enter the channel downstream due to levee confinement. Growth in this area would therefore bring new residents and assets into areas already challenged by recurring flood problems.

By contrast, the northwest growth area at Buena Vista (Area A) is largely outside mapped flood hazard zones. This location represents one of the few areas where Watsonville can accommodate new growth without directly placing additional population and assets into high flood risk zones.

Taken together, this analysis shows that Watsonville's most significant areas of planned growth—downtown, station areas, Atkinson Lane, and the Highway 1 Gateway—are also areas of concentrated flood risk. While this supports smart-growth principles, it underscores the importance of integrating hazard mitigation into future land use planning. Investments in levee improvements, stormwater system upgrades, resilient design standards, and climate-informed flood mapping will be essential to ensure that Watsonville's growth does not also amplify its vulnerability to flooding.

National Flood Insurance Program

The National Flood Insurance Program (NFIP) makes federally backed flood insurance available to homeowners, renters, and business owners in participating communities. FEMA has prepared a detailed Flood Insurance Study (FIS) for Santa Cruz County and municipalities. The study presents water surface elevations for floods of various magnitudes, including the 1% annual chance flood (100-YR flood) and the 0.2% annual chance flood (500-YR flood). Base flood elevations and the boundaries of the 100- and 500-YR floodplains are shown on Flood Insurance Rate Maps (FIRMs), which are the principal tools for identifying the extent and location of the flood hazard. FIRMs are the most detailed and consistent data source available, and for many communities they represent the minimum area of oversight under their floodplain management program. See Section 4 of Volume 1 for general information on the NFIP.

The City of Watsonville has participated in the NFIP since 1984 and has adopted the most recent FIRMs and FIS issued by FEMA (effective on August 3, 2016) as well as local floodplain development regulations in compliance with the minimum NFIP standards. These minimum standards include procedures and provisions for substantial improvements and substantial damages to existing structures, in accordance with NFIP requirements. By code, implementation and enforcement of the city's floodplain regulations are assigned to the City Administrator, City Clerk, or County Building Official. Currently, the City Administrator serves as the floodplain administrator.

The City of Watsonville is currently in good standing with the provisions of the NFIP. Compliance is monitored by FEMA regional staff and by the California Department of Water Resources under a contract with FEMA. Maintaining compliance under the NFIP is an important component of flood risk reduction. See Table 3-11 for more information on the City's policies and historic flood insurance claims.

Table 3-11: City of Watsonville - National Flood Insurance Program Information

City of Watsonville NFIP Status and Flood Insurance Statistics	
NFIP Status	Participating Since 1984
Community Identification (CID)	060357
CRS Class (Entry Date)	Class 8 (October 1992)
Policies in Force (Total Coverage)	360 Policies ($100,866,000 in Coverage)
Policies Inside SFHA / Outside SFHA	234 Inside / 36 Outside
Total Claims (Total Paid)	144 Claims ($1,623,932 Paid)
Repetitive Loss (RL) / Severe Repetitive Loss (SRL) Properties	3 RL / 0 SRL
Repetitive Loss Payments	$107,891 for Buildings / $2,677 for Contents

Note: The number of policies is by property and does not count policies for individual buildings. The Privacy Act of 1974 (5 USC 522a) restricts the release of certain types of data to the public. Flood insurance policy and claims data is included in the list of restricted information. FEMA can only release such data to state and local governments, and only if the data is used for floodplain management, mitigation, or research purposes. Therefore, this plan does not identify the repetitive loss properties or include claims data for any individual property.

Community Rating System

The City of Watsonville has participated in FEMA's Community Rating System (CRS) since October 1, 1992. The CRS is a voluntary program under the National Flood Insurance Program (NFIP) that rewards communities for implementing floodplain management practices beyond NFIP minimum standards. Participation provides flood insurance policyholders with reduced premiums while encouraging local investment in flood risk reduction.

Watsonville currently holds a Class 8 rating, which provides all policyholders within FEMA-designated Special Flood Hazard Areas (SFHAs) with a 10% discount on annual flood insurance premiums (FEMA CRS Eligible Communities, 2022).

Over the years, Watsonville has supported projects, programs and other flood mitigation measures that have reduced repetitive loss risk and helped property owners lower their flood insurance costs. Funding sources for these projects have included FEMA Hazard Mitigation Assistance grants, Community Development Block Grant (CDBG) programs, and Army Corps/State Reclamation Board initiatives. Some projects have been completed, while additional properties remain in need of elevation or retrofit to meet current flood protection standards.

Through CRS, the city also documents and addresses repetitive loss properties, earning credits for activities that reduce the likelihood of future claims. Each class improvement in CRS corresponds to an additional 5% premium discount for policyholders in SFHAs. By expanding CRS activities—such as higher building standards, enhanced public outreach, and integration of Pajaro River levee improvements—Watsonville has the opportunity to pursue a Class 7 rating, which would increase flood insurance discounts to 15% while further strengthening resilience to flooding.

3.5.2.3 Earthquake Hazard

Watsonville is located in a seismically active region of California and is highly susceptible to the impacts of earthquakes due to its proximity to the San Andreas Fault and several local active faults, including the Zayante and Butano, which can produce earthquakes in the magnitude 6.4–7.4 range. While no active faults run directly through the city, the entire community is exposed to strong ground shaking and secondary hazards such as liquefaction. A scenario magnitude 7.1 earthquake on the San Andreas Fault in the Santa Cruz Mountains demonstrates the scale of this hazard. Based upon this modeled event, Figure 3-16 shows that all of Watsonville would experience strong to very strong shaking.

Older residential structures, many of which predate modern seismic codes, are particularly vulnerable to collapse or severe damage. Disadvantaged residents, including renters and mobile home occupants, face elevated risks because they may lack earthquake insurance, adequate emergency supplies, or the ability to afford post-disaster repairs, leaving them vulnerable to long-term displacement. The city also contains a small number of unreinforced masonry buildings in the downtown core and industrial areas, which are at high risk of failure in strong seismic events.

Seismic events also threaten Watsonville's lifeline systems. A major earthquake could disrupt pipelines, water storage tanks, wastewater infrastructure, and electrical facilities, leading to cascading service failures and long-term outages. Shaking may also damage roadways, bridges, and culverts, delaying emergency response and evacuation efforts. Beyond shaking damage, liquefaction poses a severe secondary hazard across much of the city due to its soft soils and high groundwater table. Figure 3-17 shows that more than 23,000 people, 4,500 parcels, and three essential facilities are in liquefaction hazard zones.

Finally, Watsonville lacks a formal program to inventory and retrofit its highest-risk buildings, such as unreinforced masonry or soft-story structures. This leaves well-documented vulnerabilities unaddressed. Together, these factors illustrate that earthquakes remain one of the most consequential hazards for Watsonville, threatening not only lives and property but also critical infrastructure, lifeline systems, and the city's most vulnerable populations.



Figure 3-16: Exposure Summary – City of Watsonville Earthquake Risk (M7.1 San Andreas Shaking)



Figure 3-17: Exposure Summary – City of Watsonville Liquefaction Risk

3.5.2.4 Severe Weather Hazard

Severe storms are a recurring hazard in Watsonville, typically driven by high winds, heavy rainfall, and atmospheric river events during the winter months. While tornadoes, hail, and snow are rare in the region, severe storm impacts can be significant due to the city's vulnerable infrastructure, older housing stock, and concentrations of at-risk populations.

Residents in mobile homes and older housing, many of whom are low-income or elderly, are particularly vulnerable during storm events. These households face heightened risks from power outages, mobility limitations, and health impacts during prolonged high-wind or heavy-rain events.

High winds frequently cause downed trees and power lines in and around Watsonville, leading to widespread power outages, communication disruptions, and blocked roadways. Such conditions strain emergency response capabilities, delay evacuations, and exacerbate challenges for dependent populations.

Heavy rainfall during atmospheric river events can overwhelm Watsonville's aging stormwater infrastructure, especially in older downtown areas and low-lying neighborhoods near culverts and sloughs. These localized flash floods result in hazardous road conditions, temporary isolation of neighborhoods, and damage to property and infrastructure.

Severe storm frequency and intensity are projected to increase because of climate change. Watsonville already faces frequent winter storms and recurring atmospheric rivers, which are contributing to repeated road closures, localized flooding, and long-term infrastructure strain. Climate-driven changes to storm severity highlight the city's continued vulnerability to cascading hazards, including flooding and slope instability along the slough system.

While severe storms in Watsonville may not produce catastrophic destruction, their compounding effects on vulnerable populations, lifeline infrastructure, and mobility make them a critical hazard for ongoing mitigation planning. Strategies to reduce risk should prioritize hardening power and drainage systems, enhance stormwater infrastructure, and develop targeted preparedness and response measures that reach the city's most at-risk residents.

3.5.2.5 Slope Failure Hazard

Slope failure, which includes landslides and localized slope instability, is a secondary but important hazard for the City of Watsonville. These events are typically triggered by earthquakes, prolonged rainfall, loss of vegetation, or grading activities. Although most of Watsonville lies on relatively flat terrain, slope failure risk is concentrated along the banks of the Watsonville Slough system and in limited hillside neighborhoods on the western and northern edges of the city.

Figure 3-18 illustrates the areas of Watsonville mapped as highly susceptible to slope failure. Nearly 2,200 residents and more than 250 parcels are located in these zones. The total value of improvements at risk is estimated at $172 million, with an additional $95 million in contents value. Critical facilities are not widely exposed; however, several transportation and lifeline assets (4% of citywide total) are located within mapped hazard areas, reflecting the potential for slope failures to interrupt connectivity and access.

Slope failure has the potential to damage roadways, culverts, and underground utilities, restricting emergency access and service delivery in affected neighborhoods. The city's underlying geology, including Santa Margarita Sandstone and Santa Cruz Mudstone formations, is particularly prone to landslides when exposed to heavy rainfall or seismic shaking, conditions that can exacerbate slope instability.

While slope failure is less widespread than flooding or earthquakes in Watsonville, its impacts can be severe at the neighborhood scale, isolating residents and disrupting critical services. Mitigation efforts should focus on monitoring unstable slopes along slough banks, restricting future development in high-susceptibility zones, and stabilizing vulnerable areas where feasible, while also integrating slope failure risk into emergency access planning.



Figure 3-18 City of Watsonville - Landslide Risk Exposure Map

3.5.2.6 Drought Hazard

Drought is a chronic hazard for Watsonville and the Pajaro Valley, with conditions recurring regularly over the past two decades. As shown in Figure 3-19, Santa Cruz County has experienced multiple prolonged drought cycles since 2000, including exceptional drought (D4) conditions between 2014–2016 and again during 2021–2022. These cycles have had profound impacts on local water supply, agriculture, and vulnerable populations.

Watsonville depends heavily on the Pajaro Valley Groundwater Basin, which is already overdrafted and subject to chronic depletion. Extended drought reduces recharge of aquifers and surface water flows, placing stress on municipal wells and water supplies for fire suppression. Declining groundwater levels also heighten the risk of saltwater intrusion from Monterey Bay into the Pajaro Valley Basin, further threatening long-term water quality and reliability.

Drought impacts disproportionately affect low-income residents, farm workers, and disadvantaged households, who may face rising utility costs, stricter water use restrictions, and employment disruptions in the agriculture and food processing sectors. In rural and fringe neighborhoods where residents rely on shallow or aging wells, prolonged drought increases the risk of well failure or degraded water quality, further exacerbating inequities in water access.

Climate change is expected to intensify the frequency and duration of multi-year droughts, increasing Watsonville's dependence on the already overdrawn Pajaro Valley Basin. The city's limited storage capacity compounds this vulnerability, leaving residents and agricultural operations more exposed to recurring water shortages. Drought conditions also interact with other hazards, such as increasing wildfire risk by drying vegetation and reducing water available for suppression.

Building resilience to drought in Watsonville will require expanding groundwater recharge projects, investing in water conservation and efficiency programs, and advancing equitable drought planning that prioritizes at-risk communities. Collaboration with the Pajaro Valley Water Management Agency, local farmers, and regional partners remains critical to ensuring long-term water security for residents, agriculture, and the local economy.

Table 3-12: Drought Classifications and Impacts

Category	Description	Possible Impacts
D0	Abnormally Dry	▪ Soil is dry; irrigation delivery begins early ▪ Dryland crop germination is stunted ▪ Active fire season begins
D1	Moderate Drought	▪ Dryland pasture growth is stunted; producers give supplemental feed to cattle ▪ Landscaping and gardens need irrigation earlier; wildlife patterns begin to change ▪ Stock ponds and creeks are lower than usual
D2	Severe Drought	▪ Producers increase water efficiency methods and drought-resistant crops ▪ Grazing land inadequate ▪ Fire season is longer, with high burn intensity, dry fuels, and large fire spatial extent; more fire crews on staff ▪ Lake- and river-based tourism declines; boat ramps close ▪ Trees are stressed; plants increase reproductive mechanisms; wildlife diseases increase ▪ Water temperatures increase; programs to divert water to protect fish begin ▪ River flows decrease; reservoir levels are low and banks are exposed
D3	Extreme Drought	▪ Federal water not adequate to meet irrigation contracts; extracting supplemental groundwater is expensive ▪ Fire season lasts year-round; fires occur in typically wet parts of the state; burn bans are implemented ▪ Ski and rafting business is low; mountain communities suffer ▪ Low water levels impede fish migration and cause lower survival rates ▪ Wildlife encroach on developed areas; little native food and water is available for bears, which hibernate less ▪ Water sanitation is a concern; reservoir levels drop significantly; surface water is nearly dry, flows are very low; water theft occurs ▪ Livestock need supplemental feed, cattle and horses are sold; little pasture remains ▪ Well and aquifer levels decrease; homeowners drill new wells
D4	Exceptional Drought	▪ Fire season is very costly; number of fires and areas burned are extensive ▪ Many recreational activities are affected ▪ Fields are left fallow; orchards are removed; vegetable yields are low; honey harvest is small; agricultural unemployment is high, food aid is needed ▪ Fish rescue and relocation begins; pine beetle infestation occurs; forest mortality is high; wetlands dry up; wildlife death is widespread; algae blooms appear ▪ Poor air quality affects health; greenhouse gas emissions increase as hydropower production decreases; West Nile outbreaks rise ▪ Water shortages are widespread; surface water is depleted; federal irrigation water deliveries are curtailed; water prices are extremely high; wells are dry, more and deeper wells are drilled; water quality is poor

Source: Adapted from U.S. Drought Monitor Drought Classifications and Impacts



Figure 3-19: Drought Severity Timeline 2000-2024

3.5.2.7 Extreme Heat Hazard

The city's inland valley location and reliance on outdoor agricultural labor make it particularly sensitive to rising temperatures and more frequent extreme heat days. While the coastal influence of Monterey Bay provides some natural moderation, climate change is projected to increase both the frequency and intensity of heat waves in the region, posing growing risks to public health, agriculture, and infrastructure.

Heat waves are becoming more common across California, with projections showing a significant rise in the number of extreme heat days by mid-century. In Watsonville, outdoor agricultural workers face elevated risks during extreme heat events, particularly those without access to shaded rest areas, cooling stations, or protective equipment. Seniors, low-income residents, and individuals in older housing stock without air conditioning are also especially vulnerable to heat-related illness and may lack transportation to reach cooling centers.

The city's population exposure is compounded by socioeconomic factors. Many households in Watsonville are cost-burdened and lack adaptive measures such as air conditioning or urban tree canopy coverage, increasing health risks during prolonged heat events. This mirrors statewide findings that low-income and minority populations are disproportionately affected by extreme heat.

The frequency of extreme heat days is projected to rise significantly across inland Santa Cruz County by mid-century. For Watsonville, this means disproportionate impacts on agricultural workers in the Pajaro Valley as well as low-income neighborhoods with limited adaptive capacity. By the end of the century, the number of warm nights—when temperatures remain elevated and prevent recovery from daytime heat—is also projected to increase dramatically.

Extreme heat often coincides with elevated wildfire risk, reduced air quality from ozone and particulates, and public safety power shutoffs designed to prevent utility-caused ignitions. These secondary hazards can compound vulnerabilities by cutting access to cooling or disrupting medical care reliant on electricity.

3.5.2.8 Climate Change Hazard

Climate change is a cross-cutting hazard that intensifies the risks posed by flooding, drought, wildfire, severe storms, and extreme heat. For Watsonville, located in the Pajaro Valley at the intersection of coastal, riverine, and agricultural systems, climate change is already evident in more frequent atmospheric rivers, longer drought cycles, and hotter summers. Projections show these stressors will continue to worsen through mid- and late-centuries, compounding risks across natural and built environments.

Vulnerable Populations

Watsonville's most vulnerable residents—including seniors, renters, farmworkers, low-income households, and limited-English communities—are disproportionately at risk from climate-driven hazards. These groups often face barriers such as limited financial resources, lack of insurance, or reduced mobility during emergencies. Farm workers are directly exposed to rising temperatures and wildfire smoke during agricultural labor, while renters in older housing may lack cooling, insulation, or flood protection measures.

Stress on Critical Systems

Climate change amplifies stress on critical infrastructure systems. Heavier rainfall and atmospheric rivers test aging stormwater networks, while drought reduces groundwater recharge in the overdrafted Pajaro Valley Basin. Energy systems are increasingly strained during heat waves and Public Safety Power Shutoffs (PSPS), while transportation networks are vulnerable to both flood damage and wildfire-related closures. These cascading disruptions highlight the interdependence of lifeline systems and the growing need for redundancy and resilience planning.

Projected Hazards & Future Risks

Climate projections indicate an increase in both frequency and intensity of hazards, including extreme heat, severe winter storms, drought, wildfire, and sea-level rise. Sea-level rise is expected to elevate flood risk along the Pajaro River and adjacent sloughs, threatening Watsonville's neighborhoods and agricultural economy. Extreme heat days are projected to rise sharply by mid-century, disproportionately affecting outdoor workers and inland communities. These overlapping threats compound and cascade, magnifying risks across sectors and lengthening recovery times.

3.5.3 Planning for Hazards & Growth

As a charter city, Watsonville manages growth within the framework of its municipal charter while also adhering to California's planning, zoning, subdivision, and environmental regulations. Watsonville is bordered by prime agricultural lands, the Pajaro River, and an extensive network of sloughs, meaning future growth will occur primarily through infill development and redevelopment of underutilized properties within the existing urban footprint. This growth pattern places new development in areas already exposed to hazards, including flooding along the Pajaro River and local creeks, liquefaction-prone soils, and localized stormwater flooding in low-lying neighborhoods.

By coordinating with the General Plan Safety Element, hazard vulnerability is integrated into land use decisions, infrastructure investments, and redevelopment approvals. This approach satisfies state and federal requirements for hazard mitigation planning and positions Watsonville to pursue disaster recovery and resilience funding.

Climate change is expected to intensify hazards such as flooding, severe storms, drought, wildfire at the wildland urban interface, and extreme heat. For Watsonville, where much of the city lies within flood-prone areas of the Pajaro Valley, this means that new projects must be designed with resilience in mind. Growth management therefore emphasizes sustainable building practices, water conservation, agricultural preservation, and integration of climate adaptation strategies to ensure that redevelopment and infill do not increase existing risks.

Long-Range Planning & Growth Management

Planning for future growth in the City of Watsonville requires a proactive approach that balances development needs with hazard awareness and risk reduction. As Watsonville continues to evolve, careful planning and compliance with state and local standards are essential to safeguard public safety, protect infrastructure, and reduce vulnerabilities. By embedding hazard mitigation into long-range planning and growth management, the city strengthens its overall resilience to natural hazards.

The General Plan serves as Watsonville's overarching blueprint for growth and community priorities, addressing land use, circulation, housing, utilities, open space, conservation, noise, and public safety. Within it, the Safety Element establishes policies to address hazards such as flooding, seismic risk, wildfire at the wildland urban interface, and extreme weather, and it is to be used in close coordination with the County-Wide MJHMP. The General Plan Land Use Element provides guidance on where future development will occur, with an emphasis on infill development, redevelopment of underutilized properties, and farmland preservation. At the time of this MJHMP update, Watsonville is preparing a new General Plan that will more fully integrate hazard mitigation and climate adaptation into its planning framework.

Watsonville does not have a large Sphere of Influence compared to other cities, but its growth policies, shaped by the Santa Cruz County Local Agency Formation Commission (LAFCO), require balancing housing and employment needs with the preservation of surrounding agricultural lands. In addition to the General

Plan, the city relies on specific plans, master plans, and infrastructure plans to manage growth in key areas, such as downtown revitalization, industrial redevelopment, and neighborhood-scale infill projects. These plans often incorporate hazard data to ensure that new development is consistent with both the General Plan and state regulatory standards.

As part of its planning framework, Watsonville integrates hazard information from the MJHMP directly into land use and capital improvement planning. The 2025 MJHMP update expands on this integration by introducing new mapping and analytical tools, including the Risk Assessment and Mitigation Planning (RAMP) platform (see Volume 1, Section 2.2.1), which supports data-driven decisions about where and how development should occur. By applying these updated tools and policies, Watsonville ensures that future growth is resilient, sustainable, and responsive to the evolving challenges of climate change and natural hazards.

Building Codes & Development Standards

Watsonville's development strategies combine comprehensive planning frameworks with strong regulatory measures to guide growth while reducing risks from natural hazards. Building codes play a central role in this approach. Nationally, continual improvements to building codes since 1990 have added only about one percent to construction costs while significantly improving disaster resilience (National Institute of Building Sciences, 2019). In California, building codes are among the most stringent in the world, establishing minimum standards to safeguard against hazards such as earthquakes, flooding, wildfire, landslides, and severe weather. Watsonville enforces these standards locally, providing a strong foundation for resilient construction and hazard reduction.

The City is required to regularly update its development regulations to align with the California Building Code (CBC), which is revised every three years and was most recently updated in 2025. The CBC establishes some of the world's highest construction standards, ensuring occupant safety in the face of natural hazards. Climate change is also addressed through adoption and enforcement of the California Green Building Standards (CALGreen) and Energy Codes, which incorporate energy efficiency, sustainable design, and climate adaptation measures.

The City of Watsonville's Municipal Code sets forth stringent regulations to mitigate hazards for both new and existing structures. These include:

- **Title 8 Adoption of most recent California building codes**, including the California Fire Code and seismic standards, which ensure structures are resilient to wildfire, earthquake, and other hazards.
- **Title 9, Chapter 2 Floodplain management regulations** to ensure new development avoids or mitigates risks in flood-prone areas.
- **Title 14 Zoning restrictions** that prevent development in hazardous zones, including floodplains and WUI areas.

Watsonville also participates in the National Flood Insurance Program (NFIP) and the Community Rating System (CRS), requiring that all new developments in designated flood hazard areas meet or exceed FEMA's minimum flood protection standards. This participation provides direct benefits to residents through reduced flood insurance premiums and demonstrates the City's commitment to proactive floodplain management.

Through these building and development regulations, Watsonville ensures that new development in hazard-prone areas is either restricted or subject to strict hazard-mitigation requirements. Where development is permitted, codes emphasize reducing exposure and vulnerability through appropriate siting, resilient construction techniques, stormwater management, and emergency access provisions. For example, new structures in liquefaction-prone areas must comply with geotechnical design standards, and development along the Pajaro River is subject to strict floodproofing requirements.

Beyond code enforcement, Watsonville integrates these mandates into its broader planning framework, including the General Plan, Housing Element, and Hazard Mitigation Plan (HMP). This alignment ensures that growth management, environmental review, and hazard mitigation strategies work together to address emerging risks from flooding, drought, extreme heat, wildfire, and severe storms, all of which are projected to intensify with climate change.

California Environmental Quality Act (CEQA)

The California Environmental Quality Act (CEQA) requires General Plans, Specific Plans, and major development projects to evaluate hazards such as flooding, wildfire, seismic risk, and slope instability. Environmental documents must identify these risks and propose mitigation measures to reduce impacts, which may include infrastructure upgrades, evacuation planning, geotechnical design standards, or limits on development in high-risk areas.

In Watsonville, CEQA is especially important for projects near the Pajaro River floodplain, local sloughs, and liquefaction-prone soils. For example, if new residential uses are proposed near the wildland urban interface (WUI) or flood zones, CEQA would require an assessment of hazard exposure and could recommend setbacks, fire-resistant construction, and improved emergency access.

By embedding hazard considerations into land use review, CEQA ensures that future growth in Watsonville is planned with both environmental protection and public safety in mind.

3.5.3.1 Development & Hazard Considerations

The City of Watsonville covers approximately 6.6 square miles and functions as a regional hub for housing, agriculture, and industry in the Pajaro Valley. Unlike smaller neighboring jurisdictions, Watsonville maintains both infill opportunities and designated areas for new growth within its Sphere of Influence (SOI). Future development is expected to occur through a combination of downtown and corridor infill, redevelopment near the proposed passenger rail station, and expansion into planned growth areas such as Buena Vista (Area A), Atkinson Lane (Area B), and the Highway 1 Gateway (Area C) (See Figure 3-11).

Watsonville's regulatory framework requires that new development conform to California's strict planning and building codes, reducing—but not eliminating—exposure to natural hazards. As the city continues to grow, hazard considerations are increasingly important because many of the areas designated for future development overlap with zones at risk from flooding, liquefaction, and other geologic hazards.

Flood Hazards: Flood risk is concentrated along the Pajaro River, Corralitos Creek, and Salsipuedes Creek, as well as throughout the Watsonville Slough system. FEMA Flood Insurance Rate Maps (FIRMs) identify large portions of the downtown, industrial districts, and eastern neighborhoods within the 100-year floodplain. Future growth in low-lying areas near the Highway 1 Gateway and Atkinson Lane will require strict compliance with FEMA and state flood protection standards, along with investments in stormwater and levee infrastructure to reduce chronic flood risk.

Liquefaction Hazards: Much of Watsonville is underlain by unconsolidated alluvial soils with shallow groundwater, placing nearly half of the city's population—more than 23,000 residents—at risk of liquefaction during a major earthquake. Growth in areas such as Buena Vista and the rail station district will require geotechnical investigations, soil stabilization measures, and resilient infrastructure design to mitigate earthquake-induced ground failure risks.

Slope Failure Hazards: While landslide hazards are less widespread, areas along the western hillsides and near slough embankments show susceptibility to slope instability. These hazards are most relevant where road access and utility infrastructure cross hazard-prone areas. Growth in hillside or slough-adjacent areas should incorporate slope stabilization, erosion control, and redundant access routes to maintain emergency connectivity.

Wildfire Hazards: Watsonville's wildfire exposure is limited compared to inland communities; however, the northwestern city edge near Buena Vista lies within a moderate to high wildfire hazard zone. Development in this area must comply with California Fire Code standards, including defensible space and fire-resistant construction. While the overall risk remains low, planning for emergency evacuation and fire-safe design will be essential in this growth area.

Drought and Water Supply: Future growth will place additional demand on Watsonville's water system, which relies heavily on groundwater from the Pajaro Valley Basin. This basin is already overdrafted and threatened by saltwater intrusion, making drought and climate change significant stressors. Planned

development must therefore integrate water efficiency, conservation, and reliance on recycled or supplemental water supplies to avoid exacerbating long-term scarcity.

In summary, Watsonville is not fully built out and retains significant growth capacity. However, much of its expansion potential lies in areas already exposed to flooding, liquefaction, and water supply stress. By embedding hazard data into General Plan implementation, Specific Plans, and CEQA review, the city can ensure that growth occurs in a way that is resilient, sustainable, and protective of both people and infrastructure.

3.5.4 Hazard Problem Statements

As part of the mitigation action identification process, the internal planning group for each jurisdiction identified areas of concern (aka problem statements) for their respective facilities based on the risk assessment and vulnerability analysis. Problem statements focused on the impact, victim, and the threat that the hazard could create in the jurisdiction, as described in Table 3-13 Identifying common issues and weaknesses through these problem statements assisted the planning group in understanding the realm of resources needed for mitigation.

The goal is to have at least one mitigation action for every problem statement. Projects or actions have been developed to mitigate each problem identified. See Table 3-15 for a full list of mitigation actions and corresponding problem statements that they address. Each problem statement is coded with a problem number for cross-referencing between Table 3-13 and Table 3-15.

Table 3-13: City of Watsonville Problem Statements

Hazard	Area of Concern	Problem ID	Description
Climate Change	Victim	**ps-CC-WTS-01**	Watsonville's vulnerable populations, including seniors, renters, farmworkers, low-income families, and limited-English communities, face increased cumulative risk from intersecting climate change-driven hazards such as heatwaves, floods, wildfire, and drought.
Climate Change	Impact	**ps-CC-WTS-02**	Critical systems like stormwater, water supply, energy, and transportation, are increasingly stressed during compounding, climate change-driven events.
Climate Change	Threat	**ps-CC-WTS-03**	Climate projections show increasing frequency and intensity of hazards, including extreme heat, severe storms, drought, wildfire, and sea-level rise, that compound and cascade risk across sectors.
Drought	Victim	**ps-DR-WTS-01**	Low-income residents and farmworkers may be disproportionately impacted by drought-related water restrictions, rising utility costs, and potential employment disruptions in agriculture and food processing sectors.
Drought	Victim	**ps-DR-WTS-02**	Rural and fringe-area residents relying on shallow or aging wells face heightened risk of well failure or poor water quality during prolonged drought cycles.
Drought	Impact	**ps-DR-WTS-03**	Declining recharge during extended droughts reduces groundwater levels, stressing municipal wells and water supply reliability for fire suppression.
Drought	Impact	**ps-DR-WTS-04**	Drought-induced groundwater depletion exacerbates the chronic threat of saltwater intrusion into the Pajaro Valley Basin.

Hazard	Area of Concern	Problem ID	Description
Drought	Threat	**ps-DR-WTS-05**	Climate change is projected to intensify the frequency and duration of multi-year drought cycles and dependence on the overdrafted Pajaro Valley groundwater basin creates chronic vulnerability, especially since the city's existing storage capacity is insufficient for drought resilience.
Earthquake	Victim	**ps-EQ-WTS-01**	Watsonville contains a concentration of older residential buildings often occupied by disadvantaged households, many of which may not meet current seismic codes and are more likely to suffer collapse or life-threatening damage during an earthquake.
Earthquake	Victim	**ps-EQ-WTS-02**	Disadvantaged residents, including renters and mobile home occupants, may lack earthquake insurance, emergency supplies, or the ability to afford post-disaster repairs, increasing vulnerability to long-term displacement.
Earthquake	Impact	**ps-EQ-WTS-03**	The city contains numerous unreinforced masonry buildings, particularly in the downtown core and industrial areas, which are at high risk of structural failure during strong seismic events.
Earthquake	Impact	**ps-EQ-WTS-04**	A major earthquake could disrupt essential infrastructure systems, including pipelines, water storage tanks, sewage networks, and electrical facilities, leading to cascading failures and long-term service outages.
Earthquake	Impact	**ps-EQ-WTS-05**	Seismic activity could damage roadways, bridges, and culverts, restricting emergency vehicle access and delaying evacuations or aid delivery in affected areas.
Earthquake	Threat	**ps-EQ-WTS-06**	Watsonville is exposed to high seismic hazard due to proximity to the San Andreas Fault and local active faults (Zayante, Butano), which are capable of producing magnitude 6.4–7.4 earthquakes.
Earthquake	Threat	**ps-EQ-WTS-07**	The city lacks a formal or consistently enforced program to inventory, evaluate, and retrofit high-risk structures such as unreinforced masonry or soft-story buildings, leaving known vulnerabilities unaddressed.
Extreme Heat	Victim	**ps-EH-WTS-01**	Outdoor agricultural workers in the Watsonville area face heightened health risks from increasing extreme heat days, particularly those lacking access to shaded rest areas, cooling stations, or protective equipment.
Extreme Heat	Victim	**ps-EH-WTS-02**	Seniors, low-income residents, and individuals in older housing without air conditioning are especially vulnerable to heat-related illness during high heat days and may lack transportation to reach cooling centers.
Extreme Heat	Threat	**ps-EH-WTS-03**	The frequency of extreme heat days is projected to rise significantly by mid-century, with disproportionate impacts on inland agricultural zones and low-income neighborhoods.
Extreme Heat	Threat	**ps-EH-WTS-04**	Watsonville lacks formal procedures for opening and staffing cooling centers, outreach to vulnerable populations, and pre-positioning resources on extreme heat days.
Flood	Victim	**ps-FL-WTS-01**	Elderly residents in neighborhoods and unhoused encampments adjacent to the Pajaro River face mobility challenges and are less able to evacuate or access emergency services during flood events.
Flood	Victim	**ps-FL-WTS-02**	Low-income and Spanish-speaking communities living in downtown and industrial areas are disproportionately located in flood-prone zones and may lack access to warnings, insurance, and recovery support.
Flood	Impact	**ps-FL-WTS-03**	The City's wastewater treatment plant, police station, and other critical infrastructure lie within the 1% annual chance floodplain, placing essential services at risk of prolonged disruption during major flood events.
Flood	Impact	**ps-FL-WTS-04**	Flood events damage stormwater systems and roadways in downtown and east Watsonville, leading to road closures, business disruption, and restricted emergency access.
Flood	Impact	**ps-FL-WTS-05**	Flooding poses a contamination risk to drinking water sources, including the Watsonville Slough, which may serve as a water source during drought or emergency periods.

Hazard	Area of Concern	Problem ID	Description
Flood	Threat	**ps-FL-WTS-06**	Watsonville experiences chronic flood risk from the Pajaro River and Corralitos and Salsipuedes Creeks. Aging levees and increased storm intensity due to climate change exacerbate this threat despite ongoing planning efforts.
Flood	Threat	**ps-FL-WTS-07**	Urbanization and impervious surfaces are increasing stormwater runoff volume and frequency, worsening flood severity in areas with inadequate drainage or no levee protection.
Flood	Threat	**ps-FL-WTS-08**	Flood maps are outdated and do not fully reflect sea level rise, sedimentation, or storm surge interactions with sloughs and the Pajaro River, underestimating future hazard exposure.
Flood	Victim	**ps-FL-WTS-09**	Flood impacts to farmworkers are increased due to potential employment disruptions in agriculture and food processing sectors.
Heavy Rain	Impact	**ps-HR-WTS-01**	Heavy rain during atmospheric river events overwhelms stormwater infrastructure, causing localized flash flooding in low-lying roadways and near culverts, particularly in older downtown areas.
Heavy Rain	Threat	**ps-HR-WTS-02**	Watsonville faces frequent winter storms and atmospheric river events, which are increasing in severity due to climate change and contribute to recurring road closures and local flooding.
Liquefaction	Threat	**ps-LQ-WTS-01**	Large portions of Watsonville are susceptible to liquefaction, particularly in areas with high water tables and soft alluvial soils, exacerbating ground shaking impacts and structural instability.
Severe Weather	Victim	**ps-SW-WTS-01**	Residents in mobile homes and older housing, many of whom are low-income or elderly, are particularly vulnerable to power outages, loss of access, and associated health risks during high wind and heavy rain events.
Severe Weather	Impact	**ps-SW-WTS-02**	High wind events, especially following heavy rain, regularly down trees and power lines, disrupting power, communications, and road access throughout Watsonville and straining emergency response capabilities.
Severe Weather	Victim	**ps-SW-WTS-03**	Severe storms disproportionately impact farmworker communities due to increased insecurity from potential employment disruptions in agriculture and food processing sectors.
Slope Failure	Victim	**ps-SF-WTS-01**	Residents in hillside neighborhoods along the city's western and northern edges may face evacuation challenges resulting from landslides blocking access, especially dependent populations.
Slope Failure	Impact	**ps-SF-WTS-02**	Landslides and debris flows can damage roadways, pipelines, bridges, and culverts, restricting emergency access and utility service in areas of steeper slopes and less stable soils.
Slope Failure	Threat	**ps-SF-WTS-03**	Local geology, including Santa Margarita Sandstone and Santa Cruz Mudstone, is highly prone to landslides exacerbated by heavy rain, vegetation loss, or grading activities.
Wildfire	Victim	**ps-WF-WTS-01**	Watsonville residents living near the wildland-urban interface (WUI), especially vulnerable populations such as senior and limited-English speakers, face evacuation challenges due to limited road access, insufficient route redundancy, and emergency communications barriers.
Wildfire	Impact	**ps-WF-WTS-02**	Multiple critical facilities, including emergency shelters, water infrastructure, and hazardous materials storage facilities, are located in high or moderate wildfire hazard zones, posing risk of fire-related service interruption or secondary hazards.
Wildfire	Threat	**ps-WF-WTS-03**	Wildfire risk is increasing due to hotter, drier conditions, fuel accumulation, and proximity of development to flammable vegetation along the city's edges.

3.5.4.1 Climate Change Impacts & Vulnerable Populations

The City of Watsonville is home to diverse and vibrant communities, yet many residents face disproportionate risks from climate change–driven hazards. Seniors, renters, farmworkers, low-income families, and limited-English speakers are particularly vulnerable due to a combination of socioeconomic, linguistic, and housing-related factors. Vulnerability is not uniform; some groups may face elevated risks from certain hazards such as extreme heat or flooding while being less impacted by others. Climate change is expected to intensify these disparities by increasing the frequency and severity of compounding hazard events.

Drought and Water Supply: Watsonville depends heavily on the Pajaro Valley Groundwater Basin, which is chronically overdrafted and subject to saltwater intrusion. Prolonged droughts reduce recharge, lower groundwater levels, and stress water availability for municipal and agricultural uses. Low-income households and farmworker communities are disproportionately impacted by water restrictions, higher utility costs, and employment disruptions in agriculture and food processing sectors. Rural residents dependent on shallow or aging wells also face elevated risks of water shortage or contamination.

Flooding and Severe Storms: Watsonville faces chronic flood risk from the Pajaro River, Corralitos Creek, and Salsipuedes Creek, with nearly 1,000 residents and multiple critical facilities—including the wastewater treatment plant and police station—located in the one percent annual chance floodplain. Aging levees and outdated flood maps compound the threat, while increasing storm intensity from atmospheric rivers elevates future flood exposure. Elderly residents, unhoused populations along the river, and low-income or Spanish-speaking households face heightened vulnerability due to evacuation challenges, limited insurance coverage, and barriers to recovery resources. Farmworkers also experience secondary impacts through job loss when agriculture and food processing facilities are disrupted by flooding.

Earthquake and Liquefaction: Watsonville is located near the San Andreas Fault and other active local faults, making it highly susceptible to seismic activity. Although not impacted by climate change, the city has a concentration of older residential buildings and unreinforced masonry structures, particularly in the downtown core, which are especially vulnerable to collapse. Liquefaction risk is elevated in areas with soft soils and high groundwater. Renters, mobile home residents, and low-income households often lack earthquake insurance, retrofits, or the resources to recover from damage, leading to higher displacement risk.

Extreme Heat: Outdoor agricultural workers face significant health risks from increasing numbers of extreme heat days, particularly when shaded rest areas or cooling stations are unavailable. Seniors, low-income households, and residents in older housing without air conditioning are also highly vulnerable. Rising energy costs may force some households to avoid using cooling systems, increasing health risks during prolonged heatwaves. The city currently lacks formal heat response procedures such as pre-positioned cooling centers and outreach strategies for at-risk populations.

Slope Failure: Hillside neighborhoods on the city's western and northern edges are prone to landslides and debris flows during heavy rain, which can block access routes and restrict emergency services. Local

geology, including Santa Margarita Sandstone and Santa Cruz Mudstone, further elevates susceptibility to slope instability. Populations with limited mobility or financial resources may be unable to address slope hazards on private land or evacuate quickly when needed.

Wildfire: While Watsonville's urban core faces lower wildfire risk, residents near the wildland-urban interface (WUI) are increasingly exposed to fire hazards. Vulnerable populations, including seniors and limited-English speakers, face challenges with evacuation and emergency communications. Wildfire also poses risks to critical facilities such as emergency shelters, water infrastructure, and hazardous materials storage sites. Hotter, drier conditions and accumulated fuels increase the likelihood of fire spread, while post-wildfire recovery is complicated by limited funding and socioeconomic disparities.

The compounding effects of climate change on Watsonville's vulnerable populations require proactive and equitable strategies. Enhancing emergency communication in multiple languages, investing in resilient infrastructure, expanding resources for renters and farmworker households, and integrating climate adaptation into daily city operations will strengthen Watsonville's resilience and reduce disparities across its most at-risk populations.

3.6 Mitigation Strategy

This section provides the framework for how the City of Watsonville will reduce hazard risk within its jurisdiction while supporting the broader goals of the Santa Cruz County MJHMP. It includes an overview of existing capabilities, opportunities to strengthen resilience, and the City's prioritized mitigation actions. Together, these elements demonstrate how Watsonville integrates hazard awareness into its planning and development processes while contributing to a coordinated countywide approach.

Within the Santa Cruz County MJHMP, the mitigation strategy serves as the roadmap for future hazard mitigation efforts. For Watsonville, the strategy outlined in this annex reflects the outcomes of the countywide planning process while also addressing the City's unique risks, priorities, and community needs. The strategy is designed to reduce vulnerabilities identified in the risk assessment, including the problem statements developed for flooding, earthquakes and liquefaction, slope failure, wildfire, drought, severe storms, extreme heat, and climate change.

Mitigation actions identified in this annex include both policy-based and project-based initiatives, with an emphasis on integrating resilience into land use planning, infrastructure investments, and community programs. Actions are structured to align with FEMA's requirements and to coordinate with existing city, county, and regional planning mechanisms. Each action identifies responsible parties, potential funding sources, and the resources needed for implementation.

For Watsonville, this strategy provides a framework for strengthening resilience by combining city-led initiatives—such as infrastructure improvements, building code enforcement, and community preparedness—with regional coordination through the MJHMP. By advancing these efforts in alignment with the General Plan and other local planning documents, Watsonville enhances its ability to reduce hazard risk while supporting long-term community safety, sustainability, and economic stability.

The subsections that follow describe these elements in detail:

- **Section 4.6.1 Aligning Action Planning** with Capabilities provides a summary of the City's capacity to address natural hazards.
- **Section 4.6.3 Mitigation Action Plan** presents Watsonville's prioritized actions to guide implementation in coordination with countywide strategies.

3.6.1 Aligning the Action Plan

This section connects the City of Watsonville's mitigation actions with its existing capabilities and areas for growth. Capability assessments are a required element of hazard mitigation planning under the Disaster Mitigation Act of 2000 and FEMA's 2023 guidance, ensuring that actions are realistic, achievable, and aligned with available resources.

The section begins with a summary of Watsonville's capabilities across four areas: planning and regulatory, administrative and technical, fiscal, education and outreach. This overview highlights the tools and

strengths that the city's already uses to reduce hazard risk. The section then provides a detailed analysis of each capability area, identifying both current practices and opportunities to expand resilience.

Planning & Regulatory Capabilities

The City of Watsonville maintains strong planning and regulatory tools that directly reduce hazard risks and guide future development. The city adopts and enforces the California Building Code through its Municipal Code (Title 8), ensuring that all new construction meets some of the most rigorous seismic, fire, and structural standards in the nation. In addition, Titles 9 and 14 of the Municipal Code apply specialized hazard-related development standards, including flood protection requirements, seismic safety overlays, hillside protections, and coastal zone regulations. These measures are reinforced by Watsonville's Zoning Ordinance (Title 14) and a Growth Management Ordinance, which establishes an Urban Limit Line and ties annual development caps to the General Plan's Land Use and Housing Elements.

Watsonville's Capital Improvement Program (2023–2027) prioritizes drainage, levee, and pump infrastructure upgrades in flood-prone areas, directly supporting flood risk reduction. The city also implements an Erosion and Sediment Control Program under Municipal Code Chapter 7-6, which regulates grading and filling activities, and requires compliance with post-construction stormwater standards.

Public outreach on hazards is supported through the Fire Department and County OR3, with seasonal campaigns related to flood and fire awareness. The City also coordinates hazard reduction through its Urban Water Management Plan (2020), which addresses long-term drought resilience, water conservation, and supply reliability.

As a regulated MS4 stormwater operator, Watsonville conducts annual inspections to ensure compliance with the City's Stormwater Management Program, reducing flood and water quality risks. Seismic safety is addressed in the Municipal Code through the Seismic Safety District (Section 14-16.2300), which requires site-specific geologic investigations for development in known hazard areas.

Although Watsonville does not maintain a dedicated retrofit program for unreinforced masonry (URM) or soft-story structures, the General Plan's Safety Element acknowledges seismic risks and provides policy direction for addressing them. This remains an opportunity for future program development to further reduce earthquake vulnerability.

Administrative & Technical Capacity

The City of Watsonville has a well-established administrative and technical framework for hazard mitigation, anchored by its Community Development, Public Works and Utilities, and Fire Departments. These departments collectively provide planning, engineering, and emergency management services that support implementation of the City's hazard reduction programs.

Watsonville maintains professional planning and engineering staff across multiple departments, including community planners, land development engineers, and construction engineers, ensuring that hazard

considerations are integrated into site review, permitting, and capital projects. The Building Official, housed in the Community Development Department, serves as both the City's Building Code Official and Floodplain Administrator, enforcing California Building Code provisions and FEMA floodplain management standards.

The Fire Department provides a dedicated Fire Marshal who leads plan review, building inspections, and fire hazard mitigation activities. Emergency coordination is managed by a designated Emergency Manager within the Fire Department, who also participates in the County's Emergency Operations Center (EOC).

While the City has strong in-house expertise, certain specialized capacities remain limited. Watsonville does not maintain a dedicated resiliency planner or public outreach personnel, though adaptation planning is integrated into the City's 2022 Climate Action and Adaptation Plan (CAAP). Similarly, the city relies on cross-trained planners and engineers for climate and flood planning but does not yet employ dedicated hazard scientists. GIS services are available through the Community Development and Information Services Departments, but staffing is limited, and the city frequently partners with consultants for advanced mapping and analysis.

Grant-writing and management are handled by staff in Public Works and Finance, though the city lacks a dedicated full-time grant manager or mitigation specialist. This has not prevented Watsonville from successfully securing outside funds for hazard-related projects, but additional capacity could strengthen future applications for state and federal resilience grants.

Overall, Watsonville's administrative and technical strengths lie in its multidisciplinary staff capacity and integration across departments, combined with strong interagency partnerships. Expanding specialized functions such as resiliency planning, dedicated outreach, and GIS analysis would further enhance the City's ability to proactively address hazard vulnerabilities.

Warning Systems & Services

The City of Watsonville relies heavily on the regional emergency alert and warning infrastructure coordinated by County OR3. The CruzAware system serves as the City's primary platform for hazard alerts, providing residents with real-time notifications by text, phone, or email. CruzAware issues warnings for a broad range of hazards including floods, wildfires, geological hazards, and severe weather events, ensuring consistency across the countywide emergency management framework.

Although the City does not operate its own independent warning system, it actively supports dissemination of alerts through City-managed communication channels. This includes integration with the City's website, social media platforms (Facebook, Instagram, and Twitter/X), and coordination with the Fire and Police Departments, which amplify urgent messages during emergencies. The city also maintains a strong relationship with the National Weather Service Monterey Office, which provides storm forecasts, flood warnings, and coastal hazard alerts specific to the region.

Watsonville's emergency warning capacity is strengthened through participation in countywide systems, but there remain opportunities for expansion. For example, the city does not currently participate in FEMA's

StormReady program, though Santa Cruz County has achieved StormReady and TsunamiReady status. Additionally, hazard-specific public education campaigns—such as neighborhood flood alerts or fire season preparedness messaging—are conducted only on a limited basis, often seasonally.

In practice, Watsonville's role is to amplify and localize county and state warnings while ensuring that alerts reach its diverse population. Given the City's large Spanish-speaking community and agricultural workforce, expanding multilingual emergency communications and ensuring alerts are accessible to residents with limited connectivity are critical next steps.

Fiscal Capabilities

The City of Watsonville maintains a broad set of fiscal tools that support hazard mitigation and resilience investments. Unlike smaller jurisdictions, Watsonville can both levy voter-approved taxes and administer a range of development-related fees, providing a diversified base for funding capital projects and disaster preparedness.

The City has the authority to levy special taxes for specific purposes, as demonstrated by past measures such as Measure G, which funded police and fire services. In addition, Watsonville generates stable revenue through stormwater, solid waste, and water utility fees, which directly support drainage system maintenance, water reliability projects, and compliance with state and federal stormwater requirements.

Watsonville also relies on system development fees charged to new development, which fund public improvements, including stormwater and transportation infrastructure. Capital Improvement Program (CIP) funding is another cornerstone of the City's fiscal capacity. The 2023–2027 CIP dedicates significant investment toward levee improvements, pump station upgrades, and other drainage projects in flood-prone areas, reflecting a strong linkage between fiscal policy and hazard risk reduction.

Additional resources come from federal and state programs, including annual allocations of Community Development Block Grants (CDBG), which have historically supported ADA accessibility, emergency response, and infrastructure improvements in vulnerable neighborhoods. These external funds help extend the City's reach, particularly in low-income and hazard-prone areas.

While Watsonville has the authority to issue general obligation bonds and special tax bonds, these tools are not currently utilized for hazard mitigation projects. Expanding their use could provide long-term funding for major infrastructure upgrades, particularly flood protection. Similarly, the City does not currently use benefit assessments or formal policies for withholding development in hazard-prone areas, though hazard-related zoning standards and urban limit lines already reduce exposure in high-risk zones.

In practice, Watsonville's fiscal strategy blends local fees and taxes with external grant funding, creating a flexible, layered approach to resilience. Opportunities remain to leverage untapped financing mechanisms—such as bonds or benefit assessments—to address large-scale capital needs, particularly as climate change intensifies flooding, drought, and extreme weather impacts.

Education & Outreach Capabilities

The City of Watsonville maintains strong education and outreach programs that connect hazard awareness with community preparedness. These efforts are led primarily by the Fire Department, Police Department, Public Works and Utilities, with additional support from regional partners such as the Santa Cruz County Fire Safe Council and the Pajaro Valley Water Management Agency.

The city uses its website and social media platforms (Facebook, Instagram, and X) to provide real-time emergency alerts, preparedness tips, and seasonal safety reminders. These channels are widely used during winter storm events, wildfire smoke episodes, and flood advisories, offering residents timely, accessible information. However, opportunities remain to centralize hazard-related resources into a single web portal for easier community access.

Watsonville also participates in annual public safety events, including National Night Out, Preparedness Month activities, fire safety school visits, and station tours. These events provide direct opportunities for residents to learn about evacuation planning, flood safety, and emergency communications. Outreach efforts are supported by seasonal mailers and flyers, though a recurring hazard mitigation newsletter could further strengthen ongoing public awareness.

At the neighborhood level, Watsonville supports community preparedness through its Community Emergency Response Team (CERT) program, part of the Santa Cruz County CERT network. Local CERT volunteers receive training in basic disaster response, first aid, and search-and-rescue, expanding the City's response capacity during major hazard events.

Partnerships also play a critical role. The Fire Safe Council of Santa Cruz County works with Watsonville to expand defensible space programs, vegetation management, and community education, while the City's collaboration with regional conservation and water agencies promotes drought awareness, flood preparedness, and groundwater conservation. Watsonville is also home to a designated Firewise community, with potential to expand this program into other high-risk neighborhoods along hillside edges.

Overall, Watsonville's education and outreach capabilities reflect a community-based approach: combining digital tools, in-person events, and regional partnerships to ensure hazard information reaches a diverse population, including vulnerable residents such as seniors, farmworkers, and limited-English speakers.

3.6.2 Capabilities & Opportunities Assessment

To develop a realistic and actionable mitigation strategy, it must account for existing jurisdictional capabilities and what future opportunities there are to enhance those capabilities for purposes of hazard mitigation. This section provides an assessment of the City of Watsonville's existing capabilities and future opportunities, including planning and regulatory, administrative and technical, fiscal, and public outreach and education capabilities. This assessment also identifies opportunities to integrate this MJHMP into future planning, policies, or programs to weave mitigation efforts into daily operations and address hazard problems wholistically. Capabilities are categorized into four groups and include various mechanisms.

- **Planning and Regulatory Capabilities:** Existing long-range plans, emergency response plans, hazard-specific plans, land use policies, and building and development standards.
- **Administrative and Technical Capabilities:** Available expertise in emergency services, engineering, grant management, and community planning.
- **Fiscal Capabilities:** Budgetary capacity, taxing authority, grants, and other funding mechanisms that can support mitigation projects.
- **Outreach and Education Capabilities:** Existing programs for providing technical assistance, community education, public warnings, and stakeholder engagement.

A full description of the process used to develop the capabilities assessment is provided in Volume 1, Section 2.3.3.

This capabilities and opportunities assessment for Watsonville lists the various types of capabilities along with how they have been, currently are, or will in the future be integrated into hazard mitigation planning efforts. The three "HMP Integration" columns that identify the capability's status and usage are color-coded with green, yellow, or orange shading to communicate the following:

- **Status:** If the capability is present at all and what level of use it has generally.
- **Current Mitigation Use:** If the capability is currently being used in mitigation efforts, specifically, and at what level.
- **Future Opportunity:** If there is a future opportunity to integrate the capability into mitigation efforts and at what level.

CAPABILITY ASSESSMENT LEGEND

HMP Integration

Status	Current Mitigation Use	Future Opportunity
Currently in use or present.	Used widely for mitigation.	Opportunity to expand and integrate.
(Sort of) Seldomly used or limited presence.	Limited use in mitigation planning.	Limited opportunity to expand and integrate.
(No) Not present or available.	Not used in mitigation planning.	No opportunity to expand or integrate.

Table 3-14: City of Watsonville Capabilities Assessment

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planning and Regulatory Capabilities				
Construction and Future Development Regulations				
Building Codes				City Municipal Code Title 8, Building Regulations, adopting the 2022 California Building Code (Part 2 of Title 24 of the California Code of Regulations)
Hazard-Related Development Standards				City Municipal Code Titles 9 and 14, Planning / Zoning, apply Coastal, Flood Protection, Seismic Safety, and Hillside zones and development standards; Title 8, Building Regulations, applies fire hazard standards
Zoning Ordinance				City Municipal Code Title 14, Zoning
Hazard-Specific Ordinance				City Municipal Code Titles 9 and 14, Planning / Zoning, apply Coastal, Flood Protection, Seismic Safety, and Hillside zones and development standards
Growth Management Ordinance				Urban Limit Line and annual development caps tied to the General Plan Land Use and Housing Elements
Hazard Reduction Programs (Annually Conducted)				
Capital Improvements Program (CIP) or Plan				2023-2027 CIP includes drainage, levee, and pump infrastructure upgrades in flood-prone areas
Erosion/Sediment Control Program				City Municipal Code Chapter 7-6, Excavations, Grading, Filling, and Erosion Control, and Public Improvement Standards Stormwater Post Construction Standards
Hazard-Related Public Outreach Program				Emergency preparedness outreach through Fire Department and County OES; some seasonal flood/fire awareness efforts
Urban Water Management Plan				2020 UWMP supports drought planning, conservation, and water reliability
Stormwater Management Program (Annual Inspections)				Classified as an MS4 operating under a NPDES permit; annual inspections conducted
Seismic Safety Program (Non-structural)				City Municipal Code Section 14-16.2300, Seismic Safety District, requires site-specific geologic reports within areas of known hazards
Earthquake Modernization Plan (Building Safety)				No specific soft-story or URM retrofit program; General Plan Safety Element addresses seismic hazards but no structured mitigation program currently
Hazard Plans				
General Plan Safety Element				Current General Plan Public Safety Element addresses hazards such as seismic, flood, and coastal
Site Plan Review Requirements				Site plan reviews enforced through City Municipal Code Title 14, Zoning, and CEQA review processes

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
General Plan Environmental Justice Element				No standalone element in current General Plan; to be integrated upon next update and through CAAP implementation
Community Wildfire Protection Plan (CWPP)				Covered under 2022 Santa Cruz County CWPP (WUI risk minimal within City limits)
Economic Development Plan				No formal plan, but priorities embedded in General Plan, Downtown Watsonville Specific Plan, and CAAP
Floodplain Management Plan				No formal plan, but City Municipal Code Titles 9 and 14, Planning / Zoning, apply Flood Protection development standards
Stormwater Management Plan				Watsonville Stormwater Management Plan under NPDES Phase II MS4 Permit; updated BMPs and outreach conducted annually
Emergency Operations Plan				2019 Emergency Operations Plan; participates in the Santa Cruz County Operational Area Plan
Climate Action Plan				2022 Climate Action & Adaptation Plan (CAAP) includes mitigation strategies for sea level rise, extreme heat, and wildfire smoke
Climate Vulnerability Assessment				Completed as part of 2022 CAAP; includes social vulnerability mapping, hazard exposure, and future climate projections
Urban Greening Plan				Community Forestry Project; tree canopy and nature-based stormwater infrastructure projects via CAAP
Ground Water Management Planning / Plans				2020 UWMP; City coordinates on groundwater recharge and water conservation; covered through Pajaro Valley Water Management Agency (PV Water)
National Flood Protection Program (NFIP)				
Floodplain Management Regulations				City Municipal Code Titles 9 and 14, Planning / Zoning, apply Flood Protection development standards
Flood Insurance Education and Technical Assist.				Public outreach through floodplain permitting process and website; no formal technical assistance program
Flood Insurance Study				Effective FEMA FIS adopted by reference in City Municipal Code Chapter 9-2, Floodplain Management
Elevation Certificates				Maintained by Engineering Division
Flood Hazard Mapping / Re-Mapping				Effective FEMA FIRMs adopted by reference in City Municipal Code Chapter 9-2, Floodplain Management
Community Rating System (CRS)				Joined October 1992; currently Class 8
Administrative and Technical				
Community Planning and Development Services				
Community Planner				Staff in Community Development Department

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Planner/Engineer (Land Development)				Staff in Community Development and Public Works and Utilities Departments
Engineer/Professional (Construction)				Staff in Public Works and Utilities Department
Planner/Engineer/Scientist (Natural Hazards)				No dedicated staff; however, cross-trained planners and engineers support climate and flood planning
Transportation Planner				No dedicated staff; limited future opportunity
Resiliency Planner				No dedicated staff, but CAAP includes adaptation planning tasks
Building Official (Full time or Augmented)				Building Official housed in Community Development Department
Floodplain Administrator				Role fulfilled by Engineering staff
Fire Marshal				Fire Marshall housed in Watsonville FD administration; Planning Department manages plan review with consultant ensuring fire code compliance; inspections conducted by both Building and Fire Department staff
Dedicated Public Outreach Personnel				No dedicated staff; future opportunity
GIS Specialist and Capability				GIS Coordinator in Information and Technology Services Department, but limited capacity
Emergency Manager				Emergency services coordination housed in City Manager's Office; participates in County EOC functions
Dedicated Grant Manager, Writer, or Specialist				No dedicated staff: however, staff in Public Works and Finance manage grant applications when needed
Other	N/A	N/A	N/A	
Warning Systems and Services				
General				Participates in Santa Cruz County's regional emergency alert system CruzAware
Flood				CruzAware alerts
Tornado				CruzAware alerts
Wildfire				CruzAware alerts
Geological Hazards				CruzAware alerts
Fiscal Capabilities				
Financial Resources (for Hazard Mitigation)				
Levy Taxes for Specific Purposes				Watsonville can levy special taxes via voter approval (e.g., Measure G for police/fire)
Utilities Fees				Stormwater, solid waste, and water utility fees
Benefit Assessments				Not currently, future opportunity
Community Development Block Grants (CDBG)				Annual CDBG allocations for emergency response and ADA infrastructure

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
System Development Fee				Collected on new developments to fund public improvements including stormwater and transportation
General Obligation Bonds to Incur Debt				Bond issuance is authorized but not currently used for hazard mitigation; may be considered for levee or drainage upgrades
Special Tax Bonds to Incur Debt				No special tax bonds for hazard mitigation; may be explored to fund specific flood mitigation
Withheld Spending in Hazard-Prone Areas				No formal policies, but development is constrained in high-risk zones via zoning and development standards (e.g., floodplain)
Stormwater Service Fees				Fees support drainage system maintenance and improvements per MS4 permit compliance
Capital Improvement Project Funding				2023-2027 CIP includes drainage, levee, and pump infrastructure upgrades in flood-prone areas
Education / Outreach Capabilities				
Education/Outreach Resources				
Website Dedicated to Hazard Topics				Emergency preparedness and hazard-specific webpages under City Manager, Public Works and Utilities, and Fire Department; opportunity to centralize content
Dedicated Social Media				City posts emergency alerts and preparedness tips via Facebook, Instagram, and Twitter (X)
Local Citizen Groups That Communicate Hazard Risks				Fire Safe Council of Santa Cruz County; partner organizations (e.g., PV Water, environmental NGOs) conduct limited outreach
Hazard Info. Avail. at Library/ Planning Desk				Not currently, future opportunity
Annual Public Safety Events				Watsonville Fire and Police host National Night Out, Preparedness Month, fire safety school visits, station tours, and other public safety activities
Ability to Field Public Tech. Assistance Requests				Requests related to hazard information, code enforcement, and stormwater handled via general service request system
Public Safety Newsletters or Printed Outreach				Limited seasonal outreach via flyers or mailers (e.g., storm prep), but no recurring hazard mitigation newsletter
Community Emergency Response Team (CERT)				Has a city team through Santa Cruz County CERT program with local training options
Fire Safe Councils				City is covered by Fire Safe Council of Santa Cruz County, but activity is limited in urban Watsonville
Firewise				Only one Firewise community in Watsonville as of 2025; could pursue additional in hillside-adjacent zones
StormReady				City does not participate, but Santa Cruz County is both StormReady and TsunamiReady

Resource	HMP Integration: Status	HMP Integration: Current Mitigation Use	HMP Integration: Future Opportunity	Notes / Additional Detail
Resource Conservation Districts				Resource Conservation District of Santa Cruz County supports groundwater recharge, fire fuel management, and climate education
Other	N/A	N/A	N/A	

3.6.3 City of Watsonville Mitigation Action Plan

Watsonville's mitigation actions were developed through a collaborative process informed by the updated risk assessment, local priorities, and extensive stakeholder engagement. As part of this 2025 MJHMP update, the City reviewed mitigation actions from its prior Local Hazard Mitigation Plan to determine which actions to carry forward, which to consolidate, and where entirely new strategies were required. This careful evaluation ensured that the updated action plan builds upon past commitments while also responding to current risks and future challenges.

The plan addresses Watsonville's most significant hazards, including flooding, earthquakes, severe storms, drought, wildfire, extreme heat, and climate change. Each mitigation action is designed to align with FEMA's hazard mitigation guidance and the requirements of the Disaster Mitigation Act of 2000. Where appropriate, overlapping or redundant actions were consolidated into broader, more comprehensive strategies that improve clarity, increase feasibility, and strengthen regional coordination.

The mitigation action prioritization method used by all participating jurisdictions is described in Volume 1, Section 4. Each action specific to Watsonville is documented in Table 3-15, which identifies the responsible department, implementation timeframe, potential funding sources, and resources required to complete the action. Each action is also assigned a unique alphanumeric identifier (see Figure 3-20) that links the strategy to its associated hazard and supports consistent monitoring and reporting.



Figure 3-20: Mitigation Action Number Key

Watsonville's approach recognizes that some hazards are most effectively addressed through regional efforts. Flood protection, drought resilience, and wildfire risk reduction often extend beyond the city's boundaries and require collaboration with county, regional, and state partners. By aligning local actions with regional strategies, Watsonville helps to consolidate resources, maximize funding opportunities, and ensure that mitigation projects achieve the greatest benefit for the Pajaro Valley and the wider Santa Cruz County community.

Collectively, these mitigation actions provide a roadmap for reducing hazard risk, protecting vulnerable populations, and strengthening the long-term resilience of Watsonville.

PAGE INTENTIONALLY BLANK

Table 3-15: City of Watsonville Mitigation Action Plan

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
All Hazard	**ma-AH-WTS-01**	Emergency Center Activation Plan	Expand formal procedures and funding for activating, staffing, and advertising emergency centers for warming, cooling, or other sheltering needs during extreme weather and other hazard events.	PRV, PE&A	Short 1-3 Years	City Parks + County, City of Santa Cruz, and other regional partners	Low	High	General fund, staff Time	other state grants	High	ps-AH-SCC-08, ps-EH-SCC-02, ps-EH-SVL-05, ps-EH-WTS-04, ps-CC-SCC-05, ps-DF-SCC-03, ps-SW-SCC-03, ps-WW-SCC-01, ps-WW-SCC-02, ps-CC-WTS-01, ps-CC-WTS-03, ps-EH-WTS-02, ps-EH-WTS-03, ps-FL-WTS-01, ps-FL-WTS-02, ps-WF-WTS-02
Climate Change	**ma-CC-WTS-01**	Neighborhood Climate Resilience Program	Develop an enhanced multilingual and multigenerational outreach and assistance program to increase resilience through activities such as urban gardening, tree planting, and xeriscaping.	PE&A, PRV	Medium 3-5 Years	City Sustainability + County OR3, CBOs, HOAs, Community Advisory Committee, Promotoras	Low	High	Water Conservation Program, general fund, staff time	Measure Q	High	ps-CC-WTS-01, ps-CC-WTS-02, ps-CC-WTS-03, ps-DR-WTS-01, ps-DR-WTS-02, ps-DR-WTS-05, ps-EH-WTS-01, ps-EH-WTS-02, ps-EH-WTS-03, ps-FL-WTS-01, ps-SW-WTS-03
Drought	**ma-DR-WTS-01**	Drought-Resilient Storage & Reuse	Build new water tank and expand non-potable reuse systems to offset supply stress during droughts.	SP	Short 1-3 Years	City Water + DWR	High	High	Water fund, staff time	DWR Urban & Multi Benefit Drought Relief Grant	Low	ps-DR-WTS-03, ps-DR-SPD-03, ps-CC-WTS-02, ps-CC-WTS-03, ps-DR-WTS-01, ps-DR-WTS-02, ps-DR-WTS-04, ps-DR-WTS-05
Earthquake	**ma-EQ-WTS-01**	Retrofit High-Risk Buildings	Develop and implement an incentive-based retrofit program for unreinforced masonry and soft-story buildings, prioritized by occupancy and proximity to critical facilities.	PRV	Medium 3-5 Years	City Building + contractors	High	High	General fund, staff time (Limited)	CDBG	Medium	ps-EQ-SVL-04, ps-EQ-WTS-03, ps-EQ-WTS-07, ps-EQ-WTS-06, ps-EQ-WTS-01, ps-EQ-WTS-02, ps-EQ-WTS-06, ps-LQ-WTS-01
Earthquake	**ma-EQ-WTS-02**	Critical Infrastructure Seismic Hardening	Strengthen and stabilize critical facilities and infrastructure, including upgrading pipelines, drainage channels, storage tanks, reservoirs, roads, and bridges, based on vulnerability analysis. May include establishing backup power or enhancing communication systems.	SP, PPRO	Medium 3-5 Years	City Public Works and Utilities + utility and road partners	High	High	General fund, water fund, sewer fund, staff time	HMGP	Medium	ps-EQ-WTS-04, ps-EQ-WTS-05, ps-EQ-WTS-06, ps-LQ-WTS-01
Extreme Heat	**ma-EH-WTS-01**	Meet Urban Forest Master Plan Goals	Implement the Urban Forest Master Plan, Urban Greening Plan, and Climate Action Plan to achieve their goals, including reducing extreme heat impacts.	PRV, PE&A	Long 5-10 Years	City Parks + CBOs	Medium	High	General fund, staff time, Measure R	Measure Q, Prop 4, EPA	Medium	ps-EH-CPT-02, ps-EH-SVL-05, ps-EH-WTS-03, ps-CC-WTS-01, ps-CC-WTS-02, ps-CC-WTS-03, ps-EH-WTS-01, ps-EH-WTS-03
Flood	**ma-FL-WTS-01**	Green Stormwater Infrastructure	Expand stormwater BMPs and green infrastructure (e.g., raingardens, bioswales) in urban flood-prone areas, to retain stormwater and reduce the risk of flooding in adjacent or downstream areas. Integrate with climate change projections.	NRP, SP, PRV	Long 5-10 Years	City Public Works and Planning	High	High	Staff time, general fund, utility fund (when applicable)	Measure Q, Prop 4, EPA	Very High	ps-FL-SCC-07, ps-FL-SVL-04, ps-FL-WTS-04, ps-FL-WTS-05, ps-FL-WTS-06, ps-FL-WTS-07, ps-CC-WTS-02, ps-CC-WTS-03, ps-FL-WTS-01, ps-FL-WTS-02, ps-FL-WTS-08, ps-FL-WTS-09, ps-HR-WTS-01, ps-HR-WTS-02, ps-SW-WTS-01
Flood	**ma-FL-WTS-02**	Critical Facility Floodproofing	Elevate, floodproof, or relocate the wastewater treatment plant, police station, and emergency shelters located within the 1% annual chance floodplain.	PPRO, SP	Medium 3-5 Years	City Public Works and Utilities + County	High	High	Sewer fund, staff time	HMGP	High	ps-FL-CPT-04, ps-FL-WTS-03, ps-CC-WTS-03, ps-FL-WTS-04, ps-FL-WTS-06
Heavy Rain	**ma-HR-WTS-01**	Culvert & Drainage Retrofit Program	Upgrade culverts in flood prone areas and implement green infrastructure drainage solutions, using both nature-based and structural solutions where appropriate, to reduce localized flooding.	SP, PPRO	Medium 3-5 Years	City Public Works + Caltrans, County	High	High	Staff time, general fund, utility fund (when applicable)	Measure Q, Prop 4, EPA	Very High	ps-HR-WTS-01, ps-HR-SCC-01, ps-HR-SVL-02, ps-CC-WTS-02, ps-CC-WTS-03, ps-FL-WTS-04, ps-FL-WTS-06, ps-FL-WTS-07, ps-FL-WTS-08, ps-FL-WTS-09, ps-HR-WTS-02, ps-SW-WTS-01, ps-SW-WTS-02

Hazard	Action ID	Action Title	Description	FEMA Mitigation Alternative	Timeline	Responsibility	Cost	Benefit	Internal Funding Source	External Funding Source	Priority (Based on Criteria)	Problems Addressed
High Wind	**ma-HW-WTS-01**	Utility High Wind Corridor Assessment & Microgrid Pilot	Identify high-risk corridors and coordinate with utility providers to bury or harden power and communication lines and poles in high-risk corridors prone to wind damage. Invest in energy redundancy through piloting microgrid development.	SP, PPRO	Long 5-10 Years	City Public Works and Utilities + PG&E and other utility providers	High	High	Enterprise funds when applicable, staff time, general fund	PG&E Vegetation Management Partnership; FEMA HMGP; Cal Fire	Low	ps-HW-CBC-01, ps-HW-SVL-01, ps-HW-SVL-03, ps-CC-WTS-02, ps-CC-WTS-03, ps-SW-WTS-01, ps-SW-WTS-02
Slope Failure	**ma-SF-WTS-01**	Landslide Hazard Inventory & Mapping	Update slope stability and landslide risk maps to reflect local geology and rainfall trends.	PRV	Medium 3-5 Years	City Public Works and Planning + consultants	Medium	High	Staff time, general fund	FEMA	Medium	ps-SF-WTS-03, ps-SF-WTS-01, ps-SF-WTS-02, ps-SF-WTS-03
Slope Failure	**ma-SF-WTS-02**	Hillside Stabilization & Drainage Improvements	Conduct outreach to owners of high-risk properties to install slope stabilizing drainage and vegetation controls in western/northern neighborhoods.	PPRO, SP	Short 1-3 Years	City Planning + County OR3, RCD, CDFA, NRCS	Medium	High	Staff time, general fund	HMGP Cal Trans	Medium	ps-SF-WTS-01, ps-SF-CPT-02, ps-SF-WTS-02, ps-SF-WTS-03
Wildfire	**ma-WF-WTS-02**	Evacuation Education & Awareness	Create targeted multilingual and multigenerational outreach for mitigation resources, evacuation routes, and wildfire response in vulnerable WUI neighborhoods.	PE&A	Long 5-10 Years	City Police + County OR3, CERT, CBO partners	Medium	Medium	Staff time,	HMGP CAL FIRE CalOES	Medium	ps-WF-SVL-01, ps-CC-WTS-02, ps-CC-WTS-03, ps-WF-WTS-01, ps-WF-WTS-03
Wildfire	**ma-WF-WTS-01**	Establish Defensible Space Program	Establish defensible space inspection program and ensure compliance with clearing around critical facilities and infrastructure sites.	PRV, NRP, PPRO	Short 1-3 Years	City Fire and Public Works + CAL FIRE, County OES	Medium	High	Staff time	HMGP, CAL FIRE, CalOES, Prop 4, Measure Q	Low	ps-WF-CBC-02, ps-CC-WTS-02, ps-CC-WTS-03, ps-WF-WTS-01, ps-WF-WTS-02, ps-WF-WTS-03

3.6.4 Status of Previous Mitigation Actions

In 2020, the City of Watsonville adopted its previous FEMA-approved HMP. This 2025 MJHMP represents a comprehensive update from that previous plan, as discussed in Volume 1, Section 1.5. Table 3-16 provides status updates for the previous City Mitigation Action Plan, from which many of the mitigation actions in Table 3-15 were sourced and revised.

Table 3-16: Status of 2020 City of Watsonville Mitigation Actions

Action ID	Description	Status
1	Develop and implement seismic retrofit program options for home and business owners, including through public-private partnerships	Combined and revised into ma-EQ-WTS-01
2	Strengthen and stabilize public facilities and infrastructure, including but limited to nonreinforced masonry buildings, nonductile concrete buildings and facilities, storm lines, sloughs, storm culverts, channels, streets, and bridges	Combined and revised into ma-EQ-WTS-02, ma-HR-WTS-01
3	Structural improvements to earthen reservoirs	Combined and revised into ma-EQ-WTS-02
4	Protect roads, including in downtown and green valley corridors	Combined and revised into ma-EQ-WTS-02
5	Develop an eave construction program for homes	Combined and revised into ma-WF-WTS-01
6	Develop or improve defensible space for critical facilities, including wells, pump stations, reservoirs, booster tanks, and filter plant	Combined and revised into ma-WF-WTS-01
7	Assess and develop a plan to implement a 100-foot buffer for sloughs within City limits	Combined and revised into ma-FL-WTS-01
8	Develop or improve stormwater system BMPs, including but not limited to flood attenuation ponds, bio-retention, detention basins, gutters, storm drain inlets, culverts, culvert outfalls, bio swales, catch basins, and storm outfall dissipaters	Combined and revised into ma-FL-WTS-01, ma-HR-WTS-01
9	Develop and implement watershed improvements and habitat enhancements for sloughs, storm culverts, and channels	Combined and revised into ma-FL-WTS-01, ma-HR-WTS-01
10	Protect (elevate, armor, or relocate) critical infrastructure, facilities, and systems from sea level rise, including but not limited to pump stations, wells, and the wastewater treatment facility	Combined and revised into ma-FL-WTS-02
11	Promote and sponsor programs to buy out, relocate, elevate, and flood-proof existing flood-prone structures	Cancelled, ongoing baseline mitigation activity
12	Assess and increase the development and use of community gardens to support local food production, including through partnerships	Combined and revised into ma-CC-WTS-01

Action ID	Description	Status
13	Develop and implement upgrades to City properties and facilities with features that would improve stormwater runoff, provide water saving opportunities, and incorporate low-impact development strategies—all moving toward a more green infrastructure	Combined and revised into ma-FL-WTS-01
14	Develop and implement natural resource protection and management policies and programs, including tree planting programs, monitoring of invasive species, and support for native plants	Combined and revised into ma-CC-WTS-01, ma-FL-WTS-01
15	Develop redundancy in communications systems for water, storm pump stations, sewer lift stations, and critical airport facilities	Combined and revised into ma-EQ-WTS-02
16	Conduct a flood outreach program, including increased signage in flood-prone areas and improvements to the Flood Alert System	Cancelled, ongoing baseline mitigation activity
17	Develop community empowerment programs that promote hazard mitigation leadership and action	Combined and revised into ma-WF-WTS-02
18	Develop and implement energy efficiency policies and programs, including through public-private partnerships	Combined and revised into ma-CC-WTS-01
19	Develop and implement policies and programs that increase investments in local energy production, distribution, and storage, including through microgrid development	Combined and revised into ma-HW-WTS-01
20	Assess and provide backup power for critical infrastructure and facilities, including but not limited to wells, pump stations, reservoirs, booster tanks, and traffic control facilities	Combined and revised into ma-EQ-WTS-02, ma-HW-WTS-01
21	Assess the vulnerability of public facilities, infrastructure, and structures to seismic risk	Combined and revised into ma-EQ-WTS-01, ma-EQ-WTS-02
22	Develop an inventory of private structures and identify the types that are at greatest seismic risk	Combined and revised into ma-EQ-WTS-01, ma-EQ-WTS-02
23	Evaluate current policies that relate to stormwater and flood control to accommodate and mitigate expected future impacts to property, infrastructure, and community well-being	Combined and revised into ma-FL-WTS-02
24	Develop and implement a drought plan that includes monitoring groundwater levels and supply and increasing aquifer storage and recovery	Combined and revised into ma-DR-WTS-01
25	Assess current capacity of food banks and develop strategies to increase their functionality during disasters	Combined and revised into ma-FL-WTS-02
26	Trains and prepares City employees with the skills needed to properly manage any natural disaster or major critical incident	Cancelled, ongoing baseline mitigation activity

RESOLUTION NO. _____ (CM)

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE ADOPTING THE SANTA CRUZ COUNTY MULTI-JURISDICTIONAL HAZARD MITIGATION PLAN 2025 UPDATE (VOLUME 1 AND VOLUME 2)

WHEREAS, the City of Watsonville first adopted its Local Hazard Mitigation Plan (LHMP) in 2019, which requires an update in 2025 to meet FEMA assistance requirements. To complete this update, Watsonville has joined the 2025 Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan (MJHMP) effort, led by the County's Office of Response, Recovery, and Resilience (OR3) with consulting support from Dynamic Planning + Science (DP+S); and

WHEREAS, Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan 2025 Update ("the Plan") recognizes the threat that natural hazards pose to people, property infrastructure and natural resources within our City of Watsonville; and

WHEREAS, the implementation of hazard mitigation actions can significantly reduce the risk of injury, loss of life, property damage, and disruption caused by future natural hazard events; and

WHEREAS, the federal Disaster Mitigation Act of 2000 (DMA 2000) requires all cities, counties, and special districts to have adopted a Hazard Mitigation Plan to receive pre-and post-disaster mitigation funding from the Federal Emergency Management Agency (FEMA); and

WHEREAS, the City of Watsonville fully participated in the FEMA-prescribed mitigation planning process to prepare the Plan; and

WHERAS, a coalition of Santa Cruz County local governments and special districts embarked on a planning process to prepare for and lessen the impacts of specified hazards by updating the Plan; and

WHEREAS, each participating jurisdiction, including the City of Watsonville, has been responsible for reviewing and approving its respective Jurisdictional Annex within the Plan, and the Plan compiles individual annexes into a unified framework to ensure a comprehensive and coordinated hazard mitigation strategy for the entire Santa Cruz County planning area, aligned with the goals, objectives, and priorities of the Plan; and

WHEREAS, the Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan 2025 Update is comprised of two volumes, including Volume 1: Base Plan, which contains the countywide hazard mitigation framework and risk assessment, and Volume 2: Jurisdictional Annexes, which document the hazard profiles, vulnerabilities, and mitigation actions of participating jurisdictions; and

WHEREAS, a public involvement process consistent with the requirements of DMA 2000 was conducted to develop the Plan; and

WHEREAS, the California Governor's Office of Emergency Services (Cal OES) has reviewed and approved the Plan and has forwarded the plan to FEMA Region IX for final review and approval.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. The City of Watsonville hereby adopts the Santa Cruz County Multi-Jurisdictional Hazard Mitigation Plan 2025 Update as an official plan of the jurisdiction

replacing the City's stand-alone Local Hazard Mitigation Plan. The City of Watsonville adopts Volume 1 of the Plan in its entirety and acknowledges that the City of Watsonville Jurisdictional Annex contained in Volume 2 represents the jurisdiction's specific hazard mitigation strategies and responsibilities.

2. The City Council authorizes staff to make minor technical edits or administrative corrections to the Plan, as necessary to address FEMA review comments, prior to final adoption; and

3. Per Assembly Bill 2140, the City Council resolves to integrate the Plan by reference into the Public Safety Element of the General Plan in accordance with the requirements of Government Code sections 65302, 65302.6, and 8685.9; and

4. The City Council of the City of Watsonville further encourages the respective departments identified in the implementation strategy of the plan to carry out the recommended mitigation actions assigned to them; and

5. This Resolution will be submitted to Cal OES on behalf of the City of Watsonville by Santa Cruz County Staff to enable the Plan's final approval by Cal OES and FEMA; and

6. This action is not subject to review under the California Environmental Quality Act (CEQA) pursuant to Public Resources Code Section 21000, et seq. and the CEQA Guidelines (14 Cal. Code Regs. §§ 15000 et. seq.), including without limitation, Public Resources Code section 21065 and California Code of Regulations 15378 as this is not a "project" that may cause a direct, or reasonably foreseeable indirect, physical change in the environment and because the action constitutes organizational or administrative activities of governments that will not result in direct or indirect physical

changes in the environment. Additionally, even if a "project," the action would be exempt under the "common sense" exception (14 Cal. Code Regs. § 15061(b)(3)) because it can be seen with certainty that there is no possibility that this action may have a significant effect on the environment. Adoption of the Plan is also exempt from further CEQA review pursuant to CEQA Guidelines Section 15262, Feasibility and Planning Studies, because adoption of the Plan is planning for future actions, rather than committing to a specific action.

7. The City Clerk is hereby authorized and directed to incorporate the Santa Cruz County Multi-jurisdictional Hazard Mitigation Plan 2025 Update (Volume 1 and Volume 2) to this resolution upon final review by FEMA Region IX.

****

CITY OF WATSONVILLE

APPLICATION FOR APPOINTMENT TO A CITY BOARD OR COMMISSION

You must be a registered voter in the City of Watsonville to qualify for an appointment.

INSTRUCTIONS:

If you are interested in serving on a City board or commission, complete the following application and return it to the City Clerk's Office, 275 Main Street, Suite 400, (Fourth Floor), Watsonville, CA 95076 or email to cityclerk@cityofwatsonville.org.

Upon receipt, your application for appointment will be routed to the Council Members where a vacancy exists. If a Council Member is interested in nominating you for appointment, the City Clerk's Office or the Council Member will contact you.

Please specify below the commission or board to which you are seeking appointment and provide the requested information.

Thank you for your interest in City government.

COMMISSION OR BOARD

Martha Victoria Vega
NAME

[redacted], Watsonville, CA 95076
ADDRESS

(831) [redacted] Cell
TELEPHONE (HOME) _____ (WORK) _____

[redacted]
E-MAIL ADDRESS

Since 1982
LENGTH OF RESIDENCE IN AREA

PREVIOUS COMMISSION OR BOARD SERVED (PLEASE SPECIFY):

ADVISORY BOARD	TERM
City of Watsonville Library Board	1997 - 2001
County of Santa Cruz Park & Recreation Commission District #4	Current June 2022

CITY OF WATSONVILLE

EDUCATION:

INSTITUTION	MAJOR	DEGREE	YEAR
Saint Mary's College of California	- Leadership w/ School of Education	Masters	2015
Pacific Oaks College	- Human Development w/ Specialization in Social Change	Bachelor of Arts	2013
Union Institute & University	- Criminal Justice Management	Bachelor of Science	2017
Cabrillo College	- Spanish, Liberal Arts, Bilingual Bicultural Studies	Associates of Arts	2013

WORK/VOLUNTEER EXPERIENCE:

ORGANIZATION	ADDRESS	POSITION	YEAR
Volunteer Pajaro Valley Arts Council	37 Sudden St Watsonville, CA 95076	Board & Gallery Committee	2022
Work Pajaro Valley Unified School District Pajaro Valley High School	500 Harkins Slough Watsonville, CA 95076	Teacher	Aug. 2022
Work City of Watsonville	250 Main St Watsonville, CA 95076	Code Enforcement Officer	2018-2022
	215 Union St Watsonville, CA	Police Service Specialist	2013-2018

STATEMENT OF QUALIFICATION:
Please attach a brief statement indicating why you are interested in serving on the advisory body in question.

ACKNOWLEDGEMENT:
I understand that this application is a public document and its contents will be disclosed upon request, and any misrepresentation or deliberate omission of a material fact in this application may be justification for refusal or termination of appointment.

The Political Reform Act of 1974 requires all government agencies to adopt a Conflict of Interest Code that designates the positions within an agency which make or participate in making governmental decisions and may foreseeably have a material effect on any financial interest. Members of City boards and commissions, by virtue of their positions, make or participate in making decisions which may affect their financial interests and who therefore must disclose these interests on the Fair Political Practices Commission Form 700 – Statement of Economic Interests of Designated Employees. The Form 700 is a public document and its contents will be disclosed upon request. This form is to be filed upon appointment and every year thereafter with the Office of the City Clerk on April 1.

CERTIFICATION:
I acknowledge I have read the above information and certify that the information provided by me is true and correct, and I authorize the verification of the information in the application in the event I am a finalist for the appointment.

[redacted]

[redacted]
(Date)

RESOLUTION NO.

A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE APPOINTING MARTHA VEGA TO THE CITY OF WATSONVILLE PLANNING COMMISSION

[DISTRICT 7]

WHEREAS, Section 906 of the City Charter established a seven member Planning Commission with specific powers and duties; and

WHEREAS, Section 902 of the Charter of the City of Watsonville authorizes each member of the Council to appoint one member to each Commission subject to approval by resolution of the Council adopted by at least four (4) affirmative votes; and

WHEREAS, Ed Acosta resigned from his seat on the Planning Commission effective July 1, 2025; and

WHEREAS, Council Member Parker has nominated Martha Vega to fill the vacancy and serve the remainder of the unexpired term, ending December 2026.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF WATSONVILLE, CALIFORNIA, AS FOLLOWS:

1. Adopting a Resolution appointing a member to the Planning Commission does not meet CEQA's definition of a “project,” because the action does not have the potential for resulting in either a direct physical change in the environment or a reasonably foreseeable indirect physical change in the environment.

2. That Council Member Parker hereby nominates Martha Vega for appointment to the Planning Commission (expires December 2026), representing District 7.

3. That the Council approves such appointment.

4. That the City Clerk is hereby directed to transmit a copy of this resolution to the newly appointed member and to the Secretary of the Planning Commission.

****

The foregoing resolution was introduced at a regular meeting of the Council of the City of Watsonville, held on the **8th** day of **July, 2025**, by Member **Parker,** who moved its adoption, which motion being duly seconded by Member **Clark,** was upon roll call carried and the resolution failed by the following vote:

AYES:	COUNCIL MEMBERS:	**Clark, Parker**
NOES:	COUNCIL MEMBERS:	**Dutra, Montesino, Quiroz-Carter, Salcido**
ABSENT:	COUNCIL MEMBERS:	**Orozco**

_____
Kristal Salcido, Mayor Pro Tempore

ATTEST:

_____
Deputy City Clerk

_____
Date

APPROVED AS TO FORM:

_____
Assistant City Attorney

****

I, Alejandra Pacheco, Deputy City Clerk of the City of Watsonville, do hereby certify that the foregoing Resolution No. 210-25 (CM) was duly and regularly rejected and not adopted by the Watsonville City Council at a meeting thereof held on the 8th day of July, 2025, and that the foregoing is a full, true and correct copy of said Resolution.

_____
Alejandra Pacheco, Deputy City Clerk

Date_____

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Tuesday, April 14, 2026**
TO:	**CITY COUNCIL**
WRITTEN BY:	**COMMUNITY DEVELOPMENT DIRECTOR ORBACH**
RECOMMENDED BY:	**COMMUNITY DEVELOPMENT DIRECTOR ORBACH**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**ORDINANCE AMENDING CHAPTER 14-16 (DISTRICT REGULATIONS) OF THE WATSONVILLE MUNICIPAL CODE TO CONDITIONALLY PERMIT COMMERCIAL USES ON PARCELS ZONED PUBLIC FACILITIES (PF) AND LOCATED IN THE DOWNTOWN WATSONVILLE SPECIFIC PLAN AREA**

RECOMMENDATION:

City Staff recommends the City Council introduce, for first reading only, waiving full reading of the text, an Ordinance amending Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code to conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located in the Downtown Watsonville Specific Plan area.

BACKGROUND:

On April 22, 2003, the Watsonville City Council adopted Ordinance No. 1156-03, which amended Title 9 (Planning and Zoning) and Title 14 (Zoning) of the Watsonville Municipal Code relating to Public Facilities and Institutional zoning districts.

On September 11, 2018, the Watsonville City Council adopted Ordinance No. 1373-18, which amended Section 14-16.802 (Permitted, Development Permitted, and Special Use Permit Uses (Table)) and Section 14-16.803 (Use Regulations) of Part 8: PF – Public Facilities and N – Institutional Districts of Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code to allow emergency shelters by right in the PF – Public Facilities and N – Institutional Districts within the city.

On September 9, 2025, the Watsonville City Council adopted Ordinance No. 1481-25, which amended multiple chapters within Title 14 (Zoning) of the Watsonville Municipal Code related to implementation

of programs within the City's 6th Cycle 2023-2031 Housing Element, including updates to the use table in Section 14-16.802 and the addition of Section 14-16.802.1 Accessory Uses.

On April 7, 2026, the Planning Commission adopted Resolution No. 03-26 (PC) recommending that the City Council adopt an ordinance amending Chapter 14-16 (District Regulations) within Title 14 (Zoning) of the Watsonville Municipal Code (Attachment 2).

PROCESS:

Pursuant to WMC Section 14-12.801, the text of the adopted Zoning Code may be amended in a manner identical to WMC Section 14-12.701, which outlines the process for General Plan amendments. Any proposed zoning code text amendment shall be reviewed by the Planning Commission at a public hearing for recommendation to the City Council. At the conclusion of the public hearing, the Commission shall adopt a resolution, recommending approval or denial of the proposed amendment, by the affirmative vote of the majority of the Commission members, subject to findings required by WMC Section 14-12.708.

Upon receipt of the Commission's recommendation, and before adopting any amendment, the Council shall review the matter at a public hearing noticed in accordance with Part 9 of Chapter 14-10 and conducted in accordance with Part 10 of Chapter 14-10.

To approve the Zoning Code Text Amendments, the City Council must make the findings in WMC Section 14-12.708.

STANDARD OF REVIEW:

The approval of Zoning Code text amendments by the City Council is legislative and requires environmental review. For more information on standard of review and process, see the Standard of Review and Process Overview on the City website.

DISCUSSION:

The Public Facilities (PF) zoning district, per the use table in WMC Section 14-16.802, only permits aviation-related commercial uses on the Watsonville Municipal Airport property. No other commercial uses are permitted on parcels zoned PF in any other area of the city. In order to permit commercial tenants in both the existing and newly created commercial tenant spaces in City buildings located in the Downtown Watsonville Specific Plan (DWSP) area, such as the City Hall building at 275 Main Street, City staff is proposing the following amendments to WMC Title 14 Zoning:

1. WMC Section 14-16.802 - Permitted, development permitted, Special Use Permit uses (Table)
    a. Add subsection (j) DWSP Commercial Uses
        i. AUP (in table for PF)
            1. Requires Administrative Use Permit and Design Review
        ii. X (in table for Institutional)
2. WMC Section 14-16.803 - Use Regulations

a. Add subsection (j) DWSP Commercial Uses

i. (1) For parcels with the Public Facilities (PF) zoning designation located in the Downtown Watsonville Specific Plan area, any commercial use may be allowed with an Administrative Use Permit unless prohibited elsewhere in the Watsonville Municipal Code.

For parcels with the PF zoning designation that are located in the DWSP area, the proposed amendments would conditionally permit any commercial use with an Administrative Use Permit and a Design Review Permit approved by the Zoning Administrator as long as it is not illegal or prohibited elsewhere in the Watsonville Municipal Code. Parcels with the PF zoning designation within the DWSP area are identified in blue in Figure 1 below.

Figure 1: DWSP Figure 6-1 Regulating Plan



The parcels are listed by address in Table 1 below with the current use and owner listed.

Table 1: Parcels with PF Zoning Designation in DWSP Area

	Parcel Address	Parcel APN	Current Use	Parcel Owner
1	275 Main St.	017-781-07	Civic Plaza	City of Watsonville
2	-	017-781-06	Civic Plaza Parking Garage	City of Watsonville
3	105 2nd St.	017-172-34	Watsonville Fire Department	City of Watsonville
4	350 Main St.	017-112-01	Watsonville Plaza	City of Watsonville
5	310 Union St.	017-122-20	Solari Green Technology Center	City of Watsonville
6	120 2nd St.	017-101-47	Marinovich Park & Community Center	City of Watsonville
7	215 E. Beach St.	017-033-13	Watsonville Veterans Memorial Bldg.	County of Santa Cruz
8	214 Center St.	017-033-20	American Legion Post 121	American Legion
9	133 Brennan St.	018-151-14	Moreland Notre Dame School	Moreland Notre Dame
10	634 Main St.	018-151-41	Moreland Notre Dame School	Moreland Notre Dame
11	537 Main St.	018-231-48	Radcliff Elementary School	PVUSD
12	550 Rodriguez St.	018-231-49	Radcliff Elementary School	PVUSD
13	530 Rodriguez St.	018-231-28	Radcliff Elementary School	PVUSD
14	524 Rodriguez St.	018-231-27	Radcliff Elementary School	PVUSD
15	518 Rodriguez St.	018-231-26	Radcliff Elementary School	PVUSD
16	42 W. Lake Ave.	018-231-25	Radcliff Elementary School	PVUSD
17	40 W. Lake Ave.	018-231-24	Radcliff Elementary School	PVUSD
18	38 W. Lake Ave.	018-231-52	Radcliff Elementary School	PVUSD
19	26 W. Lake Ave.	018-231-21	Parking Lot	City of Watsonville

The list includes parcels occupied by both public facilities and institutional uses. However, for parcels zoned Public Facilities in the DWSP area, the DWSP defers to the development and use standards in WMC Section 14-16.800-803. The development and use standards in those sections cover both the Public Facilities and Institutional zoning districts. The development and use standards are applied based on where the current ownership and use of the property fit under the PF or N zoning district in the use table in WMC Section 14-16.802 Permitted, Development Permitted, and Special Use Permit Uses (Table). Therefore, the proposed zoning code text amendments will only apply to the PF properties in Table 2 below.

Table 2: Parcels with Existing PF Uses and PF Zoning Designation in DWSP Area

	Parcel Address	Parcel APN	Current Use	Parcel Owner
1	275 Main St.	017-781-07	Civic Plaza	City of Watsonville
2	-	017-781-06	Civic Plaza Parking Garage	City of Watsonville
3	105 2nd St.	017-172-34	Watsonville Fire Department	City of Watsonville
4	350 Main St.	017-112-01	Watsonville Plaza	City of Watsonville
5	310 Union St.	017-122-20	Solari Green Technology Center	City of Watsonville
6	120 2nd St.	017-101-47	Marinovich Park & Community Center	City of Watsonville
7	215 E. Beach St.	017-033-13	Watsonville Veterans Memorial Bldg.	County of Santa Cruz
8	214 Center St.	017-033-20	American Legion Post 121	American Legion
9	26 W. Lake Ave.	018-231-21	Parking Lot	City of Watsonville

The proposed permitting approach will provide applicants with certainty related to permitting timing and cost while also allowing the City staff to review and condition projects as needed to ensure that new

commercial uses comply with applicable regulations and standards and that any potential negative impacts are minimized.

A Specific Plan Amendment for the DWSP is not required because the DWSP defers to the development and use standards in WMC Section 14-16.800-803 for parcels zoned Public Facilities.

The proposed amendments to WMC Title 14 Zoning are included as Attachment 1 and located in Exhibit A to the ordinance.

ZONING CODE TEXT AMENDMENT FINDINGS:

Pursuant to WMC Section 14-12.807, the Planning Commission and the City Council shall, in approving a text amendment to the zoning code, make the findings in WMC Section 14-12.708. Those findings with supportive evidence are below.

a) That the proposed amendment is consistent with the policies embodied in the General Plan.

Supportive Evidence: The proposed amendments are consistent with the following policies embodied in the General Plan as described below:

- **Goal 4.3 & Policy 4.C Commercial Land Use** – Revitalize the central business district and provide adequate neighborhood commercial services.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Providing a permitting pathway for additional commercial uses in the downtown area will help revitalize the central business district.

- **Goal 4.6 Local Employment** – Promote a variety of employment opportunities within the city providing living wage jobs to Watsonville residents. Stimulate creation of 7,500 additional jobs by 2005. Pursue opportunities for job skill training.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. New commercial uses will provide additional employment opportunities for Watsonville residents within the downtown area.

- **Policy 4.C.4 Visitor Commercial** – The City shall plan for additional visitor-serving facilities within the central business district and in suitable locations in proximity to Highway 1.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Buildings such as the City Hall building located at 275 Main Street are both centrally located and visitor-serving, with an attached parking structure (Civic Plaza Parking Garage) serving commercial uses on surrounding parcels as well as visitors to the Civic Plaza, Watsonville Public Library, and

Superior Court of Santa Cruz. Therefore, permitting commercial uses in these locations will provide additional visitor-serving facilities within the central business district.

- **Implementation Measure 4.G.2 Multiple Use** – Wherever feasible and appropriate, and where the potential impacts and mitigation measures associated with mixed use can be identified and fully considered through the CEQA process, the City shall support intensification of use by combining uses on one site, e.g. residential and commercial, institutional and recreational.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Buildings such as the City Hall building located at 275 Main Street already include a mix of public uses, such as Watsonville Civic Plaza, Watsonville Public Library, the Superior Court of Santa Cruz, and the Civic Plaza Parking Garage. Adding commercial uses in these locations is feasible and appropriate because it will complement and support the existing uses.

b) That the proposed amendment is compatible to the extent possible with the actual and general planned use of the adjacent properties.

Supportive Evidence: The proposed amendments were modeled after the allowable commercial uses in the DWSP area. Therefore, they are consistent and compatible with the land use regulations identified in the DWSP, which was adopted in October 2023, and the General Plan as modified by the DWSP. Therefore, the proposed amendment is compatible with the actual and general planned use of the adjacent properties.

These findings are located in Exhibit B to the ordinance.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

The proposed zoning code text amendment is categorically exempt from the California Environmental Quality Act under the common sense exemption in Section 15061(b)(3).

Cal. Code Regs. Title 14, §15061(b)(3) states that CEQA applies only to projects which have the potential for causing a significant effect on the environment. Where it can be seen with certainty that there is no possibility that the activity in question may have a significant effect on the environment, the activity is not subject to CEQA. There is no possibility that the amendments to the text of the Zoning Code would have significant effects on the environment because no actual physical project is being proposed at this time.

Accordingly, no further environmental review is required.

STRATEGIC PLAN:

The purpose of the City of Watsonville's 2023-2025 Strategic Plan is to help the City prioritize its efforts, allocating both fiscal and human resources to achieve a shared vision and goals. The 2023-2025 Strategic Plan identifies seven goals, concerning economic development, infrastructure and environment, housing,

fiscal health, public safety, community engagement and well-being, and efficient and well-performing government.

Conditionally permitting commercial uses on parcels zoned Public Facilities (PF) in Downtown Watsonville Specific Plan area, which will permit businesses to occupy new and currently vacant commercial tenant spaces in downtown Watsonville, the proposed Zoning Code Text Amendments support the City Council's economic development and fiscal health goals.

FINANCIAL IMPACT:

A fiscal impact analysis estimates the costs and revenues to a local government from new plans or development proposals. The proposed item involves amending the Watsonville Municipal Code to conditionally permit commercial uses on parcels zoned PF and located in the Downtown Watsonville Specific Plan area. New commercial uses would create additional sources of revenue for the City. Therefore, the proposed Zoning Code Text Amendments would have a positive financial impact on the City.

ALTERNATIVE ACTION:

The City Council may consider continuing the project and directing staff to return with additional information and/or revisions.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

1. Proposed Zoning Code Text Amendments – WMC Sections 14-16.802 & 14-16.803
2. Planning Commission Staff Report – 04.07.2026

CITY OF WATSONVILLE
CITY COUNCIL

Chapter 14-16
DISTRICT REGULATIONS

Part 8: PF – Public Facilities and N – Institutional Districts

14-16.802 Permitted, development permitted, and Special Use Permit uses (Table).

The following list represents those uses, subject to the provisions of this title, in the Public Facilities (PF) and the Institutional (N) zones that are permitted by right (P), subject to Design Review (D), require an Administrative Use Permit with Design Review approval (AUP), require a Special Use Permit with Design Review approval (SUP), require an approval of a Temporary Use Permit (TUP), or are prohibited (X).

Any other use or service establishment determined by the Zoning Administrator to be of the same general character as the foregoing permitted uses, which will not impair the present or potential use of adjacent properties, shall be permitted. If the Zoning Administrator determines that the proposed use is more in character with the conditional uses for this zone, then either an AUP or SUP shall be required to be processed.

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(a) Institutional and uses of community significance		
(1) Cemetery	SUP	SUP
(2) Churches and other places of worship	X	SUP
(3) Clinics and rehabilitation facilities (public/nonprofit)	SUP	SUP

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(4) Community center and related facilities (public/nonprofit)	AUP	AUP
(5) Daycare center (public/nonprofit/private)	AUP	AUP
(6) Educational facility (public/private)	SUP	SUP*
(7) Galleries and museums (public/nonprofit)	D	AUP
(8) Large group care or group home (public/private/nonprofit)	X	SUP
(9) Hospital (public/nonprofit/private)	X	SUP
(10) Judicial center with or without jail facilities	SUP/AUP	X/X
(11) Nursing, convalescent and residential care facility (public/nonprofit)	X	AUP
(12) Post office*	AUP	AUP
(13) Use of community significance	SUP	SUP
(b) Lodging uses		
(1) Campground (public)	SUP	X
(2) Conference center	SUP	X
(c) Government buildings		

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(1) Government offices (local/state/federal)	D	X
(2) Nonprofit organization offices	AUP	AUP
(3) Fire/Paramedic Station	D	X
(4) Library (public)	D	X
(d) Recreation uses		
(1) Equestrian facility	SUP	X
(2) Golf course	SUP	X
(3) Membership club or hall	D	SUP
(4) Outdoor recreation with lighted facilities	D/AUP	AUP/SUP
(5) Park or playfield with lighted facilities	D/AUP	AUP/SUP
(6) Public Recreation Center	D	SUP
(e) Residential uses		
(1) Affordable housing project (multi-family, rental)	SUP	X
(2) Caretaker's residence	AUP	AUP
(3) Emergency shelter	P	P
(4) Rectory/minister's residence	X	AUP
(5) Transitional housing	AUP	X
(f) Transportation uses		

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(1) Airport (airfield modifications)	D	X
(2) Airport support (terminal expansion)	D	X
(3) Aviation commercial (airport access)	AUP	X
(4) Aviation noncommercial (hangars and taxiways)	D	X
(5) Aviation compatible (research park improvements)	SUP	X
(6) Helistop	SUP	X
(7) Mass transit center	AUP	X
(8) Park and ride facility	D	AUP
(9) Parking structure or parking lot (primary use)	D	X
(10) Terminal and passenger service facility	AUP	X
(g) Utility and public service uses		
(1) Electrical power substation	AUP	X
(2) Public or quasi-public facility other than listed	AUP	AUP
(3) Public safety telecommunication facility	D	X

Uses (See Section 14-16.803 for use descriptions)	PF	N
(4) Sewage or water transmission lines	P	X
(5) Telecommunications site — Telecommunications site exceeding height limit of district	AUP/SUP	AUP/SUP
(6) Utility service facility	P	X
(7) Water tank, water treatment facility or sewer lift station	D	X
(8) Telecommunications facilities	SUP	X
(h) Accessory uses		
(1) Accessory outside storage	D	AUP
(2) Accessory structure	D	D
(3) Shipping containers	D	D
(4) Satellite earth station antennas	P	P
(i) Temporary uses		
(1) Emergency noncommercial telecommunications facility	TUP	X
(2) Temporary batch plant	TUP	X
(3) Temporary construction office and/or yard	TUP	TUP

Uses (See Section 14-16.803 for use descriptions)	PF	N
(4) Temporary dwelling unit	TUP	TUP
(j) DWSP Commercial Uses	AUP	X

*State or Federal facilities not subject to City of Watsonville Review except as leasehold project.

Key:

D — Requires Design Review
SUP — Requires Special Use Permit with Design Review
X — Prohibited
AUP — Requires Administrative Use Permit with Design Review
TUP — Temporary Use Permit
P — Principally Permitted (may require a Building Permit)

(Ord. 1156-03 C-M, eff. May 22, 2003, as amended by § 1, Ord. 1373-18 (CM), eff. October 11, 2018, and § 2(3) (Exh. A), Ord. 1481-25 (CM), eff. October 9, 2025)

14-16.802.1 Accessory uses.

The following uses are only permitted with an Administrative Review Permit if a primary residential unit is provided or present on the site:

DLU	02	Accessory dwelling unit
	02	Junior accessory dwelling unit

(§ 2(3) (Exh. A), Ord. 1481-25 (CM), eff. October 9, 2025)

14-16.803 Use regulations.

(a) Institutional and uses of community significance.

(1) Cemetery.

(i) Definition: A place designated for the burial or retention of the remains of the dead whether human or animals, including crematories, mausoleums, and columbariums operated within the boundaries of the cemetery.

(ii) Parking requirements: To be determined through a Use Permit.[1]

(iii) Loading requirements: To be determined through a Use Permit.[1]

(iv) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(2) Churches and other places of worship.

(i) Definition: A facility principally used for people to gather together for public worship, religious training, or other religious activities.

(ii) Parking requirements: One space per four (4) seats feet in the worship area, plus any parking required for accessory uses.[1]

(iii) Loading requirements: None.[1]

(iv) Additional provisions:

(aa) The structure height limitations of this code shall not apply to church spires, belfries, or cupolas;

(bb) One single-family dwelling used to house a church official and family is considered customary and incidental as a part of this use.

(cc) Daycares subject to an Administrative Use Permit.

(dd) Schools subject to a Special Use Permit.

(3) Clinics and rehabilitation facilities (public/nonprofit).

(i) Definition: An establishment where patients are admitted for study/treatment by two (2) or more medical professionals.

(ii) Parking requirement: One space per three (3) service units/beds plus one space per two (2) employees or one space per two hundred (200) square feet of area whichever is greater.[1]

(4) Community facility.

(i) Definition: A facility for a use of community significance, public or quasi-public, where public services or information is provided on a nonprofit basis, including but not limited to government offices, senior centers, meeting rooms, family counseling or family help centers, and police substations.

(ii) Parking requirements: One space per two hundred and fifty (250) square feet of office area, meeting rooms thirty percent (30%) of maximum occupancy, or as determined by Design Review.[1]

(iii) Loading requirements: To be determined through Design Review.

(5) Day care center (public/nonprofit).

(i) Definition: A facility providing less than twenty-four (24) hour care or supervision for fourteen (14) or more persons who are not related by blood, marriage, or adoption to the owner, operator, or manager. Such facility may operate by day or night, with or without compensation for such care, and with or without a stated educational purpose.

(ii) Parking requirements: One space for every eight (8) persons plus one space per employee.[1]

(iii) Additional provisions:

(aa) This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, County, State and Federal permits.

(6) Educational facility (public/private).

(i) Definition: Buildings and uses for public or private educational or research activities associated with an academic institution which has a curriculum for technical, vocational training, or higher education.

(ii) Parking requirements:[1]

(aa) Elementary or junior high school, one space per employee plus one space for every twenty (20) students of school design capacity.

(bb) High school, one space per employee plus one space for every seven (7) students of school design capacity.[1]

(7) Galleries and museums (public/nonprofit).

(i) Definition: A place offering or displaying artistic works, decorative objects or the like for public viewing or sale.

(ii) Parking requirements: three (3) parking spaces plus one space per eight hundred (800) square feet of floor space.[1]

(8) Large group care or group home (public/private/nonprofit).

(i) Definition: A facility which provides twenty-four (24) hour care or supervision of more than twelve (12) persons who are not related by blood, marriage, or adoption, to the owner, operator, or manager, and who do not meet the definition of a family. A group care or foster home may be operated by a public, nonprofit, or private agency. This definition includes halfway houses and drug or alcohol rehabilitation facilities for any number of persons, with or without twenty-four (24) hour care or supervision,

(ii) Parking requirements: One-half (0.5) parking spaces per bed or one and one-quarter (1.25) parking spaces per living unit, whichever is greater.[1]

(iii) Additional provisions:

(aa) This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the city, all applicable local, State, and Federal permits;

(9) Hospital (public/nonprofit/private).

(i) Definition: An institution where people are given medical attention and treatment including but not limited to related facilities such as laboratories, outpatient clinics, and staff offices on primarily an inpatient basis.

(ii) Parking requirements: One space per two (2) patient beds plus one per employee on shift with maximum personnel.[1]

(iii) Loading requirements: One loading space for ten thousand (10,000) or more square feet of floor area.

(iv) Setbacks: Minimum setback of thirty (30), feet from any residential district.

(v) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(vi) Helipads: Helipads shall be allowed for hospitals as long as they are setback a minimum of two hundred (200) feet from residential uses and they do not include support facilities such as refueling or similar use.

(10) Judicial center with or without jail facilities.

(i) Definition: Buildings used for courtrooms, police stations, jails, and accessory offices.

(ii) Parking requirements: To be determined through a Special Use Permit.[1]

(iii) Loading requirements: To be determined through a Special Use Permit.

(11) Nursing, convalescent and residential care facility (public/nonprofit).

(i) Definition: A facility which provides twenty-four (24) hour residential care to persons who are not related by blood, marriage, or adoption to the owner, operator, or manager of the facility. A nursing, convalescent, or residential care facility provides some level of skilled nursing or medical service to the residents.

(ii) Parking requirements: One parking space per five (5) patient beds plus one per each two (2) employees.[1]

(iii) Loading requirements: To be determined by Use Permit

(iv) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(12) Post office.

(i) Definition: A facility owned and/or operated by the United States Postal Service where public mailing services, including distribution and delivery of mail, are provided.

(ii) Parking requirements: One space per three hundred (300) square feet of gross floor area over four thousand (4,000) square feet plus one per post office vehicle and one per three (3) employees.[1]

(iii) Loading: a minimum of two (2) loading spaces shall be provided and one additional loading space per each twenty thousand (20,000) square feet of building area.

(13) Use of community significance.

(i) Definition: A use determined to have significant historic cultural, economic, social, or environmental value to the City, which does not conform to the use regulations of the district in which the use is located as a result of either the adoption or amendment of this Code, and which cannot be made conforming through any other discretionary review process under this Code.

(ii) Parking requirements: To be determined through Use Permit.[1]

(iii) Loading requirements: To be determined through Use Permit.

(iv) Additional provisions: The creation of murals falls within this definition.

(b) Lodging uses.

(1) Campground (public).

(i) Definition: An area of land where accommodations for occupation on a transient basis are located or may be placed. This includes tents and recreational vehicles.

(ii) Parking requirements: One parking space per tent or recreational vehicle space.

(2) Conference center.

(i) Definition: An indoor overnight facility, including either a single building or multi-building complex with or without individual kitchens, which serves as a destination point for visitors, which includes conference facilities.

(ii) Parking requirements: One and one-half (1.5) spaces per room or two (2) spaces per cabin, plus one space per two hundred (200) square feet of meeting room(s).[1]

(iii) Loading requirements: To be determined through Use Permit.

(iv) Additional provisions: Guest residency is limited to a transient basis.

(c) Government Buildings.

(1) Government offices (public).

(i) Definition: A building/office used by Federal, State, County or City government agencies or an instrumentality thereof.

(ii) Parking requirements: One space per five hundred (500) square feet of floor area, or as determined by Design Review based on the type of use.[1]

(2) Nonprofit organization offices.

(i) Definition: Buildings or offices used by an Internal Revenue Service (IRS) designated 501 3(c) entity. This use does not include medical/clinic facilities or other specific uses identified in this chapter where run by a non profit entity.

(ii) Parking requirement: One space per five hundred (500) square feet of floor area or as determined by Design Review.[1]

(3) Fire/Paramedic Station.

(i) Definition: A facility operated by a municipality, fire district, department, or private company which houses fire and paramedic equipment and may be used for the housing of personnel.

(ii) Parking requirements: To be determined through Design Review.[1]

(4) Library (public).

(i) Definition: Buildings used for public access to books, computers and other publications.

(ii) Parking: Ten (10) spaces plus one per each four hundred (400) square feet of floor area over five thousand (5,000) square feet.[1]

(iii) Loading: To be determined through the Design Review process.

(iv) Other standards: To be determined through the Design Review process.

(d) Recreation uses.

(1) Equestrian facility.

(i) Definition: A public or commercial facility for horse training, horse boarding, competitive equestrian events, rentals, sales and lessons.

(ii) Parking requirements: Determined through Design Review.[1]

(iii) Additional provisions:

(iv) Setback requirements:

(aa) Structures intended or designed to house animals shall be located a minimum of fifty (50) feet from all lot lines.

(bb) Outdoor lighting of facility requires Use Permit approval.

(2) Golf course.

(i) Definition: A recreational facility primarily used for the purpose of playing golf, but which may include accessory eating and drinking areas, retail sales areas, locker rooms and staff offices. The use includes stand-alone driving ranges, miniature golf and "pitch and putt" facilities.

(ii) Parking requirements: four (4) spaces per hole, plus as required for accessory uses including but not limited to pro shops and restaurants. One and one-half (1.5) space per miniature hole or driving range station.[1]

(3) Membership club or hall.

(i) Definition: A facility, including associated eating, drinking, and recreational facilities, owned or operated by a group of people organized for a common social, educational, service, or recreational purpose. These clubs are usually characterized by certain membership qualifications, payment of fees or dues, regular meetings, a constitution, and bylaws.

(ii) Parking requirements: One space per three hundred (300) square feet of floor area.[1]

(4) Outdoor recreation, for day use or with lighted fields.

(i) Definition: An area or facility which offers entertainment, recreation, or games of skill for a fee where any portion of the activity takes place outside. This includes but is not limited to a rifle range, boating facility, or tennis facility.

(ii) Parking requirements: As established through Title 9, Part 12 (Public and Quasi-Public Open Centers) standards and Design Review.[1]

(5) Park or playfield, for day use or with lighted facilities.

(i) Definition: A recreational area providing parks and playfields. This includes publicly-owned and commonly-owned recreational facilities such as playgrounds, parks, game courts, swimming pools, and playing fields.

(ii) Parking requirements: As established through Title 9, Part 12 (Public and Quasi-Public Open Centers) standards and Design Review or planned development.[1]

(6) Public recreation center.

(i) Definition: A publicly-owned area providing indoor recreational facilities such as multi-purpose rooms, basketball courts, training facilities.

(ii) Parking requirements: As established through Title 9, Part 12 (Public and Quasi-Public Open Centers) standards and Design Review or planned development.[1]

(e) Residential uses.

(1) Affordable housing project (multi-family, rental).
    (i) Definition: Two (2) or more rental dwelling units which are restricted in rental rates so as to meet the definition of affordable of the City or Redevelopment Agency.
    (ii) Parking requirements: One and a half (1.5) spaces per unit for up to three (3) bedrooms; two (2) spaces per unit for four (4) or more bedrooms. Additionally, one additional guest space shall be provided per eight (8) bedrooms.[1]
    (iii) Density and Development Standards: Affordable housing developed under these provisions shall follow the RM-2 district regulations and minimum net land area standards.
(2) Caretaker's residence.
    (i) Definition: An accessory structure intended to house an individual and immediate family who is principally employed by the principal use to provide maintenance, security or other services directly related to the facility.
    (ii) Parking requirements: Two (2) dedicated spaces per unit.[1]
    (iii) Additional provisions: There may be no more than one caretaker's residence per facility.
(3) Emergency shelter.
    (i) Definition: Housing with minimal supportive services for homeless persons that is limited to occupancy of six (6) months or less by a homeless person. No individual or household may be denied emergency shelter because of an inability to pay.
    (ii) Parking requirements: As determined by Chapter 14-43.
    (iii) Development standards: As determined by Chapter 14-43.
(4) Rectory/minister's residence.
    (i) Definition: Primary housing facility for ministry leaders, their family and guests which are located on the premises of the place of worship.
    (ii) Parking requirements: Two (2) dedicated spaces per unit.[1]
    (iii) Additional provisions: There may be no more than two (2) residences per facility.
(5) Transitional housing.
    (i) Definition: A structure or facility used as housing for a period of up to twenty-four (24) months for individuals and/or families who have been displaced from their home.
    (ii) Parking requirements: One space per unit if an additional 0.5 (1/2) spaces per unit is available on the street directly adjacent to the facility.

Otherwise, projects shall be designed to provide one and one half (1.5) parking spaces per unit on-site.[1]

(iii) Development Standards: As determined by Use Permit.

(f) Transportation uses.

(1) Airport (air field modifications).

(i) Definition: Facilities/modifications to the existing air field and infrastructure necessary to support safe aircraft arrival and departure which are identified in the Watsonville Municipal Airport Master Plan including but not limited to: Instrument Landing System (ILS) improvements, runway extension, taxiway improvements allowed when a master plan is approved.

(ii) Development Standards: As outlined in a master plan and developed in conjunction with Design Review.

(2) Airport support (terminal expansion).

(i) Definition: Facilities to improve airport operations identified in the Watsonville Municipal Airport Master Plan including but not limited to: airport administration, airport maintenance, aviation fuel facilities, pilot lounge and general services facilities, terminal expansion, and aircraft rescue and fire fighting facilities.

(ii) Development Standards: As outlined in Master Plan and developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(3) Aviation commercial (airport access).

(i) Definition: Facilities necessary to provide area for commercial uses that serve the needs of general aviation at the airport identified in the Watsonville Municipal Airport Master Plan including but not limited to: fixed base operator facilities involving the sale of general aviation products and services to the general public and limited service commercial facilities, such as avionics sales and repair shops, aircraft paint shops and aircraft maintenance facilities.

(ii) Development Standards: As outlined in Master Plan and developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(4) Aviation noncommercial (hangars and taxiways).

(i) Definition: Facilities necessary to provide area for non-commercial aircraft operators to store and service private aircraft which are

identified in the Watsonville Municipal Airport Master Plan including but not limited to: new hangars, taxiways, fuel facilities.

(ii) Development Standards: As outlined in Master Plan and developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(5) Aviation compatible (research park improvements).

(i) Definition: Facilities necessary to provide for non-aviation uses that support airport operations which are identified in the Watsonville Municipal Airport Master Plan including but not limited to automobile rental agencies, airport restaurant, motel, office park or research and development facilities.

(ii) Development Standards: As outlined in Master Plan and following the Commercial development standards within the City's development codes for the specific use or as developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(6) Helistop.

(i) Definition: Any designated area outside of the airport used for the landing and taking off of helicopters for the purpose of picking up or discharging passengers or cargo including designated emergency medical patients. This use does not include fueling, refueling, or service facilities.

(ii) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(iii) Helistops shall be no closer than two hundred feet (200') to any residential zone.

(7) Mass transit center.

(i) Definition: A transportation facility that serves as a transportation hub for buses, trains or other forms of mass transportation. These can be associated with Park and ride facilities.

(ii) Additional provisions: To be determined through the Use Permit process.

(8) Park and ride facility.

(i) Definition: A facility whose sole purpose is to provide parking for motor vehicles and bicycles with a connection to mass transit services or carpooling activities.[1]

(ii) Additional provisions: To be determined through Design Review process.

(9) Parking structure and parking lot (primary use).

(i) Definition: A structure or area the purpose of which is to allow the parking of motor vehicles, for a fee or not, as the primary use on a parcel.

(ii) Additional provisions: To be determined through the Design Review process including screening lots by landscaping from adjacent rights-of-way.

(10) Terminal and passenger service facility.

(i) Definition: Establishments engaged in the operation of motor vehicle passenger service terminals including maintenance and service facilities, including bus and taxicab fleet operations.

(ii) Parking requirements: Customer and employee parking at one space for every two hundred and fifty (250) square feet of office area and one space for every one thousand feet (1,000') of maintenance service area vehicles related to the operation of the terminal may not be parked in customer or employee parking areas.[1]

(g) Utility and public service uses.

(1) Electrical power substation.

(i) Definition: A facility operated by an electrical utility company that acts as a collection and distribution point for electricity. The facility includes transformers, and other equipment that reduce high voltage current and transfer it to utility lines.

(2) Public or quasi-public facility other than listed.

(i) Definition: A public or quasi-public facility other than those specified in this chapter.

(ii) Parking requirements: To be determined through Special Use Permit.[1]

(iii) Loading requirements: To be determined through Special Use Permit.

(3) Public safety telecommunication facility.

(i) Definition: A facility owned or operated by a governmental agency or a volunteer public safety agency officially sanctioned by a government agency for that purpose, utilized for the transmission and reception of electromagnetic or electro-optic information for public safety communication uses in accordance with the provisions of Chapter 14-35, Telecommunications Uses.

(4) Sewage or water transmission lines.

(i) Definition: Pipelines used for the transport of water (potable or non-potable) or sewage effluent.

(5) Telecommunications site.

(i) Definition: See Section 14-18.804.

(ii) Additional provisions: Comply with Chapter 14-35, Telecommunication Uses.

(6) Utility service facility.

(i) Definition: Any electrical distribution lines, natural gas distribution lines, minor gas regulator stations, cable television lines, telegraph and telephone lines, and gathering lines, or other minor service facilities.

(ii) Additional provisions: No buildings may be associated with this use.

(7) Water tank, water treatment facility or sewer lift station.

(i) Definition: A water facility with a capacity of five thousand (5,000) gallons or more for purifying, supplying, and holding water, or a sewer lift station facility, each including appurtenant wells, pumps, and control buildings.

(ii) Additional Provisions: Comply with Chapter 14-35, Telecommunications Uses.

(8) Telecommunications facilities.

(i) Definition: See Section 14-18.803.

(ii) Additional provisions: Comply with Chapter 14-35, Telecommunication Uses.

(h) Accessory uses.

An accessory use must be a use customarily incidental to and on the same parcel as the main use. A use listed in Chapter 14-16.02 may be an accessory use if the Zoning Administrator determines that the use is customarily incidental to a main use. Except as provided in this section, an accessory use must comply with all regulations applicable to the main use.

(1) Accessory outside storage.

(i) Definition: The outside placement, for a period of more than forty-eight (48) hours, of items which are customary and incidental to the main use of the property.

(ii) Additional provisions:

(aa) The area of placement may not exceed five (5%) percent of the lot area;

(bb) Items must be screened from the view of adjacent roadways and properties;

(cc) Accessory outdoor storage of agricultural products and operable agricultural equipment is exempt from these additional provisions;

(dd) For purposes of these regulations, recreational equipment includes motor homes, boats, and boat trailers, travel trailers, pick-up campers, tent trailers, utility trailers and similar equipment, and cases or boxes used for transporting recreation

equipment, whether occupied by equipment or not. Recreation equipment must be parked or stored in a carport or in an enclosed building, or up to two (2) units may be parked behind the nearest portion of a building to the street, screened by a six foot (6') solid fence or wall provided that equipment may be parked anywhere for a time period not to exceed forty-eight (48) hours during loading or unloading. Recreational equipment must not be used for living, sleeping or housekeeping purposes when parked or stored on any lot or in any location not approved for the use.

(2) Accessory structure.

(i) Definition: A structure detached from, but located on, the same lot as the principal use, the use of which is incidental and accessory to that of the principal use, and not designed for human habitation.

(ii) Additional provisions: Any accessory structure is subject to the minimum requirements of the zoning district in which it is located; however, accessory structures less than fifteen feet (15') in height from adjacent pre-developed grade may be located five feet (5') from the side or rear lot lines within the rear yard area.

(3) Shipping containers.

(i) Definition: Any enclosed container constructed of metal, wood, or other material which container was designed or patterned after structures used in containerized shipping operations used for temporary or permanent storage.

(ii) Parking requirements: None for temporary applications; at least one per three (3) container units for permanent applications as determined by Design Review.[1]

(iii) Additional provisions: See Section 14-10.170.

(4) Satellite earth station antennae.

(i) Definition: See Section 14-18.064(8).

(ii) Development Standards: See Chapter 14-35, Telecommunications Uses.

(i) Temporary uses.

(1) Emergency noncommercial telecommunications facility.

(i) Definition: A facility owned or operated by a governmental agency or a volunteer public safety agency officially sanctioned by a government agency for that purpose used for the transmission and reception of electromagnetic or electro-optic information for public safety

communication uses. This facility may operate for a maximum of six (6) months.

(ii) Parking requirements: To be determined through the Temporary Use Permit.[1]

(iii) Loading requirements: To be determined through the Temporary Use Permit.

(2) Temporary batch plant.

(i) Definition: A temporary facility for mixing concrete, asphalt or similar paving materials.

(ii) Parking requirements: To be determined through the Temporary Use Permit.[1]

(iii) Loading requirements: To be determined through the Temporary Use Permit.

(iv) Additional provisions:

(aa) Limited to a maximum six (6) months for specific project needs;

(bb) The Zoning Administrator may limit the hours of operation where the use is to be located within six hundred feet (600') of residentially zoned property.

(3) Temporary construction office and/or yard.

(i) Definition: A facility temporarily used as a construction or sales office or staging/storage area.

(ii) Parking requirements: To be determined through the Temporary Use Permit.1

(iii) Loading requirements: To be determined through the Temporary Use Permit.

(iv) Additional provisions:

(aa) Office use limited to a maximum of twelve (12) months with up to two (2) six (6) month extensions;

(bb) Storage/staging uses limited to six (6) months with up to two (2) six (6) month extensions.

(4) Temporary dwelling unit.

(i) Definition: A dwelling unit temporarily used by a watchperson during construction.

(ii) Additional provisions:

(aa) May be approved only in conjunction with the issuance of a Building Permit for a commercial project or a residential project involving construction of three (3) or more new dwelling units.

(bb) One unit per project site.

(cc) Unit must be connected to City water and sewer.

(j) DWSP Commercial Uses

(1) For parcels with the Public Facilities (PF) zoning designation located in the Downtown Watsonville Specific Plan area, any commercial use may be allowed with an Administrative Use Permit unless prohibited elsewhere in the Watsonville Municipal Code.

(Ord. 1156-03 C-M, eff. May 22, 2003, as amended by § 1, Ord. 1373-18 (CM), eff. October 11, 2018, and § 2(3) (Exh. A), Ord. 1481-25 (CM), eff. October 9, 2025)

[1] Parking requirements established by this Code supersede those established by Title 9, Chapter 3, for specific use listed.

CITY COUNCIL AGENDA REPORT

MEETING DATE:	**Monday, April 7, 2025**
TO:	**PLANNING COMMISSION**
WRITTEN BY:	MATT ORBACH, COMMUNITY DEVELOPMENT DIRECTOR
RECOMMENDED BY:	**DEPUTY CITY MANAGER MANNING**
APPROVED BY:	**TAMARA VIDES, CITY MANAGER**
SUBJECT:	**ZONING CODE TEXT AMENDMENTS ALLOWING COMMERCIAL USES IN THE PUBLIC FACILITIES (PF) ZONING DISTRICT**

RECOMMENDATION:

City Staff recommends the Planning Commission adopt a resolution recommending City Council adopt zoning code text amendments to Part 8 of Chapter 14-16 (District Regulations) within Title 14 (Zoning) of the Watsonville Municipal Code to conditionally permit commercial uses in the Public Facilities (PF) zoning district in the Downtown Watsonville Specific Plan area; and finding the action exempt from review under the California Environmental Quality Act (CEQA) as it is not a "project" but if a project, exempt pursuant to CEQA Guidelines section 15061(b)(3).

BACKGROUND:

On April 22, 2003, the Watsonville City Council adopted Ordinance No. 1156-03, which amended Title 9 (Planning and Zoning) and Title 14 (Zoning) of the Watsonville Municipal Code relating to Public Facilities and Institutional zoning districts.

On September 11, 2018, the Watsonville City Council adopted Ordinance No. 1373-18, which amended Section 14-16.802 (Permitted, Development Permitted, and Special Use Permit Uses (Table)) and Section 14-16.803 (Use Regulations) of Part 8: PF – Public Facilities and N – Institutional Districts of Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code to allow emergency shelters by right in the PF – Public Facilities and N – Institutional Districts within the city.

On September 9, 2025, the Watsonville City Council adopted Ordinance No. 1481-25, which amended multiple chapters within Title 14 (Zoning) of the Watsonville Municipal Code related to implementation

of programs within the City's 6th Cycle 2023-2031 Housing Element, including updates to the use table in Section 14-16.802 and the addition of Section 14-16.802.1 Accessory Uses.

PROCESS:

Pursuant to WMC Section 14-12.801, the text of the adopted Zoning Code may be amended in a manner identical to WMC Section 14-12.701, which outlines the process for General Plan amendments. Any proposed zoning code text amendment shall be reviewed by the Planning Commission at a public hearing for recommendation to the City Council. At the conclusion of the public hearing, the Commission shall adopt a resolution, recommending approval or denial of the proposed amendment, by the affirmative vote of the majority of the Commission members, subject to findings required by WMC Section 14-12.708.

STANDARD OF REVIEW:

The decision regarding whether to recommend approval of Zoning Code text amendments to the City Council is legislative and requires environmental review. For more information on standard of review and process, see the Standard of Review and Process Overview on the City website.

DISCUSSION:

The Public Facilities (PF) zoning district, per the use table in WMC Section 14-16.802, only permits aviation-related commercial uses on the Watsonville Municipal Airport property. No other commercial uses are permitted on parcels zoned PF in any other area of the city. In order to permit commercial tenants in both the existing and newly created commercial tenant spaces in City buildings located in the Downtown Watsonville Specific Plan (DWSP) area, such as the City Hall building at 275 Main Street, City staff is proposing the following amendments to WMC Title 14 Zoning:

1. WMC Section 14-16.802 - Permitted, development permitted, Special Use Permit uses (Table)
    a. Add subsection (j) DWSP Commercial Uses
        i. AUP (in table for PF)
            1. Requires Administrative Use Permit and Design Review
        ii. X (in table for Institutional)
2. WMC Section 14-16.803 - Use Regulations
    a. Add subsection (j) DWSP Commercial Uses
        i. (1) For parcels with the Public Facilities (PF) zoning designation located in the Downtown Watsonville Specific Plan area, any commercial use may be allowed with an Administrative Use Permit unless prohibited elsewhere in the Watsonville Municipal Code.

For parcels with the PF zoning designation that are located in the DWSP area, the proposed amendments would conditionally permit any commercial use with an Administrative Use Permit and a Design Review Permit approved by the Zoning Administrator as long as it is not illegal or prohibited elsewhere in the Watsonville Municipal Code. Parcels with the PF zoning designation within the DWSP area are identified in blue in Figure 1 below.

Figure 1: DWSP Figure 6-1 Regulating Plan



The parcels are listed by address in Table 1 below with the current use and owner listed.

Table 1: Parcels with PF Zoning Designation in DWSP Area

	Parcel Address	Parcel APN	Current Use	Parcel Owner
1	275 Main St.	017-781-07	Civic Plaza	City of Watsonville
2	-	017-781-06	Civic Plaza Parking Garage	City of Watsonville
3	105 2nd St.	017-172-34	Watsonville Fire Department	City of Watsonville
4	350 Main St.	017-112-01	Watsonville Plaza	City of Watsonville
5	310 Union St.	017-122-20	Solari Green Technology Center	City of Watsonville
6	120 2nd St.	017-101-47	Marinovich Park & Community Center	City of Watsonville
7	215 E. Beach St.	017-033-13	Watsonville Veterans Memorial Bldg.	County of Santa Cruz
8	214 Center St.	017-033-20	American Legion Post 121	American Legion
9	133 Brennan St.	018-151-14	Moreland Notre Dame School	Moreland Notre Dame
10	634 Main St.	018-151-41	Moreland Notre Dame School	Moreland Notre Dame
11	537 Main St.	018-231-48	Radcliff Elementary School	PVUSD
12	550 Rodriguez St.	018-231-49	Radcliff Elementary School	PVUSD
13	530 Rodriguez St.	018-231-28	Radcliff Elementary School	PVUSD

14	524 Rodriguez St.	018-231-27	Radcliff Elementary School	PVUSD
15	518 Rodriguez St.	018-231-26	Radcliff Elementary School	PVUSD
16	42 W. Lake Ave.	018-231-25	Radcliff Elementary School	PVUSD
17	40 W. Lake Ave.	018-231-24	Radcliff Elementary School	PVUSD
18	38 W. Lake Ave.	018-231-52	Radcliff Elementary School	PVUSD
19	26 W. Lake Ave.	018-231-21	Parking Lot	City of Watsonville

The list includes parcels occupied by both public facilities and institutional uses. However, for parcels zoned Public Facilities in the DWSP area, the DWSP defers to the development and use standards in WMC Section 14-16.800-803. The development and use standards in those sections cover both the Public Facilities and Institutional zoning districts. The development and use standards are applied based on where the current ownership and use of the property fit under the PF or N zoning district in the use table in WMC Section 14-16.802 Permitted, Development Permitted, and Special Use Permit Uses (Table). Therefore, the proposed zoning code text amendments will only apply to the PF properties in Table 2 below.

Table 2: Parcels with Existing PF Uses and PF Zoning Designation in DWSP Area

	Parcel Address	Parcel APN	Current Use	Parcel Owner
1	275 Main St.	017-781-07	Civic Plaza	City of Watsonville
2	-	017-781-06	Civic Plaza Parking Garage	City of Watsonville
3	105 2nd St.	017-172-34	Watsonville Fire Department	City of Watsonville
4	350 Main St.	017-112-01	Watsonville Plaza	City of Watsonville
5	310 Union St.	017-122-20	Solari Green Technology Center	City of Watsonville
6	120 2nd St.	017-101-47	Marinovich Park & Community Center	City of Watsonville
7	215 E. Beach St.	017-033-13	Watsonville Veterans Memorial Bldg.	County of Santa Cruz
8	214 Center St.	017-033-20	American Legion Post 121	American Legion
9	26 W. Lake Ave.	018-231-21	Parking Lot	City of Watsonville

The proposed permitting approach will provide applicants with certainty related to permitting timing and cost while also allowing the City staff to review and condition projects as needed to ensure that new commercial uses comply with applicable regulations and standards and that any potential negative impacts are minimized.

A Specific Plan Amendment for the DWSP is not required because the DWSP defers to the development and use standards in WMC Section 14-16.800-803 for parcels zoned Public Facilities.

The proposed amendments to WMC Title 14 Zoning are included as Attachment 1 and located in Exhibit A to the resolution.

ZONING CODE TEXT AMENDMENT FINDINGS:

Pursuant to WMC Section 14-12.807, the Planning Commission and the City Council shall, in approving a text amendment to the zoning code, make the findings in WMC Section 14-12.708. Those findings with supportive evidence are below.

a) That the proposed amendment is consistent with the policies embodied in the General Plan.

Supportive Evidence: The proposed amendments are consistent with the following policies embodied in the General Plan as described below:

- **Goal 4.3 & Policy 4.C Commercial Land Use** – Revitalize the central business district and provide adequate neighborhood commercial services.

  The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Providing a permitting pathway for additional commercial uses in the downtown area will help revitalize the central business district.

- **Goal 4.6 Local Employment** – Promote a variety of employment opportunities within the city providing living wage jobs to Watsonville residents. Stimulate creation of 7,500 additional jobs by 2005. Pursue opportunities for job skill training.

  The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. New commercial uses will provide additional employment opportunities for Watsonville residents within the downtown area.

- **Policy 4.C.4 Visitor Commercial** – The City shall plan for additional visitor-serving facilities within the central business district and in suitable locations in proximity to Highway 1.

  The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Building such as the City Hall building located at 275 Main Street are both centrally located and visitor-serving, with an attached parking structure (Civic Plaza Parking Garage) serving commercial uses on surrounding parcels as well as visitors to the Civic Plaza, Watsonville Public Library, and Superior Court of Santa Cruz. Therefore, permitting commercial uses in these locations will provide additional visitor-serving facilities within the central business district.

- **Implementation Measure 4.G.2 Multiple Use** – Wherever feasible and appropriate, and where the potential impacts and mitigation measures associated with mixed use can be identified and fully considered through the CEQA process, the City shall support intensification of use by combining uses on one site, e.g. residential and commercial, institutional and recreational.

  The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Building such as the City Hall building located at 275 Main Street already include a mix of public uses, such as Watsonville Civic Plaza, Watsonville Public Library, the Superior Court of Santa Cruz, and the Civic Plaza Parking

Garage. Adding commercial uses in these locations is feasible and appropriate because it will complement and support the existing uses.

b) That the proposed amendment is compatible to the extent possible with the actual and general planned use of the adjacent properties.

Supportive Evidence: The proposed amendments were modeled after the allowable commercial uses in the DWSP area. Therefore, they are consistent and compatible with the land use regulations identified in the DWSP, which was adopted in October 2023, and the General Plan as modified by the DWSP. Therefore, the proposed amendment is compatible with the actual and general planned use of the adjacent properties.

These findings are located in Exhibit B to the resolution.

CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) DETERMINATION:

The proposed zoning code text amendment is categorically exempt from the California Environmental Quality Act under the common sense exemption in Section 15061(b)(3).

Cal. Code Regs. Title 14, §15061(b)(3) states that CEQA applies only to projects which have the potential for causing a significant effect on the environment. Where it can be seen with certainty that there is no possibility that the activity in question may have a significant effect on the environment, the activity is not subject to CEQA. There is no possibility that the amendments to the text of the Zoning Code would have significant effects on the environment because no actual physical project is being proposed at this time.

Accordingly, no further environmental review is required.

ALTERNATIVE ACTION:

The Planning Commission may consider continuing the project and directing staff to return with additional information and/or revisions.

ATTACHMENTS AND/OR REFERENCES (IF ANY):

1. Proposed Zoning Code Text Amendments – WMC Sections 14-16.802 & 14-16.803

ORDINANCE NO. Introduction (CC)

AN ORDINANCE OF THE CITY COUNCIL OF THE CITY OF WATSONVILLE AMENDING CHAPTER 14-16 (DISTRICT REGULATIONS) WITHIN TITLE 14 (ZONING) OF THE WATSONVILLE MUNICIPAL CODE TO CONDITIONALLY PERMIT COMMERCIAL USES ON PARCELS ZONED PUBLIC FACILITIES (PF) AND LOCATED IN THE DOWNTOWN WATSONVILLE SPECIFIC PLAN AREA; AND FINDING THE ACTION EXEMPT FROM REVIEW UNDER THE CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) PURSUANT TO CEQA GUIDELINES SECTION 15061(B)(3)

WHEREAS, Watsonville Municipal Code (WMC) Chapter 14-16 regulates uses and development in specific zoning districts in the City; and

WHEREAS, WMC § 14-16.802 identifies uses within the Public Facilities (PF) and Institutional (N) zoning districts that are permitted by right, subject to design review, require an Administrative Use Permit with Design Review approval, require a Special Use Permit with Design Review approval, require approval of a Temporary Use Permit, or are prohibited; and

WHEREAS, the PF zoning district only permits aviation-related commercial uses on the Watsonville Municipal Airport property; and

WHEREAS, no other commercial uses are permitted on parcels zoned PF in any other area of the city; and

WHEREAS, providing a permitting pathway for commercial tenants to occupy vacant tenant spaces in existing buildings on parcels zoned PF in the Downtown Watsonville Specific Plan (DWSP) area supports the City Council Strategic Plan goal of economic development and multiple General Plan goals, policies, and implementation measures related to employment opportunities and revitalization of the City's commercial core; and

WHEREAS, City Staff reviewed the project under the California Environmental Quality Act (CEQA) and determined that the project qualifies for a common sense exemption under California Code of Regulations Title 14, §15061(b)(3) because the proposed zoning text amendment does not have the potential for causing a significant impact on the environment and it can be seen with certainty that there is no possibility that the amendment may have a significant effect on the environment; and

WHEREAS, on April 7, 2026, the Planning Commission held a duly noticed public hearing to review the proposed Zoning Code Text Amendments, at which time during the hearing, members of the public were given an opportunity to testify regarding the proposed amendments; and

WHEREAS, the Planning Commission considered all evidence received, both oral and documentary, and adopted Resolution No. 03-26 (PC) recommending that the City Council adopt an ordinance amending Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code; and

WHEREAS, notice of time and place of the City Council hearing to consider the zoning code text amendment was given as required by law and a public hearing was held according to Part 9: Public Hearing Notice Provisions of Chapter 14-10: Administration and Procedure of the WMC; and

WHEREAS, on April 14, 2026, the Council held a duly noticed public hearing to review the proposed Zoning Code Text Amendments, at which time during the hearing members of the public were given an opportunity to testify regarding the proposed Zoning Code Text Amendments; and

WHEREAS, the City Council has considered all evidence received, both oral and documentary, and the matter was submitted for decision.

NOW, THEREFORE, THE CITY COUNCIL OF THE CITY OF WATSONVILLE DOES ORDAIN AS FOLLOWS:

SECTION 1: RECITALS

The foregoing recitations are true and correct and are hereby incorporated into this Ordinance.

SECTION 2: ENACTMENT

1. The City Council adopts an ordinance amending Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code, attached hereto as Exhibit A, to conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located in the Downtown Watsonville Specific Plan area.

2. The City Council finds that the proposed zoning code text amendments are consistent with the purposes of the General Plan and Municipal Code as set forth in Exhibit B, which is attached hereto and incorporated herein by this reference.

SECTION 3: CEQA

The City Council determined that the proposed Zoning Code Text Amendments are exempt from review under the California Environmental Quality Act (CEQA) under the common sense exemption under CEQA Guidelines Section 15061(b)(3) as it can be seen with certainty that there is no possibility that the amendments to the Zoning Code would have significant effects on the environment because no actual physical project is being proposed at this time.

SECTION 4: PUBLICATION

This ordinance shall be published in the Watsonville Register-Pajaronian and/or Santa Cruz Sentinel in compliance with the provisions of the Charter of the City of Watsonville.

SECTION 5: EFFECTIVE DATE

This ordinance shall take effect thirty (30) days after its final adoption.

****

Chapter 14-16
DISTRICT REGULATIONS

Part 8: PF – Public Facilities and N – Institutional Districts

14-16.802 Permitted, development permitted, and Special Use Permit uses (Table).

The following list represents those uses, subject to the provisions of this title, in the Public Facilities (PF) and the Institutional (N) zones that are permitted by right (P), subject to Design Review (D), require an Administrative Use Permit with Design Review approval (AUP), require a Special Use Permit with Design Review approval (SUP), require an approval of a Temporary Use Permit (TUP), or are prohibited (X).

Any other use or service establishment determined by the Zoning Administrator to be of the same general character as the foregoing permitted uses, which will not impair the present or potential use of adjacent properties, shall be permitted. If the Zoning Administrator determines that the proposed use is more in character with the conditional uses for this zone, then either an AUP or SUP shall be required to be processed.

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(a) Institutional and uses of community significance		
(1) Cemetery	SUP	SUP
(2) Churches and other places of worship	X	SUP
(3) Clinics and rehabilitation facilities (public/nonprofit)	SUP	SUP
(4) Community center and related facilities (public/nonprofit)	AUP	AUP
(5) Daycare center (public/nonprofit/private)	AUP	AUP
(6) Educational facility (public/private)	SUP	SUP*

Uses (See Section 14-16.803 for use descriptions)	PF	N
(7) Galleries and museums (public/nonprofit)	D	AUP
(8) Large group care or group home (public/private/nonprofit)	X	SUP
(9) Hospital (public/nonprofit/private)	X	SUP
(10) Judicial center with or without jail facilities	SUP/AUP	X/X
(11) Nursing, convalescent and residential care facility (public/nonprofit)	X	AUP
(12) Post office*	AUP	AUP
(13) Use of community significance	SUP	SUP
(b) Lodging uses		
(1) Campground (public)	SUP	X
(2) Conference center	SUP	X
(c) Government buildings		
(1) Government offices (local/state/federal)	D	X
(2) Nonprofit organization offices	AUP	AUP
(3) Fire/Paramedic Station	D	X
(4) Library (public)	D	X
(d) Recreation uses		
(1) Equestrian facility	SUP	X
(2) Golf course	SUP	X

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(3) Membership club or hall	D	SUP
(4) Outdoor recreation with lighted facilities	D/AUP	AUP/SUP
(5) Park or playfield with lighted facilities	D/AUP	AUP/SUP
(6) Public Recreation Center	D	SUP
(e) Residential uses		
(1) Affordable housing project (multi-family, rental)	SUP	X
(2) Caretaker's residence	AUP	AUP
(3) Emergency shelter	P	P
(4) Rectory/minister's residence	X	AUP
(5) Transitional housing	AUP	X
(f) Transportation uses		
(1) Airport (airfield modifications)	D	X
(2) Airport support (terminal expansion)	D	X
(3) Aviation commercial (airport access)	AUP	X
(4) Aviation noncommercial (hangars and taxiways)	D	X
(5) Aviation compatible (research park improvements)	SUP	X
(6) Helistop	SUP	X
(7) Mass transit center	AUP	X
(8) Park and ride facility	D	AUP

Uses (See Section 14-16.803 for use descriptions)	PF	N
(9) Parking structure or parking lot (primary use)	D	X
(10) Terminal and passenger service facility	AUP	X
(g) Utility and public service uses		
(1) Electrical power substation	AUP	X
(2) Public or quasi-public facility other than listed	AUP	AUP
(3) Public safety telecommunication facility	D	X
(4) Sewage or water transmission lines	P	X
(5) Telecommunications site — Telecommunications site exceeding height limit of district	AUP/SUP	AUP/SUP
(6) Utility service facility	P	X
(7) Water tank, water treatment facility or sewer lift station	D	X
(8) Telecommunications facilities	SUP	X
(h) Accessory uses		
(1) Accessory outside storage	D	AUP
(2) Accessory structure	D	D
(3) Shipping containers	D	D

Uses (See Section 14-16.803 for use descriptions)	PF	N
(4) Satellite earth station antennas	P	P
(i) Temporary uses		
(1) Emergency noncommercial telecommunications facility	TUP	X
(2) Temporary batch plant	TUP	X
(3) Temporary construction office and/or yard	TUP	TUP
(4) Temporary dwelling unit	TUP	TUP
(j) DWSP Commercial Uses	AUP	X

*State or Federal facilities not subject to City of Watsonville Review except as leasehold project.

Key:

D — Requires Design Review
SUP — Requires Special Use Permit with Design Review
X — Prohibited
AUP — Requires Administrative Use Permit with Design Review
TUP — Temporary Use Permit
P — Principally Permitted (may require a Building Permit)

(Ord. 1156-03 C-M, eff. May 22, 2003, as amended by § 1, Ord. 1373-18 (CM), eff. October 11, 2018, and § 2(3) (Exh. A), Ord. 1481-25 (CM), eff. October 9, 2025)

14-16.802.1 Accessory uses.

The following uses are only permitted with an Administrative Review Permit if a primary residential unit is provided or present on the site:

DLU	02	Accessory dwelling unit
	02	Junior accessory dwelling unit

(§ 2(3) (Exh. A), Ord. 1481-25 (CM), eff. October 9, 2025)

14-16.803 Use regulations.

(a) Institutional and uses of community significance.

(1) Cemetery.

(i) Definition: A place designated for the burial or retention of the remains of the dead whether human or animals, including crematories, mausoleums, and columbariums operated within the boundaries of the cemetery.

(ii) Parking requirements: To be determined through a Use Permit.[1]

(iii) Loading requirements: To be determined through a Use Permit.[1]

(iv) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(2) Churches and other places of worship.

(i) Definition: A facility principally used for people to gather together for public worship, religious training, or other religious activities.

(ii) Parking requirements: One space per four (4) seats feet in the worship area, plus any parking required for accessory uses.[1]

(iii) Loading requirements: None.[1]

(iv) Additional provisions:

(aa) The structure height limitations of this code shall not apply to church spires, belfries, or cupolas;

(bb) One single-family dwelling used to house a church official and family is considered customary and incidental as a part of this use.

(cc) Daycares subject to an Administrative Use Permit.

(dd) Schools subject to a Special Use Permit.

(3) Clinics and rehabilitation facilities (public/nonprofit).

(i) Definition: An establishment where patients are admitted for study/treatment by two (2) or more medical professionals.

(ii) Parking requirement: One space per three (3) service units/beds plus one space per two (2) employees or one space per two hundred (200) square feet of area whichever is greater.[1]

(4) Community facility.

(i) Definition: A facility for a use of community significance, public or quasi-public, where public services or information is provided on a nonprofit basis, including but not limited to government offices, senior centers, meeting rooms, family counseling or family help centers, and police substations.

(ii) Parking requirements: One space per two hundred and fifty (250) square feet of office area, meeting rooms thirty percent (30%) of maximum occupancy, or as determined by Design Review.[1]

(iii) Loading requirements: To be determined through Design Review.

(5) Day care center (public/nonprofit).

(i) Definition: A facility providing less than twenty-four (24) hour care or supervision for fourteen (14) or more persons who are not related by blood, marriage, or adoption to the owner, operator, or manager. Such facility may operate by day or night, with or without compensation for such care, and with or without a stated educational purpose.

(ii) Parking requirements: One space for every eight (8) persons plus one space per employee.[1]

(iii) Additional provisions:

(aa) This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, County, State and Federal permits.

(6) Educational facility (public/private).

(i) Definition: Buildings and uses for public or private educational or research activities associated with an academic institution which has a curriculum for technical, vocational training, or higher education.

(ii) Parking requirements:[1]

(aa) Elementary or junior high school, one space per employee plus one space for every twenty (20) students of school design capacity.

(bb) High school, one space per employee plus one space for every seven (7) students of school design capacity.[1]

(7) Galleries and museums (public/nonprofit).

(i) Definition: A place offering or displaying artistic works, decorative objects or the like for public viewing or sale.

(ii) Parking requirements: three (3) parking spaces plus one space per eight hundred (800) square feet of floor space.[1]

(8) Large group care or group home (public/private/nonprofit).

(i) Definition: A facility which provides twenty-four (24) hour care or supervision of more than twelve (12) persons who are not related by blood, marriage, or adoption, to the owner, operator, or manager, and who do not meet the definition of a family. A group care or foster home may be operated by a public, nonprofit, or private agency. This definition includes halfway houses and drug or alcohol rehabilitation facilities for any number of persons, with or without twenty-four (24) hour care or supervision,

(ii) Parking requirements: One-half (0.5) parking spaces per bed or one and one-quarter (1.25) parking spaces per living unit, whichever is greater.[1]

(iii) Additional provisions:

(aa) This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the city, all applicable local, State, and Federal permits;

(9) Hospital (public/nonprofit/private).

(i) Definition: An institution where people are given medical attention and treatment including but not limited to related facilities such as laboratories, outpatient clinics, and staff offices on primarily an inpatient basis.
(ii) Parking requirements: One space per two (2) patient beds plus one per employee on shift with maximum personnel.[1]
(iii) Loading requirements: One loading space for ten thousand (10,000) or more square feet of floor area.
(iv) Setbacks: Minimum setback of thirty (30), feet from any residential district.
(v) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.
(vi) Helipads: Helipads shall be allowed for hospitals as long as they are setback a minimum of two hundred (200) feet from residential uses and they do not include support facilities such as refueling or similar use.

(10) Judicial center with or without jail facilities.
(i) Definition: Buildings used for courtrooms, police stations, jails, and accessory offices.
(ii) Parking requirements: To be determined through a Special Use Permit.[1]
(iii) Loading requirements: To be determined through a Special Use Permit.

(11) Nursing, convalescent and residential care facility (public/nonprofit).
(i) Definition: A facility which provides twenty-four (24) hour residential care to persons who are not related by blood, marriage, or adoption to the owner, operator, or manager of the facility. A nursing, convalescent, or residential care facility provides some level of skilled nursing or medical service to the residents.
(ii) Parking requirements: One parking space per five (5) patient beds plus one per each two (2) employees.[1]
(iii) Loading requirements: To be determined by Use Permit
(iv) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(12) Post office.
(i) Definition: A facility owned and/or operated by the United States Postal Service where public mailing services, including distribution and delivery of mail, are provided.
(ii) Parking requirements: One space per three hundred (300) square feet of gross floor area over four thousand (4,000) square feet plus one per post office vehicle and one per three (3) employees.[1]

(iii) Loading: a minimum of two (2) loading spaces shall be provided and one additional loading space per each twenty thousand (20,000) square feet of building area.

(13) Use of community significance.

(i) Definition: A use determined to have significant historic cultural, economic, social, or environmental value to the City, which does not conform to the use regulations of the district in which the use is located as a result of either the adoption or amendment of this Code, and which cannot be made conforming through any other discretionary review process under this Code.

(ii) Parking requirements: To be determined through Use Permit.[1]

(iii) Loading requirements: To be determined through Use Permit.

(iv) Additional provisions: The creation of murals falls within this definition.

(b) Lodging uses.

(1) Campground (public).

(i) Definition: An area of land where accommodations for occupation on a transient basis are located or may be placed. This includes tents and recreational vehicles.

(ii) Parking requirements: One parking space per tent or recreational vehicle space.

(2) Conference center.

(i) Definition: An indoor overnight facility, including either a single building or multi-building complex with or without individual kitchens, which serves as a destination point for visitors, which includes conference facilities.

(ii) Parking requirements: One and one-half (1.5) spaces per room or two (2) spaces per cabin, plus one space per two hundred (200) square feet of meeting room(s).[1]

(iii) Loading requirements: To be determined through Use Permit.

(iv) Additional provisions: Guest residency is limited to a transient basis.

(c) Government Buildings.

(1) Government offices (public).

(i) Definition: A building/office used by Federal, State, County or City government agencies or an instrumentality thereof.

(ii) Parking requirements: One space per five hundred (500) square feet of floor area, or as determined by Design Review based on the type of use.[1]

(2) Nonprofit organization offices.

(i) Definition: Buildings or offices used by an Internal Revenue Service (IRS) designated 501 3(c) entity. This use does not include medical/clinic facilities or other specific uses identified in this chapter where run by a non profit entity.

(ii) Parking requirement: One space per five hundred (500) square feet of floor area or as determined by Design Review.[1]

(3) Fire/Paramedic Station.
  (i) Definition: A facility operated by a municipality, fire district, department, or private company which houses fire and paramedic equipment and may be used for the housing of personnel.
  (ii) Parking requirements: To be determined through Design Review.[1]
(4) Library (public).
  (i) Definition: Buildings used for public access to books, computers and other publications.
  (ii) Parking: Ten (10) spaces plus one per each four hundred (400) square feet of floor area over five thousand (5,000) square feet.[1]
  (iii) Loading: To be determined through the Design Review process.
  (iv) Other standards: To be determined through the Design Review process.

(d) Recreation uses.
(1) Equestrian facility.
  (i) Definition: A public or commercial facility for horse training, horse boarding, competitive equestrian events, rentals, sales and lessons.
  (ii) Parking requirements: Determined through Design Review.[1]
  (iii) Additional provisions:
  (iv) Setback requirements:
    (aa) Structures intended or designed to house animals shall be located a minimum of fifty (50) feet from all lot lines.
    (bb) Outdoor lighting of facility requires Use Permit approval.
(2) Golf course.
  (i) Definition: A recreational facility primarily used for the purpose of playing golf, but which may include accessory eating and drinking areas, retail sales areas, locker rooms and staff offices. The use includes stand-alone driving ranges, miniature golf and “pitch and putt” facilities.
  (ii) Parking requirements: four (4) spaces per hole, plus as required for accessory uses including but not limited to pro shops and restaurants. One and one-half (1.5) space per miniature hole or driving range station.[1]
(3) Membership club or hall.
  (i) Definition: A facility, including associated eating, drinking, and recreational facilities, owned or operated by a group of people organized for a common social, educational, service, or recreational purpose. These clubs are usually characterized by certain membership qualifications, payment of fees or dues, regular meetings, a constitution, and bylaws.
  (ii) Parking requirements: One space per three hundred (300) square feet of floor area.[1]
(4) Outdoor recreation, for day use or with lighted fields.
  (i) Definition: An area or facility which offers entertainment, recreation, or games of skill for a fee where any portion of the activity takes place

outside. This includes but is not limited to a rifle range, boating facility, or tennis facility.

(ii) Parking requirements: As established through Title 9, Part 12 (Public and Quasi-Public Open Centers) standards and Design Review.[1]

(5) Park or playfield, for day use or with lighted facilities.

(i) Definition: A recreational area providing parks and playfields. This includes publicly-owned and commonly-owned recreational facilities such as playgrounds, parks, game courts, swimming pools, and playing fields.

(ii) Parking requirements: As established through Title 9, Part 12 (Public and Quasi-Public Open Centers) standards and Design Review or planned development.[1]

(6) Public recreation center.

(i) Definition: A publicly-owned area providing indoor recreational facilities such as multi-purpose rooms, basketball courts, training facilities.

(ii) Parking requirements: As established through Title 9, Part 12 (Public and Quasi-Public Open Centers) standards and Design Review or planned development.[1]

(e) Residential uses.

(1) Affordable housing project (multi-family, rental).

(i) Definition: Two (2) or more rental dwelling units which are restricted in rental rates so as to meet the definition of affordable of the City or Redevelopment Agency.

(ii) Parking requirements: One and a half (1.5) spaces per unit for up to three (3) bedrooms; two (2) spaces per unit for four (4) or more bedrooms. Additionally, one additional guest space shall be provided per eight (8) bedrooms.[1]

(iii) Density and Development Standards: Affordable housing developed under these provisions shall follow the RM-2 district regulations and minimum net land area standards.

(2) Caretaker's residence.

(i) Definition: An accessory structure intended to house an individual and immediate family who is principally employed by the principal use to provide maintenance, security or other services directly related to the facility.

(ii) Parking requirements: Two (2) dedicated spaces per unit.[1]

(iii) Additional provisions: There may be no more than one caretaker's residence per facility.

(3) Emergency shelter.

(i) Definition: Housing with minimal supportive services for homeless persons that is limited to occupancy of six (6) months or less by a homeless person. No individual or household may be denied emergency shelter because of an inability to pay.

(ii) Parking requirements: As determined by Chapter 14-43.

(iii) Development standards: As determined by Chapter 14-43.

(4) Rectory/minister's residence.

(i) Definition: Primary housing facility for ministry leaders, their family and guests which are located on the premises of the place of worship.

(ii) Parking requirements: Two (2) dedicated spaces per unit.[1]

(iii) Additional provisions: There may be no more than two (2) residences per facility.

(5) Transitional housing.

(i) Definition: A structure or facility used as housing for a period of up to twenty-four (24) months for individuals and/or families who have been displaced from their home.

(ii) Parking requirements: One space per unit if an additional 0.5 (1/2) spaces per unit is available on the street directly adjacent to the facility. Otherwise, projects shall be designed to provide one and one half (1.5) parking spaces per unit on-site.[1]

(iii) Development Standards: As determined by Use Permit.

(f) Transportation uses.

(1) Airport (air field modifications).

(i) Definition: Facilities/modifications to the existing air field and infrastructure necessary to support safe aircraft arrival and departure which are identified in the Watsonville Municipal Airport Master Plan including but not limited to: Instrument Landing System (ILS) improvements, runway extension, taxiway improvements allowed when a master plan is approved.

(ii) Development Standards: As outlined in a master plan and developed in conjunction with Design Review.

(2) Airport support (terminal expansion).

(i) Definition: Facilities to improve airport operations identified in the Watsonville Municipal Airport Master Plan including but not limited to: airport administration, airport maintenance, aviation fuel facilities, pilot lounge and general services facilities, terminal expansion, and aircraft rescue and fire fighting facilities.

(ii) Development Standards: As outlined in Master Plan and developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(3) Aviation commercial (airport access).

(i) Definition: Facilities necessary to provide area for commercial uses that serve the needs of general aviation at the airport identified in the Watsonville Municipal Airport Master Plan including but not limited to: fixed base operator facilities involving the sale of general aviation products and services to the general public and limited service commercial facilities, such as avionics sales and repair shops, aircraft paint shops and aircraft maintenance facilities.

(ii) Development Standards: As outlined in Master Plan and developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(4) Aviation noncommercial (hangars and taxiways).

(i) Definition: Facilities necessary to provide area for non-commercial aircraft operators to store and service private aircraft which are identified in the Watsonville Municipal Airport Master Plan including but not limited to: new hangars, taxiways, fuel facilities.

(ii) Development Standards: As outlined in Master Plan and developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(5) Aviation compatible (research park improvements).

(i) Definition: Facilities necessary to provide for non-aviation uses that support airport operations which are identified in the Watsonville Municipal Airport Master Plan including but not limited to automobile rental agencies, airport restaurant, motel, office park or research and development facilities.

(ii) Development Standards: As outlined in Master Plan and following the Commercial development standards within the City's development codes for the specific use or as developed in conjunction with Design Review.

(iii) Height of structures and use of airspace are specified in Chapter 4 of Title 9 of this Code.

(6) Helistop.

(i) Definition: Any designated area outside of the airport used for the landing and taking off of helicopters for the purpose of picking up or discharging passengers or cargo including designated emergency medical patients. This use does not include fueling, refueling, or service facilities.

(ii) Additional provisions: This use shall provide proof of having obtained and of having maintained, as may be periodically requested by the City, all applicable local, State, and Federal permits.

(iii) Helistops shall be no closer than two hundred feet (200') to any residential zone.

(7) Mass transit center.

(i) Definition: A transportation facility that serves as a transportation hub for buses, trains or other forms of mass transportation. These can be associated with Park and ride facilities.

(ii) Additional provisions: To be determined through the Use Permit process.

(8) Park and ride facility.

(i) Definition: A facility whose sole purpose is to provide parking for motor vehicles and bicycles with a connection to mass transit services or carpooling activities.[1]

(ii) Additional provisions: To be determined through Design Review process.

(9) Parking structure and parking lot (primary use).

(i) Definition: A structure or area the purpose of which is to allow the parking of motor vehicles, for a fee or not, as the primary use on a parcel.

(ii) Additional provisions: To be determined through the Design Review process including screening lots by landscaping from adjacent rights-of-way.

(10) Terminal and passenger service facility.

(i) Definition: Establishments engaged in the operation of motor vehicle passenger service terminals including maintenance and service facilities, including bus and taxicab fleet operations.

(ii) Parking requirements: Customer and employee parking at one space for every two hundred and fifty (250) square feet of office area and one space for every one thousand feet (1,000') of maintenance service area vehicles related to the operation of the terminal may not be parked in customer or employee parking areas.[1]

(g) Utility and public service uses.

(1) Electrical power substation.

(i) Definition: A facility operated by an electrical utility company that acts as a collection and distribution point for electricity. The facility includes transformers, and other equipment that reduce high voltage current and transfer it to utility lines.

(2) Public or quasi-public facility other than listed.

(i) Definition: A public or quasi-public facility other than those specified in this chapter.

(ii) Parking requirements: To be determined through Special Use Permit.[1]

(iii) Loading requirements: To be determined through Special Use Permit.

(3) Public safety telecommunication facility.

(i) Definition: A facility owned or operated by a governmental agency or a volunteer public safety agency officially sanctioned by a government agency for that purpose, utilized for the transmission and reception of electromagnetic or electro-optic information for public safety communication uses in accordance with the provisions of Chapter 14-35, Telecommunications Uses.

(4) Sewage or water transmission lines.

(i) Definition: Pipelines used for the transport of water (potable or non-potable) or sewage effluent.

(5) Telecommunications site.

(i) Definition: See Section 14-18.804.

(ii) Additional provisions: Comply with Chapter 14-35, Telecommunication Uses.

(6) Utility service facility.

(i) Definition: Any electrical distribution lines, natural gas distribution lines, minor gas regulator stations, cable television lines, telegraph and telephone lines, and gathering lines, or other minor service facilities.

(ii) Additional provisions: No buildings may be associated with this use.

(7) Water tank, water treatment facility or sewer lift station.

(i) Definition: A water facility with a capacity of five thousand (5,000) gallons or more for purifying, supplying, and holding water, or a sewer lift station facility, each including appurtenant wells, pumps, and control buildings.

(ii) Additional Provisions: Comply with Chapter 14-35, Telecommunications Uses.

(8) Telecommunications facilities.

(i) Definition: See Section 14-18.803.

(ii) Additional provisions: Comply with Chapter 14-35, Telecommunication Uses.

(h) Accessory uses.

An accessory use must be a use customarily incidental to and on the same parcel as the main use. A use listed in Chapter 14-16.02 may be an accessory use if the Zoning Administrator determines that the use is customarily incidental to a main use. Except as provided in this section, an accessory use must comply with all regulations applicable to the main use.

(1) Accessory outside storage.

(i) Definition: The outside placement, for a period of more than forty-eight (48) hours, of items which are customary and incidental to the main use of the property.

(ii) Additional provisions:

(aa) The area of placement may not exceed five (5%) percent of the lot area;

(bb) Items must be screened from the view of adjacent roadways and properties;

(cc) Accessory outdoor storage of agricultural products and operable agricultural equipment is exempt from these additional provisions;

(dd) For purposes of these regulations, recreational equipment includes motor homes, boats, and boat trailers, travel trailers, pick-up campers, tent trailers, utility trailers and similar equipment, and cases or boxes used for transporting recreation equipment, whether occupied by equipment or not. Recreation equipment must be parked or stored in a carport or in an enclosed building, or up to two (2) units may be parked behind the nearest portion of a building to the street, screened by a six

foot (6') solid fence or wall provided that equipment may be parked anywhere for a time period not to exceed forty-eight (48) hours during loading or unloading. Recreational equipment must not be used for living, sleeping or housekeeping purposes when parked or stored on any lot or in any location not approved for the use.

(2) Accessory structure.

(i) Definition: A structure detached from, but located on, the same lot as the principal use, the use of which is incidental and accessory to that of the principal use, and not designed for human habitation.

(ii) Additional provisions: Any accessory structure is subject to the minimum requirements of the zoning district in which it is located; however, accessory structures less than fifteen feet (15') in height from adjacent pre-developed grade may be located five feet (5') from the side or rear lot lines within the rear yard area.

(3) Shipping containers.

(i) Definition: Any enclosed container constructed of metal, wood, or other material which container was designed or patterned after structures used in containerized shipping operations used for temporary or permanent storage.

(ii) Parking requirements: None for temporary applications; at least one per three (3) container units for permanent applications as determined by Design Review.[1]

(iii) Additional provisions: See Section 14-10.170.

(4) Satellite earth station antennae.

(i) Definition: See Section 14-18.064(8).

(ii) Development Standards: See Chapter 14-35, Telecommunications Uses.

(i) Temporary uses.

(1) Emergency noncommercial telecommunications facility.

(i) Definition: A facility owned or operated by a governmental agency or a volunteer public safety agency officially sanctioned by a government agency for that purpose used for the transmission and reception of electromagnetic or electro-optic information for public safety communication uses. This facility may operate for a maximum of six (6) months.

(ii) Parking requirements: To be determined through the Temporary Use Permit.[1]

(iii) Loading requirements: To be determined through the Temporary Use Permit.

(2) Temporary batch plant.

(i) Definition: A temporary facility for mixing concrete, asphalt or similar paving materials.

(ii) Parking requirements: To be determined through the Temporary Use Permit.[1]

(iii) Loading requirements: To be determined through the Temporary Use Permit.

(iv) Additional provisions:

(aa) Limited to a maximum six (6) months for specific project needs;

(bb) The Zoning Administrator may limit the hours of operation where the use is to be located within six hundred feet (600') of residentially zoned property.

(3) Temporary construction office and/or yard.

(i) Definition: A facility temporarily used as a construction or sales office or staging/storage area.

(ii) Parking requirements: To be determined through the Temporary Use Permit.1

(iii) Loading requirements: To be determined through the Temporary Use Permit.

(iv) Additional provisions:

(aa) Office use limited to a maximum of twelve (12) months with up to two (2) six (6) month extensions;

(bb) Storage/staging uses limited to six (6) months with up to two (2) six (6) month extensions.

(4) Temporary dwelling unit.

(i) Definition: A dwelling unit temporarily used by a watchperson during construction.

(ii) Additional provisions:

(aa) May be approved only in conjunction with the issuance of a Building Permit for a commercial project or a residential project involving construction of three (3) or more new dwelling units.

(bb) One unit per project site.

(cc) Unit must be connected to City water and sewer.

(j) DWSP Commercial Uses

(1) For parcels with the Public Facilities (PF) zoning designation located in the Downtown Watsonville Specific Plan area, any commercial use may be allowed with an Administrative Use Permit unless prohibited elsewhere in the Watsonville Municipal Code.

(Ord. 1156-03 C-M, eff. May 22, 2003, as amended by § 1, Ord. 1373-18 (CM), eff. October 11, 2018, and § 2(3) (Exh. A), Ord. 1481-25 (CM), eff. October 9, 2025)

1 Parking requirements established by this Code supersede those established by Title 9, Chapter 3, for specific use listed.

CITY OF WATSONVILLE **EXHIBIT "B"**
PLANNING COMMISSION

ZONING CODE TEXT AMENDMENT FINDINGS (WMC § 14-12.807)

A. That the proposed amendment is consistent with the policies in the General Plan.

The proposed amendments are consistent with the following policies embodied in the General Plan as described below:

- **Goal 4.3 & Policy 4.C Commercial Land Use** - Revitalize the central business district and provide adequate neighborhood commercial services.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Providing a permitting pathway for additional commercial uses in the downtown area will help revitalize the central business district.

- **Goal 4.6 Local Employment** - Promote a variety of employment opportunities within the city providing living wage jobs to Watsonville residents. Stimulate creation of 7,500 additional jobs by 2005. Pursue opportunities for job skill training.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. New commercial uses will provide additional employment opportunities for Watsonville residents within the downtown area.

- **Policy 4.C.4 Visitor Commercial** - The City shall plan for additional visitor-serving facilities within the central business district and in suitable locations in proximity to Highway 1.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Building such as the City Hall building located at 275 Main Street are both centrally located and visitor-serving, with an attached parking structure (Civic Plaza Parking Garage) serving commercial uses on surrounding parcels as well as visitors to the Civic Plaza, Watsonville

Public Library, and Superior Court of Santa Cruz. Therefore, permitting commercial uses in these locations will provide additional visitor-serving facilities within the central business district.

- **Implementation Measure 4.G.2 Multiple Use** - Wherever feasible and appropriate, and where the potential impacts and mitigation measures associated with mixed use can be identified and fully considered through the CEQA process, the City shall support intensification of use by combining uses on one site, e.g. residential and commercial, institutional and recreational.

  Supportive Evidence: The proposed zoning code text amendments would conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located within the Downtown Watsonville Specific Plan (DWSP) area. Building such as the City Hall building located at 275 Main Street already include a mix of public uses, such as Watsonville Civic Plaza, Watsonville Public Library, the Superior Court of Santa Cruz, and the Civic Plaza Parking Garage. Adding commercial uses in these locations is feasible and appropriate because it will complement and support the existing uses.

B. That the proposed amendment is compatible to the extent possible with the actual and general planned use of the adjacent properties.

Supportive Evidence: The proposed amendments conditionally permit the same commercial uses principally permitted in Downtown Core and Downtown Neighborhood zoning districts in the DWSP area. Because all of the PF parcels identified are adjacent to or within those zoning districts, they are consistent and compatible with the land use regulations identified in the DWSP, which was adopted in October 2023, and the General Plan as modified by the DWSP. Therefore, the proposed amendment is compatible with the actual and general planned use of the adjacent properties.

Commercial Uses in the Public Facilities Zoning District in the Downtown Watsonville Specific Plan Area

City Council

April 14, 2026

Proposal

Ordinance amending Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code to conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located in the Downtown Watsonville Specific Plan area.

Background

- The Public Facilities (PF) zoning district only permits aviation-related commercial uses on the Watsonville Municipal Airport property.
- No other commercial uses are permitted on parcels zoned PF in any other area of the city.
- There are existing commercial tenant spaces in City buildings located in the Downtown Watsonville Specific Plan (DWSP) area that currently have no permitting pathway.

Background - Continued

- City staff is recommending changes to WMC Sections 14-16.802 and 14-16.803 to conditionally permit commercial uses in the PF zoning district in the DWSP area.
- The proposed amendments would conditionally permit commercial uses with an Administrative Use Permit and a Design Review Permit approved by the Zoning Administrator as long as it is not illegal or prohibited elsewhere in the Watsonville Municipal Code.

Background - Continued

- On April 7, 2026, the Planning Commission adopted Resolution No. 03-26 (PC) recommending that the City Council adopt an ordinance amending Chapter 14-16 (District Regulations) within Title 14 (Zoning) of the Watsonville Municipal Code to conditionally permit commercial uses in the PF zoning district in the DWSP area.

Quick Aside - What about Subway?

- Subway was approved with a Zoning Clearance in 2009 when the zoning of the City Hall property was Central Commercial Core Area (CCA) with a Planned Development (PD) Overlay
- Parcel subsequently rezoned to Public Facilities (PF) to match existing use



Discussion Overview

- Proposed Zoning Code Text Amendments
- Overview of Subject Parcels
- Permitting Process
- Zoning Code Text Amendment Process
- CEQA Review

Zoning Code Text Amendments

City Staff is proposing the following Zoning Code Text Amendments:

WMC Section 14-16.802 - Permitted, development permitted, Special Use Permit uses (Table)

- Add subsection (j) DWSP Commercial Uses
  - AUP (in table for Public Facilities)
    - Requires Administrative Use Permit and Design Review
  - X (in table for Institutional)

WMC Section 14-16.803 - Use Regulations

- Add subsection (j) DWSP Commercial Uses
  - (1) For parcels with the Public Facilities (PF) zoning designation located in the Downtown Watsonville Specific Plan area, any commercial use may be allowed with an Administrative Use Permit unless prohibited elsewhere in the Watsonville Municipal Code.

Uses (See Section 14-16.803 for use descriptions)	**PF**	**N**
(4) Temporary dwelling unit	TUP	TUP
(j) DWSP Commercial Uses	AUP	X

(j) DWSP Commercial Uses

(1) For parcels with the Public Facilities (PF) zoning designation located in the Downtown Watsonville Specific Plan area, any commercial use may be allowed with an Administrative Use Permit unless prohibited elsewhere in the Watsonville Municipal Code.

DWSP Figure 6-1 Regulating Plan

- Parcels with the Public Facilities (PF) zoning designation shown in blue.
- Some parcels developed with Institutional Uses (educational and religious institutions) and would not be affected by the text amendments
- Nine parcels affected by text amendments



Subject Parcels

Table 2: Parcels with Existing PF Uses and PF Zoning Designation in DWSP Area

	Parcel Address	Parcel APN	Current Use	Parcel Owner
1	275 Main St.	017-781-07	Civic Plaza	City of Watsonville
2	-	017-781-06	Civic Plaza Parking Garage	City of Watsonville
3	105 2nd St.	017-172-34	Watsonville Fire Department	City of Watsonville
4	350 Main St.	017-112-01	Watsonville Plaza	City of Watsonville
5	310 Union St.	017-122-20	Solari Green Technology Center	City of Watsonville
6	120 2nd St.	017-101-47	Marinovich Park & Community Center	City of Watsonville
7	215 E. Beach St.	017-033-13	Watsonville Veterans Memorial Bldg.	County of Santa Cruz
8	214 Center St.	017-033-20	American Legion Post 121	American Legion
9	26 W. Lake Ave.	018-231-21	Parking Lot	City of Watsonville

Permitting Process

- Administrative Use Permit (AUP) with Design Review approval
  - Design Review only required for new construction
- Zoning Administrator is final decision-maker for AUPs and Design Review
- Requires findings to ensure compatibility with surrounding uses
- Approvals may be conditioned
- Decision may be appealed to Planning Commission

Zoning Code Text Amendment Process

- Any proposed zoning code text amendment shall be reviewed by the Planning Commission at a public hearing for recommendation to the City Council.
  - Planning Commission adopted Resolution No. 03-26 (PC) recommending the City Council adopt the proposed ordinance
- Upon receipt of the Commission's recommendation, and before adopting any amendment, the Council shall review the matter at a public hearing and make the required findings
- Findings with supportive evidence are included in the staff report and as Exhibit B to the ordinance.

California Environmental Quality Act (CEQA)

- Proposed zoning code text amendment is categorically exempt from CEQA under the common sense exemption in Section 15061(b)(3).
- Section 15061(b)(3) states that CEQA applies only to projects which have the potential for causing a significant effect on the environment.
- Where it can be seen with certainty that there is no possibility that the activity in question may have a significant effect on the environment, the activity is not subject to CEQA.
- There is no possibility that the amendments to the Zoning Code would have significant effects on the environment.

Staff Recommendation

City Staff recommends the City Council introduce, for first reading only, waiving full reading of the text, an Ordinance amending Chapter 14-16 (District Regulations) of Title 14 (Zoning) of the Watsonville Municipal Code to conditionally permit commercial uses on parcels zoned Public Facilities (PF) and located in the Downtown Watsonville Specific Plan area.